



This plan has been prepared from preliminary survey plan (SP300871) and engineering plans & mark-ups provided on the 25/01 & 12/04/18 by Premise Engineering Pty Ltd.

Development approval was granted for this subdivision (DEV2016/768) by the Minister for Economic Development Queensland (20/03/18).

The relevant authorities have granted operational works approval, for the proposed lot.

All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.

Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.

The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.

Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company.

Fill placed between proposed tiered retaining walls will generally be equal to the height of the top of the bottom retaining wall.

Issues	No.	by	Date	Description
	Α	TBG	17/04/18	Original Issue



Saunders Havill Group Pty Ltd ABN 24 144 972 949 Brisbane Emerald Rockhampton head office 9 Thompson St Bowen Hills Q 4006 phone 1300 123 SHG web www.saundershavill.com

🏿 surveying 🎜 town planning 🗗 urban design 🗗 environmental management 🗗 landscape architecture

NOT be used for any other purpose, particularly as-constructed purposes. This information is compiled from design plans only, unless otherwise stated, and therefore is subject to final survey and construction of operational works.

Disclosure Plan for Proposed Lot 1255 on SP300871

Described as part of Lot 2 on SP297192 Existing Title Reference: 51103071

Area of Fill

Area of Cut **Design Contours** - Depth of Fill Contours Proposed Retaining Wall

Proposed Tiered Retaining Wall

Proposed Earthworks Pad

XX.XX Finished Surface Design Level

Locality of Greenbank (Logan City Council)

Level Datum: AHD der. Origin of Levels: PM61308 RL of Origin: 54.66 Contour Interval: 0.25m

Scale @A3 1: 200

Dwg No. 7598 S 13 DP A 1255