

	TEVOL ROD
	GREENBANK ROAD
	NOTES This plan has been prepared from preliminary survey plan (SP317666) and engineering plans provided on the 15/06/2020 & 22/06/2020 by Premise Engineering Pty Ltd.
	Development approval was granted for this subdivision (DEV2016/768/44) by the Minister for Economic Development Queensland (07/05/20).
	The relevant authorities have granted operational works approval, for the proposed lot.
	The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.
	All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.
	Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company.
	Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.
	Fill placed between proposed tiered retaining walls will generally be equal to the height of the top of the bottom retaining wall.
	No. by Date Description
	A TBG 06/07/20 Original Issue
	<u>8</u>
81766	Origin of Levels: PSM203674
RL of Origin: 46.275 Contour Interval: 0.25m	

<u>Scale @A3 1: 200</u> Dwg No. 7598 S 31 DP A 1028