

	TEVIOT ROAD	ANK ROAD	
		SANK ROAD	
	PRECINCT 1.5a		
	NOTES This plan has been prepared from preliminary survey plan (SP317666) and engineering plans provided on the 15/06/2020 & 22/06/2020 by Premise Engineering Pty Ltd.		
	Development approval was granted for this subdivision (DEV2016/768/44) by the Minister for Economic Development Queensland (07/05/20).		
	The relevant authorities have granted operational works approval, for the proposed lot.		
	The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.		
	All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.		
	Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.		
	No. by Date	Description O Original Issue	
17666 <u>Level Datum: AHD der.</u>			
Origin of Levels: PSM		Origin of Levels: PSM203674 RL of Origin: 46.275	
Contour Interval: 0.25m			
		Scale @A3 1: 200	

Dwg No. 7598 S 31 DP A 1189