

	Tevor Roo
	GREENBANK ROAD
	PRECINCT 1.5a
	NOTES
	This plan has been prepared from preliminary survey plan (SP317666) and engineering plans provided on the 15/06/2020 & 22/06/2020 by Premise Engineering Pty Ltd.
	Development approval was granted for this subdivision (DEV2016/768/44) by the Minister for Economic Development Queensland (07/05/20).
	The relevant authorities have granted operational works approval, for the proposed lot.
	The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.
	All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.
	Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.
	No. by Date Description
1766	66 <u>Level Datum: AHD der.</u>
	Origin of Levels: PSM203674 RL of Origin: 46.275
	Contour Interval: 0.25m
	Scale @A3_1: 200

Dwg No. 7598 S 31 DP A 1191