	SHEET LIST TABLE
SHEET NUMBER	SHEET TITLE
C001	COVER SHEET LOCALITY PLAN & DRAWING SCHEDULE
C002	SURVEY SETOUT PLAN
C003	OVERALL SERVICES LAYOUT
C004	SAFETY IN DESIGN PLAN
C100	ROADWORKS & DRAINAGE LAYOUT PLAN - SHEET 1 OF 2
C101	ROADWORKS & DRAINAGE LAYOUT PLAN - SHEET 2 OF 2
C102	DRAINAGE SWALE LAYOUT AND LONG SECTION
C103	DRAINAGE SWALE TYPICAL SECTIONS
C104	DRIVEWAY SECTIONS AND DETAILS - SHEET 1 OF 2
C105	DRIVEWAY SECTIONS AND DETAILS - SHEET 2 OF 2
C106	DRIVEWAY CULVERT SECTIONS
C200	EARTHWORKS LAYOUT PLAN - SHEET 1 OF 2
C201	EARTHWORKS LAYOUT PLAN - SHEET 2 OF 2
C202	INTEFACE LOTS EARTHWORKS PLAN
C203	INTERFACE LOTS EARTHWORKS SECTIONS AND DETAILS
C204	TEVIOT ROAD SWALE LAYOUT PLAN
C205	TEVIOT ROAD SWALE SECTIONS AND DETAILS
C206	EARTHWORKS SUBGRADE ROCK PREPARATION PLAN - SHEET 1 OF 2
C207	EARTHWORKS SUBGRADE ROCK PREPARATION PLAN - SHEET 2 OF 2
C208	EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2
C209	EARTHWORKS NOTES AND DETAILS - SHEET 2 OF 2
C300	ROADWORKS TYPICAL SECTIONS & NOTES
C301	HEDGE LANE LONGITUDINAL SECTIONS
C302	HEDGE LANE CROSS SECTIONS - SHEET 1 OF 4
C303	HEDGE LANE CROSS SECTIONS - SHEET 2 OF 4
C304	HEDGE LANE CROSS SECTIONS - SHEET 3 OF 4
C305 C306	HEDGE LANE CROSS SECTIONS - SHEET 4 OF 4 GRASS LANE LONGITUDINAL AND CROSS SECTIONS
C307	LEAF STREET LONGITUDINAL AND CROSS SECTIONS
C308	AMAZON WAY LONGITUDINAL AND CROSS SECTIONS
C309	ROAD 18 LONGITUDINAL AND CROSS SECTIONS
C310	INTERSECTION DETAILS PLAN
C311	PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 1 OF 2
C312	PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 2 OF 2
C313	ACOUSTIC FENCE DETAILS
C400	STORMWATER DRAINAGE DETAILS AND NOTES
C401	STORMWATER DRAINAGE CATCHMENT PLAN - SHEET 1 OF 2
C402	STORMWATER DRAINAGE CATCHMENT PLAN - SHEET 2 OF 2
C403	STORMWATER DRAINAGE LONG SECTIONS - SHEET 1 OF 3
C404	STORMWATER DRAINAGE LONG SECTIONS - SHEET 2 OF 3
C405	STORMWATER DRAINAGE LONG SECTIONS - SHEET 3 OF 3
C406	Q2 MINOR STORM CALCULATIONS
C407	Q100 MAJOR STORM CALCULATIONS
C408	STORMWATER STRUCTURE DETAILS
C500	SEWERAGE RETICULATION LOCALITY PLAN & NOTES
C501	SEWERAGE RETICULATION LAYOUT PLAN - SHEET 1 OF 2
C502	SEWERAGE RETICULATION LAYOUT PLAN - SHEET 2 OF 2
C503	SEWERAGE RETICULATION LONG SECTIONS - SHEET 1 OF 2
C504	SEWERAGE RETICULATION LONG SECTIONS - SHEET 2 OF 2
C505	SEWERAGE RETICULATION NOTES AND DETAILS
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C601	WATER RETICULATION LAYOUT PLAN SHEET 1 OF 2
C602	WATER RETICULATION LAYOUT PLAN SHEET 2 OF 2
C603	WATER RETICULATION DETAILS
C700	EROSION AND SEDIMENT CONTROL LAYOUT - CLEAR AND GRUB PHASE
C701	EROSION AND SEDIMENT CONTROL LAYOUT - BULK EARTHWORKS - SHEET 1
C702	EROSION AND SEDIMENT CONTROL LAYOUT - BULK EARTHWORKS - SHEET 2
C703	EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE
C704	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1
C705	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2

EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT TEVIOT ROAD, GREENBANK **FOR MIRVAC**

GENERAL NOTES

- ALL DIMENSIONS GIVEN ON THESE DRAWINGS ARE IN METRES UNLESS NOTED OTHERWISE. ALL NEW WORK AND MATERIALS SHALL
- COMPLY CURRENT RELEVANT COUNCIL STANDARDS AND SPECIFICATIONS.
- ALL WORK SHALL BE JOINED NEATLY TO EXISTING CONSTRUCTION.
- THE CONTRACTOR IS TO LOCATE. IDENTIFY AND ESTABLISH THE CONNECTIVITY OF ALL EXISTING SERVICES WITHIN THE LIMITS OF PROPOSED WORKS AND CONFIRM THIS INFORMATION WITH THE ENGINEER PRIOR TO THE
- COMMENCEMENT OF WORK.
 THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MEASURING DEVICES, SAFETY EQUIPMENT AND MACHINERY REQUIRED TO CARRY OUT
 INSPECTIONS/MEETINGS AS SPECIFIED OR
- REQUESTED BY THE ENGINEER.

 6. PROOF ROLLING NOMINATED SHALL BE CARRIED OUT USING A SINGLE AXLE HIGHWAY TRUCK WITH A REAR AXLE LOAD NOT LESS THAN 10 TONNES AND TYRES INFLATED TO 550kPa OR APPROVED EQUIVALENT. EQUIPMENT LABOUR AND LOADING REQUIRED FOR PROOF ROLLING IS TO BE PROVIDED BY THE CONTRACTOR.
- THESE NOTES SHALL APPLY TO ALL PORTIONS OF WORK.
- THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATIONS. ANY POINT OF CONFLICT WILL BE RESOLVED BY THE SUPERINTENDENT.

NOISE

1. ALL PLANT AND EQUIPMENT SHALL BE CONTROLLED TO MINIMISE NOISE EMISSION IN ACCORDANCE WITH AS2436 (GUIDE TO NOISE CONTROL ON CONSTRUCTION, MAINTENANCE AND DEMOLITION). THE SITE WORKING HOURS SHOULD BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS. WHERE NOT SPECIFIED THE HOURS SHALL BE:

MONDAY - SATURDAY 7:00am to 6:00pm SUNDAY OR PUBLIC HOLIDAY NO WORK

PRE-CONSTRUCTION & APPROVALS


- NO LOCATING/ POTHOLING OF EXISTING SERVICES HAS BEEN CARRIED OUT. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND DEPTH OF ALL EXISTING SERVICES WHICH AFFECT THE WORKS AND REPORT ANY POTENTIAL CLASHES TO THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORKS.
- THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING WITH THE APPROPRIATE AUTHORITY FOR LOCATING EXISTING SERVICES AND FOR ANY MODIFICATIONS TO EXISTING SERVICES REQUIRED AS A RESULT OF THE WORKS.
- THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL EXISTING SERVICES FROM DAMAGE.
- ANY WORKS DAMAGED AS A RESULT OF CONSTRUCTION ARE TO BE REINSTATED TO RELEVANT AUTHORITY'S REQUIREMENTS AT THE CONTRACTORS
- COST.
 FINISHED SURFACE LEVELS ARE TO BE GRADED UNIFORMLY BETWEEN LEVELS INDICATED ON THE DRAWINGS.

WORKPLACE HEALTH & SAFETY

- THE CONTRACTOR SHALL BE THE PRINCIPAL CONTRACTOR AS DESIGNATED BY THE WORK HEALTH AND SAFETY ACT (2011). THE CONTRACTOR SHALL PREPARE AND
- IMPLEMENT A WORKPLACE HEALTH AND SAFFTY PLAN AS REQUIRED BY THE WORK HEALTH AND SAFETY ACT (2011).

SETOUT NOTES

- CO-ORDINATE SETOUT PROVIDED ON THESE DRAWINGS IS BASED ON A CO-ORDINATE BASE PROVIDED BY SAUNDERS HAVILL GROUP. REFERENCE MARKS AND CORRESPONDING CO-ORDINATES ARE PROVIDED ON
- DRAWING C002.
 THE LEVEL DATUM FOR WORKS IS A.H.D (AUSTRALIAN HEIGHT DATUM).



LOCALITY PLAN

SCALE 1:5000




FOR CONSTRUCTION DATE REV DESCRIPTION



BRISBANE OFFICE

LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, OLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au







MIRVAC EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK

SHEET TITLE COVER SHEET LOCALITY PLAN & DRAWING SCHEDULE

MIR001-05 C001





DESIGN HAZARD NOTES:

- 1. PREMISE, HAVING BEEN COMMISSIONED TO CARRY OUT DETAILED DESIGN AND DOCUMENTATION OF THESE WORKS, CONFIRM THAT THE PREMISE DRAWING SET HAS BEEN INTERNALLY REVIEWED FOR DESIGN SAFETY IN ACCORDANCE WITH SECTION 22 OF THE WORK HEALTH AND SAFETY ACT 2011 OLD.
- 12. THIS REPORT SUMMARISES AN INTERNAL REVIEW OF PREMISE'S DETAILED DESIGN DRAWINGS FOR DESIGN SAFETY.

 3. THIS REPORT IN NO WAY RELIEVES THE PRINCIPAL, CONTRACTOR OR ANY OTHER PARTY OF THEIR OWN OBLIGATIONS AND RESPONSIBILITIES UNDER THE WORK HEALTH AND SAFETY ACT 2011 QLD, INCLUDING (BUT NOT LIMITED TO) CONSULTATION WITH THE DESIGNER UNDER SECTION 294 OF THE ACT, THE PREPARATION OF SATISFACTORY SAFE WORK METHOD STATEMENTS AND DUTIES
- OF CARE.

 4. IT IS A REQUIREMENT UNDER SECTION 296 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD, THAT A COPY OF THIS REPORT BE PROVIDED TO THE CONTRACTOR BY THE ENTITY COMMISSIONING THE WORK SHOWN OF THE PREMISE DRAWINGS.

 5. AS PER THE DEPARTMENT OF JUSTICE AND THE ATTORNEY-GENERAL- WORKPLACE HEALTH AND SAFETY QUEENSLAND, A WRITTEN REPORT IS NOT REQUIRED FOR DESIGNS THAT HAVE TYPICAL FEATURES.

	CONSEQUENCE TABLE	
LEVEL	CONSEQUENCE	COST/TIME
5 - CATASTROPHIC	FATALITY OR MULTIPLE PERSONS ONSITE WITH LIFE THREATENING HEALTH EFFECT OR INABILITY TO CONTINUE	HUGE FINANCIAL OR TIME LOSS
4 - MAJOR	EXTENSIVE INJURIES, OR ONSET OF SEVERE OR LIFE THREATENING HEALTH EFFECT TO SINGLE PERSON ONSITE. MULTIPLE PERSONS WITH ONSET OF IRREVERSIBLE HEALTH EFFECTS. PREMANENT INJURT TO PERSON INSITE.	MAJOR FINANCIAL OR TIME LOSS
3 - MODERATE	MEDICAL TREATMENT REQUIRED. IRREVERSIBLE HEALTH EFFECT TO A SINGLE PERSON. MULTIPLE PERSONS ONSITE WITH REVERSIBLE HEALTH EFFECTS.	HIGH FINANCIAL OR TIME LOSS
2 - MINOR	FIRST AID, SINGLE OR MULTIPLE INJURIES AMONGST PERSONS ONSITE. SINGLE PERSON ONSITE WITH MODERATE SHORT TERM REVERSIBLE HEALTH EFFECTS.	MEDIUM FINANCIAL OR TIME LOSS
1 - INSIGNIFICANT	NO INJURIES. OVER EXPOSURE TO A SINGLE PERSON ONSITE, BUT NO REPORTED HEALTH EFFECTS.	LOW FINANCIAL OR TIME LOSS

CONSTRUCTION HAZARD NOTES:

UNDER THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011, THE WORK HEALTH AND SAFETY REGULATION 2011 AND OTHER LEGISLATION AND GUIDELINES, THE PRINCIPAL CONTRACTOR HAS SPECIFIC OBLIGATIONS IN RELATION TO THE SAFE OPERATION OF THE SITE AND OF THE WORKS.

TO ASSIST THE PRINCIPAL CONTRACTOR IN COMPLYING WITH THESE OBLIGATIONS THE PROJECT DESIGNERS HAVE IDENTIFIED BY DRAWING NOTES, AREAS WHERE POTENTIAL HAZARDS MAY ARISE. THESE NOTES OR ADVICE, SHALL NOT NECESSARILY BE CONSIDERED COMPLETE AND ARE BASED UPON THE DESIGNERS' UNDERSTANDING OF THE SAFETY RISKS ASSOCIATED WITH THE

WORNS.
THESE NOTES OR ADVICE SHALL NOT RELIEVE THE PRINCIPAL CONTRACTOR OF ANY OBLIGATION UNDER THE RELEVANT LEGISLATION
OR GUIDELINE. THE PRINCIPAL CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE PREPARATION OF AN APPROPRIATE WORK HEALTH
SAFETY MANAGEMENT PLAN AND SAFE WORK METHOD STATEMENTS FOR THE SITE.

2. PURSUANT TO THE WORK HEALTH AND SAFETY ACT 2011 WE HEREBY ADVISE THAT OUR DESIGN SAFETY REVIEW HAS IDENTIFIED UNUSUAL OR ATYPICAL DESIGN FEATURES THAT MAY PRESENT ADDITIONAL HAZARDS OR RISKS DURING THE CONSTRUCTION PHASE AND THESE ARE LISTED IN THE CONSTRUCTION HAZARD SCHEDULE.

		RISI	K ANALYSI	S MATRIX		
		1 - INSIGNIFICANT	2 - MINOR	3 - MODERATE	4 - MAJOR	5 - CATASTROPHIC
	A - ALMOST CERTAIN	MODERATE	HIGH	EXTREME	EXTREME	EXTREME
Q0	B - LIKELY	MODERATE	HIGH	HIGH	EXTREME	EXTREME
LIKELIHOOD	C - POSSIBLE	LOW	MODERATE	HIGH	EXTREME	EXTREME
Ĭ	D - UNLIKELY	LOW	LOW	MODERATE	HIGH	EXTREME
	E - RARE	LOW	LOW	MODERATE	HIGH	HIGH

	RISK EVALUATION TABLE
RISK LEVEL	ACTION REQUIRED
EXTREME	UNACCEPTABLE RISK. RE-DESIGN REQUIRED. DO NOT PROCEED WITHOUT ADDITIONAL CONTROLS.
HIGH	UNACCEPTABLE RISK. ADDITIONAL CONTROLS NEEDED. CONSIDER FURTHER REVIEW AND CONSIDER RE-DESIGN
MODERATE	RISK MAY BE ACCEPTABLE. MANAGEMENT TO DETERMINE ACTIONS REQUIRED
LOW	ACCEPTABLE. MANAGE RISK THROUGH ROUTINE PROCEDURES AND OTHER ADMINISTRATIVE CONTROLS

	LIKELIHOOD TABLE	
LEVEL	DESCRIPTION	QUANTIFICATION GUIDE
A - ALMOST CERTAIN	THE EVENT IS EXPECTED TO OCCUR IN MOST CERTAIN CIRCUMSTANCES	MORE THAN ONCE PER YEAR
B - LIKELY	THE EVENT WILL PROBABLY OCCUR IN MOST CIRCUMSTANCES	AT LEAST ONCE IN 5 YEARS
C - POSSIBLE	THE EVEN T SHOULD OCCUR AT SOME TIME	AT LEAST ONCE IN 10 YEARS
D - UNLIKELY	THE EVENT COULD OCCUR AT SOME TIME	AT LEAST ONCE IN 30 YEARS
E - RARE	THE EVENT MAY OCCUR IN EXCEPTIONAL CIRCUMSTANCES	LESS THAN ONCE IN 30 YEARS

FOR	C	ONSTRUCT	ION	
15/11/19	Α	ORIGINAL ISSUE	MM	JS
DATE	REV	DESCRIPTION	REC	APP
			REVISIONS	



BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222


	DESIGNED		SCALE	
	M. MAJZNER			
	CHECKED		1	
	J. STONE			
	PROJECT COORDINATOR		ĺ	
	C. THORP			
	PROJECT CERTIFIER			
		15/11/19		
	JOSHUA STONE	RPEQ 15187		ORIGINAL SHEET SIZE A1
_				


MIRVAC	JOB CODE
EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT	MIR001-
TEVIOT ROAD, GREENBANK	SHEET NUMBER
SAFETY IN DESIGN PLAN	C004
	EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT TEVIOT ROAD, GREENBANK


-05

	DESIGN HAZARD SCHEDULE							
ITEM	DESIGN HAZARD		RISK	ELIMINATION / MINIMISATION OF HAZARD / RISK	RESIDUAL RISK			
D1	URBAN LAYOUT HAZARD	THE URBAN LAYOUT IS DESIGNED AROUND A PARTICULAR HAZARD: - INTERSECTION IS UNCLEAR WHICH ROAD HAS PRIORITY	HIGH	THE HAZARD HAS BEEN REDUCED/ELIMINATED BY: LINE MARKED INTERSECTION TO ENSURE IT IS CLEAR WHICH ROAD HAS PRIORITY - DESIGN VEHICLE SWEPT PATH CHECKED FOR COMPLIANCE	LOW			
D2	EXISTING UNDERGROUND / OVERHEAD SERVICES HAZARD	EXISTING UNDERGROUND AND/OR OVERHEAD SERVICES HAZARD EXIST ON SITE AND NEEDS TO BE REMOVED AND RELOCATED.	HIGH	THE DESIGN OF THE PROJECT HAS INCORPORATED THE RELOCATION OF THESE EXISTING SERVICES AND THE CONTRACTOR IS TO BE MADE AWARE OF THESE EXISTING SERVICES AND TAKE ALL ACTIONS NECESSARY TO MITIGATE THIS HAZARD DURING CONSTRUCTION.	MEDIUM			
D3	DEEP EXCAVATION HAZARD	DEEP EXCAVATION IS REQUIRED TO INSTALL SEWER TO SERVICE STRUCTURE.	HIGH	THE DEEP EXCAVATION HAZARD CANNOT BE AVOIDED AND THE CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEDIUM			
D4	HIGH RETAINING WALLS	SOME AREAS OF WORKS CONTAIN HIGH RETAINING WALLS WHERE LAND MORPHOLOGY DICTATES.	HIGH	HIGH RETAINING WALLS CANNOT BE AVOIDED DUE TO EXISTING LAND MORPHOLOGY. SINGLE TIER WALLS HAVE LIMITED TO A MAX HEIGHT OF 2m. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEIDUM			
D5	WATER BODIES	PROPOSED CONSTRUCTION WATER DAMS WILL BE PRESENT ON SITE.	MEDIUM	PROPOSED WATER BODIES HAVE BEEN LOCATED AWAY FROM PUBLIC ACCESS AREAS. ACCESS TO THESE LOCATION WILL BE RESTRICTED FROM THE PUBLIC. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	LOW			


		CONSTRUCTION HAZARD SCHEDULE
ITEM	POTENTIAL HAZARD	POSSIBLE PREVENTATIVE ACTION
C1	DEEP EXCAVATION HAZARD	ALL STEPS MUST BE TAKEN TO OBTAIN CURRENT UNDERGROUND SERVICES INFORMATION BEFORE EXCAVATION WORKS COMMENCE. EXCAVATION WORK MUST BE UNDERTAKEN BY APPROPRIATELY EXPERIENCED AND QUALIFIED PERSONNEL. EXCAVATIONS SHALL BE ADEQUATELY SHORED AND APPROPRIATE BARRICADES AND SIGNAGE ERECTED, IF REQUIRED.
C2	OVERHEAD POWER HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF LIVE OVERHEAD CABLES. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING EARTHWORKS AND ANY OTHER HIGH RISK WORKS, IF REQUIRED.
C3	122200111101110111, 071371110 11711211	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF THE EXISTING SERVICE. THE SERVICE SHALL BE IDENTIFIED AND MARKED BY THE SUPPLY AUTHORITY PRIOR TO THE COMMENCEMENT OF EXCAVATION. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING THE EXCAVATION WORK, IF REQUIRED.
C4		ALL REQUIRED PERMITS, APPROVALS AND SAFETY REQUIREMENTS FROM THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHALL REMAIN ON SITE DURING CONSTRUCTION WHILE THE HAZARD REMAINS.
C5	PEDESTRIAN ACCESS HAZARD	WORK WITHIN OR ADJACENT TO AREAS WHICH THE PUBLIC REQUIRES PEDESTRIAN ACCESS MUST HAVE APPROPRIATE BARRICADES AND SIGNAGE ERECTED AT ALL TIMES.
C6	POTENTIAL VEHICLE HAZARD	SITE PERSONNEL SHALL BE ADVISED OF THE POTENTIAL HAZARDS AND THE APPROPRIATE PROCEDURES FOR WORKING ADJACENT TO OPERATING PUBLIC ROADS. APPROPRIATE SAFETY CLOTHING SHALL BE WORN AND THE REQUIRED SIGNAGE SHALL BE ERECTED. THE WORKS SHALL BE UNDERTAKEN IN A MANNER WHICH DOES NOT COMPROMISE THE SAFETY OF THE VEHICLE OCCUPANTS OR THE SITE PERSONNEL.
C7	DEMOLITION AND CLEARING HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE DEMOLITION AND CLEARING WORKS FOR THE PROJECT AT ALL TIMES. THE CONTRACTORS WORK METHOD STATEMENT SHALL ALSO GIVE CONSIDERATION TO FALLING DEBRIS, COLLAPSE AND DANGEROUS AIRBORNE AGENTS.
C8	TRAFFIC MANAGEMENT HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC THROUGH THE PROJECT AT ALL TIMES. THE CONTRACTOR SHALL DEVELOP A TRAFFIC MANAGEMENT PLAN (TMP) FOR THE PROJECT TO ESTABLISH APPROPRIATE CONTROLS IN ACCORDANCE WITH THE MANUAL FOR UNIFORM TRAFFIC CONTROL.
С9	ASBESTOS HAZARD	ALL PERSONNEL SHOULD BE ADVISED OF THE POTENTIAL PRESENCE OF ASBESTOS AND AN IDENTIFICATION AND ACTION PLAN SHALL BE PUT IN PLACE. SAMPLING AND IDENTIFICATION IS TO BE UNDERTAKEN IN ACCORDANCE WITH WORKPLACE HEALTH AND SAFETY REGULATIONS. IF SAMPLING CONFIRMS THE PRESENCE OF ASBESTOS THEN THE ACTION PLAN IS TO BE IMPLEMENTED TO REMEDIATE THE SITE.
C10	POTENTIAL ROCK FALL	LAND ABOVE THE SITE HAS BEEN CLEARED AND SOME EARTHWORKS HAS BEEN UNDERTAKEN CREATING A POTENTIAL ROCK FALL HAZARD. SUITABLE PERSONNEL SHALL BE RESPONSIBLE FOR IDENTIFYING ANY POTENTIAL HAZARD AND THE CONTRACTOR SHALL TAKE APPROPRIATE ACTION TO ELIMINATE THE HAZARD.














TYPICAL DRAINAGE SWALE SECTION CH0.00 TO CH17.5





TYPICAL DRAINAGE SWALE SECTION CH17.5 TO CH22.5 NTS




TYPICAL DRAINAGE SWALE SECTION CH22.5 TO CH58.5 NTS









						_		
FOR CONSTRUCTION		BRISBANE OFFICE	M. MAJZNER		SCALE	CLIENT	JOB CODE	
		LEVEL 1, 100 BRUNSWICK STREET PO BOX 361	P. BRADY PROJECT COORDINATOR		NTS	PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT	MIR001-0	05
29/05/20 B ADDED 0100 WATER LEVEL AND ADDED WIDTHS MM PB		FORTITUDE VALLEY, QLD 4006	C. THORP PROJECT CERTIFIER			LOCATION TEVIOT ROAD, GREENBANK	SHEET NUMBER F	REV
15/11/19 A ORIGINAL ISSUE MM JS DATE REV DESCRIPTION REC APP	Premise	PH: (07) 3253 2222 WEB: www.premise.com.au	PAT BRADY	29/05/20 RPEO 7112		SHEET TITLE DRAINAGE SWALE TYPICAL SECTIONS	C103	В
REVISIONS		0	PAT DRAUT	KPEŲ /112	ORIGINAL SHEET SIZE A1			







CULVERT	DETAILS
CULVERT SIZE AND CLASS	600x300 RCBC CLASS B2
LENGTH	7.32m
USIL	53.294
DSIL	53.104
DESIGN FLOW (+20% BLOCKAGE FACTOR)	Q _{max} : 0.210637
VELOCITY	2.3501m/s
HEADWATER DEPTH (Q ₁₀₀)	53.6890m
TAILWATER DEPTH (Q ₁₀₀)	53.2534m



CULVER1	Γ DETAILS
CULVERT SIZE AND CLASS	600x300 RCBC CLASS B2
LENGTH	9.76m
USIL	52.565
DSIL	52.516
DESIGN FLOW (+20% BLOCKAGE FACTOR)	Q _{max} : 0.313867
VELOCITY	1.7439m/s
HEADWATER DEPTH (Q ₁₀₀)	53.1533m
TAILWATER DEPTH (Q ₁₀₀)	52.8160m



CULVERT DETAILS					
CULVERT SIZE AND CLASS	2 x 900x300 RCBC CLASS B2				
LENGTH	9.76				
USIL	51.645				
DSIL	51.596				
DESIGN FLOW (+20% BLOCKAGE FACTOR)	Q _{max} : 0.606260				
VELOCITY	1.5138m/s				
HEADWATER DEPTH (Q ₁₀₀)	52.0306m				
TAILWATER DEPTH (Q ₁₀₀)	51.8185m				



FOR	C	ONSTRUCTION		
29/05/20	В	AMENDED CULVERT DETAILS AND CULVERT SECTIONS	MM	PB
15/11/19	Α	ORIGINAL ISSUE	MM	JS
DATE	REV	DESCRIPTION	REC	APP
		REVISIONS		





BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 Premise PH: (07) 3253 2222
WEB: www.premise.com.au


DESIGNED		SCALE	
M. MAJZNER			
CHECKED			
P. BRADY		0	0.5
PROJECT COORDINATOR			
C. THORP			SCALE 1:2
PROJECT CERTIFIER			50,122 1.2
PG)	29/05/20		
PAT BRADY	RPEO 7112		00150111 51155
TAT DIGIDT	III LQ 7112		ORIGINAL SHEE


SCALE			
0	0.5	1.0	1.5m
		_	
	SCALE 1	L:25 (A1)	
	SCALE 1	L:25 (A1)	
	SCALE 1	L:25 (A1)	
	SCALE 1	1:25 (A1)	


MIRVAC MIR001-05 PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK C106 SHEET TITLE DRIVEWAY CULVERT SECTIONS




















NOTES

- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- EARTHWORKS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH DRAWING COO1, EROSION AND SEDIMENT CONTROL LAYOUT PLANS AND EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
 ALL EARTHWORKS TO BE CARRIED OUT UNDER 'LEVEL ONE' GEOTECHNICAL
- CONTROL IN ACCORDANCE WITH LOCAL AUTHORITIES AND AS3798.
 EXCESS CUT TO BE STOCKPILED IN THE LOCATION SHOWN OR AS DIRECTED
- ALL BATTERS ARE 1 IN 4 UNLESS SHOWN OTHERWISE.
- CONTRACTOR TO INSTALL TEMPORARY CONSTRUCTION FENCING ALONG THE FULL PERIMETER BOUNDARY INCLUDING APPROPRIATE SIGNAGE.

TESTING

THE SUPERINTENDENT MAY ORDER ADDITIONAL TESTS. REFER TO THE LOCAL AUTHORITIES SPECIFICATION FOR STANDARDS OF COMPACTION AND MATERIAL STANDARDS.

EARTHWORKS TESTING

COMPACTION TESTS

LOCATION	AREA PER TEST
FINISHED LEVEL OR ROAD SUBGRADE (IN CUT OR FILL)	
LOWEST TWO LEVELS OF EMBANKMENT (PER LAYER)	REFER TO THE LOCAL AUTHORITY
OTHER LAYERS OF EMBANKMENT	SPECIFICATION
PREPARED NATURAL GROUND UNDER EMBANKMENT	

QUALITY TESTS QUALITY TESTS OF IMPORTED MATERIAL ARE REQUIRED AS SET OUT BY LOCAL AUTHORITY.

THE NUMBER AND LOCATION OF PAVEMENT SUBGRADE TESTS SHALL BE AS DETERMINED BY THE SUPERINTENDENT WHO SHALL RECOMMEND CBR VALUES TO BE USED IN ROAD PAVEMENT DESIGN. THE NUMBER AND TYPES OF CBR TESTS SHALL BE DETERMINED BY THE SOILSTESTING CONSULTANT TO BEST REPRESENT THE CONDITION OF THE SUBGRADE EXPECTED IN SERVICE.

DUST

- NO VISIBLE DUST EMISSIONS MUST OCCUR AT THE BOUNDARIES OF THE SITE DURING FARTHWORKS AND CONSTRUCTION ACTIVITIES ON THE SITE DUST CONTROL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH AS/N7S3580.10.1:2003. DUST CONTROL SHALL COMPLY WITH THE NSW DEPARTMENT OF ENVIRONMENT AND CONSERVATION REPORT "APPROVED METHODS & GUIDANCE FOR THE MODELLING AND ASSESSMENT OF AIR
- THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN CONTROLS TO ACHIEVE THE REQUIREMENTS OF ITEM 1 ABOVE.

THE CONTRACTOR IS TO CONFIRM THE LOCATION OF SERVICE CONDUITS WITH THE SUPERINTENDENT PRIOR TO LAYING

FILL MANAGEMENT

- ALL FILL MATERIAL WILL BE PLACED IN ACCORDANCE WITH THE SPECIFICATION SET OUT IN THE GEOTECHNICAL REPORTS TITLED "RECOMMENDATIONS FOR FILLING OPERATIONS AND THE USE OF SILT FROM THE LOWER DAM" AND "RECOMMENDED FILLING EARTHWORKS
- SPECIFICATION" PREPARED BY MORRISON GEOTECHNIC DATED 28 JUNE 2019. THE FILL MATERIAL WILL COMPRISE ONLY OF NATURAL EARTH AND ROCK AND SHALL BE FREE OF ALL CONTAMINATES, NOXIOUS, HAZARDOUS, DELETERIOUS AND ORGANIC MATERIAL.
- ALL SITE PREPARATION WORK SHOULD GENERALLY BE CARRIED OUT IN ACCORDANCE WITH AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS'.
 THE SITE SHOULD BE STRIPPED OF ANY TOPSOIL FROM CUT AND FILL AREAS.
- ROAD ALIGNMENTS AND CARPARKING AREAS, AND STOCKPILED FOR LATER
- PRIOR TO THE PLACEMENT OF ANY STRUCTURAL FILL THE SITE SHOULD BE PROOF ROLLED USING A MINIMUM 10 TONNE (STATIC WEIGHT) PADEOOT ROLLER. ANY LOOSE OR SOFT AREAS SHOULD BE REMOVED AND RECOMPACTED OR REPLACED USING A COMPACTED SELECT FILL
- DEPRESSIONS FORMED BY THE REMOVAL OR VEGETATION, EXISTING STRUCTURES, UNDERGROUND SERVICES ETC, SHOULD HAVE ALL DISTURBED SOIL CLEANED OUT AND BE BACKFILLED WITH COMPACTED SELECT FILL
- THE PLACEMENT OF ALL STRUCTURAL FILL TO BE INSPECTED, TESTED AND CERTIFIED BY A GEOTECHNICAL ENGINEER TO A LEVEL 1 REQUIREMENT DURING THE EARTHWORKS OPERATIONS TO ENSURE THAT ALL FILL IS PLACED IN A 'CONTROLLED MANNER', IN ACCORDANCE WITH AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS'.
- ALL COMPLIANCE TESTING SHALL BE CARRIED OUT BY THE CLIENT'S GEOTECHNICAL ENGINEER AND SHALL BE ARRANGED THROUGH THE SUPERINTENDENT, ABY/ALL TESTING NECESSARY FOR GUIDANCE OR RE-TESTS WILL BE AT THE COST OF THE CONTRACTOR.
- THE PLACEMENT OF FILL TO BE EXECUTED SUCH THAT TO BE FREE DRAINING AT ALL TIMES AND NOT TO BE A NUISANCE OR PONDING TO ADJOINING PROPERTY OR ROADS
- NO DEMOLITION MATERIAL TO BE USED AS FILL MATERIAL
- WHERE UNSUITABLE MATERIAL IN AREAS OF FILL IS ENCOUNTERED, THIS WILL BE TREATED AS SET OUT IN THE EARTHWORK SPECIFICATION.
- ALL VEHICLES EXITING FROM THE SITE TO BE CLEAN TO PREVENT MATERIAL BEING TRACKED OR DEPOSITED ON THE ADJOINING PUBLIC ROADS, REFER ENVIRONMENTAL MANAGEMENT NOTES ON DRG. No. C701.
- ACCESS TRACKS THROUGH THE SITE WILL BE LIMITED TO THOSE DETERMINED BY THE SUPERINTENDENT AND THE CONTRACTOR PRIOR TO ANY WORK COMMENCING.

TOPSOIL RESPREAD REQUIREMENTS

TOPSOIL RESPREAD THICKNESS SHALL BE AS SPECIFIED BELOW IN THE FOLLOWING

REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TOPSOIL RESPREAD LOCATIONS AND THICKNESS.

CONTRACTOR SHALL SUPPLY AND LAY TURF AS SPECIFIED IN THE FOLLOWING

REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TURF SUPPLY AND LAY AREAS.

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM

AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS. AND SHALL BE FREE DRAINING

EXCAVATION IN ROCK

CONTRACT SHALL INCLUDE TREATING SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNIC REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

EVERLEIGH EARTHWORKS TOLERANCE TABLE

ITEM	TOLERANCE
EARTHWORKS IN ALLOTMENTS AND VERGES ^(a)	EWL or FSL +/- 50mm
CUT BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 150mm ^(b)
FILL BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 300mm ^(b)
EARTHWORKS IN PARKS	EWL or FSL +/- 50mm

(a) TOLERANCE IS -0mm / +50mm WHERE ADJACENT DRAINAGE ELEMENT.


MEASURED FROM THE AVERAGE SLOPE PLANE.

- 1. EARTHWORKS LEVEL (EWL) IS 100mm BELOW FINISHED SURFACE LEVEL
- 2. FINISHED SURFACE LEVEL (FSL) IS TOP OF TURF / STABILISED TOPSOIL LEVEL.
- 3. ROADWORKS SUBGRADE, PAVEMENT, ASPHALT CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
- 4. STORMWATER DRAINAGE CONSTRUCTION LEVEL TOLERANCES AS PER LCC
- 5. SEWER AND WATER RETICULATION CONSTRUCTION LEVEL TOLERANCES AS
- PER SEQ D&C CODE.


DISPERSIVE SOILS MANAGEMENT NOTES

- 1. STABILISATION OF DISTURBED AREAS AND MANAGEMENT OF EROSION AND SEDIMENT SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLANS IN THIS DRAWING SET.
- 2. CONTRACTOR MUST CONSTRUCT AND ESTABLISH THE EROSION AND SEDIMENT CONTROL DEVICES, CONSTRUCTION WATER HOLDING DAM AND HES BASIN PRIOR TO COMMENCING EARTHWORKS OPERATION.


 3. ALL DISTURBED AREAS SHALL BE STABILISED AS SOON AS PRACTICABLE (BUT
- NOT MORE THAN 10 DAYS) FOLLOWING FINALISATION OF LEVELS.
 STABILISATION TO BE IN ACCORDANCE WITH DRAWING C405 EROSION & SEDIMENT CONTROL - STABILISATION PHASE



BATTERS BETWEEN LOTS SCALE 1:20



TYPICAL SUBSOIL DRAIN **UNDER SWALES DETAIL**






BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au

. MAJZNER THORD 15/11/19 RPEQ 15187

NTS

MIRVAC PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2

MIR001-05 C208



NOTES

- 1. ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARD DRAWINGS AND METHODS (U.N.O.).
- NOTWITHSTANDING THE LIMITS OF CUTTING AND FILLING SHOWN ON THE DRAWINGS, THE ACTUAL LIMITS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT DURING CONSTRUCTION AND SIMILARLY THE FINISHED SURFACE CONTOURS MAY BE ADJUSTED BY WRITTEN DIRECTION OF THE SUPERINTENDENT DURING CONSTRUCTION.
- THE CONTRACTOR IS TO ASCERTAIN THE EXACT LOCATION OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE COST OF RECTIFICATION OF ANY DAMAGES TO EXISTING SERVICES WHICH MAY OCCUR. THE LOCATION OF EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY
- SUBGRADE TEST RESULTS TO BE FORWARDED TO SUPERINTENDENT FOR DETERMINATION OF BOX DEPTHS PRIOR TO EXCAVATION. TESTS SHALL INCLUDE SOAKED CBR AND/OR OTHER TESTS AS REQUESTED BY THE SUPERINTENDENT.
- ALLOTMENT FILLING TO BE COMPACTED TO 95% (min) OF THE R.D.D. (AS 1289 TESTS E1.1, E4.1). LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.
- LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS APPROVED BY THE SUPERINTENDENT TO ACHIEVE SATISFACTORY CONNECTION TO THE EXISTING WORKS.
- SIDE DRAINS AND MITRE DRAINS TO BE CONSTRUCTED ADJACENT TO ALL KERB AND CHANNEL
- PROVIDE FLUSH POINTS TO SUBSOIL DRAINS, LOCATIONS TO BE CONFIRMED ON SITE.
- ALL STORMWATER PIPES SHALL BE CLASS 12' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION. ALL PIPES ARE 375mm DIAMETER U.N.O.
- 11. GULLIES AND GULLY GRATES SHALL BE TO STD, DRGs BSD-8051 BSD-8059.

 12. KACEY GALV. STEEL KERB ADAPTORS ARE TO BE INSTALLED TO THE REQUIREMENTS OF THE LOCAL COUNCILS STANDARD DRAWINGS AND SPECIFICATIONS.
- 13. ALL LOTS SHOWN BOXED TO HAVE ROOFWATER FOOTPATH CROSSINGS TO KERB. CROSSINGS ARE TO BE 88.9 DIA. GALV. CHS.TO KACEY KERB ADAPTOR.
- 14 ALL TEMPORARY ROOFWATER OLITLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE
- 15. ROOFWATER PITS ARE TO BE 600mm DIAMETER FOR DEPTHS LESS THAN 750mm, 900mm DIAMETER FOR DEPTHS BETWEEN 750mm AND 1500mm DEEP AND 1050mm DIAMETER FOR DEPTHS GREATER
- ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- 17. HAZARD MARKERS (D4-4A) TO BE PLACED AT THE END OF NEW WORKS AS DIRECTED BY
- 18. SITE CBR VALUE AND PAVEMENT DESIGN AND DEPTHS TO BE VERIFIED WITH CBR TESTS PRIOR TO CONSTRUCTION.
- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 20. TO BE READ IN CONJUNCTION WITH ALL STORMWATER DRAINAGE LAYOUT PLANS & ROADWORKS

ROADWORKS NOTES

- GEOTECHNICAL TESTING FOR PAVEMENT CONSTRUCTION IS TO BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT SPECIFICATION. TEST CERTIFICATES ARE TO BE PREPARED BY A REGISTERED N.A.T.A. LABORATORY AT THE CONTRACTORS COST AND SHALL BE PROVIDED TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS. THE CONTRACTOR IS TO NOTIFY THE ENGINEER OF ANY NON-CONFORMANCES.
- ALL NON CONFORMING WORK IS TO BE RECTIFIED AS DIRECTED BY THE ENGINEER. FULL DEPTH PAVEMENT CONSTRUCTION SHALL EXTEND BEHIND ALL KERB AND KERB AND CHANNEL FOR A DISTANCE WHICH IS THE GREATER OF 150mm FROM THE BACK OF KERB OR ACROSS TO THE OUTER LIMIT OF SIDE DRAIN FILTER MATERIAL.
- TRANSITION KERB AND CHANNEL TO BARRIER KERB SMOOTHLY OVER MIN. 1.0m LENGTH.
 PAVEMENT THICKNESSES NOMINATED ON THESE DRAWINGS ARE PROVISIONAL ONLY AND MAY BE
- VARIED BY THE SUPERINTENDENT SUBJECT TO INSITU PAVEMENT SUBGRADE TESTING, PAVEMENT SUBGRADES ARE TO BE INITIALLY CONSTRUCTED TO THE UNDERSIDE OF THE NOMINATED LOWER SUBBASE COURSE WITHIN FILL AREAS, AND TO THE UNDERSIDE OF THE NOMINATED UPPER SUBBASE COURSE WITHIN CUT AREAS. INSITU SUBGRADE CBR TESTING AS SPECIFIED FOR PAVEMENT DESIGN VERIFICATION IS TO BE CARRIED OUT AT THESE LEVELS.
- REPAIR ANY DAMAGE TO EXISTING KERB AND CHANNEL FOOTPATH OR ROADWAY (INCLUDING REMOVAL OF CONCRETE SLURRY FROM FOOTPATHS, ROADS, KERB AND CHANNEL AND STORMWATER GULLIES AND SIDEDRAINS) THAT MAY OCCUR DURING ANY WORKS CARRIED OUT.

CONCRETE PAVEMENT

- THE CONCRETE PAVEMENT HAS BEEN DESIGNED BASED ON A CBR 5 AND IS SUBJECT TO CONFIRMATION UPON RECEIPT OF CBR TEST RESULT AT TIME OF CONSTRUCTION.
- CONCRETE PAVEMENT SPECIFICATION:

FOR CONSTRUCTION

REV DESCRIPTION


COMPRESSIVE STRENGTH: 25 MPa @ 28 DAYS 3.5 MPa @28 DAYS MAXIMUM AGGREGATE SIZE: 20mm

MESH: SL72, 50 TOP COVER BEDDING: 100mm MIN CBR 15 BEDDING


- MATERIALS AND WORKMANSHIP SHALL COMPLY WITH AS1379, AS3600 AND AS3610.
- PROJECT ASSESSMENT OF STRENGTH IN ACCORDANCE WITH AS3600 SHALL BE ADOPTED FOR SAMPLING AND TESTING. THE CONTRACTOR SHALL PAY ALL TESTING COSTS.
- CONSTRUCTION JOINTS SHALL BE MADE ONLY AT APPROVED LOCATIONS.
 ALL JOINTS ARE TO BE SEALED JUST PRIOR TO HANDOVER WITH DOW CORNING '888' SEALANT INSTALLED IN ACCORDANCE WITH MANUFACTURING RECOMMENDATIONS.
- IOINTS ARE TO BE INSPECTED AND SEALANT REGULARLY REPLACED IF REQUIRED.
- DIMENSIONAL TOLERANCES OF AS3600, MODIFIED BY AS3610, SHALL APPLY UNLESS OTHERWISE NOTED. SLAB SURFACE FLATNESS TOLERANCE SHALL BE 5mm MAXIMUM DEVIATION FOR A 3m STRAIGHT FDGE.
- CONCRETE PAVEMENTS ARE TO BE BROOM FINISHED. SLAB THICKNESSES NOTED ARE EXCLUSIVE OF APPLIED FINISHES
- 10. CURE ALL CONCRETE BY AN APPROVED METHOD FOR 7 DAYS AFTER HARDENING. PVA AND RESIN BASED CURING COMPOUNDS SHALL NOT BE USED.

CONCRETE PAVEMENT MAINTENANCE NOTES


- NOTE THAT UPKEEP AND REPLACEMENT OF SEALANTS IS PART OF THE ONGOING MAINTENANCE
- NOTE THAT SHRINKAGE CRACKS OF WIDTH < 1.5mm MAY OCCUR IN CONCRETE PAVEMENTS WITHIN 12
- NOTE THAT THE PAVEMENT WILL NOT BE MAINTENANCE FREE FOR ITS DESIGN LIFE.
- INSPECT FLUSH SIDE DRAINS AND SUBSOIL DRAINS EVERY 12 MONTHS




SAWCUT JOINT (S.J.)




TYPICAL PAVEMENT CUT-BACK DETAIL





NOTE: REFER LAYOUT PLAN FOR TRANSITION RECESS & KERB END LOCATIONS & LENGTHS

TYPICAL KERB RECESS / END DETAIL



CONCRETE REQUIREMENTS


ITEM	28 DAY STRENGTH	CONCRETE CYLINDER TEST	TESTING FREQUENCY
KERB & CHANNEL	N32	REQUIRED	1 TEST PER 300m
VEHICULAR CROSSINGS	N25	REQUIRED	1 TEST PER CROSSING
BIKEWAYS	N25	REQUIRED	1 TEST PER 300m
FOOTPATHS	N25	REQUIRED	1 TEST PER 300m
CONCRETE CHANNELS	N25	REQUIRED	1 TEST PER 150m ²
STRUCTURES	AS DESIGN	REQUIRED	AS DIRECTED
ROOFWATER MH'S	N20	NOT REQUIRED	
STORMWATER MH'S	N25	NOT REQUIRED	
PRECAST MANHOLE ROOF SLABS	N40	NOT REQUIRED	
GULLY PITS			
PRECAST LINTEL	N30	NOT REQUIRED	
OTHER	N25	NOT REQUIRED	





BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au


. MAJZNER THORD NTS 15/11/19 RPEQ 15187


MIRVAC MIR001-05 PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK C300 FROADWORKS TYPICAL SECTIONS & NOTES





















1178 1179 1191 1178 1191



LEGEND

FINISHED MAJOR CONTOURS (0.5m)

FINISHED MINOR CONTOURS (0.1m)

PROPOSED 1.5m WIDE CONCRETE FOOTPATH. (UNO)
REFER CONC. REQUIREMENTS ON DRG. No. C300

PROPOSED KERB RAMP.
REFER IPWEA STD DWG RS-090.

PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.

LIP OF KERB LEVEL

TRANSITION IN KERB AND CHANNEL TYPE

PROPOSED STORMWATER

PROPOSED SEWER

PROPOSED WATER

EXISTING - LEGEND


— — D — — D — EXISTING STORMWATER
 — — S — — S — EXISTING SEWER
 — — W — — W — EXISTING WATER
 — — E — — E — EXISTING ELECTRICAL
 — — T — — T — EXISTING TELSTRA
 — — G — — G — EXISTING GAS
 — — RM — — RM — EXISTING SEWER RISING MAIN


FOR CONSTRUCTION		BRISBANE OFFICE	M. MAJZNER		SCALE	CLIENT MIRVAC
		LEVEL 1, 100 BRUNSWICK STREET PO BOX 361	P. BRADY PROJECT COORDINATOR		-	PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT
77000		FORTITUDE VALLEY, QLD 4006	C. THORP PROJECT CERTIFIER		0 5 10 15m	LOCATION TEVIOT ROAD, GREENBANK
23/06/20 B AMENDED ROAD NAME MM PB 15/11/19 A ORIGINAL ISSUE MM JS DATE REV DESCRIPTION REC APP	Premise	PH: (07) 3253 2222 WEB: www.premise.com.au	PE	23/06/20	SCALE 1:250 (A1)	SHEET TITLE INTERSECTION DETAILS PLAN
REVISIONS			PAT BRADY	RPEQ 7112	ORIGINAL SHEET SIZE A1	


NOTE
LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.

MIR001-05

C310









REFER TO DRAWING C311 FOR NOTES AND LEGEND

FOR	C(ONSTRUCTION			
					4
23/06/20	В	AMENDED ROAD NAME	ММ	PB	
15/11/19	Α	ORIGINAL ISSUE	MM	JS	Drei
DATE	REV	DESCRIPTION	REC	APP	LIE
		REVISIONS			4


LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 MEB: www.premise.com.au

SNED		SCALE		
/AJZNER				
KED				
RADY				
ECT COORDINATOR				
HORP		0	10	20
ECT CERTIFIER		1 —	10	20
HO	23/06/20		SCALE 1:	500 (A1)
BRADY	RPEQ 7112		ORIGINAL SH	IEET SIZE A1
		•		

CLIENT	MIRVAC
PROJECT	EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 2 OF 2

MIR001-05

C312



STORMWATER DRAINAGE NOTES


- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE STORMWATER DRAINAGE DRAWINGS
- 2. STORMWATER DRAINGS DRAWINGS

 2. STORMWATER PITS ARE TO BE CONSTRUCTED INSITU IN ACCORDANCE WITH DRAWINGS OR AS VARIED AS NOTED ON THE DRAWING. PREFABRICATED STORMWATER PITS CAN BE USED SUBJECT TO WRITTEN APPROVAL FROM THE SUPERINTENDENT. CLASS D HEAVY DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN TRAFFIC AREAS, CLASS B LIGHT DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN LANDSCAPE AREAS UNLESS NOTED OTHERWISE.
- ALL DRAINAGE EXCAVATION AND CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3500 AND THE APPLICABLE LOCAL AUTHORITY SPECIFICATIONS AND STANDARD DETAILS.
- AUTHORITY SPECIFICATIONS AND STANDARD DETAILS.
 4. ALL MATERIALS SHALL MEET THE REQUIREMENTS OF AS1254 & AS1372
- AS1273.

 ALL upVC PIPES SHALL BE CLASS 'SN8' FOR Ø150 & Ø225, AND CLASS 'SN8' FOR Ø150 & Ø225, AND CLASS
- 'SN6' FOR Ø100 UNLESS NOTED OTHERWISE.
 6. PIPES SHALL BE LAID AT MIN. 1% GRADE UNLESS NOTED OTHERWISE.
- 7. CONTRACTOR MUST VERIFY THAT ALL PIPE LEVELS AND GRADES CAN
 BE ACHIEVED PRIOR TO CONSTRUCTING DRAIN LINES. ANY CONFLICT
 SHALL BE REPORTED TO THE SUPERINTENDENT FOR ANY NECESSARY
 ALTERATIONS PRIOR TO ANY CONSTRUCTION OF CONNECTING
- PIPEWORK.

 8. WHERE PIPES ARE TO BE LAID WITHIN THE ZONE OF INFLUENCE OF STRUCTURAL LOADINGS (e.g., BUILDING FOOTINGS, RETAINING WALLS...etc) THE BUILDER SHALL PROVIDE ADEQUATE BRIDGING / PROTECTION. WHERE ANY DOUBT MAY EXIST REFERENCE SHALL BE MADE TO THE DESIGNER OF THE STRUCTURE.
- BENCHING OF PIT STRUCTURES SHALL HAVE A SMOOTH FINISHED SURFACE, AND PIPES SHALL NOT PROJECT INSIDE THE SHAFT OF THE STAFF OF THE SHAFT OF THE
- WHERE RECTANGULAR PIT STRUCTURES ARE USED, PIPES MUST NOT CONNECT TO THE PIT AT CORNERS.
- ALL CONSTRUCTION AND EXCAVATIONS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT REQUIREMENTS OF THE WORK HEALTH AND SAFETY ACT 2011 AND SUBSEQUENT AMENDMENTS.
- HEALTH AND SAFETY ACT 2011 AND SUBSEQUENT AMENDMENTS.

 12. REFER TO LCC STD DWG'S FOR TYPICAL ROOF SLAB REINFORCEMENT
 PETALS.





TYPICAL ROOFWATER KERB ADAPTOR OUTLET DETAIL

N.T.S.

REFERENCE POINT LOCATION FOR DRAINAGE STRUCTURES


STRUCTURE TYPE	HORIZONTAL CONTROL POINT [REFERENCE POINT LOCATION]	VERTICALCONTROL REFERENCE LEVEL	
MANHOLE	CENTRELINE OF MAIN SHAFT	FINISHED SURFACE LEVEL AT CENTRE OF MAIN SHAFT.	
GULLY PIT OVER MANHOLE	CENTRE OF GULLY PIT	LIP LEVEL	
GULLY PIT (LIP IN LINE)	CENTRE OF GULLY PIT	LIP LEVEL	
HEADWALL	INTERSECTION OF HEADWALL FACE AND PIPE CENTRE LINE	INVERT LEVEL	
FIELD INLET	CENTRE OF PIT	TOP OF CONCRETE PIT	
ROOFWATER PIT	CENTRE OF PIT	TOP OF GRATE	





TYPICAL ROOFWATER PROPERTY PIT TO KERB ADAPTOR OUTLET DETAIL

N.T.S.



GRATED PIT IN CONCRETE PAVEMENT 1:20 @ A1




BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au


DESIGNED		SCALE			
4. MAJZNER					
HECKED					
. STONE					
PROJECT COORDINATOR					
. THORP					
PROJECT CERTIFIER	1	0	10	20	30m
4	15/11/19				
		SCALE 1:500 (A1)			
OSHUA STONE	RPEQ 15187	ORIGINAL SHEET SIZE A1			


IENT	MIRVAC
OJECT	EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT
CATION	TEVIOT ROAD, GREENBANK
EET TITLE	STORMWATER DRAINAGE DETAILS AND NOTES


MIR001-05


C400












	LOCATION	7	ГІМЕ	SUB-CATCHM	IENT RIINOFF	<u> </u>	INI	_ET DESIGN	J				DRAIN [FSIGN						HE/	ADLOSSES			PART FULL	<u> </u>	DESIGN LEV	/FLS
	LOCATION	tc	I C	A CA			IINL	Qg		tc I	CA	Qp		S		Vf=Q/A	4		STRUCTUR	RE RATIOS V2/2g		Kw hw	Sf hf	dn Vn		DESIGN EE	/LL3
STRUCTURE NUMBER	DOWNSTREAM STRUCTURE SUB-CATCHMENTS CONTRIBUTING		RAINFALL INTENSITY CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA EQUIVALENT AREA	SUB-CATCHMENT DISCHARGE FLOW IN K &C (INC. BYPASS)	FLOW WIDTH FLOW DEPTH	ROAD GRADE AT INLET	INLET	щ	CRITICAL TIME OF CONCENTRATION RAINFALL INTENSITY	TOTAL (C × A)	SUM ADDITIONAL PIPE FLOW PIPE FLOW	REACH LENGTH	PIPE GRADE PIPE/BOX DIMENSIONS	LASS	FULL PIPE VELOCITY	TIME OF FLOW IN REACH	CHARTS USED	09/00	ТҮ НЕАБ	UPSTREAM HEADLOSS CO-EFFICIENT UPSTREAM HEADLOSS	W.S.E. CO-EFFICIENT CHANGE IN W.S.E.	PIPE FRICTION SLOPE PIPE FRICTION HEADLOSS (L × Sf)	NORMAL DEPTH NORMAL DEPTH VELOCITY	UPSTREAM OBVERT LEVEL DOWNSTREAM OBVERT LEVEL	UPSTREAM H.G.L. DOWNSTREAM H.G.L.	W.S.E. SURFACE OR GRATE LEVEL STRUCTURE NUMBER
1A/113 1B/113 1/113 2/113	18/113 1A/113 1/113 1/113 1A/113 1B/113 1/113 1A/113 1B/113 1/113 3/113 1A/113 1B/113 1/11	6 1 9 1	mm/h	0.009 0.006 0.23 0	0 0	m m 0.12 0.003 1.875 0.061	28 2.74	5 105 C 2 C 0 C	l/s 1B/113 1/200 1/200 4/113	21.06 76 21.18 76	ha 0.5 0.505 0.505 0.663	0 106 0 106	15.625 7 21.148 3 31.118 3	.63 375	2 2 2 2 2	m/s 0.95 0.96 0.96 0.85	0.06 0.12 0.17 0.24	33 34 33 34	1 0.02 1 0 1 0.3 0.8			m 0.276 0.017 0.01 0.045	3.67 0.776 3.78 1.179	m m/s 0.119 3.5 0.146 2.68 0.143 2.74 0.186 2.17	m m 55.672 54.481 54.461 53.694 53.674 52.475 52.45 51.85	54.461 53.684 53.674 52.495	m m 55.948 56.12 1A/11: 54.477 55.242 1B/11: 53.684 54.698 1/113 52.495 53.459 2/113
3/113 4/113 5/113	4/113 1A/113 1B/113 1/113 2/113 3/113 5/113 1A/113 1B/113 1/113 2/113 3/113 4/113 1B/113 1/113 2/113 2/113 1A/113 1B/113 1/113 2/113 2/113 1A/113 1A/113 1A/113 1A/113 2/113 1A/113 1A/1	6 1		0.022 0.014 0.139 0.104 0.325 0.243	35 39	1.05 0.037 2.709 0.069 3.655 0.098	0.76 116) 1/121	21.88 74	0.677 0.781 0.707	0 162		.88 525 .81 525 .82 600	2	0.63 0.75 0.73		46 47 42 46 43 47 37 42 43	0.03 0.80 0.22 1 0.32 0.80	1.12 0.028	2.11 0.043 1.89 0.054	2.69 0.055 2.19 0.062 2.04 0.055	0.64 0.396	0.211 1.68 0.237 1.7 0.204 2.43	51.555 51.055	51.865 51.609 51.555 51.159 51.11 51.008	
6/113 7/113 1/121	7/113 3/113 4/113 5/113 7/113 1/121 1A/113 1B/113 1/113 2/113 3/113 4/113 5/113 6/113 1/121			0.328 0.246		3.834 0.102				9.16 108	0.953		45.332 0		2	0.97	0.38	42 43	0 1	1.13 0.048		1.61 0.077	0.83 0.377	0.295 1.97	50.936 50.556 51.052 51.027	50.936 50.559	51.013 52.041 6/113 50.559 51.532 7/113
1/121 1/200 2/200 3/200			76 0.6	2.122 1.278		3.225 0.088		28 269 0	1/252	21 76 21.11 76 21.28 75	1.278 (1.559 (1.841 (1.	0 269	24.568 5 23.327 1 23.667 0	600x3		1.5 1.18 1.38		Inlet Contro	0 1 0 1	1.63 0.114 1.05 0.071		0.19 0.032	5.17 1.23 1.09 0.255	0.173 1.33 0.13 3.47 0.305 2.3 0.379 2.08	51.15 49.922	51.15 49.88 49.849 49.594	51.34 51.6 1/200
4/200 5/200	5/200 1/249 1/250 1/251 1/252 1/253 1/200 1/257 1/248 1/249 6/200 1/250 1/251 1/252 1/253									21.49 75 21.55 75	1.981		14.166 3 31.275 0		2	1.49	0.06	33 34 33 34	0 1		0.23	0.026		0.252 3.72 0.59 1.46	49.368 48.883	49.368 48.931 48.908 48.805	49.394 50.406 4/200 48.931 50.272 5/200
6/200	7/200 1/236 1/237 1/232 1/233 1/200 1/226 1/227 2/227 1/248 7/200 1/249 1/250 1/251 1/252 1/253 1/200										2.535		50.071 0		2	1.19	0.42		0 1		0.23 0.016			0.419 2.07	48.789 48.48		
7/200	8/200 1/224 1/225 1/226 1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200									18.87 80	2.902	0 655	5.893 0	.45 750	2	1.48	0.06	37 42	0 1	1.31 0.112	0.79 0.088	0.089	0.35 0.02	0.544 1.91	48.405 48.378	48.548 48.527	48.636 49.514 7/200
8/200	9/200 1/223 2/223 1/224 1/225 1/226 1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200									18.93 80	3.213	0 713	40.251 1	.7 900	2	1.12	0.18	37 42 43	0 0.9	7 1.09 0.064	1.11 0.071	1.2 0.077	1.65 0.664	0.339 3.25	48.456 47.771	48.456 47.792	48.533 49.514 8/200
9/200																											47.792 48.809 9/200
	1A/211 1/211	_		0.054 0.041											2	_	_		1		9.7 0.008						58.673 59.641 1/211
1A/211 2/211	2/211 1/211 1A/211 3/211 1/217 1/211 1A/211 2/211	_	.22 0.75	0.26 0.195 0.292 0.219		2.197 0.063 2.36 0.067		_		6 122 6.36 121	0.235	0 69	75.463 4	_	2	0.63	0.36	32 34 37	0.8 1		5.09 0.102 1.98 0.186	0.102	4.69 3.539 5.85 2.322	0.107 2.65	58.23 54.553		58.331 59.183 1A/211 54.69 55.405 2/211
3/211	4/211 1/217 1/211 1A/211 2/211 4/211 3/211			0.151 0.113		1.916 0.056				6.52 120			39.705 6 25.851 5		2	1.79	0.17		0.44 1		1.33 0.218			0.184 3.67		51.965 50.833	
4/211	5/211 1/217 1/211 1A/211 2/211 5/211 3/211 4/211	8 1	.13 0.6	0.429 0.258	81 81	0.03	1.32 375	5 81 0) 2/223	6.72 119	0.832	0 268	29.196 1	.57 450	2	1.69	0.22	42 46 43 47	0.29 0.8	3 1.73 0.145	1.92 0.278	2.26 0.329	1.29 0.377	0.292 2.46	50.555 50.098	50.555 50.177	50.883 51.634 4/211
5/211	6/211 1/213 1/217 1/211 1A/211 2/211 3/211 4/211 5/211	6 1	.22 0.75	0.022 0.016	6 6	0.736 0.03	5 333	3 6 0	6/211	6.93 118	0.939	0 308	34.811 4	.82 450	2	1.94	0.15	34 37	0.02 1	1.22 0.192	0.52 0.099	0.099	2.59 0.9	0.223 3.92	50.078 48.401	50.078 49.178	50.177 50.997 5/211
6/211																											49.187 49.274 6/211
1/213	5/211 1/213	6 1	.22 0.75	0.12 0.09	30 38	1.726 0.053	5 334	4 38 0	7/211	6 122	0.09	0 38	7.987 1	375	2	0.34	0.08	32	1	1.36 0.006	9.7 0.058	0.058	0.05 0.004	0.118 1.27	50.102 50.023	50.181 50.177	50.239 51.043 1/213
1/217	2/211 1/217	6 1	.22 0.75	0.065 0.049	17 17	1.207 0.041	5.25 346	6 17 0	4/211	6 122	0.049	0 17	8.06 1	375	2	0.15	0.08	32	1	1.03 0.001	9.7 0.011	0.011	0.61 0.049		54.739 54.659	54.739 54.69	54.75 55.479 1/217
1/223	2/223 1/223		_	0.127 0.095		1.657 0.051) 1/222	6 122	0.095	0 32	20.935 3		2	0.29	0.11		1	1.11 0.004		0.042		0.078 1.93		49.559 48.796	
2/223			.05 0.6	0.358 0.216		2.366 0.068					0.31	0 81	14.881 1		2	0.51	_		3 0.63 0.8		4.02 0.054	4.02 0.054		0.138 1.96	48.742 48.453		48.796 49.722 2/223
1/224			.05 0.6				0.26 375		1/225		0.365		3.128 1		2	1.09	0.03		1		6.67 0.404	0.404		0.228 1.71		48.721 48.636	
1/225	7/200 1/225 6/200 1/226	-	_	0.293 0.219		3.114 0.085			1/222A		0.219	0 69	10.642 1		2	0.62	0.11		1		9.64 0.192	0.192		0.163 1.49	48.783 48.676		48.975 49.541 1/225
1/226	6/200 1/226 2/227 1/227		.05 0.6	0.412 0.248 0.034 0.026		2.985 0.085) 2/227		0.248	0 68	2.651 1 9.146 1		2	0.43	0.02		1	1.2 0.009 1.01 0	9.7 0.09 9.7 0.003	0.09	12.2 0.227 1.19 0.11	0.149 1.47 0.057 0.83	49.19 49.163 49.12 49.028		49.279 49.937 1/226 49.123 50.088 1/227
2/227	5/200 1/227 2/227			0.034 0.026	7 7		1.27 375 0.6 375	5 7 () 2/22/		0.026	15	12.608 0	_	2	0.08	0.1		0.43 1		2.27 0.002			0.057 0.83	49.12 49.028 49.008 48.958		49.123 50.088 1/227 49.011 50.067 2/227
1/248			_	0.026 0.02	59 59	0.081		5 59 0) 1/226		0.261	0 59	7.873 3		2	0.14	0.21		1	1.27 0.015		0.103		0.108 2.26	49.671 49.393		49.774 50.26 1/248
1/249	4/200 1/249			0.036 0.023		1.172 0.041			1/226		0.023	0 7	2.487 1	375	2	0.06	0.03		1	1.01 0	9.7 0.002	0.002		0.052 0.78			49.617 50.357 1/249
1/250	4/200 1/250		_	0.157 0.118		2.495 0.065) 1/227		0.118	0 42	5.735 1	375	2	0.38	0.06		1	1.19 0.007		0.002		0.124 1.3	49.601 49.544		49.671 50.356 1/250
1/251			32 0.6	0.467 0.281		0.085		5 64 0			0.281	0 64	7.75 1	375	2	0.58	0.08		1	1.32 0.017		0.119				49.883 49.594	
1/252	2/200 1/252			0.168 0.126		2.321 0.071			1/249		0.126	0 49	2.512 1		2	0.45	0.03		1	1.26 0.01		0.099		0.136 1.36		50.123 49.88	
1/253	2/200 1/253		_	0.208 0.156		2.472 0.071			1/250		0.156	0 51	5.558 1	375	2	0.46	0.06		1	1.28 0.011			0.64 0.036		49.916 49.86		
EOD	CONCEDITOR										DESIGNED			SCALE	E			T T	ENT.				41D\/^C				JOB CODE
FUK	CONSTRUCTION								BANE OFFIC 1 100 BRUNSW		M. MAJZN	NER						CLI	ENT			N	IIRVAC				MIRO01 0



FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361


CHECKED
J. STONE
PROJECT COORDINATOR

C. THORP
PROJECT CERTIFIER 15/11/19

PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT

LOCATION TEVIOT ROAD, GREENBANK SHEET TITLE Q2 MINOR STORM CALCULATIONS MIR001-05

		LOCATION	TI	ME	SUB	B-CATCHM		JNOFF			DESIGN						DRAIN D	ESIGN						HEADLO					PART			DESIGN	LEVELS)	RU'	JNOFF	
			tc		A	CA	Q		_	Qg Q	b	tc	ı	CA		Qp	L	S	Vf=Q/	A		STRUCTU	JRE RATIOS	V2/2g Ki	ı hu	Kw hw	/ Sf	_	dn	Vn						+	$\overline{}$
STRUCTURE NUMBER	DOWNSTREAM STRUCTURE			KAINFALL IN LENSI I Y CO-EFFICIENT OF RUNOFF	3-CATCHMENT ARE	IVALENT AREA	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS)	ROAD GRADE AT INLET	FLOW INTO INLET	BYPASS STRUCTURE NUMBER	CRITICAL TIME OF CONCENTRATION	RAINFALL INTENSITY	TOTAL (C × A)	SUM ADDITIONAL PIPE FLOW	PIPE FLOW		PIPE GRADE PIPE/BOX DIMENSIONS	CLASS FULL PIPE VELOCITY	TIME OF FLOW IN REACH	CHARTS USED	09/00	Du/Do S/Do	VELOCITY HEAD UPSTREAM HEADLOSS	CO-EFFICIENT UPSTREAM HEADLOSS	W.S.E. CO-EFFICIENT CHANGE IN W.S.E.	6	PIPE FRICTION HEADLOSS (L x Sf)	NORMAL DEPTH	NORMAL DEPTH VELOCITY	UPSTREAM OBVERT LEVEL	DOWNSTREAM OBVERT LEVEL UPSTREAM H.G.L.	DOWNSTREAM H.G.L.	W.S.E.	ON GRATE RFACE	MAJOR SURFACE FLOW	STRUCTURE NUMBER
		ı	min mı	n/h	ha	a ha	l/s	l/s	%	l/s l/			mm/h	ha	l/s	l/s	m	% mm	m/s	min				m	m	m	%	m	m	m/s	m	m m	m	m m	n l/s	l/s	
1A/113	1B/113	1A/113 2	1 16	9 0.84	1 0.83	0.697	327	327	1	.45 182	2 1B/113	21	169	0.697	0 1	45	15.625 7.	62 375	2 1.31	0.06	32	1	2.08	0.088 4.6	2 0.407	0.40	7 6.95	1.087	0.141	3.83	55.672	54.481 55.672	54.585	56.079 56.1	2	\perp	1A/113
1B/113	1/113	1A/113 1B/113 6	27	5 0.84	4 0.009	9 0.008	6	188	2	8 160	1/200	21.06	169	0.705	0 1	70	21.148 3.	63 375	2 1.54	0.12	33 34	0.16 1	1.33	0.121 1.0	0.124	0.12	4 2.14	0.454	0.19	3.04	4.461	53.694 54.461	54.007	54.585 55.2	42	\perp	1B/113
1/113		1A/113 1B/113 1/113 9	24	2 1	0.23	0.23	154	154	2.74 1	.06 48	1/200	21.18	168	0.935	0 2	29	31.118 3.	85 375	2 2.07	0.17	33 34	0.38 1	1.89	0.219 1.5	2 0.333	0.33	3 3.23	1.006	0.223	3.33	3.674	52.475 53.674	52.668	54.007 54.6	98 1680	154	1/113
2/113	3/113	1A/113 1B/113 1/113 2/113 8	25	2 1	0.21	1 0.211	148	148	3.95	9 49	4/113	21.34	168	1.146	0 2	77	34.48 1.	74 450	2 1.74	0.24	33 34	0.3 0.8	83 1.48	0.155 1.2	0.189	0.18	9 0.94	0.326	0.287	2.58	52.45	51.85 52.479	52.153	52.668 53.4	59 1743	148	2/113
3/113	4/113	1A/113 1B/113 1/113 2/113 3/113 6	27	5 0.89	0.02	2 0.019	15	15 (0.75	11	5/113	21.59	167	1.165	0 2	72	32.951 0.	88 525	2 1.26	0.3	46 47	0.01 0.8	86 1.64	0.081 2.0	7 0.166	2.63 0.21	2 0.4	0.132	0.316	2	1.865	51.575 51.987	51.855	52.199 52.8	1787	15	3/113
4/113	5/113	1A/113 1B/113 1/113 2/113 3/113 4/113	27	5 1	0.139	9 0.139	106	155	0.76	90 65	1/121	21.88	166	1.304	0 3	17	62.034 0.	81 525	2 1.46	0.58	42 46 43 47	0.25 1	1.63	0.109 1.8	8 0.205	2.17 0.23	7 0.54	0.337	0.362	1.99	51.555	51.055 51.649	51.312	51.886 52.5	23 1968	155	4/113
5/113	6/113	1A/113 1B/113 1/113 2/113 3/113 4/113 5/113	27	5 1	0.32	5 0.325	248	260	0.5 1	.14 146	5 1/252	10.29	231	1.225	0 3	67	6.03 1.	82 600	2 1.3	0.03	37 42 43	0.26 0.8	88 1.37	0.086 1.7	0.146	1.96 0.16	8 0.36	0.022	0.28	2.84	51.11	51 51.166	51.144	51.334 52.0	04 1787	260	5/113
6/113	7/113	1/121 1A/113 1B/113 1/113 2/113 3/113 4/113 5/113										10.32	230	1.553	0 4	64	45.332 0.	84 600	2 1.64	0.38	42 43	0 1	1.37	0.137 1.5	2 0.208	1.61 0.22	2 0.76	0.344	0.415	2.22	50.936	50.556 50.936	50.592	51.158 52.0	41		6/113
7/113			+						_	-						\dashv												+						50.592 51.5	32	+	7/113
1/121	6/113	1/121 6	27	5 1	0.32	8 0.328	251	316	0.5 1	.39 17	7 1/120	6	275	0.328	0 1	39	2.487 1	375	2 1.26	0.03	32	1	2.42	0.081 5.2	4 0.424	0.42	4 0.63	0.016	0.252	1.76	51.052	51.027 51.16	51.144		93 1787	316	1/121
1/200	2/200	1/200 2	1 16	9 0.84	4 2.12	2 1.783	835	1043	3	83 663	1 1/252	21	169	1.783	0 3	83	24.568 5	600x300	2 2.13	0.11	Inlet Control		2.5	0.231 1.9	5 0.45	0.45	5.25	1.156	0.165	3.86	51.15	49.922 51.15	49.86	51.6 51.6	2531	1043	1/200
2/200	3/200	1/252 1/253 1/200										21.11	168	2.159	0 2	72	23.327 1.	11 600	2 0.96	0.17	33 34	0 1	1.02	0.047 0.2	4 0.011	0.01	1 1.09	0.254	0.272	2.19	19.849	49.59 49.849	49.595	49.86 50.9	01		2/200
3/200	4/200	1/251 1/252 1/253 1/200										21.28	168	2.551	0 3	55	23.667 0.	77 600	2 1.25	0.21	34 37	0 1	1.04	0.08 0.3	1 0.025	0.02	5 0.69	0.163	0.355	2.03	19.57	49.388 49.57	49.408	49.595 50.6	3	T	3/200
4/200	5/200	1/249 1/250 1/251 1/252 1/253 1/200										21.49	167	2.74	0 4	35	14.166 3.	43 600	2 1.54	0.06	34 37	0 1	1.07	0.121 0.3	3 0.039	0.03	9 1.37	0.194	0.258	3.75	19.368	48.883 49.368	49.174	49.408 50.4	06		4/200
5/200	6/200	1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200										21.55	167	3.165	0 5	07	31.275 0.	3 675	2 1.42	0.4	33 34	0 1	1.43	0.102 0.2	5 0.026	0.02	6 0.36	0.114	0.675	1.42	18.883	48.789 49.148	49.034	49.174 50.2	72		5/200
6/200	7/200	1/226 1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200										21.95	166	3.511	0 6	79	50.071 0.	62 750	2 1.54	0.42	34	0 1	1.33	0.12 0.2	7 0.032	0.03	2 0.37	0.186	0.496	2.19	18.789	48.48 49.002	48.816	49.034 49.9	77		6/200
7/200	8/200	1/224 1/225 1/226 1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200										19.17	176	4.042	0 8	54	5.893 0.	45 750	2 1.93	0.06	37 42 43	0 1	1.55	0.191 0.8	9 0.17	0.91 0.17	3 0.59	0.035	0.75	1.93	48.405	48.378 48.646	48.611	48.819 49.5	14		7/200
8/200	9/200	1/223 2/223 1/224 1/225 1/226 1/227 2/227 1/248 1/249 1/250 1/251 1/252 1/253 1/200										18.93	177	4.437	0 1	033	40.251 1.	7 900	2 1.62	0.18	37 42 43	0 0.9	97 1.19	0.135 1.1	0.155	1.25 0.16	8 1.54	0.619	0.416	3.59	18.456	47.771 48.456	47.837	48.624 49.5	14		8/200
9/200																																		47.837 48.8	09		9/200
1/211	1A/211	1/211 6	27	5 1	0.054	4 0.054	41	41	4.59	1 1	1/217	6	275	0.054	0 4	1	12.757 3.	26 375	2 0.37	0.08	32	1	1.18	0.007 9.7	0.068	0.06	8 0.55	0.072	0.091	1.96	8.665	58.25 58.665	58.593	58.733 59.6	41 1607	41	1/211
1A/211	2/211	1/211 1A/211 6	27	5 1	0.26	0.26	199	199	4.59 1	.20 78	2/211	6	275	0.313	0 1	61	75.463 4.	87 375	2 1.45	0.36	32 34 37	0.75 1	1.97	0.108 3.3	7 0.364	0.36	4 4	3.016	0.168	3.34	8.23	54.553 58.23	55.213	58.593 59.1	83		1A/211
2/211	3/211	1/217 1/211 1A/211 2/211 6	27	5 1	0.29	2 0.292	223	302	5.25 1	.53 148	3/211	6.36	271	0.671	0 3	52	39.705 6.	35 375	2 3.19	0.17	33 34	0.43 1	2.89	0.519 1.3	7 0.709	0.70	9 5.66	2.248	0.253	4.44	4.505	51.985 54.505	52.256	55.213 55.4	05 1607	302	2/211
3/211	4/211	1/217 1/211 1A/211 2/211 3/211 6	27	5 1	0.15	1 0.151	116	264	7.06	260	1/213	6.52	269	0.822	0 3	49	25.851 5.	45 375	2 3.16	0.12	33 34	0.01 1	1.78	0.511 0.3	0.155	0.15	5 3.97	1.027	0.267	4.16	51.965	50.555 52.101	51.074	52.256 53.1	25 1567	264	3/211
4/211	5/211	1/217 1/211 1A/211 2/211 3/211 4/211	25	2 0.84	1 0.429	9 0.36	252	256	1.32 2	229	9 2/223	6.72	266	1.125	0 3	44	29.196 1.	57 450	2 2.16	0.22	42 46 43 47	0.07 0.8	83 2.34	0.238 1.5	4 0.367	1.89 0.45	1.45	0.424	0.355	2.55	50.555	50.098 50.707	50.283	51.157 51.6	34		4/211
5/211	6/211	1/213 1/217 1/211 1A/211 2/211 3/211 4/211 5/211 6	27	5 1	0.02	2 0.022	17	17	5 1	.7 0	6/211	6.86	265	1.263	0 4	01	34.811 4.	82 450	2 2.52	0.15	34 37	0.04 1	1.46	0.324 0.6	3 0.205	0.20	5 2.31	0.804	0.262	4.18	50.078	48.401 50.078	49.274	50.283 50.9	97 1631	17	5/211
6/211																																		49.259 49.2	74	$\perp \perp \perp$	6/211
1/213			_	5 1	_	0.12	_				7/211	_		0.12		\rightarrow	7.987 1	375	2 0.48	0.08		1		0.012 8.2	_		7 0.09					50.023 50.29			_	352	1/213
1/217	2/211		27		_	5 0.065				16 4	4/211			0.065		_	8.06 1	375	2 0.42	0.08		1		0.009 5.3		0.04	7 0.07	_	0.131			54.659 55.219				$\perp \perp \perp$	1/217
1/223				5 1	_	7 0.127	_			3 24		+		0.127			20.935 3.		2 0.66	0.11		1		0.022 9.3	_	0.21		0.331				48.773 49.559					1/223
2/223				3 0.84	_		_	-			4 1/224	_		0.428		\rightarrow	14.881 1.	_	2 1.56		32 37 42	0.72 0.8		0.124 3.9	_		6 0.88	_		_		48.453 48.742	_			424	2/223
1/224	7/200		0 23	_			_		_		93 1/225	+	233		_	\rightarrow	3.128 1.		2 1.75	0.03		1	_	0.157 3.8				0.039				48.688 48.855			_	4.	1/224
1/225	7/200		27		_	3 0.293					11 1/222A			0.293		-	10.642 1.		2 1.57	0.11		1	2.79	0.125 4.2				_	0.303					49.454 49.5	_		1/225
1/226			0 23	_		_	_	_			22 1/224	_		0.346		_		01 450	2 1.56	0.02		1		0.124 5.1	_				0.325					49.833 49.9			1/226
1/227	2/227		27	-	_	4 0.034	_	-		-	3 2/227	_		0.034		_		01 375	2 0.32	0.1		1 0	3.58	0.005 3.1			7 0.04	0.004	0.115			49.028 50.071				249	1/227
1/248		1/227 2/227 6	27 8 18	_		6 0.026 3 0.364	_			.04 79	7 1/225 1/226	_			0 2	\rightarrow	12.608 0. 7.873 3.		2 0.02	0.21	46 47	1	1.44	0.045 6.0	9 0	2.66 0	1 6.31	–	0.035			48.958 49.174 49.393 49.671			_	183	2/227 1/248
1/248			8 18	_	_	6 0.032								0.364		-	7.873 S. 2.487 1	375	2 0.76	0.04		1	1.72	0.045 6.0			6 8.34	_	0.145			49.59 49.615			_		1/248
1/249				5 1	_						3 1/227	_		0.032		-+	5.735 1	375	2 0.76	0.03		1	_	0.029 8.7	_			0.127				49.544 49.601					1/250
1/251			_	1 0.84	-	7 0.392	_	-		.01 96		+		0.392	_	01		375	2 0.91	0.08		1		0.042 6.1		0.12			0.204			49.805 49.883				197	1/251
	2/200		27	_		8 0.168	_				2 1/249	_		0.168		_	2.512 1.		2 0.02	0.03		1	1	0.042 0.1		0.20		0.262				50.097 50.123			_		1/252
	2/200			5 1	_	8 0.208			1.71		9 1/250	+		0.208		_	5.558 1	375	2 0	0.06		1	1	0 9.7		0	1	0.056				49.86 49.916				159	1/253
			\neg																																	+	
																_																					
		TOLICTION														DESIG																					



Premise PH: (07) 3253 2222
WEB: www.premise.com.au


BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006

DESIGNED M. MAJZNER CHECKED J. STONE PROJECT CORDINATOR C. THORP PROJECT CERTIFIER 15/11/19				
CHECKED J. STONE PROJECT COORDINATOR C. THORP PROJECT CERTIFIER		DESIGNED		SCALE
J. STONE PROJECT COORDINATOR C. THORP PROJECT CERTIFIER		M. MAJZNER		
PROJECT COORDINATOR C. THORP PROJECT CERTIFIER	т.	CHECKED		
C. THORP PROJECT CERTIFIER	:1	J. STONE		
PROJECT CERTIFIER		PROJECT COORDINATOR		
		C. THORP		
15/11/19		PROJECT CERTIFIER		
			15/11/19	
IOSHUA STONE RPFO 15187		IOSHUA STONE	RPFO 15187	

MIRVAC

PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT

LOCATION TEVIOT ROAD, GREENBANK SHEET TITLE Q100 MAJOR STORM CALCULATIONS MIR001-05



EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK **FOR MIRVAC**

SEWERAGE RETICULATION



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844

Sheet List Table									
Sheet Number	Sheet Title								
C500	SEWERAGE RETICULATION LOCALITY PLAN & NOTES								
C501	SEWERAGE RETICULATION LAYOUT PLAN - SHEET 1 OF 2								
C502	SEWERAGE RETICULATION LAYOUT PLAN - SHEET 2 OF 2								
C503	SEWERAGE RETICULATION LONG SECTIONS - SHEET 1 OF 2								
C504	SEWERAGE RETICULATION LONG SECTIONS - SHEET 2 OF 2								
C505	SEWERAGE RETICULATION NOTES AND DETAILS								

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND SEWERAGE CODE SPECIFICATIONS AND
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- THE CONSTRUCTION OF THE SEWERAGE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. SEWERAGE WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER SEWERAGE
- ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE CONTRACTOR UNDER LOGAN WATER SUPERVISION AT THE DEVELOPER'S COST.
- ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE "ACCEPTED PRODUCTS AND MATERIALS" LIST.
- FOR ALLOTMENTS OTHER THAN SINGLE RESIDENTIAL, A DN150 PROPERTY CONNECTION SHALL BE PROVIDED.
- PROPERTY CONNECTIONS SHALL BE LOCATED WITHIN THE PROPERTY AS SHOWN IN THE DRAWINGS.

 PROPERTY CONNECTION BRANCHES SHALL EXTEND INTO THE PROPERTY A
- MINIMUM OF 300mm AND A MAXIMUM OF 750mm. WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE CARRIED OUT IN
- LAYERS NOT EXCEEDING 300mm (LOOSE) IN DEPTH AND SHALL BE COMPACTED UNTIL THE COMPACTION IS NOT LESS THAN 95% OF THE MATERIALS MAXIMUM COMPACTION WHEN TESTED IN ACCORDANCE WITH A S 1289 (MODIFIED COMPACTION) TESTING SHALL BE CARRIED OUT AFTER EACH ALTERNATE LAYER. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED SEWERS WILL NOT BE ISSUED BY THE SEO SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED
- 10. WHERE SEWERS HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS SHALL
- BE CONSTRUCTED IN ACCORDANCE WITH THE SEQ SEWER CODE.

 11. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
- 12. SEWERS SHALL BE DISUSED /ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ SEWER CODE.

 13. BENCH MARK AND LEVELS TO AHD.
- 14. REFER TO BULK EARTHWORKS DRAWINGS FOR FINISHED SURFACE LEVELS.
 15. ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR
- SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT FOR INFORMATION PHONE: 1300 369 915
- 16. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS TO ALLOW CONSTRUCTION OF THE SEWER SYSTEM
- THE CONTRACTOR IS RESPONSIBLE FOR EXCAVATION AND SAFE SHORING TO ALLOW SEWER MAINTENANCE SECTION TO CARRY OUT LIVE SEWER
- 18. CONSTRUCT TRENCHES TO SEQ-SEW-1200-2, WITH EMBEDMENT TYPE 3 SUPPORT MINIMUM TO SEQ-SEW-1201-1, AND ROAD CROSSINGS TO SEQ-SEW-1205-1 AND LCC STANDARDS.

 19. CONSTRUCT PROPERTY CONNECTIONS TO SEQ-SEW-1100 SERIES.
- 20. CONSTRUCT MAINTENANCE STRUCTURES TO SEQ-SEW-1300 SERIES. 21. CONSTRUCT BULKHEADS TO SEQ-SEW-1206-1.
- 22. INSTALL DETECTABLE MARKER TAPE ON ALL MAINS AND PROPERTY
- 23. CALCAREOUS CONCRETE IN MAINTENANCE HOLES REQUIRED IN ACCORDANCE WITH SEO WS&S D&C CODE REQUIREMENTS

VEGETATION PROTECTION

A. TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.

B. WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES S HALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.

TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE. D. ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED

SOIL

A. TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
B. CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.

IF ACID SULPHATE SOILS EXIST IN THE WORKS AREA, ACID SULPHATE SOILS ARE TO MANAGED IN ACCORDANCE WITH AN APPROVED ACID SUI PHATE SOIL

CREEK CROSSINGS

A. SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.

B. APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.

C. NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK

REHABILITATION

A. PREDISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE B PREDISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED

A. THE DESIGN AND CONSTRUCTION OF THE WORKS SHALL COMPLY WITH ALL

INDEMNITY - EXISTING SERVICES


NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THI DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING

ALL SEWER CONSTRUCTION WORK LINDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE OLIFFNSLAND WORKPLACE HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF HEALTH & SAFETY FOR PHONE: 1300 369 915

CONTACT "DIAL BEFORE YOU DIG" ON 1100 FOR LOCATION

NAME OF ES	STATE	EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT				
SUBDIVIDER		MIRVAC				
APPLICATION No.		-				
SP DELEGATE APPR	OVAL DATE	5 JUNE 2017				
COUNCIL DA APPRO	VAL No.	DEV 2016 / 768				
DRAWING/PLAN No.		C501-C505				
No. OF ALLOTMENT	S	50				
AREA IN Ha.		6.88 Ha				
LENGTH OF	DN150 uPVC SN8	732m				
SEWERS	DN100 uPVC SN8	121m				





BRISBANE OFFICE

LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, OLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au

DESIGNED		SCA
M. MAJZNER		
CHECKED		
J. STONE		
PROJECT COORDINATOR		
C. THORP		
PROJECT CERTIFIER		
	15/11/19	
JOSHUA STONE	RPEO 15187	-
70311071310112	10 20 13107	

SCALE			
İ			
0	100	200	300m
]	SCALE 1	5000 (A1)	
	SCHEE II	3000 (7.12)	
	ORIGINAL SH		


		CLIENT
) 3	00m	PROJECT
A1)	1	LOCATION
		CHEET TITLE


MIRVAC EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT


TEVIOT ROAD, GREENBANK


SEWERAGE RETICULATION LOCALITY PLAN & NOTES


MIR001-05 C500











EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT TEVIOT ROAD, GREENBANK **FOR MIRVAC**

WATER RETICULATION



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844 LOT 9 on S312355

Sheet List Table									
Sheet Number	Sheet Title								
C600	WATER RETICULATION LOCALITY PLAN & NOTES								
C601	WATER RETICULATION LAYOUT PLAN SHEET 1 OF 2								
C602	WATER RETICULATION LAYOUT PLAN SHEET 2 OF 2								
C603	WATER RETICULATION DETAILS								

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- ADOPT LIP OF KERB OR SHOULDER OF ROAD AS PERMANENT LEVEL. COVER OF MAIN FROM PERMANENT LEVEL TO BE AS SHOWN IN
- CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD
- ALL MATERIALS LISED IN THE WORKS SHALL COMPLY WITH SEO-SP's
- ACCEPTED PRODUCTS AND MATERIALS LIST OR BE APPROPRIATELY SHOWN LISTED AND DEFINED IN THE ENGINEERING SUBMISSION SO THAT THE ALTERNATIVE PRODUCT OR MATERIAL CAN BE ASSESSED AND IF APPROPRIATE APPROVED BY SEO-SP's
- ALL CONCRETE FOOTPATHS TO BE CLEAR OF WATER MAINS. WHERE
- CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEO REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT TO THE RETICULATION SYSTEM.
- ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION.
- 10. CONSTRUCT THRUST BLOCKS ON ALL BENDS, TEES, TAPERS AND DEAD ENDS IN ACCORDANCE WITH SEQ-WAT-1205-1, AND SEQ-WAT-1206-1.
- 11 CONSTRUCT TRENCHES IN ACCORDANCE WITH SEO-WAT-1200-2 PIPE EMBEDMENT TO SEQ-WAT-1201-1 (TYPE C SUPPORT) AND ROAD
- CROSSINGS TO SEQ. WAT-1204-1 AND LCC STANDARDS.
 INSTALL SCOURS IN ACCORDANCE WITH SEQ.-WAT-1307-3. 13. INSTALL DETECTABLE MARKER TAPE ON ALL WATER MAINS AND
- PROPERTY SERVICES. 14. INSTALL HYDRANTS IN ACCORDANCE WITH SEQ-WAT-1302-1
- 15. INSTALL PAVEMENT MARKERS IN ACCORDANCE WITH SEQ-WAT-1300-1

VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION OR REPLACED IF DESTROYED
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN

TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY. CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.

CREEK CROSSINGS

- 1. SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

REHABILITATION

- PRE-DISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL
- PRE-DISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED ALL DISTURBED AREAS ASSOCIATED WITH CONSTRUCTION SHALL BE REHABILITATED, HEAVILY COMPACTED AREAS SHOULD BE RIPPED
- ALL DISTURBED AREAS ARE TO BE LEFT IN STABLE CONDITION ALL PLANTING/RE-VEGETATION WILL NEED TO BE MAINTAINED
- THROUGHOUT THE MAINTENANCE PERIOD.

CONSTRUCTION REQUIREMENTS

- LIVE WATER CONNECTIONS TO BE CARRIED OUT BY CONTRACTOR IN WATER SUPERVISION AT DEVELOPERS EXPENSE AT LOCATION
- PRIOR TO ANY EXCAVATION CONTRACTOR IS TO LOCATE ACTUAL POSITIONS OF PUBLIC SERVICE UTILITIES BY POT HOLES.
- LIPON COMPLETION OF ALL WORKS CONTRACTORS SHALL SUPPLY THE SUPERVISING RPEQ DETAILED "AS CONSTRUCTED" INFORMATION OF THE WORK "AS CONSTRUCTED" INFORMATION SHALL COMPLY WITH CURRENT SEQ CODE OR LOCAL AUTHORITY STANDARDS FOR PLAN AND DIGITAL INFORMATION.
 CONTRACTOR IS TO BE RESPONSIBLE FOR ARRANGING ALL LOGAN
- WATER CONNECTIONS AND PAYMENTS OF CONNECTION FEES

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MA NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS NFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CALISED AS A RESULT OF THE WORKS

RPEQ CERTIFICATION

THE CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO LOGAN WATER RETICULATION SYSTEM. ALL RPEQ CERTIFIED DRAWINGS COMPLY WITH SEQ CODE AND LOGAN WATER REQUIREMENTS.

INSPECTION REQUIREMENTS

PRIOR TO COMMENCEMENT OF WORKS, CONTACT PREMISE (07) 3253 2222 AND LOGAN WATER TO CONFIRM INSPECTIO REQUIREMENTS INCLUDING LIVE CONNECTIONS.

A MINIMUM 48 HOURS NOTICE IS REQUIRED

INSPECTIONS ARE REQUIRED TO BE ORGANIZED WITH PREMISE AND LOGAN WATER ANY COSTS ASSOCIATED WITH ENGAGING LOGAN WATER TO UNDERTAKE INSPECTIONS OUTSIDE OF THE FEE PAID SHALL BE BORNE BY THE


ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING

ALL WATER CONSTRUCTION WORK LINDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE OLIFENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFFTY FOR INFORMATION PHONE: 1300 362 128

SEQ CODE STD DRAWING SCHEDULE

SOIL CLASSIFICATION EMBEDMENT AND TRENCH FILL SEQ-WAT-1200-1 SEO-WAT-1200-2 THRUST BLOCK DETAILS SEQ-WAT-1205-1 VALVE THRUST BLOCKS SEO-WAT-1206-1 IDENTIFICATION MARKERS SEQ-WAT-1300-1,2







BRISBANE OFFICE PO BOX 361 FORTITUDE VALLEY, OLD 4006

LEVEL 1, 100 BRUNSWICK STREET PH: (07) 3253 2222 WEB: www.premise.com.au


DESIGNED		SCALE
M. MAJZNER		
CHECKED		
J. STONE		0
PROJECT COORDINATOR		
C. THORP		
PROJECT CERTIFIER	T	
	16/09/19	
JOSHUA STONE	RPEO 15187	
•		


SCALE			
0	100	200	300n
	SCALE 1:	5000 (A1)	
	ORIGINAL SE	HEET SIZE A1	


MIRVAC EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK


WATER RETICULATION LOCALITY PLAN & NOTES


MIR001-05


















EROSION & SEDIMENT CONTROL NOTES


- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION
- REFER EARTHWORKS DRAWINGS FOR ADDITIONAL NOTES.
- ALL TRENCHES, FOOTPATH EXCAVATIONS & STOCKPILES TO BE PROTECTED BY TEMPORARY SEDIMENT FENCES UNTIL 80% GRASS COVERAGE IS ACHIEVED TO DISTURBED AREAS.
- 4. EVERY PRECAUTION IS TO BE TAKEN TO PREVENT THE TRANSPORT OF SILT INTO THE NEWLY LAID STORMWATER PIPES THAT ARE CONNECTED TO THE DOWNSTREAM PIPE SYSTEMS, AND ANY EXISTING
- THESE NOTES SHALL BE READ IN CONJUNCTION WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- THE EROSION AND SEDIMENT CONTROL WORKS SHALL COMPLY WITH THE REQUIREMENTS OF THE
- LOCAL AUTHORITIES EROSION AND SEDIMENT CONTROL STANDARDS.
 THE CONTRACTOR SHALL TAKE ALL REASONABLE AND PRACTICABLE MEASURES TO:
- ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON EROSIVE FLOW VELOCITIES:
- MINIMISE SOIL EROSION FROM WATER AND WIND:
- MINIMISE ADVERSE FEFECTS OF SEDIMENT RUN-OFF
- MINIMISE OR PREVENT ENVIRONMENTAL HARM ASSOCIATED WITH DISCHARGES FROM THE SITE (E.G. THE EFFECTS OF SEDIMENTATION ON THE ENVIRONMENTAL VALUES OF RECEIVING WATERS); AND
- ENSURE THAT THE VALUE AND USE OF RESIDENTIAL PROPERTIES ADJACENT TO THE DEVELOPMENT (SUCH AS DRAINAGE AND ROADS) ARE NOT DIMINISHED AS A RESULT OF THE MIGRATION OF SEDIMENT FROM THE DEVELOPMENT.
- THE CONTRACTOR SHALL APPOINT AN APPROPRIATELY EXPERIENCED PERSON TO BE MADE RESPONSIBLE FOR IMPLEMENTATION OF THE ESC.
- ALL ESC MEASURES SHALL BE INSPECTED:
- AT LEAST DAILY (WHEN WORK IS OCCURRING ON SITE).
- AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON SITE).
- WITHIN 24 HOURS OF EXPECTED RAINFALL.
- WITHIN 18 HOURS OF RAINFALL OCCURRING
- MAINTENANCE OF ESC MEASURES SHALL OCCUR TO ENSURE THEY ARE OPERATING EFFICIENTLY AND IN ACCORDANCE WITH THE FOLLOWING SCHEDULE:

ESC MEASURES	MAINTENANCE TRIGGER	TIME FRAME FOR UNDERTAKING MAINTENANCE
ESC MEASURES	WHEN SETTLED SEDIMENT VOLUME EXCEEDS 25% OF THE CAPACITY OF THE ESC MEASURE	BY THE END OF THE DAY


- INSTALL DIVERSION CATCH DRAINS UPSTREAM OF, AND SILT FENCE DOWNSTREAM OF, STOCKPILES. STOCKPILES ARE TO BE LOCATED AWAY FROM EROSION HAZARD AREAS SUCH AS DRAINAGE LINES AND STEEP SLOPES.
- STOCKPILES ARE TO BE PROTECTED FROM EROSION BY THE WIND.
- 10. ADEQUATE SUPPLIES OF EMERGENCY MAINTENANCE MATERIALS, INCLUDING (BUT NOT LIMITED TO) TIE WIRE, STAKES, FILTER CLOTH, WIRE MESH AND CLEAN GRAVEL SHOULD BE AVAILABLE ON-SITE
- 11. ESC MAINTENANCE ACTIVITIES ARE TO BE RECORDED IN AN ON-SITE REGISTER. THE REGISTER IS TO SUPERINTENDENT
- 12. DISTURBED AREA ARE TO BE STABILISED AS SOON AS POSSIBLE ON COMPLETION OF BULK
- FARTHWORKS, LOTS TO BE STABILISED FOLLOWING RESPREADING OF TOPSOIL 13. SUPPLEMENTARY ESC MEASURES SHALL BE DIRECTED BY THE SUPERINTENDENT




(a) Rock entry/exit pad for construction sites (refer to Standard Drawing Exit-03 for building sites)



(c) Alternative low maintenance arrangement (still under development)



(b) Rock pad sloping away from road



(d) Rock pad sloping towards the road

CONSTRUCTION ENTRANCE DETAIL

COMPOSTS MUST COMPLY WITH THE REQUIREMENTS OF AS4454.

(i) WELL-DECOMPOSED 100% ORGANIC MATTER PRODUCED BY CONTROLLED AEROBIC (BIOLOGICAL) DECOMPOSITION

(iii) MAXIMUM SOLUBLE SALT CONCENTRATION OF 5dS/m, AND pH RANGE OF 5.0 TO 8.5.

(iv) MOISTURE CONTENT OF 30 TO 50% PRIOR TO APPLICATION.

INSTALLATION

- 1 REFER TO APPROVED PLANS FOR 1. REFER TO APPROVED PLANS FOR LOCATION AND EXTENT. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, EXTENT, MATERIAL TYPE, OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.
- 2. WHEN SELECTING THE LOCATION OF A COMPOST FILTER BERM, TO THE MAXIMUM DEGREE PRACTICABLE, ENSURE THE BERM IS LOCATED:

(i) TOTALLY WITHIN THE PROPERTY BOUNDARIES;

(ii) ALONG A LINE OF CONSTANT ELEVATION (PREFERRED, BUT NOT ALWAYS PRACTICAL);

(iii) AT LEAST 1m, IDEALLY 3m, FROM THE TOE OF A FILL EMBANKMENT;

CONCENTRATED FLOW.

3. ENSURE THE BERM IS INSTALLED IN A

CONCENTRATION OF FLOW ALONG THE ENDS OF THE BERM.

- 4. ENSURE THE BERM HAS BEEN PLACED ALONG THE CONTOUR SUCH THAT WATER WILL POND EVENLY ALONG THE LENGTH OF THE BERM.
- 5. ENSURE BOTH ENDS OF THE BERM ARE ADEQUATELY TURNED UP THE SLOPE TO PREVENT FLOW BYPASSING PRIOR TO WATER PASSING OVER THE
- 6. ENSURE 100% CONTACT WITH THE
- 7. WHERE SPECIFIED, TAKE APPROPRIATE STEPS TO VEGETATE THE

- 1. DURING THE CONSTRUCTION PERIOD INSPECT THE BERMAT LEAST WEEKLY AND AFTER ANY SIGNIFICANT RAIN. MAKE NECESSARY REPAIRS IMMEDIATELY.
- 2. REPAIR OR REPLACE ANY DAMAGED
- 3. WHEN MAKING REPAIRS ALWAYS 3. WHEN MANING REPAIRS, ALWAYS RESTORE THE SYSTEM TO ITS ORIGINAL CONFIGURATION UNLESS AN AMENDED LAYOUT IS REQUIRED OR SPECIFIED.
- 4. REMOVE ACCUMULATED SEDIMENT IF THE SEDIMENT DEPOSIT EXCEEDS A DEPTH OF 100mm OR 1/3 THE HEIGHT OF
- 5. DISPOSE OF SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

REMOVAL (IF REQUIRED)

1. WHEN DISTURBED AREAS UP-SLOPE OF THE BERM ARE SUFFICIENTLY STABILISED TO RESTRAIN EROSION, THE BERM MAYBE REMOVED.

2 REMOVE ANY COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR

3. REHABILITATE/REVEGETATE THE DISTURBED GROUND AS NECESSARY TO MINIMISE THE EROSION HAZARD.





Figure 1 - Typical profile of a compost filter berm

MULCH BUND DETAIL

CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

CHRIS HUTTON CPESC NO. 624:





BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361

FORTITUDE VALLEY, OLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au

DESIGNED		SCALE
M. MAJZNER		
CHECKED		
J. STONE		
PROJECT COORDINATOR		
C. THORP		
PROJECT CERTIFIER		
	15/11/19	
JOSHUA STONE	RPEO 15187	ORIGII
		Oition

NED		SCALE
IAJZNER		
ŒD		
ONE		
CT COORDINATOR		
HORP		
CT CERTIFIER	1	
	15/11/19	
HUA STONE	RPEO 15187	ORIGINAL SHEET SIZE A1
	_	ORIGINAL SHEET SIZE 712

MIRVAC PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1

MIR001-05 C704

ROLES AND RESPONSIBILITIES

ROLE	RESPONSIBILITY		
PROJECT MANAGER	 OVERALL RESPONSIBILITY OF ESC IMPLEMENTATION 		
	 NOTIFY THE ENVIRONMENTAL MANAGER IMMEDIATELY OF ANY NON-COMPLIANCE WITH ESCP 		
	 ENSURE THE PROMPT IMPLEMENTATION OF MEASURES TO MITIGATE EROSION AND SEDIMENT GENERATION 		
SITE SUPERVISOR / FOREMEN	MONITOR DAILY RAINFALL		
	 NOTIFY ENVIRONMENTAL ADVISOR/CONSULTANT WHEN RUNOFF GENERATING RAINFALL OCCURS IN THE PREVIOUS 24 HOURS 		
	 MAINTAIN CURRENT RECORDS OF RAINFALL, STORAGE VOLUMES, WATER QUALITY, TREATMENT PRACTICES, DISCHARGE VOLUMES (AS APPROPRIATE) 		
	• INSTALLATION AND MAINTENANCE OF ESC		
ENVIRONMENTAL MANAGER	PROVIDE DESIGN INFORMATION AS REQUIRED		
	 CONDUCT IN-SITU MONITORING (AS REQUIRED) 		
	 COLLECT AND SUBMIT SAMPLES TO LABORATORY (AS REQUIRED) 		
	• COLLATE RESULTS AND PREPARE REPORTS (AS REQUIRED)		
	 CONDUCT SITE INSPECTIONS AN AUDITS (AS REQUIRED) 		
	• INSPECT ESC INSTALLATION AND MAINTENANCE		
	• INSPECT OFFSITE IMPACTS AND MANAGEMENT		
	• PROVIDE ADVICE REGARDING ESC SITE IMPROVEMENT (AS REQUIRED)		
ALL PERSONNEL	 REPORT ANY DAMAGE TO ESC DEVICES AND ANY POTENTIAL OR ACTUAL ENVIRONMENTAL HARM IN LINE WITH DUTY TO NOTIFY UNDER THE REQUIREMENTS OF THE ENVIRONMENTAL PROTECTION ACT 1994 		

CORRECTIVE AND PREVENTATIVE ACTION

AN ENVIRONMENTAL INCIDENT WITH RESPECT TO THE ESCP IS DEFINED AS ANY OCCURRENCE WHERE SEDIMENT IS RELEASED FROM THE SITE, WHETHER CONTROLLED OR UNCONTROLLED, OR WHERE STORM WATER IS RELEASED (CONTROLLED) FROM SITE WHICH DOES NOT MEET THE WATER OUALITY REQUIREMENTS.


ALL INCIDENTS AND NON-CONFORMANCES ARE TO BE REPORTED, INVESTIGATED AND CORRECTED IN ACCORDANCE WITH THE ESCP TO ENSURE EFFECTIVE SOIL AND WATER QUALITY MANAGEMENT PRACTICES AT ALL TIMES.

BEST PRACTICE SITE MANAGEMENT REQUIRES ALL ESC MEASURES TO BE INSPECTED BY THE CONTRACTORS NOMINATED REPRESENTATIVE AT LEAST DAILY WHEN RAIN IS OCCURRING, WITHIN 24 HOURS PRIOR TO EXPECTED RAINFALL, AND WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE ONSITE RUNOFF (IECA, 2008). SUCH INSPECTIONS MUST CHECK:

- DAILY SITE INSPECTIONS (DURING PERIODS OF RUNOFF PRODUCING RAINFALL)
- ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
- ALL SITE DISCHARGE POINTS (INCLUDING DEWATERING ACTIVITIES AS APPROPRIATE)
- WEEKLY SITE INSPECTIONS (EVEN IF WORK IS NOT OCCURRING ON-SITE)
 - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
- OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
- OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.
- LITTER AND WASTE RECEPTORS
- OIL, FUEL AND CHEMICALS STORAGE FACILITIES
- PRIOR TO ANTICIPATED RUNOFF PRODUCING RAINFALL
- ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 ALL TEMPORARY FLOW DIVERSION AND DRAINAGE WORKS
- FOLLOWING RUNOFF PRODUCING RAINFALL
- ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
- OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
- OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED
 OR BLOWN FORM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

CHRIS HUTTON CPESC NO. 6241





BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 Premise WEB: www.premise.com.au

DESIGNED		SCALE
M. MAJZNER		
CHECKED		
J. STONE		
PROJECT COORDINATOR		
C. THORP		
PROJECT CERTIFIER		
	15/11/19	
JOSHUA STONE	RPEQ 15187	ORIGINAL SHEET SIZE A1

MIRVAC PROJECT EVERLEIGH PRECINCT 1.5A SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK

BHEET TITLE EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2

MIR001-05