


EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT TEVIOT ROAD, GREENBANK FOR MIRVAC GROUP



LOCALITY PLAN
Scale 1:5000



SHEET LIST TABLE	
SHEET NO.	SHEET TITLE
C001	COVER SHEET
C002	SURVEY SETOUT PLAN
C003	OVERALL SERVICES LAYOUT
C004	SAFETY IN DESIGN
C100	ROADWORKS AND DRAINAGE LAYOUT - SHEET 1
C101	ROADWORKS AND DRAINAGE LAYOUT - SHEET 2
C200	BULK EARTHWORKS LAYOUT - SHEET 1 OF 2
C201	BULK EARTHWORKS LAYOUT - SHEET 2 OF 2
C210	BULK EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2
C211	BULK EARTHWORKS NOTES AND DETAILS - SHEET 2 OF 2
C300	ROADWORKS NOTES AND DETAILS
C310	RUSSETT STREET LONG & CROSS SECTIONS
C311	OLIVE AVENUE LONGITUDINAL SECTION
C312	OLIVE AVENUE CROSS SECTIONS
C313	MOSS STREET LONGITUDINAL SECTION
C314	MOSS STREET CROSS SECTIONS - SHEET 1 OF 2
C315	MOSS STREET CROSS SECTIONS - SHEET 2 OF 2
C316	BOTANICA ROAD LONGITUDINAL SECTION
C317	BOTANICA ROAD CROSS SECTIONS
C318	DWAY 4 LONG & CROSS SECTIONS
C319	BAMBOO ROAD LONGITUDINAL SECTION
C320	BAMBOO ROAD CROSS SECTIONS
C321	DWAY 1 LONG & CROSS SECTIONS
C322	DWAY 2 LONG & CROSS SECTIONS
C323	AMBER CIRCUIT LONGITUDINAL SECTION
C324	AMBER CIRCUIT CROSS SECTIONS
C330	INTERSECTION DETAILS LAYOUT
C340	PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 1 OF 2
C341	PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 2 OF 2
C350	ACOUSTIC FENCE LAYOUT PLAN
C400	STORMWATER DRAINAGE CATCHMENT PLAN
C410	STORMWATER DRAINAGE LONG SECTIONS - SHEET 1
C411	STORMWATER DRAINAGE LONG SECTIONS - SHEET 2
C412	STORMWATER DRAINAGE LONG SECTIONS - SHEET 3
C420	STORMWATER DRAINAGE NOTES AND DETAILS
C430	STORMWATER DRAINAGE STRUCTURE DETAILS
C440	STORMWATER CALCULATIONS 39% AEP STORM
C441	STORMWATER CALCULATIONS 1% AEP STORM
C500	SEWERAGE LOCALITY PLAN & NOTES
C510	SEWERAGE LAYOUT PLAN - SHEET 1
C511	SEWERAGE LAYOUT PLAN - SHEET 2
C520	SEWERAGE LONG SECTIONS - SHEET 1
C521	SEWERAGE LONG SECTIONS - SHEET 2
C522	SEWERAGE LONG SECTIONS - SHEET 3
C530	SEWERAGE NOTES AND DETAILS
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C610	WATER RETICULATION LAYOUT PLAN - SHEET 1
C611	WATER RETICULATION LAYOUT PLAN - SHEET 2
C700	EROSION AND SEDIMENT CONTROL - STABILISATION PHASE
C710	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1 OF 2
C711	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2 OF 2
C900	TEMPORARY WORKS - ROADWORKS AND DRAINAGE - SHEET 1 OF 2
C901	TEMPORARY WORKS - ROADWORKS AND DRAINAGE - SHEET 2 OF 2

GENERAL NOTES

- ALL DIMENSIONS GIVEN ON THESE DRAWINGS ARE IN METRES UNLESS NOTED OTHERWISE.
- ALL NEW WORK AND MATERIALS SHALL COMPLY CURRENT RELEVANT COUNCIL STANDARDS AND SPECIFICATIONS.
- ALL WORK SHALL BE JOINED NEATLY TO EXISTING CONSTRUCTION.
- THE CONTRACTOR IS TO LOCATE, IDENTIFY AND ESTABLISH THE CONNECTIVITY OF ALL EXISTING SERVICES WITHIN THE LIMITS OF PROPOSED WORKS AND CONFIRM THIS INFORMATION WITH THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MEASURING DEVICES, SAFETY EQUIPMENT AND MACHINERY REQUIRED TO CARRY OUT INSPECTIONS/MEETINGS AS SPECIFIED OR REQUESTED BY THE ENGINEER.
- PROOF ROLLING NOMINATED SHALL BE CARRIED OUT USING A SINGLE AXLE HIGHWAY TRUCK WITH A REAR AXLE LOAD NOT LESS THAN 10 TONNES AND TYRES INFLATED TO 550kPa OR APPROVED EQUIVALENT. EQUIPMENT LABOUR AND LOADING REQUIRED FOR PROOF ROLLING IS TO BE PROVIDED BY THE CONTRACTOR.
- THESE NOTES SHALL APPLY TO ALL PORTIONS OF WORK.
- THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATIONS. ANY POINT OF CONFLICT WILL BE RESOLVED BY THE SUPERINTENDENT.

NOISE

- ALL PLANT AND EQUIPMENT SHALL BE CONTROLLED TO MINIMISE NOISE EMISSION IN ACCORDANCE WITH AS2436 (GUIDE TO NOISE CONTROL ON CONSTRUCTION, MAINTENANCE AND DEMOLITION). THE SITE WORKING HOURS SHOULD BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS. WHERE NOT SPECIFIED THE HOURS SHALL BE:

MONDAY - SATURDAY 7:00am to 6:00pm
SUNDAY OR PUBLIC HOLIDAY NO WORK PERMITTED

PRE-CONSTRUCTION & APPROVALS

- NO LOCATING/ POTHOLING OF EXISTING SERVICES HAS BEEN CARRIED OUT. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND DEPTH OF ALL EXISTING SERVICES WHICH AFFECT THE WORKS AND REPORT ANY POTENTIAL CLASHES TO THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORKS.
- THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING WITH THE APPROPRIATE AUTHORITY FOR LOCATING EXISTING SERVICES AND FOR ANY MODIFICATIONS TO EXISTING SERVICES REQUIRED AS A RESULT OF THE WORKS.
- THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL EXISTING SERVICES FROM DAMAGE.
- ANY WORKS DAMAGED AS A RESULT OF CONSTRUCTION ARE TO BE REINSTATED TO RELEVANT AUTHORITY'S REQUIREMENTS AT THE CONTRACTORS COST.
- FINISHED SURFACE LEVELS ARE TO BE GRADED UNIFORMLY BETWEEN LEVELS INDICATED ON THE DRAWINGS.

WORKPLACE HEALTH & SAFETY

- THE CONTRACTOR SHALL BE THE PRINCIPAL CONTRACTOR AS DESIGNATED BY THE WORK HEALTH AND SAFETY ACT (2011).
- THE CONTRACTOR SHALL PREPARE AND IMPLEMENT A WORKPLACE HEALTH AND SAFETY PLAN AS REQUIRED BY THE WORK HEALTH AND SAFETY ACT (2011).

SETOUT NOTES

- CO-ORDINATE SETOUT PROVIDED ON THESE DRAWINGS IS BASED ON A CO-ORDINATE BASE PROVIDED ON THE DETAIL SURVEY DRAWING 7598 S 02 DTH, PREPARED BY SAUNDERS HAVILL GROUP. REFERENCE MARKS AND CORRESPONDING CO-ORDINATES ARE PROVIDED ON DRAWING C002.
- THE LEVEL DATUM FOR WORKS IS A.H.D (AUSTRALIAN HEIGHT DATUM).


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
25/02/2021	B	AMENDED SHEET LIST TABLE	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	




BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED K KIWANG	 PATRICK BRADY RPEQ 7112
CHECKED M MAJZNER	
PROJECT MANAGER S STEINHOFER	
PROJECT DIRECTOR	



CLIENT MIRVAC GROUP	JOB CODE MIR012-02
PROJECT EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER C001
LOCATION TEVIOT ROAD, GREENBANK	REV B
SHEET TITLE COVER SHEET	



LEGEND

- PROPOSED ROAD CENTRELINE
- - - STAGE BOUNDARY

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

LEVEL DATUM: AHD (DERIVED)

ORIGIN - PM61308
 RL OF ORIGIN - 54.660m A.H.D

ORIGIN OF COORDINATES: STATION C1 (PM 73506)

PROJECT COORDINATES - STN C1, 8792.646 E, 32093.723 N

FOR FURTHER DETAILS REFER TO DETAIL SURVEY DRAWING 7598 S 02 DT H PREPARED BY SAUNDERS HAVILL GROUP.

SITE AREA

38,321m²

REAL PROPERTY DESCRIPTION

LOT 2 on SP297192


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
23/02/21	B	AMENDED ROAD NAMES	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB
DATE	REV	DESCRIPTION	REC	APP




BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SURVEY SETOUT PLAN

JOB CODE
MIR012-02
 SHEET NUMBER
C002
 REV
B



LEGEND - PROPOSED


- D—D—D— STORMWATER
- S—S—S— GRAVITY SEWER
- RM—RM—RM— SEWER RISING MAIN
- TS—TS—TS— TRUNK SEWER
- W—W—W— WATER
- E—E—E— ELECTRICITY

LEGEND - EXISTING

- - - D - - - D - - - STORMWATER
- - - S - - - S - - - GRAVITY SEWER
- - - RM - - - RM - - - SEWER RISING MAIN
- - - TS - - - TS - - - TRUNK SEWER
- - - W - - - W - - - WATER
- - - E - - - E - - - ELECTRICITY

LEGEND - PROPERTY SERVICE CONNECTIONS

- W **WATER** - POLY SERVICE FROM WATER MAIN, METER BOX & COVER INSTALLED. BUILDER TO MAKE APPLICATION TO LOGAN CITY COUNCIL FOR METER ASSEMBLY SUPPLY AND INSTALLATION. WHERE WATER METER IS LOCATED BEHIND RETAINING WALL, 25mm POLYPIPE WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "WATER".
- **SEWER** - CAPPED Ø100 PVC PIPE (BURIED MAX 1.5m). MARKED WITH 40Ø ORANGE PVC CONDUIT AT SURFACE (BURIED TO CAPPED PIPE). CONDUIT LABELLED "SEWER".
- RW **ROOFWATER** - CONNECTION LOCATION CAN BE EITHER FRONT OF LOT VIA KERB ADAPTOR OUTLET TO ROAD, OR REAR OF LOT INTO ROOFWATER DRAINAGE PIPE VIA PIT. CAPPED PVC Ø100 PIPES (BURIED MAX 1.5m) MARKED WITH 900x50x25 HW STAKE LABELLED "ROOFWATER".
- SSD **RETAINING WALL SUB-SOIL DRAINAGE** - OUTLET POINT TO LOT FOR RETAINING WALL SUB-SOIL DRAINAGE TO BE CONNECTED TO YARD DRAINAGE BY BUILDER. Ø100 NON-SLOTTED AGG PIPE CAPPED AND TERMINATED 200m ABOVE SURFACE. PVC DUCT TAPED TO 900x50x25 HW STAKE LABELLED "RETAINING WALL SUBSOIL OUTLET".
- **TELECOMMUNICATIONS/NBN** - PVC CONDUIT (BURIED APPROX 300mm). MARKED WITH 900x50x25 HW STAKE LABELLED "TELECOMMS".
- **ELECTRICITY** - ELECTRICITY PILLAR EXISTS IN ROAD VERGE. BUILDER TO MAKE APPLICATION WITH ENERGY PROVIDER FOR SERVICE INSTALLATION TO LOT. WHERE ELECTRICITY PILLAR IS LOCATED BEHIND RETAINING WALL, CONDUIT WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "ELECTRICITY".
- **GAS** - GAS MAIN EXISTS IN ROAD VERGE. BUILDER/HOME OWNER TO MAKE APPLICATION TO GAS PROVIDER FOR SERVICE INSTALLATION TO LOT.
- RETAINING WALL**
- ⊗ ⊠ **SERVICE TERMINATION POINT MARKER.** 900x50x25 HW STAKE, OR 40Ø ORANGE PVC CONDUIT STAKE



TYPICAL PROPERTY SERVICES CONNECTIONS DETAIL
NTS

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
24/02/2021	C	AMENDED ROAD NAMES	KK PB
08/09/2020	B	AMENDED LINE COLOURS AND LINE WEIGHTS	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK
			REC APP

Premise

BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG

CHECKED
M MAJZNER

PROJECT MANAGER
S STEINHOFER

PROJECT DIRECTOR
[Signature]
PATRICK BRADY RPEQ 7112

SCALE

SCALE 1:1000 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
OVERALL SERVICES LAYOUT

JOB CODE
MIR012-02

SHEET NUMBER
C003

REV
C

DESIGN HAZARD NOTES:

- PREMISE, HAVING BEEN COMMISSIONED TO CARRY OUT DETAILED DESIGN AND DOCUMENTATION OF THESE WORKS, CONFIRM THAT THE PREMISE DRAWING SET HAS BEEN INTERNALLY REVIEWED FOR DESIGN SAFETY IN ACCORDANCE WITH SECTION 22 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD.
- THIS REPORT SUMMARISES AN INTERNAL REVIEW OF PREMISE'S DETAILED DESIGN DRAWINGS FOR DESIGN SAFETY.
- THIS REPORT IN NO WAY RELIEVES THE PRINCIPAL, CONTRACTOR OR ANY OTHER PARTY OF THEIR OWN OBLIGATIONS AND RESPONSIBILITIES UNDER THE WORK HEALTH AND SAFETY ACT 2011 QLD, INCLUDING (BUT NOT LIMITED TO) CONSULTATION WITH THE DESIGNER UNDER SECTION 294 OF THE ACT, THE PREPARATION OF SATISFACTORY SAFE WORK METHOD STATEMENTS AND DUTIES OF CARE.
- IT IS A REQUIREMENT UNDER SECTION 296 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD, THAT A COPY OF THIS REPORT BE PROVIDED TO THE CONTRACTOR BY THE ENTITY COMMISSIONING THE WORK SHOWN OF THE PREMISE DRAWINGS.
- AS PER THE DEPARTMENT OF JUSTICE AND THE ATTORNEY-GENERAL- WORKPLACE HEALTH AND SAFETY QUEENSLAND, A WRITTEN REPORT IS NOT REQUIRED FOR DESIGNS THAT HAVE TYPICAL FEATURES.

CONSEQUENCE TABLE		
LEVEL	CONSEQUENCE	COST/TIME
5 - CATASTROPHIC	FATALITY OR MULTIPLE PERSONS ONSITE WITH LIFE THREATENING HEALTH EFFECT OR INABILITY TO CONTINUE	HUGE FINANCIAL OR TIME LOSS
4 - MAJOR	EXTENSIVE INJURIES, OR ONSET OF SEVERE OR LIFE THREATENING HEALTH EFFECT TO SINGLE PERSON ONSITE. MULTIPLE PERSONS WITH ONSET OF IRREVERSIBLE HEALTH EFFECTS. PERMANENT INJURY TO PERSON ONSITE.	MAJOR FINANCIAL OR TIME LOSS
3 - MODERATE	MEDICAL TREATMENT REQUIRED. IRREVERSIBLE HEALTH EFFECT TO A SINGLE PERSON. MULTIPLE PERSONS ONSITE WITH REVERSIBLE HEALTH EFFECTS.	HIGH FINANCIAL OR TIME LOSS
2 - MINOR	FIRST AID, SINGLE OR MULTIPLE INJURIES AMONGST PERSONS ONSITE. SINGLE PERSON ONSITE WITH MODERATE SHORT TERM REVERSIBLE HEALTH EFFECTS.	MEDIUM FINANCIAL OR TIME LOSS
1 - INSIGNIFICANT	NO INJURIES. OVER EXPOSURE TO A SINGLE PERSON ONSITE, BUT NO REPORTED HEALTH EFFECTS.	LOW FINANCIAL OR TIME LOSS

CONSTRUCTION HAZARD NOTES:

- UNDER THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011, THE WORK HEALTH AND SAFETY REGULATION 2011 AND OTHER LEGISLATION AND GUIDELINES, THE PRINCIPAL CONTRACTOR HAS SPECIFIC OBLIGATIONS IN RELATION TO THE SAFE OPERATION OF THE SITE AND OF THE WORKS.
TO ASSIST THE PRINCIPAL CONTRACTOR IN COMPLYING WITH THESE OBLIGATIONS THE PROJECT DESIGNERS HAVE IDENTIFIED BY DRAWING NOTES, AREAS WHERE POTENTIAL HAZARDS MAY ARISE. THESE NOTES OR ADVICE, SHALL NOT NECESSARILY BE CONSIDERED COMPLETE AND ARE BASED UPON THE DESIGNERS' UNDERSTANDING OF THE SAFETY RISKS ASSOCIATED WITH THE WORKS.
THESE NOTES OR ADVICE SHALL NOT RELIEVE THE PRINCIPAL CONTRACTOR OF ANY OBLIGATION UNDER THE RELEVANT LEGISLATION OR GUIDELINE. THE PRINCIPAL CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE PREPARATION OF AN APPROPRIATE WORK HEALTH SAFETY MANAGEMENT PLAN AND SAFE WORK METHOD STATEMENTS FOR THE SITE.
- PURSUANT TO THE WORK HEALTH AND SAFETY ACT 2011 WE HEREBY ADVISE THAT OUR DESIGN SAFETY REVIEW HAS IDENTIFIED UNUSUAL OR ATYPICAL DESIGN FEATURES THAT MAY PRESENT ADDITIONAL HAZARDS OR RISKS DURING THE CONSTRUCTION PHASE AND THESE ARE LISTED IN THE CONSTRUCTION HAZARD SCHEDULE.

RISK ANALYSIS MATRIX						
		1 - INSIGNIFICANT	2 - MINOR	3 - MODERATE	4 - MAJOR	5 - CATASTROPHIC
LIKELIHOOD	A - ALMOST CERTAIN	MODERATE	HIGH	EXTREME	EXTREME	EXTREME
	B - LIKELY	MODERATE	HIGH	HIGH	EXTREME	EXTREME
	C - POSSIBLE	LOW	MODERATE	HIGH	EXTREME	EXTREME
	D - UNLIKELY	LOW	LOW	MODERATE	HIGH	EXTREME
	E - RARE	LOW	LOW	MODERATE	HIGH	HIGH

RISK EVALUATION TABLE	
RISK LEVEL	ACTION REQUIRED
EXTREME	UNACCEPTABLE RISK. RE-DESIGN REQUIRED. DO NOT PROCEED WITHOUT ADDITIONAL CONTROLS.
HIGH	UNACCEPTABLE RISK. ADDITIONAL CONTROLS NEEDED. CONSIDER FURTHER REVIEW AND CONSIDER RE-DESIGN
MODERATE	RISK MAY BE ACCEPTABLE. MANAGEMENT TO DETERMINE ACTIONS REQUIRED
LOW	ACCEPTABLE. MANAGE RISK THROUGH ROUTINE PROCEDURES AND OTHER ADMINISTRATIVE CONTROLS

LIKELIHOOD TABLE		
LEVEL	DESCRIPTION	QUANTIFICATION GUIDE
A - ALMOST CERTAIN	THE EVENT <u>IS</u> EXPECTED TO OCCUR IN MOST CERTAIN CIRCUMSTANCES	MORE THAN ONCE PER YEAR
B - LIKELY	THE EVENT <u>WILL</u> PROBABLY OCCUR IN MOST CIRCUMSTANCES	AT LEAST ONCE IN 5 YEARS
C - POSSIBLE	THE EVENT <u>SHOULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 10 YEARS
D - UNLIKELY	THE EVENT <u>COULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 30 YEARS
E - RARE	THE EVENT <u>MAY</u> OCCUR IN EXCEPTIONAL CIRCUMSTANCES	LESS THAN ONCE IN 30 YEARS

DESIGN HAZARD SCHEDULE					
ITEM	DESIGN HAZARD	POTENTIAL HAZARD	RISK	ELIMINATION / MINIMISATION OF HAZARD / RISK	RESIDUAL RISK
D1	URBAN LAYOUT HAZARD	THE URBAN LAYOUT IS DESIGNED AROUND A PARTICULAR HAZARD :- - INTERSECTION IS UNCLEAR WHICH ROAD HAS PRIORITY	HIGH	THE HAZARD HAS BEEN REDUCED/ELIMINATED BY:- - LINE MARKED INTERSECTION TO ENSURE IT IS CLEAR WHICH ROAD HAS PRIORITY - DESIGN VEHICLE SWEEP PATH CHECKED FOR COMPLIANCE	LOW
D2	EXISTING UNDERGROUND / OVERHEAD SERVICES HAZARD	EXISTING UNDERGROUND AND/OR OVERHEAD SERVICES HAZARD EXIST ON SITE AND NEEDS TO BE REMOVED AND RELOCATED.	HIGH	THE DESIGN OF THE PROJECT HAS INCORPORATED THE RELOCATION OF THESE EXISTING SERVICES AND THE CONTRACTOR IS TO BE MADE AWARE OF THESE EXISTING SERVICES AND TAKE ALL ACTIONS NECESSARY TO MITIGATE THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D3	DEEP EXCAVATION HAZARD	DEEP EXCAVATION IS REQUIRED TO INSTALL SEWER TO SERVICE STRUCTURE.	HIGH	THE DEEP EXCAVATION HAZARD CANNOT BE AVOIDED AND THE CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D4	HIGH RETAINING WALLS	SOME AREAS OF WORKS CONTAIN HIGH RETAINING WALLS WHERE LAND MORPHOLOGY DICTATES.	HIGH	HIGH RETAINING WALLS CANNOT BE AVOIDED DUE TO EXISTING LAND MORPHOLOGY. SINGLE TIER WALLS HAVE LIMITED TO A MAX HEIGHT OF 2m. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D5	WATER BODIES	PROPOSED CONSTRUCTION WATER DAMS WILL BE PRESENT ON SITE.	MEDIUM	PROPOSED WATER BODIES HAVE BEEN LOCATED AWAY FROM PUBLIC ACCESS AREAS. ACCESS TO THESE LOCATION WILL BE RESTRICTED FROM THE PUBLIC. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	LOW

CONSTRUCTION HAZARD SCHEDULE		
ITEM	POTENTIAL HAZARD	POSSIBLE PREVENTATIVE ACTION
C1	DEEP EXCAVATION HAZARD	ALL STEPS MUST BE TAKEN TO OBTAIN CURRENT UNDERGROUND SERVICES INFORMATION BEFORE EXCAVATION WORKS COMMENCE. EXCAVATION WORK MUST BE UNDERTAKEN BY APPROPRIATELY EXPERIENCED AND QUALIFIED PERSONNEL. EXCAVATIONS SHALL BE ADEQUATELY SHORED AND APPROPRIATE BARRICADES AND SIGNAGE ERECTED, IF REQUIRED.
C2	OVERHEAD POWER HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF LIVE OVERHEAD CABLES. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING EARTHWORKS AND ANY OTHER HIGH RISK WORKS, IF REQUIRED.
C3	UNDERGROUND ELECTRICAL, TELECOMMUNICATION, GAS AND WATER MAIN HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF THE EXISTING SERVICE. THE SERVICE SHALL BE IDENTIFIED AND MARKED BY THE SUPPLY AUTHORITY PRIOR TO THE COMMENCEMENT OF EXCAVATION. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING THE EXCAVATION WORK, IF REQUIRED.
C4	WORKS NEAR RAIL, AIRPORTS AND ROADS HAZARD	ALL REQUIRED PERMITS, APPROVALS AND SAFETY REQUIREMENTS FROM THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHALL REMAIN ON SITE DURING CONSTRUCTION WHILE THE HAZARD REMAINS.
C5	PEDESTRIAN ACCESS HAZARD	WORK WITHIN OR ADJACENT TO AREAS WHICH THE PUBLIC REQUIRES PEDESTRIAN ACCESS MUST HAVE APPROPRIATE BARRICADES AND SIGNAGE ERECTED AT ALL TIMES.
C6	POTENTIAL VEHICLE HAZARD	SITE PERSONNEL SHALL BE ADVISED OF THE POTENTIAL HAZARDS AND THE APPROPRIATE PROCEDURES FOR WORKING ADJACENT TO OPERATING PUBLIC ROADS. APPROPRIATE SAFETY CLOTHING SHALL BE WORN AND THE REQUIRED SIGNAGE SHALL BE ERECTED. THE WORKS SHALL BE UNDERTAKEN IN A MANNER WHICH DOES NOT COMPROMISE THE SAFETY OF THE VEHICLE OCCUPANTS OR THE SITE PERSONNEL.
C7	DEMOLITION AND CLEARING HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE DEMOLITION AND CLEARING WORKS FOR THE PROJECT AT ALL TIMES. THE CONTRACTORS WORK METHOD STATEMENT SHALL ALSO GIVE CONSIDERATION TO FALLING DEBRIS, COLLAPSE AND DANGEROUS AIRBORNE AGENTS.
C8	TRAFFIC MANAGEMENT HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC THROUGH THE PROJECT AT ALL TIMES. THE CONTRACTOR SHALL DEVELOP A TRAFFIC MANAGEMENT PLAN (TMP) FOR THE PROJECT TO ESTABLISH APPROPRIATE CONTROLS IN ACCORDANCE WITH THE MANUAL FOR UNIFORM TRAFFIC CONTROL.
C9	ASBESTOS HAZARD	ALL PERSONNEL SHOULD BE ADVISED OF THE POTENTIAL PRESENCE OF ASBESTOS AND AN IDENTIFICATION AND ACTION PLAN SHALL BE PUT IN PLACE. SAMPLING AND IDENTIFICATION IS TO BE UNDERTAKEN IN ACCORDANCE WITH WORKPLACE HEALTH AND SAFETY REGULATIONS. IF SAMPLING CONFIRMS THE PRESENCE OF ASBESTOS THEN THE ACTION PLAN IS TO BE IMPLEMENTED TO REMEDIATE THE SITE.
C10	POTENTIAL ROCK FALL	LAND ABOVE THE SITE HAS BEEN CLEARED AND SOME EARTHWORKS HAS BEEN UNDERTAKEN CREATING A POTENTIAL ROCK FALL HAZARD. SUITABLE PERSONNEL SHALL BE RESPONSIBLE FOR IDENTIFYING ANY POTENTIAL HAZARD AND THE CONTRACTOR SHALL TAKE APPROPRIATE ACTION TO ELIMINATE THE HAZARD.

FOR CONSTRUCTION					
DATE	REV	DESCRIPTION	REC	APP	REVISIONS
20/08/2020	A	APPROVAL ISSUE	MM	PB	
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK		


Premise
 BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SAFETY IN DESIGN

JOB CODE
MIR012-02
 SHEET NUMBER
C004
 REV
A



LEGEND - PROPOSED

- PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
- PROPOSED 1.5m WIDE (U.N.O.) CONCRETE FOOTPATH. REFER LSC STD DWGS.
- PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
- DURATHM THRESHOLD TREATMENT. REFER TO LANDSCAPE PLANS FOR COLOUR AND PATTERN.
- PROPOSED STORMWATER
- PROPOSED STORMWATER STRUCTURE No.
- ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C400.
- ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C400.
- ROOFWATER DRAINAGE KERB ADAPTORS & PROPERTY PIT. REFER DETAIL ON DWG C400.
- PROPOSED ROOFWATER HOUSE CONNECTION (150 Ø uPVC)
- PROPOSED RETAINING WALL
- ZERO LOT BOUNDARY
- PROPOSED FUTURE DRIVEWAY LOCATION
- PROPOSED SEWER
- PROPOSED WATER
- PROPOSED WATER CONDUIT
- PAD MOUNTED TRANSFORMER
- PROPOSED LANDSCAPING WITHIN VERGE. CONCRETE EDGE RESTRAINT BY LANDSCAPING CONTRACTOR. CIVIL CONTRACTOR TO COORDINATE WITH LANDSCAPING CONTRACTOR TO CARRY OUT THEIR WORKS. REFER TO LANDSCAPE DRAWINGS FOR FURTHER DETAIL.

LEGEND - EXISTING

- EXISTING STORMWATER
- EXISTING SEWER
- EXISTING WATER
- EXISTING ELECTRICAL
- EXISTING TELSTRA
- EXISTING GAS
- EXISTING RISING MAIN
- EXISTING RETAINING WALL
- EXISTING STORMWATER STRUCTURE No.

PAVEMENT SUBGRADE GUARANTEE:
 CONTRACTOR SHALL UNDERTAKE EARTHWORKS REQUIRED IN EITHER CUT OR FILL TO ENSURE THE SUBGRADE QUALITY IS AT CBR10 OR GREATER. CONTRACTOR TO LAISE WITH OWN GEOTECHNICAL ENGINEER TO ACHIEVE REQUIREMENT.

- FOR TYPICAL SECTIONS AND NOTES REFER TO DRAWING No. C300 - ROADWORKS TYPICAL SECTIONS AND NOTES, AND DRAWING No. C400 - STORMWATER DRAINAGE DETAILS AND NOTES.

STORMWATER TRENCH BACKFILL NOTE:
 ALL STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

FOR CONSTRUCTION		REVISIONS	
DATE	REV	DESCRIPTION	
24/02/2021	C	AMENDED ROAD NAMES	KK PB
02/10/2020	B	AMENDED FOOTPATH AND KERB RAMPS ALIGNMENT	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK


Premise
 BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112

SCALE
 0 10 20 30m
 SCALE 1:500 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
ROADWORKS AND DRAINAGE LAYOUT - SHEET 1

JOB CODE		MIR012-02	
SHEET NUMBER	REV	C100	C




REFER TO C100 FOR LEGEND AND NOTES

FOR CONSTRUCTION		REVISIONS
DATE	REV	DESCRIPTION
24/02/2021	C	AMENDED ROAD NAME
02/10/2020	B	AMENDED FOOTPATH AND KERB RAMPS ALIGNMENT
20/08/2020	A	APPROVAL ISSUE
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION
DATE	REV	DESCRIPTION




BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
ROADWORKS AND DRAINAGE LAYOUT - SHEET 2

JOB CODE		MIR012-02
SHEET NUMBER	REV	
C101	C	




LEGEND - PROPOSED

- EXTENT OF CUT (EARTHWORKS UNDERTAKEN UNDER P12.1 CONTRACT)
- EXTENT OF FILL (EARTHWORKS UNDERTAKEN UNDER P12.1 CONTRACT)
- FINISHED MAJOR CONTOURS (0.50m)
- FINISHED MINOR CONTOURS (0.25m)
- FINISHED SURFACE LEVEL
- PROPOSED CONCRETE SLEEPER RETAINING WALL (AND HEIGHT), TIMBER TEXTURED SLEEPERS AND 2 COAT PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED CONCRETE PANEL RETAINING WALL (AND HEIGHT), 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED MASONRY WALL TO ENERGEX STANDARDS
- FEATURE FENCE ON TOP OF RETAINING WALL BY LANDSCAPER
- FOOTPATH SPOT LEVEL
- ZERO LOT LINE
- PROPOSED FUTURE DRIVEWAY LOCATION
- PAD MOUNTED TRANSFORMER
- VEGETATION CLEARING EXTENT
- STAGE BOUNDARY

LEGEND - EXISTING

- EXISTING RETAINING WALL
- EXISTING CONTOURS (0.50m)
- EXISTING STORMWATER
- EXISTING SEWER
- EXISTING TRUNK SEWER
- EXISTING SEWER RISING MAIN
- EXISTING WATER
- EXISTING ELECTRICITY
- EXISTING TELECOMMUNICATIONS
- EXISTING GAS
- EPBC EXCISION BOUNDARY



- NOTES**
1. REFER TO BULK EARTHWORKS NOTES & DETAILS DRAWINGS FOR:
 - EARTHWORKS NOTES AND DETAILS
 - RETAINING WALL NOTES AND DETAILS
 2. PROPOSED SERVICES ARE WITHIN THE VICINITY OF RETAINING WALLS. REFER SERVICE DRAWINGS FOR SERVICE LOCATIONS AND DETAILS.
 3. EXISTING DWELLINGS, FENCES ETC TO BE DEMOLISHED AND REMOVED OFF SITE BY OTHERS (UNLESS NOTED OTHERWISE)
 4. FINAL RETAINING WALL TYPES AND FINISHES SHALL BE CONFIRMED WITH THE SUPERINTENDENT PRIOR TO CONSTRUCTION.

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
24/02/2021	C	AMENDED ROAD NAME AND ADDED VIEWPORT TO SHOW RETAINING WALL	KK PB
08/09/2020	B	AMENDED NOTES	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK

Premise

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG

CHECKED
M MAJZNER

PROJECT MANAGER
S STEINHOFER

PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112

SCALE

0 10 20 30m

SCALE 1:500 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
BULK EARTHWORKS LAYOUT - SHEET 1 OF 2


JOB CODE
MIR012-02

SHEET NUMBER
C200

REV
C



JOINS DRAWING C200



- FOR TYPICAL SECTIONS AND NOTES REFER TO EARTHWORKS NOTES AND DETAILS
- REFER TO DRAWING No. C200 FOR LEGEND.


FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
24/02/2021	D	AMENDED ROAD NAMES	KK PB
16/12/2020	C	AMENDED RETAINING WALLS	KK PB
02/10/2020	B	AMENDED FOOTPATH AND KERB RAMP ALIGNMENT, AND EARTHWORKS IN PEDESTRIAN LINK	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK
			APP



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFFER
 PROJECT DIRECTOR

 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
BULK EARTHWORKS LAYOUT - SHEET 2 OF 2

JOB CODE		MIR012-02	
SHEET NUMBER	REV	C201	D

NOTES

1. LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
2. EARTHWORKS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL LAYOUT PLANS AND EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
3. ALL EARTHWORKS TO BE CARRIED OUT UNDER 'LEVEL ONE' GEOTECHNICAL CONTROL IN ACCORDANCE WITH LOCAL AUTHORITIES AND AS3798.
4. EXCESS CUT TO BE STOCKPILED IN THE LOCATION SHOWN OR AS DIRECTED ON SITE.
5. ALL BATTERS ARE 1 IN 4 UNLESS SHOWN OTHERWISE.
6. CONTRACTOR TO INSTALL TEMPORARY CONSTRUCTION FENCING ALONG THE FULL PERIMETER BOUNDARY INCLUDING APPROPRIATE SIGNAGE.

TESTING

1. THE SUPERINTENDENT MAY ORDER ADDITIONAL TESTS. REFER TO THE LOCAL AUTHORITIES SPECIFICATION FOR STANDARDS OF COMPACTION AND MATERIAL STANDARDS. FAILED TESTS WILL BE AT THE CONTRACTOR'S EXPENSE.

EARTHWORKS TESTING

1. COMPACTION TESTS

LOCATION	AREA PER TEST
FINISHED LEVEL OR ROAD SUBGRADE (IN CUT OR FILL)	REFER TO THE LOCAL AUTHORITY SPECIFICATION
LOWEST TWO LEVELS OF EMBANKMENT (PER LAYER)	
OTHER LAYERS OF EMBANKMENT	
PREPARED NATURAL GROUND UNDER EMBANKMENT	

2. QUALITY TESTS
QUALITY TESTS OF IMPORTED MATERIAL ARE REQUIRED AS SET OUT BY LOCAL AUTHORITY.
3. SUBGRADE TESTS
THE NUMBER AND LOCATION OF PAVEMENT SUBGRADE TESTS SHALL BE IN ACCORDANCE WITH LOGAN CITY COUNCIL SPECIFICATION REQUIREMENTS.

DUST

1. NO VISIBLE DUST EMISSIONS MUST OCCUR AT THE BOUNDARIES OF THE SITE DURING EARTHWORKS AND CONSTRUCTION ACTIVITIES ON THE SITE. DUST CONTROL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH AS/NZS3580.10.1:2003. DUST CONTROL SHALL COMPLY WITH THE NSW DEPARTMENT OF ENVIRONMENT AND CONSERVATION REPORT 'APPROVED METHODS & GUIDANCE FOR THE MODELLING AND ASSESSMENT OF AIR POLLUTANTS IN NSW.'
2. THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN CONTROLS TO ACHIEVE THE REQUIREMENTS OF ITEM 1 ABOVE.

FILL MANAGEMENT

1. ALL FILL MATERIAL WILL BE PLACED IN ACCORDANCE WITH THE FILL SPECIFICATION PROVIDED ON THIS SHEET, OR WHERE PROVIDED, THE REQUIREMENTS OF THE GEOTECHNICAL REPORT SPECIFIC TO THIS CONTRACT.
2. THE FILL MATERIAL WILL COMPRISE ONLY OF NATURAL EARTH AND ROCK AND SHALL BE FREE OF ALL CONTAMINATES, NOXIOUS, HAZARDOUS, DELETERIOUS AND ORGANIC MATERIAL.
3. ALL SITE PREPARATION WORK SHOULD GENERALLY BE CARRIED OUT IN ACCORDANCE WITH AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS'.
4. THE SITE SHOULD BE STRIPPED OF ANY TOPSOIL FROM CUT AND FILL AREAS, ROAD ALIGNMENTS AND CARPARKING AREAS, AND STOCKPILED FOR LATER USE.
5. PRIOR TO THE PLACEMENT OF ANY STRUCTURAL FILL THE SITE SHOULD BE PROOF ROLLED USING A MINIMUM 10 TONNE (STATIC WEIGHT) PADFOOT ROLLER. ANY LOOSE OR SOFT AREAS SHOULD BE REMOVED AND RECOMPACTED OR REPLACED USING A COMPACTED SELECT FILL.
6. DEPRESSIONS FORMED BY THE REMOVAL OR VEGETATION, EXISTING STRUCTURES, UNDERGROUND SERVICES ETC, SHOULD HAVE ALL DISTURBED SOIL CLEANED OUT AND BE BACKFILLED WITH COMPACTED SELECT FILL MATERIAL.
7. ALL COMPLIANCE TESTING SHALL BE CARRIED OUT BY THE GEOTECHNICAL ENGINEER WHO WILL BE ENGAGED BY THE PRINCIPAL CONTRACTOR. ANY/ALL TESTING NECESSARY FOR GUIDANCE OR RE-TESTS WILL BE AT THE COST OF THE CONTRACTOR.
8. THE PLACEMENT OF FILL TO BE EXECUTED SUCH THAT TO BE FREE DRAINING AT ALL TIMES AND NOT TO BE A NUISANCE OR PONDING TO ADJOINING PROPERTY OR ROADS.
9. NO DEMOLITION MATERIAL TO BE USED AS FILL MATERIAL.
10. WHERE UNSUITABLE MATERIAL IN AREAS OF FILL IS ENCOUNTERED, THIS WILL BE TREATED AS SET OUT IN THE EARTHWORK SPECIFICATION.
11. ALL VEHICLES EXITING FROM THE SITE TO BE CLEAN TO PREVENT MATERIAL BEING TRACKED OR DEPOSITED ON THE ADJOINING PUBLIC ROADS, REFER ENVIRONMENTAL MANAGEMENT NOTES ON THE EROSION AND SEDIMENT CONTROL DRAWINGS.
12. SITE ACCESS TO AND ACROSS THE SITE ARE SUBJECT TO SUPERINTENDENT APPROVAL.

TOPSOIL RESPREAD REQUIREMENTS

TOPSOIL RESPREAD THICKNESS SHALL BE AS SPECIFIED BELOW IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TOPSOIL RESPREAD LOCATIONS AND THICKNESS.

TURF

CONTRACTOR SHALL SUPPLY AND LAY TURF AS SPECIFIED IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TURF SUPPLY AND LAY AREAS.

TRENCH SPOIL

EXCESS TRENCH SPOIL MATERIAL GENERATED BY THIS CONTRACT SHALL BE PLACED EITHER WITHIN THE FILL ZONE NOMINATED ON THE EARTHWORKS DRAWINGS OR WITHIN A FILL ZONE NOMINATED BY THE SUPERINTENDENT THAT SHALL BE CONFIRMED PRIOR TO CONSTRUCTION COMMENCEMENT. FILL TO BE PLACED UNDER LEVEL 1 SUPERVISION AND IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION.

TRENCH BACKFILL

CBR15 STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

EXCAVATION IN ROCK

CONTRACT SHALL INCLUDE TREATING, SIZING, CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED TO ENSURE THAT FILL SPECIFICATION AND LEVEL ONE CERTIFICATION IS ACHIEVED.

EVERLEIGH EARTHWORKS TOLERANCE TABLE

ITEM	TOLERANCE
EARTHWORKS IN ALLOTMENTS AND VERGES ^(a)	EWL or FSL +/- 50mm
CUT BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 150mm ^(b)
FILL BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 300mm ^(b)
EARTHWORKS IN PARKS	EWL or FSL +/- 50mm

- ^(a) TOLERANCE IS -0mm / +50mm WHERE ADJACENT DRAINAGE ELEMENT.
^(b) MEASURED FROM THE AVERAGE SLOPE PLANE.

TOLERANCE NOTES

1. EARTHWORKS LEVEL (EWL) IS 100mm BELOW FINISHED SURFACE LEVEL (FSL) ON ALLOTMENTS (TOPSOIL RESPREAD THICKNESS).
2. FINISHED SURFACE LEVEL (FSL) IS TOP OF TURF / STABILISED TOPSOIL LEVEL.
3. ROADWORKS SUBGRADE, PAVEMENT, ASPHALT CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
4. STORMWATER DRAINAGE CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
5. SEWER AND WATER RETICULATION CONSTRUCTION LEVEL TOLERANCES AS PER SEQ D&C CODE.

DISPERSIVE SOILS MANAGEMENT NOTES

1. DISPERSIVE SOIL TREATMENT MEASURES IN THE FOLLOWING AREAS SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE REQUIREMENTS OF THE EVERLEIGH DISPERSIVE SOIL MANAGEMENT:
- WITHIN SERVICE TRENCHES
- SURFACE AREAS SURROUNDING STORMWATER HEADWALLS
- TURF/LANDSCAPED AREAS SUBJECT TO WATER FLOW
- TURF/LANDSCAPED AREAS SUBJECT TO WATER PONDING
2. STABILISATION OF DISTURBED AREAS AND MANAGEMENT OF EROSION AND SEDIMENT SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLANS IN THIS DRAWING SET.
3. CONTRACTOR MUST CONSTRUCT AND ESTABLISH THE EROSION AND SEDIMENT CONTROL DEVICES, CONSTRUCTION WATER HOLDING DAM AND HES BASIN PRIOR TO COMMENCING EARTHWORKS OPERATION.
4. ALL DISTURBED AREAS SHALL BE STABILISED AS SOON AS PRACTICABLE (BUT NOT MORE THAN 10 DAYS) FOLLOWING FINALISATION OF LEVELS. STABILISATION TO BE IN ACCORDANCE WITH EROSION & SEDIMENT CONTROL - STABILISATION PHASE.

TOPSOIL AMELIORATION

ONSITE STRIPPED TOPSOIL SHALL BE AMELIORATED PRIOR TO RESPREAD. THE FOLLOWING AMELIORATION SPECIFICATIONS SHALL APPLY:

A-GRADE QUALITY TOPSOIL AMELIORATION:

- SCREEN STRIPPED TOPSOIL
- ON-SITE COMPOST INCORPORATION (0.15kg/m³ OF TOPSOIL)
- DOLOMITE (15kg/m³ OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m³ OF TOPSOIL)
- FERTILISER (0.4kg/m³ OF TOPSOIL)

B-GRADE QUALITY TOPSOIL AMELIORATION:

- SCREEN STRIPPED TOPSOIL
- DOLOMITE (15kg/m³ OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m³ OF TOPSOIL)
- FERTILISER (0.4kg/m³ OF TOPSOIL)

ROCK TREATMENT IN ALLOTMENTS

WHERE ALLOTMENTS ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 500mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL), AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

ALL CUT LOTS WHICH ARE NOT LOCATED IN ROCK MUST ACHIEVE 100kPa BEARING CAPACITY. WHERE THIS CAN'T BE ACHIEVED, THE CONTRACTOR SHALL RECTIFY THE SUBGRADE IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION TO ACHIEVE A 100kPa BEARING CAPACITY.

ROCK TREATMENT IN VERGES

WHERE ROAD RESERVES ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 1000mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL) AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

EARTHWORKS SPECIFICATION

SPECIFICATION	DEPTH RANGE (m)				PAVEMENT SUBGRADE	TRENCH BACKFILL
	0.0 - 0.6	0.6 - 3.00	3.00 - 5.00	> 5.00		
CBR %	-	-	-	-	10	15
LAYER THICKNESS (mm)	300	300	300	300	BETWEEN SUBGRADE AND 0.3m BELOW	300
MAXIMUM PARTICLE SIZE (mm)	200	500	500	500	200	200
% PASSING 37.5mm	80% MIN	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES
% PASSING 0.075mm	30% MIN	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES AND AS3798
COMPACTION	95% STD	95% STD	95% STD	95% STD	100% STD	95% MOD IN ROADS AND 95% STD OUTSIDE ROADS
MOISTURE	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	60% - 90% OF OMC	+/- 2% OMC

- NOTES:**
1. OMC - OPTIMUM MOISTURE CONTENT
 2. LAYER OF THICKNESS IS LIMITED TO 300mm TO ALLOW IDENTIFICATION OF LARGER PARTICLES AND ALLOW EVERY CHANCE OF BREAK DOWN IN FILLING OR REMOVAL.
 3. TREATMENT OF ROCK TO SIZES ABOVE SHOULD BE CARRIED OUT IN CUT PRIOR TO LOADING TO FILL AREAS. TREATED ROCK TO BE APPROVED BY GITA PRIOR TO TRANSPORTING.
 4. UPPER 0.6m, (PARTICULARLY IN AREAS OF DEEP FILL), OF THE FILL PROFILE TO BE RELATIVELY IMPERMEABLE HENCE INCREASE IN FINES COMPONENT.
 5. PROOF ROLL TESTING ON EACH COMPACTED LAYER USING RUBBER WHEELED PLANT SUCH AS LOADED ADT'S OR LOADED SCRAPERS. UNFAVOURABLE DEFORMATION OF THE COMPACTED SURFACE UNDER LOAD OF ADT'S OR SCRAPERS WILL REQUIRE REPAIR PRIOR TO ADDITIONAL PLACEMENT.
 6. MECHANICAL INTERLOCK METHODOLOGY IS NOT APPROPRIATE DUE TO POOR DURABILITY OF SITE WON SANDSTONE. FILL COMPOSITION IS REQUIRED TO INCLUDE AN APPROPRIATE SAND GRAVEL AND FINES COMPONENT CONFORMING TO THE REQUIREMENTS OF AS798.

KEY OUTCOMES FOR EARTHWORKS OPERATIONS

1. DELIVER RESIDENTIAL LOTS WITH FAVOURABLE LOT CLASSIFICATIONS - I.E - NO P CLASSIFICATIONS
2. FILL THICKNESS DOES NOT VARY MORE THAN 2m OVER A DISTANCE OF 10m
3. CONSTRUCT FILL AND LIMIT LONG TERM CREEP SETTLEMENTS TO WITHIN 0.5% TO 1.0% OF THE FILL THICKNESS
4. BUILDING PLATFORM THAT ALLOWS BUILDERS TO CONSTRUCT SLAB ON GROUND RAFTS USING LIGHT EARTHMOVING EQUIPMENT
5. MATERIAL WON FROM CUTS AND USED IN FILL WITH REQUIRE
 - CUTS IN ROCK AS WELL AS BLENDED WITH
 - CUTS IN FINER MATERIALS SUCH AS SANDS AND CLAYS
6. CREATING A FILL PLATFORM THAT IS ABLE TO BE TESTED IN ACCORDANCE WITH AS3798 AND AS1289

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
08/09/2020	B	AMENDED NOTES	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK
DATE	REV	DESCRIPTION	REC APP

Premise
BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au


DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
[Signature]
PAT BRADY RPEQ 7112

SCALE


ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
BULK EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2


JOB CODE
MIR012-02
SHEET NUMBER
C210
REV
B




TYPICAL RETAINING WALL SUBSOIL OUTLET TO ROAD
N.T.S.



TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT
0.4m-2m MAX HIGH
N.T.S.




TYPICAL RETAINING WALL DETAIL
ROAD ADJACENT TO LOT WHERE ROAD LEVEL IS HIGHER
N.T.S.




TYPICAL RETAINING WALL DETAIL
ROAD ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER
N.T.S.


* WHERE WALL IS RETAINING PRIVATE ALLOTMENT PROVIDE TYPICALLY 100mm ADDITIONAL HEIGHT ABOVE FINISHED PAD LEVEL TO ACCOMMODATE FUTURE BUILDING SLAB AND TOP SOIL LEVELS. REFER TO TYPICAL RETAINING WALL LOT FINISHING DETAIL THIS SHEET.




TYPICAL RETAINING WALL SUBSOIL OUTLET TO ALLOTMENTS
N.T.S.




TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT
2m-3m MAX HIGH
N.T.S.




TYPICAL RETAINING WALL DETAIL
PARK ADJACENT TO LOT WHERE PARK LEVEL IS HIGHER
N.T.S.




TYPICAL RETAINING WALL DETAIL
PARK ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER
N.T.S.



TYPICAL INTER ALLOTMENT RETAINING WALL TOP OF WALL SETOUT AND END DETAIL
N.T.S.



TYPICAL RETAINING WALL TOP AND BOTTOM FINISHING LEVEL DETAIL
N.T.S.



TYPICAL SECTION FOR BATTERS BETWEEN LOTS
SCALE 1:20

RETAINING WALL DESIGN:
ALL RETAINING WALLS SHALL BE DESIGNED & CONSTRUCTED IN ACCORDANCE WITH THE "DESIGN AND CONSTRUCTION RETAINING WALL SPECIFICATION" PREPARED BY PREMISE ENGINEERING.

RETAINING WALL SUBSOIL DRAINAGE OUTLET DESIGN:
RETAINING WALL SUBSOIL DRAINAGE PIPE OUTLET LOCATIONS SHALL BE IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION. THE PRINCIPAL CIVIL CONTRACTOR SHALL DETERMINE THE LOCATION OF RETAINING WALL SUBSOIL DRAINAGE PIPES IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION AND PROVIDE PROPOSAL TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION.

RETAINING WALL SHOP DRAWINGS
CONTRACTOR MUST PREPARE RETAINING WALL SHOP DRAWINGS FOR APPROVAL BY SUPERINTENDENT PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION. SHOP DRAWINGS ARE TO DETAIL THE FOLLOWING ELEMENTS:
- ELEVATIONS OF ALL PROPOSED RETAINING WALLS AND ACOUSTIC FENCES
- TOP AND BOTTOM RLS TO SLEEPER/PANEL
- FINISHED PAD/ROAD SURFACE LEVELS
- DIMENSIONS OF RETAINING WALL END FINISHING CONFIGURATION, OFFSETS FROM BOUNDARIES
- POST DETAILS FOR INTRICATE INTERSECTION POINTS

PROPERTY SERVICES UNDER RETAINING WALLS:
CONTRACTOR SHALL REFER TO ALL LATEST SERVICE DRAWINGS TO ENSURE PROVISIONS ARE MADE FOR ALL PROPERTY SERVICE CONNECTIONS UNDER RETAINING WALLS.

PAD MOUNTED TRANSFORMER NOTE
- RETAINING WALLS AND THEIR FOOTINGS SHALL NOT ENCOACH INTO THE PMT SITE (AS PER RETAINING WALLS LOCATED ADJACENT ROAD RESERVES DETAIL) UNLESS THE RETAINING WALL SPECIFIED IS AN ENERGEX STANDARD MASONRY WALL.
- RETAINING WALL DESIGN SHALL CONSIDER ENERGEX REQUIREMENT WHERE RETAINING WALLS ARE LOCATED WITHIN 2m OF PMT SITE.

RETAINING WALL TYPE
PRIVATE FACING RETAINING WALLS:
CONCRETE SLEEPER RETAINING WALL. TIMBER TEXTURED SLEEPERS AND 2 COAT PAINT (COLOUR WARM GREY 10C). DESIGN SPECIFICATION BY MANUFACTURER.
PUBLIC FACING RETAINING WALLS:
CONCRETE PANEL RETAINING WALL. 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER.

FENCE BRACKETS
PROVIDE FENCE BRACKETS TO ALL RETAINING WALLS. NO BRACKETS TO BE PROVIDED WITHIN THE FIRST 5m FROM FRONT BOUNDARY FOR INTER-ALLOTMENT RETAINING WALLS.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
08/09/2020	B	ADDED NOTES	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB

Premise
BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
NTS
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
BULK EARTHWORKS NOTES AND DETAILS - SHEET 2 OF 2

JOB CODE
MIR012-02
SHEET NUMBER
C211
REV
B

NOTES

- ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARD DRAWINGS AND METHODS (U.N.O.).
- NOTWITHSTANDING THE LIMITS OF CUTTING AND FILLING SHOWN ON THE DRAWINGS, THE ACTUAL LIMITS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT DURING CONSTRUCTION AND SIMILARLY THE FINISHED SURFACE CONTOURS MAY BE ADJUSTED BY WRITTEN DIRECTION OF THE SUPERINTENDENT DURING CONSTRUCTION.
- THE CONTRACTOR IS TO ASCERTAIN THE EXACT LOCATION OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE COST OF RECTIFICATION OF ANY DAMAGES TO EXISTING SERVICES WHICH MAY OCCUR. THE LOCATION OF EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY.
- SUBGRADE TEST RESULTS TO BE FORWARDED TO SUPERINTENDENT FOR DETERMINATION OF BOX DEPTHS PRIOR TO EXCAVATION. TESTS SHALL INCLUDE SOAKED CBR AND/OR OTHER TESTS AS REQUESTED BY THE SUPERINTENDENT.
- ALLOTMENT FILLING TO BE COMPACTED TO 95% (min) OF THE R.D.D. (AS 1289 - TESTS E1.1, E4.1).
- LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.
- LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS APPROVED BY THE SUPERINTENDENT TO ACHIEVE SATISFACTORY CONNECTION TO THE EXISTING WORKS.
- SIDE DRAINS AND MITRE DRAINS TO BE CONSTRUCTED ADJACENT TO ALL KERB AND CHANNEL.
- PROVIDE FLUSH POINTS TO SUBSOIL DRAINS, LOCATIONS TO BE CONFIRMED ON SITE.
- ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION. ALL PIPES ARE 375mm DIAMETER U.N.O.
- GULLIES AND GULLY GRATES SHALL BE TO STD. DRGs BSD-8051 - BSD-8059.
- KACEY GALV. STEEL KERB ADAPTORS ARE TO BE INSTALLED TO THE REQUIREMENTS OF THE LOCAL COUNCILS STANDARD DRAWINGS AND SPECIFICATIONS.
- ALL LOTS SHOWN BOXED TO HAVE ROOFWATER FOOTPATH CROSSINGS TO KERB. CROSSINGS ARE TO BE 88.9 DIA. GALV. CHS. TO KACEY KERB ADAPTOR.
- ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
- ROOFWATER PITS ARE TO BE 600mm DIAMETER FOR DEPTHS LESS THAN 750mm, 900mm DIAMETER FOR DEPTHS BETWEEN 750mm AND 1500mm DEEP AND 1050mm DIAMETER FOR DEPTHS GREATER THAN 1500mm.
- ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- HAZARD MARKERS (D4-4A) TO BE PLACED AT THE END OF NEW WORKS AS DIRECTED BY SUPERINTENDENT.
- SITE CBR VALUE AND PAVEMENT DESIGN AND DEPTHS TO BE VERIFIED WITH CBR TESTS PRIOR TO CONSTRUCTION.
- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- TO BE READ IN CONJUNCTION WITH ALL STORMWATER DRAINAGE LAYOUT PLANS & ROADWORKS DETAILS.

ROADWORKS NOTES

- GEOTECHNICAL TESTING FOR PAVEMENT CONSTRUCTION IS TO BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT SPECIFICATION. TEST CERTIFICATES ARE TO BE PREPARED BY A REGISTERED N.A.T.A. LABORATORY AT THE CONTRACTORS COST AND SHALL BE PROVIDED TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS. THE CONTRACTOR IS TO NOTIFY THE ENGINEER OF ANY NON-CONFORMANCES. ALL NON CONFORMING WORK IS TO BE RECTIFIED AS DIRECTED BY THE ENGINEER.
- FULL DEPTH PAVEMENT CONSTRUCTION SHALL EXTEND BEHIND ALL KERB AND CHANNEL FOR A DISTANCE WHICH IS THE GREATER OF 150mm FROM THE BACK OF KERB OR ACROSS TO THE OUTER LIMIT OF SIDE DRAIN FILTER MATERIAL.
- TRANSITION KERB AND CHANNEL TO BARRIER KERB SMOOTHLY OVER MIN. 1.0m LENGTH.
- PAVEMENT THICKNESSES NOMINATED ON THESE DRAWINGS ARE PROVISIONAL ONLY AND MAY BE VARIED BY THE SUPERINTENDENT SUBJECT TO INSITU PAVEMENT SUBGRADE TESTING. PAVEMENT SUBGRADES ARE TO BE INITIALLY CONSTRUCTED TO THE UNDERSIDE OF THE NOMINATED LOWER SUBBASE COURSE WITHIN FILL AREAS, AND TO THE UNDERSIDE OF THE NOMINATED UPPER SUBBASE COURSE WITHIN CUT AREAS. INSITU SUBGRADE CBR TESTING AS SPECIFIED FOR PAVEMENT DESIGN VERIFICATION IS TO BE CARRIED OUT AT THESE LEVELS.
- REPAIR ANY DAMAGE TO EXISTING KERB AND CHANNEL, FOOTPATH OR ROADWAY (INCLUDING REMOVAL OF CONCRETE SLURRY FROM FOOTPATHS, ROADS, KERB AND CHANNEL AND STORMWATER GULLIES AND SIDEDRAINS) THAT MAY OCCUR DURING ANY WORKS CARRIED OUT.

CONCRETE PAVEMENT

- THE CONCRETE PAVEMENT HAS BEEN DESIGNED BASED ON A CBR 5 AND IS SUBJECT TO CONFIRMATION UPON RECEIPT OF CBR TEST RESULT AT TIME OF CONSTRUCTION.
- CONCRETE PAVEMENT SPECIFICATION:

COMPRESSIVE STRENGTH: 25 MPa @ 28 DAYS
 FLEXURAL STRENGTH: 3.5 MPa @ 28 DAYS
 MAXIMUM AGGREGATE SIZE: 20mm
 SLUMP: 80mm+15mm
 MESH: SL72, 50 TOP COVER
 BEDDING: 100mm MIN CBR 15 BEDDING


- MATERIALS AND WORKMANSHIP SHALL COMPLY WITH AS1379, AS3600 AND AS3610.
- PROJECT ASSESSMENT OF STRENGTH IN ACCORDANCE WITH AS3600 SHALL BE ADOPTED FOR SAMPLING AND TESTING. THE CONTRACTOR SHALL PAY ALL TESTING COSTS.
- CONSTRUCTION JOINTS SHALL BE MADE ONLY AT APPROVED LOCATIONS.
- ALL JOINTS ARE TO BE SEALED JUST PRIOR TO HANDOVER WITH DOW CORNING '888' SEALANT INSTALLED IN ACCORDANCE WITH MANUFACTURING RECOMMENDATIONS.
- JOINTS ARE TO BE INSPECTED AND SEALANT REGULARLY REPLACED IF REQUIRED.
- DIMENSIONAL TOLERANCES OF AS3600, MODIFIED BY AS3610, SHALL APPLY UNLESS OTHERWISE NOTED. SLAB SURFACE FLATNESS TOLERANCE SHALL BE 5mm MAXIMUM DEVIATION FOR A 3m STRAIGHT EDGE.
- CONCRETE PAVEMENTS ARE TO BE BROOM FINISHED. SLAB THICKNESSES NOTED ARE EXCLUSIVE OF APPLIED FINISHES
- CURE ALL CONCRETE BY AN APPROVED METHOD FOR 7 DAYS AFTER HARDENING. PVA AND RESIN BASED CURING COMPOUNDS SHALL NOT BE USED.

CONCRETE PAVEMENT MAINTENANCE NOTES


- NOTE THAT UPKEEP AND REPLACEMENT OF SEALANTS IS PART OF THE ONGOING MAINTENANCE REQUIREMENTS FOR THIS SITE.
- NOTE THAT SHRINKAGE CRACKS OF WIDTH < 1.5mm MAY OCCUR IN CONCRETE PAVEMENTS WITHIN 12 MONTHS OF INITIAL CASTING.
- NOTE THAT THE PAVEMENT WILL NOT BE MAINTENANCE FREE FOR ITS DESIGN LIFE.
- INSPECT FLUSH SIDE DRAINS AND SUBSOIL DRAINS EVERY 12 MONTHS.

CONCRETE REQUIREMENTS

ITEM	28 DAY STRENGTH	CONCRETE CYLINDER TEST	TESTING FREQUENCY
KERB & CHANNEL	N32	REQUIRED	1 TEST PER 300m
VEHICULAR CROSSINGS	N25	REQUIRED	1 TEST PER CROSSING
BIKEWAYS	N25	REQUIRED	1 TEST PER 300m
FOOTPATHS	N25	REQUIRED	1 TEST PER 300m
CONCRETE CHANNELS	N25	REQUIRED	1 TEST PER 150m ²
STRUCTURES	AS DESIGN	REQUIRED	AS DIRECTED
ROOFWATER MH'S	N20	NOT REQUIRED	
STORMWATER MH'S	N25	NOT REQUIRED	
PRECAST MANHOLE ROOF SLABS	N40	NOT REQUIRED	
GULLY PITS			
.. PRECAST LINTEL	N30	NOT REQUIRED	
.. OTHER	N25	NOT REQUIRED	




SAWCUT JOINT (S.J.)




TYPICAL PAVEMENT CUT-BACK DETAIL

N.T.S




TYPICAL KERB RECESS / END DETAIL




PLAN

NOTE: REFER LAYOUT PLAN FOR TRANSITION RECESS & KERB END LOCATIONS & LENGTHS



KERB END DETAIL



TYPICAL FUTURE ROADS BOX-OUT TREATMENT

SCALE 1:20


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	
DATE	REV	DESCRIPTION	REC	APP



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED: K KIWANG
 CHECKED: M MAJZNER
 PROJECT MANAGER: R LLEWELYN
 PROJECT DIRECTOR: PAT BRADY
 RPEQ 7112



CLIENT

MIRVAC GROUP

PROJECT: EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION: TEVIOT ROAD, GREENBANK
 SHEET TITLE: ROADWORKS NOTES AND DETAILS

JOB CODE

MIR012-02

SHEET NUMBER: C300
 REV: A

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- RUSSETT STREET
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data


Vertical Geometry Grade (%)
Vertical Grade Length (m)

Vertical Curve Length (m)
Vertical Curve Radius (m)


DATUM R.L.56.0

CUT (-)/FILL DEPTH	-0.586	-0.986	-1.661	-2.358	-3.352	-3.472	-3.211	-4.463	-4.356	-3.904	-3.159	-1.773	-0.967	-0.768	-0.316	-0.113	0.024	0.057	0.063	0.070	0.032	0.000
LHS LIP LEVEL	*	62.825	62.889	63.066	64.638	66.209	67.229	67.760	69.038	69.683	69.993	70.875	71.757	72.639	72.847	72.932	73.019	73.348	73.418	73.450	73.493	0.000
RHS LIP LEVEL	*	62.825	62.889	63.066	64.638	66.209	67.229	67.760	69.038	69.683	69.993	70.875	71.757	72.639	72.847	72.932	73.019	73.348	73.418	73.450	73.493	0.000
DESIGN SURFACE	62.695	62.601	62.559	62.581	62.912	62.976	63.153	64.725	66.296	67.316	67.847	69.125	69.770	70.080	70.962	71.844	72.726	72.954	73.019	73.348	73.450	73.493
NATURAL SURFACE	63.281	63.587	64.220	64.938	66.244	66.448	66.364	69.188	70.652	71.219	71.006	70.898	70.737	70.848	71.278	71.956	72.702	72.877	72.957	73.386	73.438	73.493
CHAINAGE	0.00	3.75	7.13	9.58	16.90	17.75	20.00	40.00	60.00	72.97	80.00	100.00	112.97	120.00	140.00	160.00	180.00	184.72	186.72	196.10	198.72	201.72


RUSSETT STREET LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



CHAINAGE 60* DATUM R.L. 63.00



CHAINAGE 40 DATUM R.L. 61.00



CHAINAGE 20 DATUM R.L. 59.00

RUSSETT STREET LONGITUDINAL SECTION
SCALE 1:100


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAMES	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
S STEINHOFER
PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
RUSSETT STREET LONG & CROSS SECTIONS

JOB CODE	
MIR012-02	
SHEET NUMBER	REV
C310	B

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- OLIVE AVENUE
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm


CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS

Vertical Geometry Grade (%)
Vertical Grade Length (m)
Vertical Curve Length (m)
Vertical Curve Radius (m)

DATUM R.L.48.0

CHAINAGE	NATURAL SURFACE	DESIGN SURFACE	RHS LIP LEVEL	LHS LIP LEVEL	CUT (-)/FILL DEPTH
0.00	54.107	54.107			0.000
8.50	53.831	53.894			0.063
19.46	53.757	53.757	53.695	53.700	0.000
20.00	53.758	53.758	53.696	53.700	0.000
28.50	53.850	53.850	53.788	53.793	0.000
35.73	53.999	53.999	53.957	53.942	0.000
40.00	54.090	54.090	54.028	54.032	0.000
60.00	54.571	54.571	54.509	54.513	0.000
75.73	55.017	55.017	54.955	54.959	0.000
80.00	55.146	55.146	55.084	55.088	0.000
100.00	55.751	55.751	55.689	55.694	0.000
106.12	55.936	55.936	55.874	55.879	0.000
120.00	56.413	56.413	56.351	56.355	0.000
140.00	57.297	57.297	57.235	57.240	0.000
156.12	58.181	58.181	58.119	58.124	0.000
160.00	58.412	58.412	58.350	58.354	0.000
180.00	59.602	59.602	59.540	59.545	0.000
200.00	60.793	60.793	60.731	60.736	0.000
220.00	61.984	61.984	61.922	61.926	0.000
240.00	63.174	63.174	63.112	63.117	0.000
260.00	64.365	64.365	64.303	64.308	0.000
264.58	64.638	64.638	64.576	64.580	0.000
280.00	65.394	65.394	65.332	65.337	0.000
290.50	65.725	65.725	65.663	65.667	-0.000
300.00	65.895	65.895	65.822	65.824	-0.000
304.58	65.933	65.933	65.855	65.856	-0.000
312.10	65.972	65.972	65.885	65.885	-0.000
320.00	66.014	66.014	65.927	65.927	-0.000
340.00	66.118	66.118	66.031	66.031	-0.000
360.00	66.223	66.223	66.136	66.136	-0.000
365.53	66.289	66.252	66.165	66.165	-0.037
380.00	66.627	66.523	66.436	66.436	-0.105
395.53	67.329	67.247	67.160	67.160	-0.081
400.00	67.737	67.521	67.434	67.434	-0.216
406.37	68.138	67.910	67.823	67.823	-0.228
420.00	69.019	68.600	68.513	68.513	-0.418
436.37	69.649	69.052	68.965	68.965	-0.597
440.00	69.745	69.106	69.019	69.019	-0.639
460.00	70.191	69.406	69.319	69.319	-0.786
466.38	70.246	69.501	69.414	69.414	-0.745
472.60	70.276	69.548	69.461	69.461	-0.728
473.85	70.278	69.546	69.459	69.459	-0.732
480.00	70.104	69.482	69.395	69.395	-0.622
495.45	68.906	68.918	68.831	68.831	0.012
496.38	68.817	68.866	68.779	68.779	0.049
500.00	68.469	68.658	68.571	68.571	0.189
520.00	66.254	67.512	67.425	67.425	1.258
539.45	65.917	66.396	66.309	66.309	2.480
540.00	63.857	66.366	66.279	66.279	2.509
549.20	62.843	66.117	66.117	66.117	3.274
553.45	62.363	66.170	66.170	66.170	3.807
557.20	61.980	66.264	66.264	66.264	4.284




FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK
DATE	REV	DESCRIPTION	REC APP



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
[Signature]
PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT



LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
OLIVE AVENUE LONGITUDINAL SECTION

JOB CODE
MIR012-02

SHEET NUMBER
C311

REV
A



FOR CONSTRUCTION


DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR

 PAT BRADY RPEQ 7112



CLIENT **MIRVAC GROUP**
 PROJECT **EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT**
 LOCATION **TEVIOT ROAD, GREENBANK**
 SHEET TITLE **OLIVE AVENUE CROSS SECTIONS**

JOB CODE **MIR012-02**
 SHEET NUMBER **C312**
 REV **A**

EXISTING PRECINCT 1.1 EXISTING PRECINCT 12.1 PRECINCT 12.2 FUTURE PRECINCT

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- MOSS STREET
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ²
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.


* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

Vertical Geometry Grade (%)
Vertical Grade Length (m)
Vertical Curve Length (m)
Vertical Curve Radius (m)

DATUM R.L.55.0

CUT (-)/FILL DEPTH	LHS LIP LEVEL	RHS LIP LEVEL	DESIGN SURFACE	NATURAL SURFACE	CHAINAGE
0.00			62.505	62.505	0.00
-0.029			62.411	62.440	3.75
0.064			62.327	62.263	10.47
0.000	62.339	62.339	62.426	62.426	17.75
0.000	62.400	62.400	62.487	62.487	20.00
0.000	62.568	62.568	62.655	62.655	26.20
0.000	62.905	62.905	62.992	62.992	40.00
0.000	63.208	63.208	63.295	63.295	56.20
0.000	63.267	63.267	63.354	63.354	60.00
0.000	63.365	63.365	63.452	63.452	66.26
-0.016	63.599	63.599	63.686	63.702	80.00
3.019	64.014	64.014	64.101	61.083	100.00
3.061	64.162	64.162	64.249	61.188	106.26
3.184	64.496	64.496	64.583	61.398	120.00
3.197	64.981	64.981	65.068	61.871	140.00
3.238	65.467	65.467	65.554	62.315	160.00
3.792	*	65.952	66.039	62.247	180.00
4.754	66.438	66.438	66.525	61.771	200.00
5.272	66.802	66.802	66.889	61.617	215.00
5.280	66.886	66.886	66.973	61.693	218.45
5.285	66.923	66.923	67.010	61.726	220.00
5.283	66.944	66.944	67.031	61.749	220.87
4.592	67.283	67.283	67.370	62.778	233.66
4.332	67.384	67.384	67.471	63.139	237.11
4.113	67.471	67.471	67.558	63.445	240.00
3.049	67.826	67.826	67.913	64.864	250.87
2.013	*	68.140	68.227	66.214	260.00
0.651	68.830	68.830	68.917	68.265	280.00
0.010	69.502	69.502	69.589	69.579	300.00
0.110	70.018	70.018	70.105	69.995	315.46
0.060	70.162	70.162	70.249	70.189	320.00
-0.001	70.608	70.608	70.695	70.696	340.00
-0.120	70.677	70.677	70.764	70.885	345.46
-0.251	70.831	70.831	70.918	71.169	360.00
-0.486	71.043	71.043	71.130	71.616	380.00
-0.030	71.255	71.255	71.342	71.372	400.00
-0.012	71.262	71.262	71.349	71.361	400.69
-0.045	71.296	71.296	71.383	71.429	403.96
-0.016	71.303	71.303	71.390	71.406	404.54
0.010	71.455	71.455	71.542	71.532	418.94
-0.002	71.461	71.461	71.548	71.550	419.52
-0.024	71.466	71.466	71.553	71.577	420.00




FOR CONSTRUCTION



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au



DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
S STEINHOFER
PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
MOSS STREET LONGITUDINAL SECTION

JOB CODE
MIR012-02
SHEET NUMBER
C313
REV
B

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAMES AND FINISHED SURFACE LEVELS	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB
		REVISIONS		




FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAME	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT


LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
MOSS STREET CROSS SECTIONS - SHEET 1 OF 2

JOB CODE
MIR012-02

SHEET NUMBER
C314

REV
B




FOR CONSTRUCTION



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
MOSS STREET CROSS SECTIONS - SHEET 2 OF 2

JOB CODE
MIR012-02
 SHEET NUMBER
C315
 REV
A

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	

EXISTING PRECINCT 1.1

EXISTING PRECINCT 12.1

PRECINCT 12.2

FUTURE PRECINCT 9.2

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- BOTANICA ROAD
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS


Horiz Curve Data

Vertical Geometry Grade (%)
Vertical Grade Length (m)

Vertical Curve Length (m)
Vertical Curve Radius (m)

DATUM R.L.47.0

CUT (-)/FILL DEPTH	LHS LIP LEVEL	RHS LIP LEVEL	DESIGN SURFACE	NATURAL SURFACE	CHAINAGE
0.000			55.078	55.078	0.00
-0.000			54.984	54.984	3.75
0.000			54.876	54.876	12.40
0.000			54.917	54.917	17.75
0.000			54.952	54.952	20.00
0.000			55.262	55.262	40.00
0.000			55.299	55.299	42.40
0.000			55.698	55.698	60.00
0.000			56.460	56.460	80.00
0.044			56.573	56.529	82.40
4.595			57.377	52.782	97.40
4.693			57.440	52.834	100.00
4.910			58.167	53.257	112.40
4.864			58.521	53.656	120.00
4.612			59.163	54.551	133.81
4.412			59.447	55.035	140.00
3.454			60.309	56.854	160.00
2.426			61.087	58.661	180.00
1.694			61.225	59.532	183.81
0.912			61.808	60.895	200.00
0.098			62.235	62.138	211.89
-0.169			62.590	62.559	216.19
-0.369			62.519	62.888	220.00
-0.386			62.849	63.234	233.49
-0.795			62.804	63.186	236.19
-0.163			62.857	63.107	240.00
-0.179			63.001	63.267	250.19
-0.356			63.098	63.541	257.11
-0.480			63.129	63.696	259.19
-0.551			63.143	63.760	260.00
-1.476			63.555	65.118	277.11
-1.485			63.646	65.219	280.00
-3.543			64.274	67.904	299.84
-3.566			64.279	67.932	300.00
-3.980			64.507	68.487	304.65
-4.149			64.650	68.799	309.71
-4.225			64.757	68.982	313.84
-4.278			64.851	69.129	317.59




FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAMES	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB





BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
S STEINHOFER
PROJECT DIRECTOR
(Signature)
PATRICK BRADY RPEQ 7112



CLIENT	MIRVAC GROUP	JOB CODE	MIR012-02
PROJECT	EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER	C316
LOCATION	TEVIOT ROAD, GREENBANK	REV	B
SHEET TITLE	BOTANICA ROAD LONGITUDINAL SECTION		



*FOR SURFACE STABILISATION TREATMENT OF WORKS OUTSIDE OF PRECINCT 12.2, REFER TO DRAWING C730 - EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAME	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB
DATE	REV	DESCRIPTION	REC	APP

REVISIONS

Premise

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG

CHECKED
M MAJZNER

PROJECT MANAGER
S STEINHOFER

PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112

SCALE

0 2 4 6m

SCALE 1:100 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
BOTANICA ROAD CROSS SECTIONS

JOB CODE
MIR012-02

SHEET NUMBER
C317

REV
B

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- DRIVEWAY 4
CLASS	- REAR ACCESS DRIVEWAY
ESA's	- 1.1 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 100mm
TOTAL BOX	- 285mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION. ASSUMED CBR 10 SUBGRADE PRIOR TO TESTING

* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

Vertical Geometry Grade (%)
Vertical Grade Length (m)
Vertical Curve Length (m)
Vertical Curve Radius (m)



35.57% -7.38% -2.59%
-7.42% 3.56% -1.57%
-0.08% -2.62% 0.12% -4.27% -1.22%
6.33m 2.42m 1.14m 26.87m 36.65m
0.01m 0.22m 0.07m
0.04m 0.22m
0.05m
R 184.67
L 20
R 654.17

DATUM R.L.55.0	
CUT (-)/FILL DEPTH	3.502
LHS LIP LEVEL	* 64.604
RHS LIP LEVEL	* 64.515
DESIGN SURFACE	64.627
NATURAL SURFACE	61.125
CHAINAGE	0.00

DRIVEWAY 4 LONGITUDINAL SECTION

SCALE 1:1000(H) 1:100(V)

INT. BAMBOO ROAD CH.0
SAG CH. 3.83 RL.64.513
IP CH. 3.83 RL.64.513
CH. 4.00 RL.64.513
IP CH. 4.00 RL.64.513
CREST CH. 4.13 RL.64.618
IP CH. 4.13 RL.64.618
IP CH. 4.18 RL.64.618
IP CH. 10.51 RL.64.519
IP CH. 37.38 RL.63.370



DRIVEWAY 4 LONGITUDINAL SECTION

SCALE 1:1000(H) 1:100(V)

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	

Premise
BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
DWAY 4 LONG & CROSS SECTIONS

JOB CODE
MIR012-02
SHEET NUMBER
C318
REV
A

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- BAMBOO ROAD
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ²
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

Vertical Geometry Grade (%)


Vertical Grade Length (m)

Vertical Curve Length (m)

Vertical Curve Radius (m)

DATUM R.L.55.0

CUT (-)/FILL DEPTH	-0.102	-0.122	-0.178	-0.264	-0.316	-0.406	-1.322	-1.832	-1.831	-1.831	-1.738	-1.889	-2.027	-1.423	-0.279	0.650	1.072	2.247	2.796	2.911	4.247	4.387	4.582	4.988	5.132	5.187	5.133
LHS LIP LEVEL				72.113	71.984	71.901	71.159	70.417	69.675	69.675	68.878	67.968	67.469	66.959	65.937	65.218	64.948	64.564	64.530	64.529	64.759	64.871	65.034	65.731	66.500	66.602	*
RHS LIP LEVEL				72.113	71.984	71.901	71.159	70.417	69.675	69.675	68.878	67.968	67.469	66.959	65.937	65.218	64.948	64.564	64.530	64.529	64.759	64.871	65.034	65.731	66.500	66.602	*
DESIGN SURFACE	72.600	72.506	72.390	72.200	72.071	71.988	71.246	70.504	69.762	69.762	68.965	68.055	67.556	67.046	66.024	65.305	65.035	64.651	64.617	64.616	64.846	64.958	65.121	65.818	66.587	66.689	67.068
NATURAL SURFACE	72.702	72.628	72.568	72.464	72.387	72.394	72.568	72.336	71.593	71.593	70.703	69.944	69.583	68.470	66.303	64.654	63.963	62.404	61.871	61.705	60.598	60.571	60.539	60.829	61.455	61.532	61.881
CHAINAGE	0.00	3.75	8.06	14.11	17.75	20.00	40.00	60.00	80.00	80.02	100.00	120.00	130.02	140.00	160.00	174.07	180.00	194.97	200.00	201.01	216.57	220.00	224.07	240.00	257.59	260.00	271.59



FOR CONSTRUCTION



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au



DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
BAMBOO ROAD LONGITUDINAL SECTION

JOB CODE
MIR012-02
SHEET NUMBER
C319
REV
A

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	



* FOR SURFACE STABILISATION TREATMENT OF WORKS OUTSIDE OF PRECINCT 12.2, REFER TO MIR-012-01 DRAWING C730 - EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
BAMBOO ROAD CROSS SECTIONS

JOB CODE
MIR012-02

SHEET NUMBER
C320

REV
A

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- DRIVEWAY 1
CLASS	- REAR ACCESS DRIVEWAY
ESA's	- 1.1 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 100mm
TOTAL BOX	- 285mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION. ASSUMED CBR 10 SUBGRADE PRIOR TO TESTING

* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

4.08%	-0.08%	0.07%
36.15%	36.3%	-7.49%
-2.59%	-2.42%	4%
2.4%	4.27%	
0.13m	0.16m	0.01m
0.12m	0.15m	1.76m
4.89m	0.02m	1.72m
2.77m	0.03m	

DATUM R.L.63.0


CUT (-)/FILL DEPTH	-0.490	-0.795	-0.801	-0.971	-0.983	-1.062	-1.164
LHS LIP LEVEL	* 69.551	69.562	69.562	69.853	69.882	70.063	70.300
RHS LIP LEVEL	* 69.551	69.562	69.562	69.853	69.882	70.063	70.300
DESIGN SURFACE	69.404	69.551	69.562	69.853	69.882	70.063	70.300
NATURAL SURFACE	69.894	70.346	70.363	70.824	70.865	71.125	71.464
CHAINAGE	0.00	7.75	8.03	15.08	15.75	20.00	25.53

DRIVEWAY 1 LONGITUDINAL SECTION

SCALE 1:1000(H) 1:100(V)

OLIVE AVENUE CH.0
 IP CH. 0.01 RL.69.404 CREST CH. 0.01 RL.69.404 IP CH. 1.73 RL.69.363 IP CH. 3.49 RL.69.317
 IP CH. 3.63 RL.69.306 SAG CH. 3.76 RL.69.297 IP CH. 3.76 RL.69.297 IP CH. 3.91 RL.69.355
 IP CH. 4.05 RL.69.402 CREST CH. 4.07 RL.69.402 IP CH. 4.07 RL.69.402 SAG CH. 4.10 RL.69.402
 IP CH. 6.87 RL.69.515 IP CH. 11.75 RL.69.711

NATURAL SURFACE
 DESIGN SURFACE



DRIVEWAY 1 CROSS SECTION

SCALE 1:100


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
 K KIWANG
 CHECKED
 M MAJZNER
 PROJECT MANAGER
 R LLEWELYN
 PROJECT DIRECTOR
 PAT BRADY RPEQ 7112



CLIENT
 MIRVAC GROUP
 PROJECT
 EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
 TEVIOT ROAD, GREENBANK
 SHEET TITLE
 DWAY 1 LONG & CROSS SECTIONS

JOB CODE
 MIR012-02
 SHEET NUMBER
 C321
 REV
 A

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- DRIVEWAY 2
CLASS	- REAR ACCESS DRIVEWAY
ESA's	- 1.1 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 100mm
TOTAL BOX	- 285mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION. ASSUMED CBR 10 SUBGRADE PRIOR TO TESTING

* REFER TO INTERSECTION DETAILS PLANS



Horiz Curve Data	-0%	36.26%	36.21%
Vertical Geometry Grade (%)	-7.41%	-2.44%	-2.5%
Vertical Grade Length (m)	0.26m	3.35m	0.13m
Vertical Curve Length (m)	0.05m	2.76m	0.28m
Vertical Curve Radius (m)			

DATUM R.L.63.0

CUT (-)/FILL DEPTH	-0.822	-0.865	-1.015	-1.772	-1.752
LHS LIP LEVEL	*	69.378	69.643	69.900	69.900
RHS LIP LEVEL	*	69.378	69.643	69.900	69.900
DESIGN SURFACE	68.961	69.051	69.378	69.643	69.900
NATURAL SURFACE	69.782	69.916	70.393	71.415	71.652
CHAINAGE	0.00	6.33	13.89	20.00	25.92

DRIVEWAY 2 LONGITUDINAL SECTION

SCALE 1:1000(H) 1:100(V)



DRIVEWAY 2 CROSS SECTION

SCALE 1:100


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
24/02/2021	B	AMENDED ROAD NAME	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
DWAY 2 LONG & CROSS SECTIONS

JOB CODE
MIR012-02
 SHEET NUMBER
C322
 REV
B

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- AMBER CIRCUIT
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 ⁵
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS


Horiz Curve Data

Vertical Geometry Grade (%)
Vertical Grade Length (m)

Vertical Curve Length (m)
Vertical Curve Radius (m)

DATUM R.L.61.0

CUT (-)/FILL DEPTH	1.289	1.101	0.751	0.654	0.615	0.159	-0.288	-0.533	-0.563	-0.766	-0.743	-0.780	-1.015	-1.385	-2.385	-2.745	-2.101	-1.382	-1.340	-1.159	-1.122	-1.180	-1.351	-1.379	-1.554	-1.584	0.088	0.158	0.207
LHS LIP LEVEL	*	*	68.168	68.198	68.466	68.678	68.733	68.754	68.932	68.956	68.972	69.059	69.182	69.305	69.427	69.550	69.673	69.680	69.721	69.847	69.890	70.219	70.276	70.817	70.921	71.372	71.427	71.466	
RHS LIP LEVEL	*	*	68.168	68.198	68.466	68.678	68.733	68.754	68.932	68.956	68.972	69.059	69.182	69.305	69.427	69.550	69.673	69.680	69.721	69.847	69.890	70.219	70.276	70.817	70.921	71.372	71.427	71.466	
DESIGN SURFACE	68.429	68.335	68.222	68.255	68.285	68.553	68.765	68.820	68.841	69.019	69.043	69.059	69.146	69.269	69.392	69.514	69.637	69.760	69.767	69.808	69.934	69.977	70.306	70.363	70.904	71.008	71.372	71.427	71.466
NATURAL SURFACE	67.141	67.235	67.471	67.601	67.669	68.394	69.053	69.353	69.405	69.785	69.786	69.839	70.161	70.652	71.777	72.259	71.738	71.141	71.107	70.966	71.055	71.156	71.657	71.742	72.459	72.592	71.284	71.269	71.259
CHAINAGE	0.00	3.75	12.86	17.75	20.00	40.00	55.78	60.00	61.75	80.00	83.35	85.78	100.00	120.00	140.00	160.00	180.00	200.00	201.18	207.88	220.00	222.78	237.88	240.00	260.00	263.82	277.82	280.00	281.57



FOR CONSTRUCTION



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
K KIWANG
CHECKED
M MAJZNER
PROJECT MANAGER
S STEINHOFER
PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT

MIRVAC GROUP

PROJECT

EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION

TEVIOT ROAD, GREENBANK

SHEET TITLE

AMBER CIRCUIT LONGITUDINAL SECTION

JOB CODE

MIR012-02



SHEET NUMBER

C323

REV

B

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	B	AMENDED ROAD NAMES AND DESIGN SURFACE LEVELS	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB



*FOR SURFACE STABILISATION TREATMENT OF WORKS OUTSIDE OF PRECINCT 12.2, REFER TO MIR-012-01 DRAWING C730 - EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
11/06/2021	B	AMENDED ROAD NAME	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	




BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PAT BRADY RPEQ 7112




CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
AMBER CIRCUIT CROSS SECTIONS


JOB CODE
MIR012-02
 SHEET NUMBER
C324
 REV
B




INTERSECTION AMBER CIRCUIT & DRIVEWAY 2



INTERSECTION OLIVE AVENUE & MOSS STREET
 INTERSECTION MOSS STREET & BAMBOO STREET
 INTERSECTION AMBER CIRCUIT & MOSS STREET



INTERSECTION BAMBOO ROAD & DRIVEWAY 4



INTERSECTION BOTANICA ROAD & RUSSETT STREET

LEGEND

- 12.0 — FINISHED MAJOR CONTOURS (0.50m)
- 0.10m — FINISHED MINOR CONTOURS (0.10m)
- ▬ PROPOSED 1.5m WIDE CONCRETE FOOTPATH. (UNO) REFER CONC. REQUIREMENTS ON DRG. No. C300
- ▬ PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
- ▬ PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- ▬ PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
- LIP OF KERB LEVEL
- TRANSITION IN KERB AND CHANNEL TYPE
- D — PROPOSED STORMWATER
- S — PROPOSED SEWER
- W — PROPOSED WATER

EXISTING - LEGEND

- - - D - - - EXISTING STORMWATER
- - - S - - - EXISTING SEWER
- - - W - - - EXISTING WATER
- - - E - - - EXISTING ELECTRICAL
- - - T - - - EXISTING TELSTRA
- - - G - - - EXISTING GAS
- - - RM - - - EXISTING SEWER RISING MAIN

NOTE

LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	C	AMENDED ROAD NAMES	KK	PB
02/10/2020	B	AMENDED FOOTPATH AND KERB RAMPS ALIGNMENT	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB





BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
PBR
 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
INTERSECTION DETAILS LAYOUT

JOB CODE MIR012-02	
SHEET NUMBER C330	REV C



LINEMARKING NOTES

- PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD, QUEENSLAND DEPARTMENT OF MAIN ROADS) AND THE SPECIFIC REQUIREMENTS OF REFERENCE SPECIFICATION S150 ROADWORKS. BRISBANE CITY COUNCILS SPECIFIC REQUIREMENTS ARE DETAILED ON STANDARD DRAWINGS BSD-3151 TO BDS-3163.
- ALL INTERNAL LINE MARKING TO CONSIST OF LINES 100mm WIDE WITH 2 COATS OF PAINT TO MANUFACTURERS SPECIFICATIONS.
- EXTENT OF LINEMARKING SHALL BE VERIFIED ON SITE PRIOR TO INSTALLATION.
- ALL PAINTED MARKINGS SHALL BE APPROVED REFLECTORISED U.N.O.
- ANY EXISTING LINE MARKINGS DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED.
- EXISTING CONFLICTING LINE MARKINGS ARE TO BE GROUND OFF BY METHODS APPROVED BY THE DISTRICT ENGINEER.
- RETRO-REFLECTIVE RAISED PAVEMENT MARKERS (RRPM's) SHALL BE PLACED 25mm TO 50mm FROM THE PAINTED LINEMARKING AND ORIENTATED SO THAT FULL REFLECTIVE EFFECT IS ACHIEVED BY AIMING THE REFLECTIVE FACE IN THE DIRECTION OF APPROACHING TRAFFIC. GENERALLY THE NORMAL SPACING BETWEEN RRPM'S IS TO BE 12.0m U.N.O.
- ANY EXISTING LINEMARKING NOT SHOWN ON THIS PLAN WHICH CONFLICTS OR IS INCOMPATIBLE WITH THE PROPOSED LINEMARKING SHALL BE REMOVED BY THE CONTRACTOR.
- NOSE OF ISLANDS TO BE PAINTED WHITE WITH GLASS BEADS.
- ALL STREET LIGHTING IN ACCORDANCE WITH AS1158.

SIGNAGE NOTES

- LOCATION OF SIGNS SHOWN INDICATED ON THIS PLAN ARE INDICATIVE ONLY. CARE AND CONSIDERATION IS TO BE GIVEN TO ON SITE CONDITIONS TO AVOID ANY VISUAL OBSTRUCTION OF THE SIGN ALONG THE INTENDED COURSE OF APPROACHING TRAFFIC. EXACT LOCATION OF ALL SIGNS SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.
- SIGNS SHOULD BE ORIENTATED AT APPROXIMATELY RIGHT ANGLES TO, AND FACING THE TRAFFIC THEY ARE INTENDED TO SERVE.
- SIGNAGE SHALL BE IN ACCORDANCE WITH:
 - AS1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
 - AS1743 ROAD SIGNS SPECIFICATION
 - AS4049.1 PAVEMENT MARKING MATERIALS
- STREET NAME SIGNS ARE TO BE INSTALLED WITH THE RELEVANT HOUSE NUMBERS IN ACCORDANCE WITH THE RELEVANT LOCAL COUNCIL STANDARD DRAWINGS.

LEGEND

- DURATHEN THRESHOLD TREATMENT. REFER TO LANDSCAPE PLANS FOR COLOUR AND PATTERN.
- AC SURFACE DRIVEWAY
- TACTILE GROUND SURFACE INDICATORS (TGSI's) TO BE INSTALLED AT ALL KERB RAMPS ON MAJOR ROADS IN ACCORDANCE WITH AUSTRALIAN STANDARD AS1428.1 (2009)

REQUIRED SIGNS



FOR CONSTRUCTION				
DATE	REV	DESCRIPTION	REC	APP
24/02/2021	C	AMENDED ROAD NAME	KK	PB
02/10/2020	B	BREAK BETWEEN TWO SOLID LINE MARKINGS AMENDED	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB

Premise
 BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au



DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
 PATRICK BRADY RPEQ 7112

SCALE

 SCALE 1:500 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 1 OF 2

JOB CODE
MIR012-02
 SHEET NUMBER
C340
 REV
C



LINEMARKING NOTES

- PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD, QUEENSLAND DEPARTMENT OF MAIN ROADS) AND THE SPECIFIC REQUIREMENTS OF REFERENCE SPECIFICATION S150 ROADWORKS. BRISBANE CITY COUNCILS SPECIFIC REQUIREMENTS ARE DETAILED ON STANDARD DRAWINGS BSD-3151 TO BDS-3163.
- ALL INTERNAL LINE MARKING TO CONSIST OF LINES 100mm WIDE WITH 2 COATS OF PAINT TO MANUFACTURERS SPECIFICATIONS.
- EXTENT OF LINEMARKING SHALL BE VERIFIED ON SITE PRIOR TO INSTALLATION.
- ALL PAINTED MARKINGS SHALL BE APPROVED REFLECTORISED U.N.O.
- ANY EXISTING LINE MARKINGS DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED.
- EXISTING CONFLICTING LINE MARKINGS ARE TO BE GROUND OFF BY METHODS APPROVED BY THE DISTRICT ENGINEER.
- RETRO-REFLECTIVE RAISED PAVEMENT MARKERS (RRPM's) SHALL BE PLACED 25mm TO 50mm FROM THE PAINTED LINEMARKING AND ORIENTATED SO THAT FULL REFLECTIVE EFFECT IS ACHIEVED BY AIMING THE REFLECTIVE FACE IN THE DIRECTION OF APPROACHING TRAFFIC.
- GENERALLY THE NORMAL SPACING BETWEEN RRPM'S IS TO BE 12.0m U.N.O.
- ANY EXISTING LINEMARKING NOT SHOWN ON THIS PLAN WHICH CONFLICTS OR IS INCOMPATIBLE WITH THE PROPOSED LINEMARKING SHALL BE REMOVED BY THE CONTRACTOR.
- NOSE OF ISLANDS TO BE PAINTED WHITE WITH GLASS BEADS.
- ALL STREET LIGHTING IN ACCORDANCE WITH AS1158.

SIGNAGE NOTES

- LOCATION OF SIGNS SHOWN INDICATED ON THIS PLAN ARE INDICATIVE ONLY. CARE AND CONSIDERATION IS TO BE GIVEN TO ON SITE CONDITIONS TO AVOID ANY VISUAL OBSTRUCTION OF THE SIGN ALONG THE INTENDED COURSE OF APPROACHING TRAFFIC. EXACT LOCATION OF ALL SIGNS SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.
- SIGNS SHOULD BE ORIENTATED AT APPROXIMATELY RIGHT ANGLES TO, AND FACING THE TRAFFIC THEY ARE INTENDED TO SERVE.
- SIGNAGE SHALL BE IN ACCORDANCE WITH:
 - AS1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
 - AS1743 ROAD SIGNS SPECIFICATION
 - AS4049.1 PAVEMENT MARKING MATERIALS
- STREET NAME SIGNS ARE TO BE INSTALLED WITH THE RELEVANT HOUSE NUMBERS IN ACCORDANCE WITH THE RELEVANT LOCAL COUNCIL STANDARD DRAWINGS.

LEGEND

- DURATHEM THRESHOLD TREATMENT. REFER TO LANDSCAPE PLANS FOR COLOUR AND PATTERN.
- AC SURFACE DRIVEWAY
- TACTILE GROUND SURFACE INDICATORS (TGSIs) TO BE INSTALLED AT ALL KERB RAMPS ON MAJOR ROADS IN ACCORDANCE WITH AUSTRALIAN STANDARD AS1428.1 (2009)

REQUIRED SIGNS



FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	C	AMENED ROAD NAME	KK	PB
02/10/2020	B	AMENED FOOTPATH AND KERB RAMPS ALIGNMENT AND BREAK BETWEEN TWO SOLID LINE MARKINGS	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG

CHECKED
M MAJZNER

PROJECT MANAGER
S STEINHOFER

PROJECT DIRECTOR
[Signature]
PATRICK BRADY RPEQ 7112

SCALE

SCALE 1:500 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP


PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
PAVEMENT MARKINGS AND SIGNAGE LAYOUT - SHEET 2 OF 2

JOB CODE
MIR012-02

SHEET NUMBER	REV
C341	C



LAYOUT PLAN
SCALE: 1:500

LEGEND - PROPOSED

- 1.8m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- 2.4m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- H1.80 TOTAL HEIGHT FROM TOP OF FENCE TO LOWEST POINT ON EITHER SIDE OF ACOUSTIC FENCE


LEGEND - EXISTING

- 1.8m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.

NOTE:
THESE ACOUSTIC FENCE PLANS SHOULD BE READ IN CONJUNCTION WITH THE C200 SERIES EARTHWORKS DRAWINGS.

THESE DRAWINGS HAVE BEEN PREPARED IN ACCORDANCE WITH THE ATP CONSULTING ENGINEERS NOISE IMPACT ASSESSMENTS, DOCUMENT NO. ATP 170617-R-TNIA-01, DATED 24 MARCH 2020, AND DOCUMENT NO. ATP 170617-R-TNIA-02, DATED 9 NOVEMBER 2020.

- THE PROPOSED ACOUSTIC FENCE SHALL BE CONSTRUCTED AS FOLLOWS:
- THE ACOUSTIC FENCE SHOULD BE CONSTRUCTED TO COMPLY WITH TMR'S ROAD TRAFFIC NOISE MANAGEMENT: CODE OF PRACTICE.
 - MATERIAL WITH MINIMUM SURFACE DENSITY OF 15kg/m², E.G. TIMBER PALINGS WITH MINIMUM THICKNESS 20mm; FIBRE-CEMENT SHEETING WITH MINIMUM THICKNESS OF 12mm; MASONRY; AND AERATED CONCRETE.
 - THE NOISE BARRIER SHOULD BE FREE OF ANY GAPS. IF THE NOISE BARRIER IS CONSTRUCTED OF TIMBER PALINGS, PLANKS SHOULD HAVE MINIMUM 35mm OVERLAP.
 - NO GAPS SHALL BE LEFT BETWEEN THE FENCE AND THE GROUND.
 - THE NOISE BARRIER SHOULD BE OF DURABLE CONSTRUCTION.



TYPICAL SECTION A-A
SCALE 1:50

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
25/02/2021	B	AMENDED NOTE AND ACOUSTIC FENCE ON LOT 3005, ADDED 2.4M HIGH MODULAR WALLS TO LEGEND	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	


Premise
 BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED: K KIWANG
 CHECKED: M MAJZNER
 PROJECT MANAGER: S STEINHOFER
 PROJECT DIRECTOR: Patrick Brady
 RPEQ 7112

SCALE
 0 10 20 30m
 SCALE 1:500 (A1)
 0 1 2 3m
 SCALE 1:50 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT: MIRVAC GROUP
 PROJECT: EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION: TEVIOT ROAD, GREENBANK
 SHEET TITLE: ACOUSTIC FENCE LAYOUT PLAN

JOB CODE: M1R012-02
 SHEET NUMBER: C350
 REV: B



LEGEND

- PROPOSED STORMWATER CATCHMENT BOUNDARY.
- STORMWATER CATCHMENT NUMBER AND AREA
- PROPOSED STORMWATER LINE
- EXISTING STORMWATER LINE
- FINISHED CONTOURS (0.50m)
- FINISHED CONTOURS (0.25m)
- EXISTING CONTOURS (0.50m)


FOR CONSTRUCTION

DD/MM/YYYY	REV	DESCRIPTION	MM REC	PB APP
20/08/2020	A	APPROVAL ISSUE		
	1	PRELIMINARY - NOT FOR CONSTRUCTION		



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
B ADAMS
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
[Signature]
 PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP


PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
STORMWATER DRAINAGE CATCHMENT PLAN

JOB CODE		MIR012-02
SHEET NUMBER	REV	
C400	A	

STRUCTURE NAME	5/502	6/502	7/502	8/502
STRUCTURE DESCRIPTION	IPWEA MANHOLE 1050mm DIA	IPWEA MANHOLE 1200mm DIA	IPWEA MANHOLE 1200mm DIA	IPWEA MANHOLE 1050mm DIA




PIPE SIZE (mm)	450	600	600
PIPE CLASS	2	2	2
PIPE GRADE (%)	3.86%	2.76%	1.80%
PIPE SLOPE (1 in X)	25.9	36.2	55.6
FULL PIPE VELOCITY (m/s)	1.42	2.58	3.16
PART FULL VELOCITY (m/s)	3.33	3.92	3.16
PIPE FLOW (cumecs)	0.226	0.731	0.895
PIPE CAPACITY AT GRADE (cumecs)	0.560	1.020	0.824
DATUM RL	51.0		

WSE IN STRUCTURE	69.102	67.421	65.178	65.178	64.417
HGL IN PIPE	69.061	67.407	65.178	65.178	64.417
DEPTH OF INVERT BELOW FSL	1.427	1.678	1.792	1.812	1.625
INVERT LEVEL	68.611	66.576	64.290	64.270	63.733
FINISHED (& EXISTING) SURFACE LEVEL	70.038 (73.534)	68.254 (66.471)	66.083 (61.999)	64.270 (61.999)	63.358 (61.999)
CHAINAGE	0.000	52.728	77.412	130.140	29.835

LINE 502

5/506	6/506	7/506	8/506	6/502
IPWEA MANHOLE 1200mm DIA	IPWEA MANHOLE 1500mm DIA	IPWEA MANHOLE 1050mm DIA	IPWEA MANHOLE 1350mm DIA	IPWEA MANHOLE 1200mm DIA




PIPE SIZE (mm)	450	600	600	600
PIPE CLASS	2	2	2	2
PIPE GRADE (%)	0.42%	0.98%	1.38%	0.78%
PIPE SLOPE (1 in X)	240.0	101.8	72.7	128.7
FULL PIPE VELOCITY (m/s)	1.60	1.16	1.16	1.66
PART FULL VELOCITY (m/s)	1.60	2.19	2.49	2.15
PIPE FLOW (cumecs)	0.254	0.329	0.327	0.469
PIPE CAPACITY AT GRADE (cumecs)	0.184	0.609	0.720	0.541
DATUM RL	53.0			

WSE IN STRUCTURE	68.558	68.100	67.874	67.558	67.421
HGL IN PIPE	68.523	68.098	67.874	67.558	67.421
DEPTH OF INVERT BELOW FSL	1.507	1.389	1.543	1.599	1.828
INVERT LEVEL	67.796	67.573	67.261	66.593	66.446
FINISHED (& EXISTING) SURFACE LEVEL	69.304 (72.835)	68.962 (71.077)	68.804 (69.518)	68.192 (67.279)	68.254 (66.471)
CHAINAGE	0.000	53.652	16.491	47.103	135.586

LINE 506

1/507	6/502
IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1200mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.1
FULL PIPE VELOCITY (m/s)	0.40
PART FULL VELOCITY (m/s)	1.32
PIPE FLOW (cumecs)	0.044
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	51.0

WSE IN STRUCTURE	67.574	67.421
HGL IN PIPE	67.495	67.407
DEPTH OF INVERT BELOW FSL	1.115	1.160
INVERT LEVEL	67.120	67.093
FINISHED (& EXISTING) SURFACE LEVEL	68.235 (66.562)	68.254 (66.471)
CHAINAGE	0.000	2.657

LINE 507

1/508	2/508	7/502
IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1200mm DIA




PIPE SIZE (mm)	375	375
PIPE CLASS	2	2
PIPE GRADE (%)	1.00%	1.70%
PIPE SLOPE (1 in X)	100.0	58.8
FULL PIPE VELOCITY (m/s)	1.14	1.61
PART FULL VELOCITY (m/s)	1.73	2.29
PIPE FLOW (cumecs)	0.126	0.177
PIPE CAPACITY AT GRADE (cumecs)	0.175	0.229
DATUM RL	47.0	

WSE IN STRUCTURE	65.841	65.178
HGL IN PIPE	65.570	65.178
DEPTH OF INVERT BELOW FSL	1.315	1.812
INVERT LEVEL	64.759	64.405
FINISHED (& EXISTING) SURFACE LEVEL	66.074 (62.931)	66.083 (61.999)
CHAINAGE	0.000	21.039

LINE 508

1/509	7/502
IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1200mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	4.00%
PIPE SLOPE (1 in X)	25.0
FULL PIPE VELOCITY (m/s)	0.07
PART FULL VELOCITY (m/s)	1.28
PIPE FLOW (cumecs)	0.007
PIPE CAPACITY AT GRADE (cumecs)	0.351
DATUM RL	47.0

WSE IN STRUCTURE	65.315	65.178
HGL IN PIPE	65.313	65.178
DEPTH OF INVERT BELOW FSL	1.115	1.251
INVERT LEVEL	64.938	64.832
FINISHED (& EXISTING) SURFACE LEVEL	66.053 (61.689)	66.083 (61.999)
CHAINAGE	0.000	2.649

LINE 509

1/516	6/506
IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1500mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.20%
PIPE SLOPE (1 in X)	83.3
FULL PIPE VELOCITY (m/s)	0.25
PART FULL VELOCITY (m/s)	1.24
PIPE FLOW (cumecs)	0.028
PIPE CAPACITY AT GRADE (cumecs)	0.192
DATUM RL	53.0

WSE IN STRUCTURE	68.220	68.100
HGL IN PIPE	68.188	68.098
DEPTH OF INVERT BELOW FSL	1.133	1.231
INVERT LEVEL	67.813	67.751
FINISHED (& EXISTING) SURFACE LEVEL	68.946 (71.326)	68.962 (71.077)
CHAINAGE	0.000	6.870

LINE 516

1/517	6/506
IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1500mm DIA



PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.53
PART FULL VELOCITY (m/s)	1.43
PIPE FLOW (cumecs)	0.059
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	53.0

WSE IN STRUCTURE	68.318	68.100
HGL IN PIPE	68.177	68.098
DEPTH OF INVERT BELOW FSL	1.116	1.186
INVERT LEVEL	67.802	67.776
FINISHED (& EXISTING) SURFACE LEVEL	68.918 (71.236)	68.962 (71.077)
CHAINAGE	0.000	2.623

LINE 517


FOR CONSTRUCTION

20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	REC	APP
DATE	REV	DESCRIPTION	REC	APP



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au


DESIGNED B ADAMS	
CHECKED M MAJZNER	
PROJECT MANAGER R LLEWELYN	
PROJECT DIRECTOR <i>Pat Brady</i>	
PAT BRADY	RPEQ 7112



CLIENT	MIRVAC GROUP
PROJECT	EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	STORMWATER DRAINAGE LONG SECTIONS - SHEET 1

JOB CODE	MIR012-02
SHEET NUMBER	C410
REV	A


STRUCTURE NAME	1/518
STRUCTURE DESCRIPTION	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel
	8/506
	IPWEA MANHOLE 1350mm DIA



PIPE SIZE (mm)	525
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.35
PART FULL VELOCITY (m/s)	1.50
PIPE FLOW (cumecs)	0.076
PIPE CAPACITY AT GRADE (cumecs)	0.430
DATUM RL	51.0

LINE 518


STRUCTURE NAME	1/519
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	8/506
	IPWEA MANHOLE 1350mm DIA



PIPE SIZE (mm)	525
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.38
PART FULL VELOCITY (m/s)	1.53
PIPE FLOW (cumecs)	0.082
PIPE CAPACITY AT GRADE (cumecs)	0.430
DATUM RL	51.0

LINE 519


STRUCTURE NAME	4/524
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	5/524
	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	6/524
	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel ON 1050mm DIA MANHOLE
	7/524
	IPWEA MANHOLE 1200mm DIA
	8/524
	IPWEA MANHOLE 1050mm DIA
	9/524
	IPWEA KERB INLET L.L.I.; 2.4m Lintel ON 1050mm DIA MANHOLE
	10/524
	IPWEA MANHOLE 1050mm DIA
	12/524
	IPWEA MANHOLE 1500mm DIA
	13/524
	IPWEA MANHOLE 1500mm DIA



PIPE SIZE (mm)	450	600	675	675	675	675	675	750
PIPE CLASS	2	2	2	2	2	2	2	2
PIPE GRADE (%)	4.88%	1.99%	4.22%	2.90%	1.72%	2.20%	3.00%	3.34%
PIPE SLOPE (1 in X)	20.5	50.1	23.7	34.5	58.0	45.5	33.3	29.9
FULL PIPE VELOCITY (m/s)	1.42	0.94	1.10	1.10	1.10	1.29	1.29	1.96
PART FULL VELOCITY (m/s)	3.64	2.69	3.91	3.41	2.82	3.23	3.61	4.42
PIPE FLOW (cumecs)	0.227	0.265	0.394	0.394	0.392	0.463	0.461	0.866
PIPE CAPACITY AT GRADE (cumecs)	0.630	0.868	1.728	1.432	1.104	1.247	1.457	2.036
DATUM RL	46.0							

LINE 524


STRUCTURE NAME	1/527
STRUCTURE DESCRIPTION	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel
	6/524
	IPWEA KERB INLET L.L.I.; 2.4m Lintel ON 1050mm DIA MANHOLE



PIPE SIZE (mm)	450
PIPE CLASS	2
PIPE GRADE (%)	1.10%
PIPE SLOPE (1 in X)	90.9
FULL PIPE VELOCITY (m/s)	0.68
PART FULL VELOCITY (m/s)	1.73
PIPE FLOW (cumecs)	0.108
PIPE CAPACITY AT GRADE (cumecs)	0.299
DATUM RL	46.0

LINE 527


STRUCTURE NAME	4/528
STRUCTURE DESCRIPTION	IPWEA MANHOLE 1050mm DIA
	5/528
	IPWEA MANHOLE 1050mm DIA
	11/524
	IPWEA MANHOLE 1200mm DIA
	12/524
	IPWEA MANHOLE 1500mm DIA



PIPE SIZE (mm)	375	450	525
PIPE CLASS	2	2	2
PIPE GRADE (%)	6.20%	6.24%	3.00%
PIPE SLOPE (1 in X)	16.1	16.0	33.3
FULL PIPE VELOCITY (m/s)	1.24	1.40	1.45
PART FULL VELOCITY (m/s)	3.49	3.96	3.28
PIPE FLOW (cumecs)	0.136	0.223	0.310
PIPE CAPACITY AT GRADE (cumecs)	0.437	0.713	0.745
DATUM RL	51.0		

LINE 528

STRUCTURE NAME	1/529
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	2/529
	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	3/529
	IPWEA KERB INLET L.L.I.; 2.4m Lintel
	12/524
	IPWEA MANHOLE 1500mm DIA



PIPE SIZE (mm)	375	375	525
PIPE CLASS	2	2	2
PIPE GRADE (%)	2.03%	1.65%	3.00%
PIPE SLOPE (1 in X)	49.2	60.7	33.3
FULL PIPE VELOCITY (m/s)	0.34	0.60	0.45
PART FULL VELOCITY (m/s)	1.62	1.77	2.38
PIPE FLOW (cumecs)	0.037	0.066	0.098
PIPE CAPACITY AT GRADE (cumecs)	0.250	0.225	0.745
DATUM RL	47.0		

LINE 529

FOR CONSTRUCTION			
07/10/2020	B	AMENDED FINISHED SURFACE LEVELS AND DEPTH TO INVERT ON STRUCTURES 9/524 AND 10/524	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	REC APP
DATE	REV	DESCRIPTION	REVISIONS

Premise

BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
B ADAMS

CHECKED
M MAJZNER

PROJECT MANAGER
R LLEWELYN

PROJECT DIRECTOR
PAT BRADY

RPEQ 7112

SCALE

HORIZONTAL 1:1000 (A1)

VERTICAL 1:100 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
STORMWATER DRAINAGE LONG SECTIONS - SHEET 2

JOB CODE
MIR012-02

SHEET NUMBER
C411

REV
B

STRUCTURE NAME	1/530	11/524
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Linet	IPWEA MANHOLE 1200mm DIA
PIPE SIZE (mm)	450	
PIPE CLASS	2	
PIPE GRADE (%)	3.00%	
PIPE SLOPE (1 in X)	33.3	
FULL PIPE VELOCITY (m/s)	0.28	
PART FULL VELOCITY (m/s)	1.92	
PIPE FLOW (cumecs)	0.044	
PIPE CAPACITY AT GRADE (cumecs)	0.494	
DATUM RL	46.0	
WSE IN STRUCTURE	61.756	61.576
HGL IN PIPE	61.718	61.576
DEPTH OF INVERT BELOW FSL	1.197	1.343
INVERT LEVEL	61.268	60.750
FINISHED (& EXISTING) SURFACE LEVEL	62.465 (64.141)	62.525 (64.119)
CHAINAGE	0.000	2.868
LINE	530	

STRUCTURE NAME	1/557	5/528
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Linet	IPWEA MANHOLE 1050mm DIA
PIPE SIZE (mm)	375	
PIPE CLASS	2	
PIPE GRADE (%)	1.29%	
PIPE SLOPE (1 in X)	77.3	
FULL PIPE VELOCITY (m/s)	0.41	
PART FULL VELOCITY (m/s)	1.46	
PIPE FLOW (cumecs)	0.045	
PIPE CAPACITY AT GRADE (cumecs)	0.199	
DATUM RL	50.0	
WSE IN STRUCTURE	64.318	63.744
HGL IN PIPE	64.236	63.885
DEPTH OF INVERT BELOW FSL	1.316	1.083
INVERT LEVEL	63.861	63.050
FINISHED (& EXISTING) SURFACE LEVEL	65.177 (69.527)	64.847 (68.942)
CHAINAGE	0.000	7.481
LINE	557	

STRUCTURE NAME	1/558	5/528
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Linet	IPWEA MANHOLE 1050mm DIA
PIPE SIZE (mm)	375	
PIPE CLASS	2	
PIPE GRADE (%)	1.01%	
PIPE SLOPE (1 in X)	99.2	
FULL PIPE VELOCITY (m/s)	0.40	
PART FULL VELOCITY (m/s)	1.32	
PIPE FLOW (cumecs)	0.044	
PIPE CAPACITY AT GRADE (cumecs)	0.175	
DATUM RL	49.0	
WSE IN STRUCTURE	64.220	63.744
HGL IN PIPE	64.141	63.864
DEPTH OF INVERT BELOW FSL	1.150	1.111
INVERT LEVEL	63.766	63.050
FINISHED (& EXISTING) SURFACE LEVEL	64.916 (69.138)	64.847 (68.942)
CHAINAGE	0.000	2.976
LINE	558	

STRUCTURE NAME	1/559	11/524
STRUCTURE DESCRIPTION	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Linet	IPWEA MANHOLE 1200mm DIA
PIPE SIZE (mm)	375	
PIPE CLASS	2	
PIPE GRADE (%)	1.01%	
PIPE SLOPE (1 in X)	99.4	
FULL PIPE VELOCITY (m/s)	0.41	
PART FULL VELOCITY (m/s)	1.33	
PIPE FLOW (cumecs)	0.045	
PIPE CAPACITY AT GRADE (cumecs)	0.175	
DATUM RL	46.0	
WSE IN STRUCTURE	61.846	61.576
HGL IN PIPE	61.763	61.576
DEPTH OF INVERT BELOW FSL	1.113	1.205
INVERT LEVEL	61.388	61.320
FINISHED (& EXISTING) SURFACE LEVEL	62.501 (64.735)	62.525 (64.119)
CHAINAGE	0.000	6.688
LINE	559	


FOR CONSTRUCTION



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
B ADAMS
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR

 PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
STORMWATER DRAINAGE LONG SECTIONS - SHEET 3

JOB CODE
MIR012-02


SHEET NUMBER
C412

REV
A

DATE	REV	DESCRIPTION	MM	PB
20/08/2020	A	APPROVAL ISSUE		
	1	PRELIMINARY - NOT FOR CONSTRUCTION	REC	APP

STORMWATER DRAINAGE NOTES

- ALL STORMWATER DRAWINGS ARE TO BE READ IN CONJUNCTION WITH DRAWING C001, STORMWATER LAYOUT PLANS, NOTES AND DETAILS.
- STORMWATER PITS ARE TO BE CONSTRUCTED INSITU IN ACCORDANCE WITH DRAWINGS OR AS VARIED AS NOTED ON THE DRAWING. PREFABRICATED STORMWATER PITS CAN BE USED SUBJECT TO WRITTEN APPROVAL FROM THE SUPERINTENDENT. CLASS D HEAVY DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN TRAFFIC AREAS, CLASS B LIGHT DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN LANDSCAPE AREAS UNLESS NOTED OTHERWISE.
- ALL DRAINAGE EXCAVATION AND CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3500 AND THE APPLICABLE LOCAL AUTHORITY SPECIFICATIONS AND STANDARD DETAILS.
- ALL MATERIALS SHALL MEET THE REQUIREMENTS OF AS1254 & AS1273.
- ALL uPVC PIPES SHALL BE CLASS 'SN8' FOR DN150 & DN225, AND CLASS 'SN6' FOR DN100 UNLESS NOTED OTHERWISE.
- PIPES SHALL BE LAID AT MIN. 1% GRADE UNLESS NOTED OTHERWISE.
- CONTRACTOR MUST VERIFY THAT ALL PIPE LEVELS AND GRADES CAN BE ACHIEVED PRIOR TO CONSTRUCTING DRAIN LINES. ANY CONFLICT SHALL BE REPORTED TO THE SUPERINTENDENT FOR ANY NECESSARY ALTERATIONS PRIOR TO ANY CONSTRUCTION OF CONNECTING PIPEWORK.
- WHERE PIPES ARE TO BE LAID WITHIN THE ZONE OF INFLUENCE OF STRUCTURAL LOADINGS (e.g. BUILDING FOOTINGS, RETAINING WALLS...etc). THE BUILDER SHALL PROVIDE ADEQUATE BRIDGING / PROTECTION. WHERE ANY DOUBT MAY EXIST REFERENCE SHALL BE MADE TO THE DESIGNER OF THE STRUCTURE.
- BENCHING OF PIT STRUCTURES SHALL HAVE A SMOOTH FINISHED SURFACE, AND PIPES SHALL NOT PROJECT INSIDE THE SHAFT OF THE PIT.
- WHERE RECTANGULAR PIT STRUCTURES ARE USED, PIPES MUST NOT CONNECT TO THE PIT AT CORNERS.
- ALL CONSTRUCTION AND EXCAVATIONS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT REQUIREMENTS OF THE WORK HEALTH AND SAFETY ACT 2011 AND SUBSEQUENT AMENDMENTS.
- ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION.
- ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
- ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- INSTALL 150mm DIAMETER PVC ROOFWATER HOUSE CONNECTION STUB INTO ROOFWATER PITS. INSTALL AT 750mm DEPTH TYPICAL OR 50mm FROM THE BASE OF PIT (WHICHEVER IS SHALLOWER).



TYPICAL ROOFWATER KERB ADAPTOR OUTLET DETAIL
N.T.S.

REFERENCE POINT LOCATION FOR DRAINAGE STRUCTURES


STRUCTURE TYPE	HORIZONTAL CONTROL POINT [REFERENCE POINT LOCATION]	VERTICAL CONTROL REFERENCE LEVEL
MANHOLE	CENTRELINE OF MAIN SHAFT	FINISHED SURFACE LEVEL AT CENTRE OF MAIN SHAFT
GULLY PIT OVER MANHOLE	CENTRE OF GULLY PIT	LIP LEVEL
GULLY PIT (LIP IN LINE)	CENTRE OF GULLY PIT	LIP LEVEL
HEADWALL	INTERSECTION OF HEADWALL FACE AND PIPE CENTRE LINE	INVERT LEVEL
FIELD INLET	CENTRE OF PIT	TOP OF CONCRETE PIT
ROOFWATER PIT	CENTRE OF PIT	TOP OF GRATE

EXCAVATION IN ROCK NOTE:


CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.



TYPICAL ROOFWATER PROPERTY PIT TO KERB ADAPTOR OUTLET DETAIL
N.T.S.



TYPICAL DETAIL
GRADED PIT IN CONCRETE PAVEMENT
SCALE 1:20

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	MM	PB
20/08/2020	A	APPROVAL ISSUE		
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	REC	APP
			REC	APP






Premise
BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
B ADAMS
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
NTS
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
STORMWATER DRAINAGE NOTES AND DETAILS

JOB CODE
MIR012-02
SHEET NUMBER
C420
REV
A




FOR CONSTRUCTION



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
 B ADAMS
 CHECKED
 M MAJZNER
 PROJECT MANAGER
 R LLEWELYN
 PROJECT DIRECTOR
 PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
STORMWATER DRAINAGE STRUCTURE DETAILS

JOB CODE
MIR012-02
 SHEET NUMBER
C430
 REV
A


DATE	REV	DESCRIPTION	MM	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
	1	PRELIMINARY - NOT FOR CONSTRUCTION	REC	APP
			REC	APP

EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK

FOR MIRVAC GROUP

SEWERAGE RETICULATION



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844
 LOT 9 on S312355

0 200 400 600m
 SCALE 1:10000 (A1)

NAME OF ESTATE	
SUBDIVIDER	
APPLICATION No.	DEV 2018/999
SP DELEGATE APPROVAL DATE	16/04/2019
COUNCIL DA APPROVAL No.	-
DRAWING/PLAN No.	-
No. OF ALLOTMENTS	63
AREA ha	3.85
LENGTH OF SEWERS	DN150 uPVC SN8 1117m DN225 uPVC SN8 -

SHEET LIST TABLE	
SHEET NO.	SHEET TITLE
C500	SEWERAGE LOCALITY PLAN & NOTES
C510	SEWERAGE LAYOUT PLAN - SHEET 1
C511	SEWERAGE LAYOUT PLAN - SHEET 2
C520	SEWERAGE LONG SECTIONS - SHEET 1
C521	SEWERAGE LONG SECTIONS - SHEET 2
C522	SEWERAGE LONG SECTIONS - SHEET 3
C530	SEWERAGE NOTES AND DETAILS

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND SEWERAGE CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- THE CONSTRUCTION OF THE SEWERAGE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. SEWERAGE WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER SEWERAGE SYSTEM.
- ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE CONTRACTOR UNDER LOGAN WATER SUPERVISION AT THE DEVELOPER'S COST.
- ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE "ACCEPTED PRODUCTS AND MATERIALS" LIST.
- EACH ALLOTMENT SHALL BE SERVED BY A DN100 PROPERTY CONNECTION. FOR ALLOTMENTS OTHER THAN SINGLE RESIDENTIAL, A DN150 PROPERTY CONNECTION SHALL BE PROVIDED.
- PROPERTY CONNECTIONS SHALL BE LOCATED WITHIN THE PROPERTY AS SHOWN IN THE DRAWINGS.
- PROPERTY CONNECTION BRANCHES SHALL EXTEND INTO THE PROPERTY A MINIMUM OF 300mm AND A MAXIMUM OF 750mm.
- WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE CARRIED OUT IN LAYERS NOT EXCEEDING 300mm (LOOSE) IN DEPTH AND SHALL BE COMPACTED UNTIL THE COMPACTION IS NOT LESS THAN 95% OF THE MATERIALS MAXIMUM COMPACTION WHEN TESTED IN ACCORDANCE WITH A.S. 1289 (MODIFIED COMPACTION). TESTING SHALL BE CARRIED OUT AFTER EACH ALTERNATE LAYER. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED SEWERS WILL NOT BE ISSUED BY THE SEQ SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED.
- WHERE SEWERS HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SEQ SEWER CODE.
- THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
- SEWERS SHALL BE DISUSED /ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ SEWER CODE.
- BENCH MARK AND LEVELS TO AHD.
- REFER TO BULK EARTHWORKS DRAWINGS FOR FINISHED SURFACE LEVELS.
- ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT. FOR INFORMATION PHONE: 1300 369 915.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS TO ALLOW CONSTRUCTION OF THE SEWER SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE FOR EXCAVATION AND SAFE SHORING TO ALLOW SEWER MAINTENANCE SECTION TO CARRY OUT LIVE SEWER WORK.
- CONSTRUCT TRENCHES TO SEQ-SEW-1200-2, WITH EMBEDMENT TYPE 3 SUPPORT MINIMUM TO SEQ-SEW-1201-1, AND ROAD CROSSINGS TO SEQ-SEW-1205-1 AND LCC STANDARDS.
- CONSTRUCT PROPERTY CONNECTIONS TO SEQ-SEW-1100 SERIES.
- CONSTRUCT MAINTENANCE STRUCTURES TO SEQ-SEW-1300 SERIES.
- CONSTRUCT BULKHEADS TO SEQ-SEW-1206-1.
- INSTALL DETECTABLE MARKER TAPE ON ALL MAINS AND PROPERTY CONNECTIONS.
- CALCAREOUS CONCRETE IN MAINTENANCE HOLES REQUIRED IN ACCORDANCE WITH SEQ WS&S D&C CODE REQUIREMENTS.
- CCTV OF SEWER TO BE UNDERTAKEN AND SUPPLIED TO SUPERINTENDENT PRIOR TO, BUT NO GREATER THAN 2 WEEKS BEFORE, THE ON-SITE INSPECTION FOR OFF MAINTENANCE.

VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST

SOIL

- TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.
- IF ACID SULPHATE SOILS EXIST IN THE WORKS AREA, ACID SULPHATE SOILS ARE TO MANAGED IN ACCORDANCE WITH AN APPROVED ACID SULPHATE SOIL MANAGEMENT PLAN.

CREEK CROSSINGS

- SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

REHABILITATION

- PREDISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- PREDISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED.

SAFETY

- THE DESIGN AND CONSTRUCTION OF THE WORKS SHALL COMPLY WITH ALL QUEENSLAND LEGISLATION.

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORKPLACE HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 369 915

CONTACT "DIAL BEFORE YOU DIG" ON 1100 FOR LOCATION OF EXISTING PUBLIC SERVICES PRIOR TO EXCAVATION.

TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	AL REC	PB APP
27/07/20	A	ORIGINAL ISSUE		



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au



DESIGNED
A LANGDON
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR

PAT BRADY RPEQ 7112

SCALE
 0 200 400 600m
 SCALE 1:10000 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SEWERAGE LOCALITY PLAN & NOTES

JOB CODE
MIR012-02
 SHEET NUMBER
C500
 REV
A



LEGEND - PROPOSED

- GRAVITY SEWER
- Ø100mm PROPERTY CONNECTION. 7.5m OFFSET FROM SIDE BDY WITH DWAY. 1.2m OFFSET FROM SIDE BDY WITHOUT DWAY. TYPICAL U.N.O.
- MAINTENANCE STRUCTURE
- PROPOSED MAINTENANCE HOLE OR MAINTENANCE SHAFT NUMBER. REFER LONG SECTION DRAWINGS FOR STRUCTURE DETAILS.
- HORIZONTAL BEND (3m RADIUS).
- 38** LOT NUMBER
- STORMWATER DRAINAGE
- DRINKING WATER MAIN
- ELECTRICAL (PROPOSED)
- FINISHED CONTOURS (0.50m)
- ZERO LOT LINE
- FUTURE DRIVEWAY LOCATION
- PROPOSED RETAINING WALL
- PROPOSED CONCRETE FOOTPATH & KERB RAMP
- STAGE BOUNDARY

LEGEND - EXISTING

- Ø100mm EXISTING PROPERTY CONNECTION
- STORMWATER DRAINAGE
- GRAVITY SEWER
- SEWER RISING MAIN
- SEWER TRUNK MAIN
- DRINKING WATER MAIN
- EXISTING CONTOURS (0.50m)

EXISTING HOUSE CONNECTION DETAILS

LOT #	INVERT LEVEL	DEPTH
2012	68.247	1.250
2013	68.382	1.250
2080	63.528	1.250
2081	62.745	1.250
2082	61.955	1.250
2083	61.251	1.250
2084	60.461	1.250
2085	59.845	1.250
2086	59.256	1.250
2087	58.873	1.250

PROPERTY CONNECTIONS HAVE BEEN DESIGNED TO CONTROL THE REQUIRED SERVICE AREA OF EACH LOT AT A GRADE OF 1:60 AND A MAXIMUM DEPTH TO INVERT OF PROPERTY CONNECTION AT 1.5m, UNLESS OTHERWISE STATED.

ALL PROPERTY CONNECTIONS DIA 100 PVC UNLESS OTHERWISE DENOTED.

FOR SEWERAGE RETICULATION NOTES REFER DWG No. C500.

CONTRACTOR TO ENSURE THAT ALL SLOPED PROPERTY CONNECTIONS LOCATED AT REAR OF LOTS SHALL TERMINATE AT SHORTEST LENGTH POSSIBLE FROM THE JUNCTION WITH THE SEWER MAIN.

CONTRACTOR TO CONSTRUCT PROPOSED SEWER MANHOLES WITH SUFFICIENT NECK HEIGHT SHOULD FUTURE LAND OWNER REQUIRE ADJUSTMENT TO LID LEVEL TO SUIT POTENTIAL DRIVEWAY.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	KK	PB
24/02/2021	C	AMENDED ROAD NAME	KK	PB
20/08/2020	B	ADDED TEMPORARY SEWER EASEMENTS TO SEWER OUTSIDE OF PRECINCT BOUNDARY	MM	PB
27/07/20	A	ORIGINAL ISSUE	AL	PB

REVISIONS

Premise

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
A LANGDON

CHECKED
M MAJZNER

PROJECT MANAGER
S STEINHOFER

PROJECT DIRECTOR
PATRICK BRADY

RPEQ 7112

SCALE

SCALE 1:500 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP


PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
SEWERAGE LAYOUT PLAN - SHEET 1

JOB CODE
MIR012-02

SHEET NUMBER	REV
C510	C



LEGEND - PROPOSED

- GRAVITY SEWER
- Ø100mm PROPERTY CONNECTION. 7.5m OFFSET FROM SIDE BDY WITH DWAY. 1.2m OFFSET FROM SIDE BDY WITHOUT DWAY. TYPICAL U.N.O.
- MAINTENANCE STRUCTURE
- PROPOSED MAINTENANCE HOLE OR MAINTENANCE SHAFT NUMBER. REFER LONG SECTION DRAWINGS FOR STRUCTURE DETAILS.
- HORIZONTAL BEND (3m RADIUS).
- 38** LOT NUMBER
- STORMWATER DRAINAGE
- DRINKING WATER MAIN
- ELECTRICAL (PROPOSED)
- FINISHED CONTOURS (0.50m)
- ZERO LOT LINE
- FUTURE DRIVEWAY LOCATION
- PROPOSED RETAINING WALL
- PROPOSED CONCRETE FOOTPATH & KERB RAMP
- STAGE BOUNDARY

LEGEND - EXISTING

- EX HC Ø100mm EXISTING PROPERTY CONNECTION
- STORMWATER DRAINAGE
- GRAVITY SEWER
- SEWER RISING MAIN
- SEWER TRUNK MAIN
- DRINKING WATER MAIN
- EXISTING CONTOURS (0.50m)

PROPERTY CONNECTIONS HAVE BEEN DESIGNED TO CONTROL THE REQUIRED SERVICE AREA OF EACH LOT AT A GRADE OF 1:60 AND A MAXIMUM DEPTH TO INVERT OF PROPERTY CONNECTION AT 1.5m, UNLESS OTHERWISE STATED.

ALL PROPERTY CONNECTIONS DIA 100 PVC UNLESS OTHERWISE DENOTED.


FOR SEWERAGE RETICULATION NOTES REFER DWG No. C500.

CONTRACTOR TO ENSURE THAT ALL SLOPED PROPERTY CONNECTIONS LOCATED AT REAR OF LOTS SHALL TERMINATE AT SHORTEST LENGTH POSSIBLE FROM THE JUNCTION WITH THE SEWER MAIN.

CONTRACTOR TO CONSTRUCT PROPOSED SEWER MANHOLES WITH SUFFICIENT NECK HEIGHT SHOULD FUTURE LAND OWNER REQUIRE ADJUSTMENT TO LID LEVEL TO SUIT POTENTIAL DRIVEWAY.

EXISTING HOUSE CONNECTION DETAILS

LOT #	INVERT LEVEL	DEPTH
2089	59.384	1.250
2160	57.745	1.250
2161	58.430	1.250
2162	59.116	1.250
2163	59.669	1.250




FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
24/02/2021	D	AMENDED ROAD NAMES	KK	PB
02/10/2020	C	AMENDED FOOTPATH AND KERB RAMP ALIGNMENT	KK	PB
20/08/2020	B	ADDED TEMPORARY SEWER EASEMENTS TO SEWER OUTSIDE OF PRECINCT BOUNDARY	MM	PB
27/07/20	A	ORIGINAL ISSUE	AL	PB



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
A LANGDON
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFFER
 PROJECT DIRECTOR
[Signature]
PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SEWERAGE LAYOUT PLAN - SHEET 2

JOB CODE
MIR012-02
 SHEET NUMBER
C511
 REV
D

MAINTENANCE HOLE / SHAFT NO.	TE1/24	HB1/24	HB2/24	4/24	5/24	HB3/24	HB4/24	6/24	HB5/24	7/24	HB6/24	8/24	TE2/24				
MH / MS COVER TYPE				B	B					B			B				
MH / MS TYPE	EX. TE	HTP	HB	HTP	HTP	HB	HTP	A	A	HTP	HB	HTP	HTP	HB	HTP	A	TE
MH DROP TYPE				W	V	V	V			V		Y	V		V	V	
LINE NO.				27	24	26	24			24		29	24		30	24	24
PROPERTY CONNECTION DEPTH								1.250	1.250	1.250	1.250						
PROPERTY CONNECTION INVERT LEVEL								67.094	67.296	67.463	67.630	67.855					
PROPERTY CONNECTION TYPE								B	B	B	B	B					
LOT NO.				2047	2048	2049	2050	2051		2054	2055	3001					

LEGEND
 RR DENOTES ROAD RESERVE
 PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.00
B	CONCRETE MANHOLE 1.20
C	CONCRETE MANHOLE 1.50
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
HB	HORIZONTAL BEND (3m HORIZ. RADIUS)
HTP	HORIZONTAL BEND TANGENT POINT

LID TYPES	
B	CLASS B NON TRAFFICABLE CONCRETE IN FILL
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CONCRETE IN FILL

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL

- NOTES:**
- EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
 - DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

HORIZONTAL BEND NOTE:
 DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).

PROPERTY CONNECTION NOTE:
 CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.

DATUM RL	54.000																	57.000												
PROPERTY DESCRIPTION																		RR												
PIPE SIZE (mm), CLASS																		DN150 uPVC SN8												
GRADE (1 IN X)	21	21	21	21	21	21	21	180	43	43	43	43	43	180	180	180	180	180	180	143										
LENGTH	0.900	1.178	1.178	5.122	1.178	1.178	6.178	11.450	6.406	1.178	1.178	4.800	1.178	1.178	53.055	6.042	1.178	1.178	66.206	9.577	0.440	0.440	41.164	1.000						
EMBEDMENT TYPE	TYPE 3																													
DEPTH OF INVERT BELOW FSL	2.570	2.551	2.523	2.498	2.336	2.304	2.287	2.271	2.231	2.160	2.110	1.692	1.656	1.659	1.796	1.813	1.841	2.134	2.114	2.230	2.225	2.235	2.828	2.788	2.690	2.678	2.662	2.577	2.557	2.556
INVERT LEVEL (IL)	63.442	63.485	63.540	63.596	63.836	63.892	63.947	64.237	64.277	64.341	64.391	64.559	64.566	64.593	64.703	64.731	64.758	65.978	65.998	66.051	66.038	66.045	66.412	66.452	66.506	66.508	66.510	66.739	66.759	66.766
FINISHED SURFACE LEVEL (FSL)	66.013	66.036	66.064	66.094	66.172	66.195	66.234	66.508	66.501	66.501	66.501	66.501	66.222	66.252	66.499	66.543	66.599	68.112	68.112	68.261	68.263	68.280	69.241	66.452	69.196	69.187	69.172	69.316	66.759	69.322
EXISTING SURFACE LEVEL (ESL)	62.934	62.929	62.950	63.023	63.331	63.424	63.553	64.267	63.719	63.719	63.719	63.719	62.894	62.765	62.273	62.188	62.133	65.589	66.380	66.509	66.576	70.362	71.212	71.212	71.243	71.270	72.863	72.869	72.869	
CHAINAGE (CH)	0.000	TP 0.900	IP 2.078	TP 3.256	TP 8.378	IP 9.556	TP 10.734	16.913	28.363	TP 34.769	IP 35.947	TP 37.125	TP 41.924	IP 43.103	TP 44.281	97.336	TP 103.378	IP 104.556	TP 105.734	171.940	TP 181.517	IP 181.958	TP 182.398	223.563	224.563	0.000	75.250	0.000	43.000	0.000

LINE 24

MAINTENANCE HOLE / SHAFT NO.	5/24	1/26	4/24	1/27	TE1/28	1/28
MH / MS COVER TYPE	B	B	B	B	B	B
MH / MS TYPE	A	A	A	J	EX. TE	J
MH DROP TYPE	V	V	W	V	V	V
LINE NO.	26	24	27	24		28
PROPERTY CONNECTION DEPTH	1.250	1.250	1.250	1.250		1.250
PROPERTY CONNECTION INVERT LEVEL	65.251	66.140	66.857	67.574	68.704	68.993
PROPERTY CONNECTION TYPE	B	B	B	B	B	B
LOT NO.	2046	2045	2044	2043	2042	2041

LINE 26 27 28

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
20/08/2020	PB	ADDED CLEARANCES TO SERVICE CROSSING TEXTS AND ADDED SHAFT SIZE TO TYPE J MS	KK PB
27/07/20	A	ORIGINAL ISSUE	AL PB

Premise
 BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
A LANGDON
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
 HORIZONTAL 1:1000 (A1)
 VERTICAL 1:100 (A1)
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SEWERAGE LONG SECTIONS - SHEET 1

JOB CODE
MIR012-02
 SHEET NUMBER
C520
 REV
B

MAINTENANCE HOLE / SHAFT NO.

MH / MS COVER TYPE	B	B	B
MH / MS TYPE	J	A	J
MH DROP TYPE	V	V	V
LINE NO.	28	31 28	28 28
PROPERTY CONNECTION DEPTH			
PROPERTY CONNECTION INVERT LEVEL			
PROPERTY CONNECTION TYPE			
LOT NO.	2079 B	2078 B	2061 B

LEGEND
 RR DENOTES ROAD RESERVE
 PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.0Ø
B	CONCRETE MANHOLE 1.2Ø
C	CONCRETE MANHOLE 1.5Ø
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
HB	HORIZONTAL BEND (3m HORIZ. RADIUS)
HTP	HORIZONTAL BEND TANGENT POINT

LID TYPES	
B	CLASS B NON TRAFFICABLE CONCRETE IN FILL
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CONCRETE IN FILL

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL

- NOTES:**
 1. EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
 2. DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

HORIZONTAL BEND NOTE:
 DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).

PROPERTY CONNECTION NOTE:
 CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.

DATUM RL	52.000	57.000
PROPERTY DESCRIPTION	RR	
PIPE SIZE (mm), CLASS	DN150 uPVC SN8	
GRADE (1 IN X)	40	21
LENGTH	98.022	39.000
EMBEDMENT TYPE	TYPE 3	
DEPTH OF INVERT BELOW FSL	2.494	2.846
INVERT LEVEL (IL)	63.492	65.933
FINISHED SURFACE LEVEL (FSL)	65.986	68.779
EXISTING SURFACE LEVEL (ESL)	61.589	68.271
CHAINAGE (CH)	10.450	108.472

LINE 28

MH / MS COVER TYPE	B	B	B
MH / MS TYPE	A	A	A
MH DROP TYPE	V	V	V
LINE NO.	29	24	30
PROPERTY CONNECTION DEPTH			
PROPERTY CONNECTION INVERT LEVEL			
PROPERTY CONNECTION TYPE			
LOT NO.	2052 B	2053 B	

LINE 29

MH / MS COVER TYPE	B	B	B
MH / MS TYPE	A	A	J
MH DROP TYPE	V	V	V
LINE NO.	31	28 32	31 31
PROPERTY CONNECTION DEPTH			
PROPERTY CONNECTION INVERT LEVEL			
PROPERTY CONNECTION TYPE			
LOT NO.			3025 B






LINE 31

MH / MS COVER TYPE	B	B	B	B
MH / MS TYPE	A	HTP	HB	HTP
MH DROP TYPE	V	V	V	V
LINE NO.	32	31		
PROPERTY CONNECTION DEPTH				
PROPERTY CONNECTION INVERT LEVEL				
PROPERTY CONNECTION TYPE				
LOT NO.	2059 B	2058 B	2057 B	2056 B

LINE 32

MH / MS COVER TYPE	B	B	B
MH / MS TYPE	EX. TE	A	J
MH DROP TYPE	V	V	Z
LINE NO.	38	43	38 38
PROPERTY CONNECTION DEPTH			
PROPERTY CONNECTION INVERT LEVEL			
PROPERTY CONNECTION TYPE			
LOT NO.	2164 B	2165 B	2166 B

LINE 38




FOR CONSTRUCTION



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
A LANGDON
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
PAT BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SEWERAGE LONG SECTIONS - SHEET 2

JOB CODE
MIR012-02
 SHEET NUMBER
C521
 REV
B

20/08/2020	B	ADDED CLEARANCES TO SERVICE CROSSING TEXTS AND ADDED SHAFT SIZE TO TYPE J MS	KK	PB
27/07/20	A	ORIGINAL ISSUE	AL	PB
DATE	REV	DESCRIPTION	REC	APP

MAINTENANCE HOLE / SHAFT NO.	17/42	1/39	TE1/39
MH / MS COVER TYPE	B	B	B
MH / MS TYPE	A	J	TE
MH DROP TYPE	V	V	V
LINE NO.	39	42	39
PROPERTY CONNECTION DEPTH			
PROPERTY CONNECTION INVERT LEVEL	61.455	62.446	63.471
PROPERTY CONNECTION TYPE	A	A	B
LOT NO.	2067	2066	3068

19/42	1/40	TE1/40
B	B	B
A	J	TE
V	V	V
40	42	40
2064	3066	3065
63.741	64.341	65.158
B	B	B

18/42	HB1/41	1/41
B	B	B
A	HTP	HTP
Y	V	V
41	42	42
2075	2076	2077
63.531	63.847	64.384
B	B	B

TE2/42	17/42	18/42	19/42	20/42	21/42	TE3/42
B	B	B	B	B	B	B
EX. TE	A	A	J	J	J	TE
V	V	V	V	V	V	V
39	42	41	42	42	42	42
2088	2070	2071	2072	2073	2074	2065
59.951	60.451	61.020	62.035	62.462	63.024	63.463
B	B	B	B	B	B	B

2/38	HB1/43	HB2/43	1/43
B	B	B	B
A	HTP	HTP	HTP
V	V	V	V
43	38		
3122	3121	3120	3119
62.025	62.332	62.713	63.155
B	B	B	B

LEGEND

RR DENOTES ROAD RESERVE
PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.00
B	CONCRETE MANHOLE 1.20
C	CONCRETE MANHOLE 1.50
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
HB	HORIZONTAL BEND (3m HORIZ. RADIUS)
HTP	HORIZONTAL BEND TANGENT POINT

LID TYPES	
B	CLASS B NON TRAFFICABLE CONCRETE IN FILL
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CONCRETE IN FILL

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL

NOTES:

- EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
- DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

HORIZONTAL BEND NOTE:
DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).

PROPERTY CONNECTION NOTE:
CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.

DATUM RL	53.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	15 21
LENGTH	60.750 1.000
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.280 2.250 1.970 1.950 1.980
INVERT LEVEL (IL)	60.268 60.298 64.257 64.277 64.326
FINISHED SURFACE LEVEL (FSL)	62.547 66.228 64.257 64.277 66.306
EXISTING SURFACE LEVEL (ESL)	63.201 71.005 71.137
CHAINAGE (CH)	-0.550 60.200 61.200

DATUM RL	52.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	21 21
LENGTH	45.000 1.000
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	61.756 2.957 61.786 2.927 63.906 2.503 63.926 2.483 63.974 2.485
INVERT LEVEL (IL)	61.756 61.786 63.906 63.926 63.974
FINISHED SURFACE LEVEL (FSL)	64.713 66.408 64.556 64.569 65.654
EXISTING SURFACE LEVEL (ESL)	62.089 67.449 60.474 60.205
CHAINAGE (CH)	0.000 45.000 46.000

DATUM RL	50.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	33 33 33 33
LENGTH	1.313 0.470 0.469 34.527
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	61.629 2.882 62.339 2.171 62.378 2.164 62.393 2.163 62.407 2.162 63.442 2.192
INVERT LEVEL (IL)	61.629 62.339 62.378 62.393 62.407 63.442
FINISHED SURFACE LEVEL (FSL)	64.510 64.543 64.556 64.569 65.654
EXISTING SURFACE LEVEL (ESL)	60.491 60.489 60.485 60.474 60.205
CHAINAGE (CH)	0.000 1.313 1.782 2.252 36.779

DATUM RL	51.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	25 50 180 180 21 22
LENGTH	52.250 64.050 15.750 13.166 31.000 1.000
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	60.268 2.280 60.348 2.200 61.629 2.882 61.669 2.842 61.756 2.957 61.796 2.917 61.869 2.896 61.889 2.876 63.393 2.651 63.413 2.611 63.458 2.617
INVERT LEVEL (IL)	60.268 60.348 61.629 61.669 61.756 61.796 61.869 61.889 63.393 63.413 63.458
FINISHED SURFACE LEVEL (FSL)	62.547 64.713 64.766 66.023 66.074
EXISTING SURFACE LEVEL (ESL)	63.201 60.491 62.089 62.541 66.358 66.499
CHAINAGE (CH)	52.250 63.201 60.491 62.089 62.541 66.358 66.499

DATUM RL	51.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	37 37 37 37 37 37 37
LENGTH	6.042 1.178 1.178 24.108 0.981 0.981 45.156
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	59.983 2.476 60.139 2.320 60.302 2.475 60.333 2.476 60.365 2.491 61.013 2.224 61.059 2.211 61.066 2.191 62.279 2.127
INVERT LEVEL (IL)	59.983 60.139 60.302 60.333 60.365 61.013 61.059 61.066 62.279
FINISHED SURFACE LEVEL (FSL)	62.459 62.777 62.809 62.857 63.237 63.250 63.256 64.405
EXISTING SURFACE LEVEL (ESL)	62.570 63.045 63.115 63.135 63.148 63.173 63.239 67.619
CHAINAGE (CH)	6.042 7.220 8.398 32.506 33.488 34.469 79.625

LINE 39 40 41 42 43



FOR CONSTRUCTION

BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
A LANGDON
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
PAT BRADY RPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
SEWERAGE LONG SECTIONS - SHEET 3

JOB CODE
MIR012-02
SHEET NUMBER
C522
REV
B



20/08/2020	PB	ADDED CLEARANCES TO SERVICE CROSSING TEXTS AND ADDED SHAFT SIZE TO TYPE J MS	KK	PB
27/07/20	A	ORIGINAL ISSUE	AL	PB
DATE	REV	DESCRIPTION	REC	APP

LIVE SEWER WORKS


No.	DESCRIPTION	DIA. SEWER	MH NO.	MH TYPE	COVER TYPE	LOT NO.	F.S.L.	E.S.L.	I.L.	DEPTH
1(A)	0.5m FROM STUB END CAP TE1/24, CONSTRUCTOR TO LAY NEW LINE 24. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/24	END	-	2039	66.013	66.013	63.442	2.570
1(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 24 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
2(A)	0.5m FROM STUB END CAP TE1/28, CONSTRUCTOR TO LAY NEW LINE 28. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/28	END	-	2039	65.931	65.931	63.434	2.497
2(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 28 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
3(A)	0.5m FROM STUB END CAP TE2/42, CONSTRUCTOR TO LAY NEW LINE 42. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE2/42	END	-	2089	60.674	60.674	58.178	2.496
3(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 42 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
4(A)	0.5m FROM STUB END CAP TE1/38, CONSTRUCTOR TO LAY NEW LINE 38. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/38	END	-	2163	60.957	60.957	58.348	2.610
4(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 38 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									

LEVELS IN THE LIVE SEWER TABLE ARE DESIGN LEVELS. AS CONSTRUCTED INFORMATION TO BE ADDED WHEN AVAILABLE.


CONSULTING ENGINEERS ARE TO CONTACT PRIOR TO COMMENCEMENT OF CONSTRUCTION TO ARRANGE FOR THIS WORK TO BE CARRIED OUT. (EXCAVATION, SAFE-SHORTING AND ASSOCIATED WORK BY CONTRACTOR). EXCAVATION WORKS CARRIED OUT BY CONTRACTORS AT DEPTH OF 1.5m OR GREATER MUST PROVIDE A "SAFE WORK PLAN" AS PER WORKPLACE HEALTH AND SAFETY LEGISLATION TO SEQ-SPS PRIOR TO SEQ-SPS COMMENCING ANY WORK. IT IS THE DEVELOPER'S RESPONSIBILITY TO ENSURE ALL LIVE SEWER WORKS ARE COMPLETE BEFORE ALLOWING PRIVATE DRAINAGE TO BE CONNECTED.



SEWER LINE CROSSING CONCRETE SLEEPER RETAINING WALL BRIDGING SLAB DETAIL



TYPICAL MAINTENANCE STRUCTURE IN CONCRETE FOOTPATH DETAIL




CONCRETE STORMWATER SUPPORT TYPICAL DETAIL

SCALE 1:20

- GENERAL CONCRETE STORMWATER SUPPORT NOTES:**
- SUPPORTS TO BE INSTALLED WHERE STORMWATER PIPE DIAMETER IS EQUAL TO OR GREATER THAN 600mm.
 - 3m MAX DEPTH OF CONCRETE STORMWATER SUPPORT 'D'
 - DESIGN BASED ON ACHIEVING 100kPa OF ULTIMATE LIMIT STATE BEARING CAPACITY. TO BE CONFIRMED BY CONTRACTOR DURING CONSTRUCTION.
 - 0.300m* WIDTH UP TO 1050 RCP CLASS 2
 - 0.500m* WIDTH BETWEEN 1050 AND 1800 RCP CLASS 2


- CONCRETE STORMWATER SUPPORT IN ROCK NOTES**
- WHERE BRIDGING STRUCTURE IS LOCATED IN ROCK SUBGRADE, CONTRACTOR SHALL PROVIDE GEOTECHNICAL ADVICE TO SUPERINTENDENT ADVISING IF SUITABLE SUBGRADE BEARING CAPACITY CAN BE ACHIEVED TO FACILITATE THIS SUPPORT TYPE.



CONCRETE STORMWATER SUPPORT IN ROCK SUBGRADE DETAIL

SCALE 1:40

STRUCTURAL DETAILS APPROVED DATE
B. Hooper
 BRIONY HOOPER RPEQ 10854



SERVICE LINE CROSSING BOULDER OR BLOCK RETAINING WALL BRIDGING SLAB DETAIL

NTS

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	AL	PB
27/07/20	A	ORIGINAL ISSUE		



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
A LANGDON
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
R. Brady
 PAT BRADY RPEQ 7112

SCALE
 ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
SEWERAGE NOTES AND DETAILS


JOB CODE
MIR012-02
 SHEET NUMBER
C530
 REV
A

EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK

FOR MIRVAC GROUP

WATER RETICULATION



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844
 LOT 9 on S312355

SHEET LIST TABLE

SHEET NO.	SHEET TITLE
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C610	WATER RETICULATION LAYOUT PLAN - SHEET 1
C611	WATER RETICULATION LAYOUT PLAN - SHEET 2

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- ADOPT LIP OF KERB OR SHOULDER OF ROAD AS PERMANENT LEVEL. COVER OF MAIN FROM PERMANENT LEVEL TO BE AS SHOWN IN SEQ-WAT-1200-2.
- CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD DRAWINGS.
- ALL MATERIALS USED IN THE WORKS SHALL COMPLY WITH SEQ-SP'S ACCEPTED PRODUCTS AND MATERIALS LIST OR BE APPROPRIATELY SHOWN, LISTED AND DEFINED IN THE ENGINEERING SUBMISSION SO THAT THE ALTERNATIVE PRODUCT OR MATERIAL CAN BE ASSESSED AND IF APPROPRIATE, APPROVED BY SEQ-SP'S
- ALL CONCRETE FOOTPATHS TO BE CLEAR OF WATER MAINS, WHERE POSSIBLE
- CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT TO THE RETICULATION SYSTEM.
- ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128.
- CONSTRUCT THRUST BLOCKS ON ALL BENDS, TEES, TAPERS AND DEAD ENDS IN ACCORDANCE WITH SEQ-WAT-1205-1, AND SEQ-WAT-1206-1.
- CONSTRUCT TRENCHES IN ACCORDANCE WITH SEQ-WAT-1200-2, PIPE EMBEDMENT TO SEQ-WAT-1201-1 (TYPE C SUPPORT) AND ROAD CROSSINGS TO SEQ-WAT-1204-1 AND LCC STANDARDS.
- INSTALL SCOURS IN ACCORDANCE WITH SEQ-WAT-1307-3.
- INSTALL DETECTABLE MARKER TAPE ON ALL WATER MAINS AND PROPERTY SERVICES.
- INSTALL HYDRANTS IN ACCORDANCE WITH SEQ-WAT-1302-1, SEQ-WAT-1303-1
- INSTALL PAVEMENT MARKERS IN ACCORDANCE WITH SEQ-WAT-1300-1 & 2.

VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED, IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST.

SOIL

- TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.

CREEK CROSSINGS

- SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

REHABILITATION

- PRE-DISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- PRE-DISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED, ALL DISTURBED AREAS ASSOCIATED WITH CONSTRUCTION SHALL BE REHABILITATED, HEAVILY COMPACTED AREAS SHOULD BE RIPPED PRIOR TO TREATMENT.
- ALL DISTURBED AREAS ARE TO BE LEFT IN STABLE CONDITION.
- ALL PLANTING/RE-VEGETATION WILL NEED TO BE MAINTAINED THROUGHOUT THE MAINTENANCE PERIOD.

CONSTRUCTION REQUIREMENTS

- LIVE WATER CONNECTIONS TO BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH A VALID NETWORK ACCESS PERMIT UNDER LOGAN WATER SUPERVISION AT DEVELOPERS EXPENSE AT LOCATION MARKED.
- PRIOR TO ANY EXCAVATION, CONTRACTOR IS TO LOCATE ACTUAL POSITIONS OF PUBLIC SERVICE UTILITIES BY POT HOLES.
- UPON COMPLETION OF ALL WORKS, CONTRACTORS SHALL SUPPLY THE SUPERVISING RPEQ DETAILED "AS CONSTRUCTED" INFORMATION OF THE WORK. "AS CONSTRUCTED" INFORMATION SHALL COMPLY WITH CURRENT SEQ CODE OR LOCAL AUTHORITY STANDARDS FOR PLAN AND DIGITAL INFORMATION.
- CONTRACTOR IS TO BE RESPONSIBLE FOR ARRANGING ALL LOGAN WATER CONNECTIONS AND PAYMENTS OF CONNECTION FEES.

TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

RPEQ CERTIFICATION

THE CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO LOGAN WATER RETICULATION SYSTEM. ALL RPEQ CERTIFIED DRAWINGS COMPLY WITH SEQ CODE AND LOGAN WATER REQUIREMENTS.

INSPECTION REQUIREMENTS

PRIOR TO COMMENCEMENT OF WORKS, CONTACT PREMISE (07) 3253 2222 AND LOGAN WATER TO CONFIRM INSPECTION REQUIREMENTS INCLUDING LIVE CONNECTIONS.

A MINIMUM 48 HOURS NOTICE IS REQUIRED.

INSPECTIONS ARE REQUIRED TO BE ORGANIZED WITH PREMISE AND LOGAN WATER. ANY COSTS ASSOCIATED WITH ENGAGING LOGAN WATER TO UNDERTAKE INSPECTIONS OUTSIDE OF THE FEE PAID SHALL BE BORNE BY THE CONTRACTOR.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128

SEQ CODE STD DRAWING SCHEDULE

SOIL CLASSIFICATION	SEQ-WAT-1200-1
EMBEDMENT AND TRENCH FILL	SEQ-WAT-1200-2
THRUST BLOCK DETAILS	SEQ-WAT-1205-1
VALVE THRUST BLOCKS	SEQ-WAT-1206-1
IDENTIFICATION MARKERS	SEQ-WAT-1300-1,2



FOR CONSTRUCTION



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWIANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
R LLEWELYN
 PROJECT DIRECTOR
[Signature]
 PAT BRADY RPEQ 7112




SCALE

 SCALE 1:10000 (A1)
 ORIGINAL SHEET SIZE A1


CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
WATER RETICULATION LOCALITY PLAN & NOTES

JOB CODE
MIR012-02
 SHEET NUMBER
C600
 REV
A

DATE	REV	DESCRIPTION	KK	PB
27/07/20	A	ORIGINAL ISSUE	KK	PB
REVISIONS				



CONNECTION 3
LIVE CONNECTION DETAIL
SCALE 1:25



CONNECTION 2
LIVE CONNECTION DETAIL
SCALE 1:25

JOINS DRAWING C611

LIVE CONNECTION NOTES:

1. LIVE CONNECTIONS BY LOGAN WATER
2. LIVE CONNECTION IN ACCORDANCE WITH SEQ-WAT-1303-1
3. THRUST BLOCKS NOT SHOWN FOR CLARITY.
4. PRE-CHLORINATION FITTINGS AS REQUIRED.

LEGEND - PROPOSED

- NEW DN100 mPVC MAIN
- DN100 GIBAULT TEMP DN100 HYDRANT 'B' RISER WITH FL-SO 90° BEND
- NEW DN150 mPVC MAIN
- DN100 GIBAULT EXISTING DEAD END TO BE REMOVED
- EXISTING DN100 HYDRANT
- EXISTING DN100 mPVC MAIN
- EXISTING DN100 SLUICE VALVE
- EXISTING DN150 mPVC MAIN
- CONNECTION 3
- NEW DN150 mPVC MAIN
- DN150 GIBAULT TEMP DN150 HYDRANT 'B' RISER WITH FL-SO 90° BEND
- NEW DN150 mPVC MAIN
- DN150 GIBAULT EXISTING DEAD END TO BE REMOVED
- EXISTING DN150 HYDRANT
- EXISTING DN150 mPVC MAIN
- EXISTING DN150 SLUICE VALVE
- EXISTING DN150 mPVC MAIN
- CONNECTION 2

LEGEND - EXISTING

- POTABLE WATERMAIN
- POTABLE WATER RETICULATION CONDUIT
- WATER SERVICES & WATER METER BOX POINT. METER BY OTHERS
- SLUICE VALVE
- FIRE HYDRANT
- TEST POINT
- REDUCER
- FLUSHING POINT
- DEAD END
- DEFLECTION
- TRUNCATIONS 5 DEGREES OR LESS
- LOT NUMBER
- STORMWATER
- GRAVITY SEWER
- SEWER RISING MAIN
- ELECTRICITY
- ZERO LOT BOUNDARY
- PREFERRED DRIVEWAY LOCATION (BY OTHERS)
- SITE BOUNDARY
- PROPOSED RETAINING WALL
- PMT
- PAD MOUNTED TRANSFORMER
- WATER
- SLUICE VALVE
- FIRE HYDRANT
- TEST POINT
- SCOUR BRANCH
- DEAD END
- WATER METER
- STORMWATER
- GRAVITY SEWER
- SEWER RISING MAIN
- ELECTRICAL
- TELSTRA
- GAS

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

AS CONSTRUCTED DETAILS FOR AMEND.

I CERTIFY THAT THE 'AS CONSTRUCTED' DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS

SIGNED: _____ DATE: _____
 NAME OF SIGNATORY
 RPEQ No. or LICENCE
 COMPANY NAME
 START DATE

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
25/02/2021	B	AMENDED ROAD NAME	KK PB
27/07/20	A	ORIGINAL ISSUE	KK PB

Premise

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED: K KIWANG
 CHECKED: M MAJZNER
 PROJECT MANAGER: S STEINHOFER
 PROJECT DIRECTOR: Patrick Brady
 RPEQ 7112

SCALE

0 10 20 30m

SCALE 1:500 (A1)

0 0.5 1.0 1.5m

SCALE 1:25 (A1)

ORIGINAL SHEET SIZE A1

CLIENT: MIRVAC GROUP

PROJECT: EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT



LOCATION: TEVIOT ROAD, GREENBANK

SHEET TITLE: WATER RETICULATION LAYOUT PLAN - SHEET 1

JOB CODE: MIR012-02

SHEET NUMBER: C610

REV: B



- LIVE CONNECTION NOTES:**
1. LIVE CONNECTIONS BY LOGAN WATER
 2. LIVE CONNECTION IN ACCORDANCE WITH SEQ-WAT-1303-1
 3. THRUST BLOCKS NOT SHOWN FOR CLARITY.
 4. PRE-CHLORINATION FITTINGS AS REQUIRED.

LEGEND - PROPOSED	
	POTABLE WATERMAIN
	POTABLE WATER RETICULATION CONDUIT
	WATER SERVICES & WATER METER BOX POINT. METER BY OTHERS
	SLUICE VALVE
	FIRE HYDRANT
	TEST POINT
	REDUCER
	FLUSHING POINT
	DEAD END
	DEFLECTION
	TRUNCATIONS 5 DEGREES OR LESS
	38 LOT NUMBER
	STORMWATER
	GRAVITY SEWER
	SEWER RISING MAIN
	ELECTRICITY
	ZERO LOT BOUNDARY
	PREFERRED DRIVEWAY LOCATION (BY OTHERS)
	SITE BOUNDARY
	PROPOSED RETAINING WALL
	PMT PAD MOUNTED TRANSFORMER

LEGEND - EXISTING	
	WATER
	SLUICE VALVE
	FIRE HYDRANT
	TEST POINT
	SCOUR BRANCH
	DEAD END
	WATER METER
	STORMWATER
	GRAVITY SEWER
	SEWER RISING MAIN
	ELECTRICAL
	TELSTRA
	GAS

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

AS CONSTRUCTED DETAILS FOR AMEND.

I CERTIFY THAT THE 'AS CONSTRUCTED' DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS

SIGNED: _____ DATE: _____
 NAME OF SIGNATORY
 RPEQ No. or LICENCE
 COMPANY NAME
 START DATE

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
25/02/2021	C	AMENDED ROAD NAME	KK PB
02/10/2020	B	AMENDED FOOTPATH AND KERB RAMPS ALIGNMENT	KK PB
27/07/20	A	ORIGINAL ISSUE	KK PB
			REC APP

Premise

BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED: K KIWANG
 CHECKED: M MAJZNER
 PROJECT MANAGER: S STEINHOFER
 PROJECT DIRECTOR: [Signature]
 PATRICK BRADY RPEQ 7112

SCALE

0 10 20 30m

SCALE 1:500 (A1)

0 0.5 1.0 1.5m

SCALE 1:25 (A1)

ORIGINAL SHEET SIZE A1

CLIENT: MIRVAC GROUP

PROJECT: EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT


LOCATION: TEVIOT ROAD, GREENBANK

SHEET TITLE: WATER RETICULATION LAYOUT PLAN - SHEET 2

JOB CODE: MIR012-02

SHEET NUMBER: C611

REV: C



LEGEND - PROPOSED

- PROPOSED STORMWATER
- GULLY INLET PROTECTION. REFER DETAIL IECA DRAWING ESC-03 FOR DETAILS.
- 100mm THICK TOPSOIL RESPREAD AND DRILL SEEDING
- 100mm THICK TOPSOIL AND TURF
- FINISHED MAJOR CONTOURS (0.50m)
- FINISHED MINOR CONTOURS (0.25m)

LEGEND - EXISTING

- MAJOR CONTOURS (1.00m)
- MINOR CONTOURS (0.50m)

SERVICE TRENCH AND ROAD CONSTRUCTION SEQUENCE

- STEP 1
PAVEMENT CONSTRUCTION
MAINTAIN SILT FENCES, AND CATCH DRAINS WHICH CONTROL SEDIMENTATION AND EROSION DURING PAVEMENT CONSTRUCTION.
- STEP 2
MAINTENANCE PERIOD
MAINTAIN CONTROL AND ESC AND VEGETATIVE TREATMENTS WHICH CONTROL SEDIMENTATION AND EROSION PRIOR TO THE ESTABLISHMENT OF STABILIZED GRASS COVER.
- STEP 3
REMOVE CONSTRUCTION ENTRANCES.
- ADDITIONAL EROSION CONTROLS ARE TO BE ERECTED AND MONITORED AS REQUIRED BY THE SUPERINTENDENT

- NOTES**
- REFER EROSION AND SEDIMENT CONTROL NOTES AND DETAILS DRAWINGS.
 - ALL FOOTPATHS ARE TO BE FULLY TURFED AS SOON AS PRACTICAL.
 - CONTRACTOR TO ENSURE THAT GRASS SEEDED AREAS SHOWN ON THIS PLAN ACHIEVE SUFFICIENT STRIKE AND COVERAGE IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARDS.
 - FOR STABILISATION MEASURES OF FUTURE PRECINCTS, REFER TO MIR012-01 - C730 EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE.

ESC RESPONSIBILITY NOTE:
THE EROSION & SEDIMENT CONTROL MANAGEMENT FOR THIS AREA SHALL BE UNDERTAKEN USING THE EXISTING HES BASIN CONSTRUCTED IN PRECINCT 1.1 AND ESC MEASURES CONSTRUCTED IN PRECINCT 12.1. THE MAINTENANCE AND OPERATION OF THE HES BASIN SHALL BE UNDERTAKEN BY THE PRINCIPAL CIVIL CONTRACTOR FOR PRECINCT 12.2. REFER TO PREMISE DRAWINGS MIR001-01 FOR AS CONSTRUCTED HES BASIN DETAILS.

TURFING AND TOPSOIL NOTE
CONTRACTOR SHALL RESPREAD AMELIORATED TOPSOIL (AMELIORATION REQUIREMENTS AS DIRECTED BY SUPERINTENDENT) TO VERGES AT A THICKNESS OF 100mm. TURFING TO VERGES WITHIN PRECINCT 12.1 WORKS SHALL BE UNDERTAKEN BY THE CIVIL CONTRACTOR.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.
C. Hutton
CHRIS HUTTON CPESC NO. 6241

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
25/02/2021	B	AMENDED ROAD NAMES	KK PB
20/08/2020	A	APPROVAL ISSUE	MM PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK PB
			REC APP

Premise
BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
C HUTTON
CHECKED
M MAJZNER
PROJECT MANAGER
S STEINHOFER
PROJECT DIRECTOR
Patrick Brady
PATRICK BRADY RPEQ 7112

SCALE
0 15 30 45m
SCALE 1:750(A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
EROSION AND SEDIMENT CONTROL - STABILISATION PHASE

JOB CODE
MIR012-02


SHEET NUMBER	REV
C700	B

EROSION & SEDIMENT CONTROL NOTES


- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- REFER EARTHWORKS DRAWINGS FOR ADDITIONAL NOTES.
- ALL TRENCHES, FOOTPATH EXCAVATIONS & STOCKPILES TO BE PROTECTED BY TEMPORARY SEDIMENT FENCES UNTIL 80% GRASS COVERAGE IS ACHIEVED TO DISTURBED AREAS.
- EVERY PRECAUTION IS TO BE TAKEN TO PREVENT THE TRANSPORT OF SILT INTO THE NEWLY LAID STORMWATER PIPES THAT ARE CONNECTED TO THE DOWNSTREAM PIPE SYSTEMS, AND ANY EXISTING OPEN CHANNELS.
- THESE NOTES SHALL BE READ IN CONJUNCTION WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- THE EROSION AND SEDIMENT CONTROL WORKS SHALL COMPLY WITH THE REQUIREMENTS OF THE LOCAL AUTHORITIES EROSION AND SEDIMENT CONTROL STANDARDS.
- THE CONTRACTOR SHALL TAKE ALL REASONABLE AND PRACTICABLE MEASURES TO:
 - ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON EROSION FLOW VELOCITIES;
 - MINIMISE SOIL EROSION FROM WATER AND WIND;
 - MINIMISE ADVERSE EFFECTS OF SEDIMENT RUN-OFF;
 - MINIMISE OR PREVENT ENVIRONMENTAL HARM ASSOCIATED WITH DISCHARGES FROM THE SITE (E.G. THE EFFECTS OF SEDIMENTATION ON THE ENVIRONMENTAL VALUES OF RECEIVING WATERS); AND
 - ENSURE THAT THE VALUE AND USE OF RESIDENTIAL PROPERTIES ADJACENT TO THE DEVELOPMENT (SUCH AS DRAINAGE AND ROADS) ARE NOT DIMINISHED AS A RESULT OF THE MIGRATION OF SEDIMENT FROM THE DEVELOPMENT.
- THE CONTRACTOR SHALL APPOINT AN APPROPRIATELY EXPERIENCED PERSON TO BE MADE RESPONSIBLE FOR IMPLEMENTATION OF THE ESC.
 - ALL ESC MEASURES SHALL BE INSPECTED:
 - AT LEAST DAILY (WHEN WORK IS OCCURRING ON SITE).
 - AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON SITE).
 - WITHIN 24 HOURS OF EXPECTED RAINFALL.
 - WITHIN 18 HOURS OF RAINFALL OCCURRING.
- MAINTENANCE OF ESC MEASURES SHALL OCCUR TO ENSURE THEY ARE OPERATING EFFICIENTLY AND IN ACCORDANCE WITH THE FOLLOWING SCHEDULE:

ESC MEASURES	MAINTENANCE TRIGGER	TIME FRAME FOR UNDERTAKING MAINTENANCE
ESC MEASURES	WHEN SETTLED SEDIMENT VOLUME EXCEEDS 25% OF THE CAPACITY OF THE ESC MEASURE	BY THE END OF THE DAY


- INSTALL DIVERSION CATCH DRAINS UPSTREAM OF, AND SILT FENCE DOWNSTREAM OF, STOCKPILES.
- STOCKPILES ARE TO BE LOCATED AWAY FROM EROSION HAZARD AREAS SUCH AS DRAINAGE LINES AND STEEP SLOPES.
- STOCKPILES ARE TO BE PROTECTED FROM EROSION BY THE WIND.
- ADEQUATE SUPPLIES OF EMERGENCY MAINTENANCE MATERIALS, INCLUDING (BUT NOT LIMITED TO) TIE WIRE, STAKES, FILTER CLOTH, WIRE MESH AND CLEAN GRAVEL SHOULD BE AVAILABLE ON-SITE.
- ESC MAINTENANCE ACTIVITIES ARE TO BE RECORDED IN AN ON-SITE REGISTER. THE REGISTER IS TO BE MAINTAINED FOR THE DURATION OF THE WORKS AND IS TO BE MADE AVAILABLE TO THE SUPERINTENDENT.
- DISTURBED AREA ARE TO BE STABILISED AS SOON AS POSSIBLE ON COMPLETION OF BULK EARTHWORKS. LOTS TO BE STABILISED FOLLOWING RESPREADING OF TOPSOIL.
- SUPPLEMENTARY ESC MEASURES SHALL BE DIRECTED BY THE SUPERINTENDENT.




(a) Rock entry/exit pad for construction sites
(refer to Standard Drawing Exit-03 for building sites)



(c) Alternative low maintenance arrangement
(still under development)



(b) Rock pad sloping away from road



(d) Rock pad sloping towards the road

CONSTRUCTION ENTRANCE DETAIL

MATERIALS

COMPOSTS MUST COMPLY WITH THE REQUIREMENTS OF AS4454.

(i) WELL-DECOMPOSED 100% ORGANIC MATTER PRODUCED BY CONTROLLED AEROBIC (BIOLOGICAL) DECOMPOSITION.

(ii) MAXIMUM OF 1% OF INERT MATERIAL.

(iii) MAXIMUM SOLUBLE SALT CONCENTRATION OF 5dS/m, AND pH RANGE OF 5.0 TO 8.5.

(iv) MOISTURE CONTENT OF 30 TO 50% PRIOR TO APPLICATION.

INSTALLATION

1. REFER TO APPROVED PLANS FOR LOCATION AND EXTENT. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, EXTENT, MATERIAL TYPE, OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.

2. WHEN SELECTING THE LOCATION OF A COMPOST FILTER BERM, TO THE MAXIMUM DEGREE PRACTICABLE, ENSURE THE BERM IS LOCATED:

(i) TOTALLY WITHIN THE PROPERTY BOUNDARIES;

(ii) ALONG A LINE OF CONSTANT ELEVATION (PREFERRED, BUT NOT ALWAYS PRACTICAL);

(iii) AT LEAST 1m, IDEALLY 3m, FROM THE TOE OF A FILL EMBANKMENT;

(iv) AWAY FROM AREAS OF CONCENTRATED FLOW.

3. ENSURE THE BERM IS INSTALLED IN A MANNER THAT AVOIDS THE

CONCENTRATION OF FLOW ALONG THE BERM, OR THE UNDESIRABLE DISCHARGE OF WATER AROUND THE ENDS OF THE BERM.

4. ENSURE THE BERM HAS BEEN PLACED ALONG THE CONTOUR SUCH THAT WATER WILL POOL EVENLY ALONG THE LENGTH OF THE BERM.

5. ENSURE BOTH ENDS OF THE BERM ARE ADEQUATELY TURNED UP THE SLOPE TO PREVENT FLOW BYPASSING PRIOR TO WATER PASSING OVER THE BERM.

6. ENSURE 100% CONTACT WITH THE SOIL SURFACE.

7. WHERE SPECIFIED, TAKE APPROPRIATE STEPS TO VEGETATE THE BERM.

MAINTENANCE

1. DURING THE CONSTRUCTION PERIOD, INSPECT THE BERM AT LEAST WEEKLY AND AFTER ANY SIGNIFICANT RAIN. MAKE NECESSARY REPAIRS IMMEDIATELY.

2. REPAIR OR REPLACE ANY DAMAGED SECTIONS.

3. WHEN MAKING REPAIRS, ALWAYS RESTORE THE SYSTEM TO ITS ORIGINAL CONFIGURATION UNLESS AN AMENDED LAYOUT IS REQUIRED OR SPECIFIED.

4. REMOVE ACCUMULATED SEDIMENT IF THE SEDIMENT DEPOSIT EXCEEDS A DEPTH OF 100mm OR 1/3 THE HEIGHT OF THE BERM.

5. DISPOSE OF SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

REMOVAL (IF REQUIRED)

1. WHEN DISTURBED AREAS UP-SLOPE OF THE BERM ARE SUFFICIENTLY STABILISED TO RESTRAIN EROSION, THE BERM MAYBE REMOVED.

2. REMOVE ANY COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

3. REHABILITATE/REVEGETATE THE DISTURBED GROUND AS NECESSARY TO MINIMISE THE EROSION HAZARD.




Figure 1 - Typical profile of a compost filter berm

MULCH BUND DETAIL

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

Chris Hutton
CHRIS HUTTON CPESC NO. 6241

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB



BRISBANE OFFICE
LEVEL 1, 100 BRUNSWICK STREET
PO BOX 361
FORTITUDE VALLEY, QLD 4006
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
C HUTTON
CHECKED
M MAJZNER
PROJECT MANAGER
R LLEWELYN
PROJECT DIRECTOR
R. Llewelyn
PAT BRADY RPEQ 7112

SCALE
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC GROUP
PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1 OF 2

JOB CODE
MIR012-02
SHEET NUMBER
C710
REV
A

ROLES AND RESPONSIBILITIES

ROLE	RESPONSIBILITY
PROJECT MANAGER	<ul style="list-style-type: none"> • OVERALL RESPONSIBILITY OF ESC IMPLEMENTATION • NOTIFY THE ENVIRONMENTAL MANAGER IMMEDIATELY OF ANY NON-COMPLIANCE WITH ESCP • ENSURE THE PROMPT IMPLEMENTATION OF MEASURES TO MITIGATE EROSION AND SEDIMENT GENERATION
SITE SUPERVISOR / FOREMEN	<ul style="list-style-type: none"> • MONITOR DAILY RAINFALL • NOTIFY ENVIRONMENTAL ADVISOR/CONSULTANT WHEN RUNOFF GENERATING RAINFALL OCCURS IN THE PREVIOUS 24 HOURS • MAINTAIN CURRENT RECORDS OF RAINFALL, STORAGE VOLUMES, WATER QUALITY, TREATMENT PRACTICES, DISCHARGE VOLUMES (AS APPROPRIATE) • INSTALLATION AND MAINTENANCE OF ESC
ENVIRONMENTAL MANAGER	<ul style="list-style-type: none"> • PROVIDE DESIGN INFORMATION AS REQUIRED • CONDUCT IN-SITU MONITORING (AS REQUIRED) • COLLECT AND SUBMIT SAMPLES TO LABORATORY (AS REQUIRED) • COLLATE RESULTS AND PREPARE REPORTS (AS REQUIRED) • CONDUCT SITE INSPECTIONS AND AUDITS (AS REQUIRED) • INSPECT ESC INSTALLATION AND MAINTENANCE • INSPECT OFFSITE IMPACTS AND MANAGEMENT • PROVIDE ADVICE REGARDING ESC SITE IMPROVEMENT (AS REQUIRED)
ALL PERSONNEL	<ul style="list-style-type: none"> • REPORT ANY DAMAGE TO ESC DEVICES AND ANY POTENTIAL OR ACTUAL ENVIRONMENTAL HARM IN LINE WITH DUTY TO NOTIFY UNDER THE REQUIREMENTS OF THE ENVIRONMENTAL PROTECTION ACT 1994

CORRECTIVE AND PREVENTATIVE ACTION

AN ENVIRONMENTAL INCIDENT WITH RESPECT TO THE ESCP IS DEFINED AS ANY OCCURRENCE WHERE SEDIMENT IS RELEASED FROM THE SITE, WHETHER CONTROLLED OR UNCONTROLLED, OR WHERE STORM WATER IS RELEASED (CONTROLLED) FROM SITE WHICH DOES NOT MEET THE WATER QUALITY REQUIREMENTS.

ALL INCIDENTS AND NON-CONFORMANCES ARE TO BE REPORTED, INVESTIGATED AND CORRECTED IN ACCORDANCE WITH THE ESCP TO ENSURE EFFECTIVE SOIL AND WATER QUALITY MANAGEMENT PRACTICES AT ALL TIMES.

BEST PRACTICE SITE MANAGEMENT REQUIRES ALL ESC MEASURES TO BE INSPECTED BY THE CONTRACTORS NOMINATED REPRESENTATIVE AT LEAST DAILY WHEN RAIN IS OCCURRING, WITHIN 24 HOURS PRIOR TO EXPECTED RAINFALL, AND WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE ONSITE RUNOFF (IECA, 2008). SUCH INSPECTIONS MUST CHECK:

- **DAILY SITE INSPECTIONS** (DURING PERIODS OF RUNOFF PRODUCING RAINFALL)
 - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
 - ALL SITE DISCHARGE POINTS (INCLUDING DEWATERING ACTIVITIES AS APPROPRIATE)

- **WEEKLY SITE INSPECTIONS** (EVEN IF WORK IS NOT OCCURRING ON-SITE)
 - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
 - OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.
 - LITTER AND WASTE RECEPTORS
 - OIL, FUEL AND CHEMICALS STORAGE FACILITIES


- **PRIOR TO ANTICIPATED RUNOFF PRODUCING RAINFALL**
 - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 - ALL TEMPORARY FLOW DIVERSION AND DRAINAGE WORKS

- **FOLLOWING RUNOFF PRODUCING RAINFALL**
 - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
 - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
 - OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.


I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

Chris Hutton
CHRIS HUTTON CPESC NO. 6241

FOR CONSTRUCTION				 BRISBANE OFFICE LEVEL 1, 100 BRUNSWICK STREET PO BOX 361 FORTITUDE VALLEY, QLD 4006 PH: (07) 3253 2222 WEB: www.premise.com.au	DESIGNED C HUTTON	SCALE	CLIENT MIRVAC GROUP		JOB CODE MIR012-02
20/08/2020	A	APPROVAL ISSUE	MM		PB		PROJECT EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT	LOCATION TEVIOT ROAD, GREENBANK	
DATE	REV	DESCRIPTION	REC	APP	CHECKED M MAJZNER	PROJECT MANAGER R LLEWELYN	SHEET TITLE EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2 OF 2		REVISIONS
				PROJECT DIRECTOR <i>Pat Brady</i> PAT BRADY RPEQ 7112	ORIGINAL SHEET SIZE A1				



NOTE
 CONTRACTOR TO ENSURE THAT THE SURFACE WATER IN TURNAROUND IS DIRECTED TO KERB AND CHANNEL AND OVERLAND FLOW PATHS ARE CONSIDERED. CONTRACTOR TO NOTIFY SUPERINTENDENT SHOULD THIS CRITERIA NOT BE MET.



TYPICAL TEMPORARY TURN AROUND DETAIL
 SCALE: 1:250


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	KK	PB
25/02/2021	B	AMENDED ROAD NAME	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB
			REC	APP




BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP
 PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT
 LOCATION
TEVIOT ROAD, GREENBANK
 SHEET TITLE
TEMPORARY WORKS - ROADWORKS AND DRAINAGE - SHEET 1 OF 2

JOB CODE
MIR012-02
 SHEET NUMBER
C900
 REV
B



JOINS DRAWING C900


REFER TO C900 FOR DETAIL AND NOTES


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
25/02/2021	B	AMENDED ROAD NAME	KK	PB
20/08/2020	A	APPROVAL ISSUE	MM	PB
DD/MM/YYYY	1	PRELIMINARY - NOT FOR CONSTRUCTION	KK	PB
			REC	APP



BRISBANE OFFICE
 LEVEL 1, 100 BRUNSWICK STREET
 PO BOX 361
 FORTITUDE VALLEY, QLD 4006
 PH: (07) 3253 2222
 WEB: www.premise.com.au

DESIGNED
K KIWANG
 CHECKED
M MAJZNER
 PROJECT MANAGER
S STEINHOFER
 PROJECT DIRECTOR

 PATRICK BRADY RPEQ 7112



CLIENT
MIRVAC GROUP

PROJECT
EVERLEIGH PRECINCT 12.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
TEMPORARY WORKS - ROADWORKS AND DRAINAGE - SHEET 2 OF 2

JOB CODE
MIR012-02

SHEET NUMBER	REV
C901	B