

Residential Design Standards and Guidelines Precinct 1.5 Acreage Lots

# Contents

UNDERSTANDING THE RESIDENTIAL DESIGN STANDARDS & GUIDELINES	MANDATORY COMPLIANCE ELEMENTS	OPTIONAL/RECOMMENDED ELEMENTS	
Residential Design Standards and Guidelines3	Part 1 Design & Siting Standards 8	Part 2 Architectural and Landscape	Part 3 Sustainable Living Guidelines 17
	Approved Plan of Development –	Design Standards 10	Objectives
How the Residential Design Standards	Envelope Plan and Design Criteria	Minimum Building Size	Energy Consumption and
and Guidelines Work 4		Roofs 10	Greenhouse gas-emission reduction
		Façade Design	Water Conservation and reuse 17
Building @ Everleigh Portal5		External Wall Materials and Colours 12	Materials and Waste18
The Approval Process6		Driveways & Entry Paths	Smart Technology
		Privacy and Cross Viewing	Landscaping
		Security and Insect Screens	
		External Services and Waste Recycling	
		Construction Obligations	
		Developer Works	
		Landscaping	
		Fences General16	
			•••••
Definitions 19	Annexure A	Annexure C	Annexure D
	Approved PoD – Envelope Plan 22	Fence Types 36	Landscape Design Guidelines 39
	Annexure B		Annexure E
	Approved PoD – Design Criteria 28		Retaining Wall Fact Sheet 55

# Residential Design Standards and Guidelines

These standards and guidelines have been prepared to assist Everleigh purchasers (and their builders/designers) to construct well designed, quality homes and to join Mirvac in creating great places for life.

The standards and guidelines are intended to help you add value to your home and protect your investment by creating an attractive streetscape. Great design creates a welcoming and attractive streetscape. This not only improves your quality of life but establishes Everleigh as a great place to live and a place in which you will be proud to be a part of.

# Street Appeal

These standards and guidelines will assist in making your home part of an attractive streetscape. This is achieved by using the right materials and colours and including some cost effective design elements to the front façade.

# Fencing

 $\Delta \Delta \Delta \Delta \Delta$ 

Fences which are visible from the street are an important part of the streetscape. So at Everleigh we ask that these are of a higher standard and quality.

# Landscaping

A great way to make your home unique is through landscaping. We ask that you include landscaping that will grow into an attractive low maintenance front yard that complements the parks and bushland that are a great part of Everleigh. This document provides design standards to ensure that cohesive and attractive landscaping is established.

# How the Residential Design Standards and Guidelines Work

# The Everleigh Residential Design Standards and Guidelines (Design Standards & Guidelines) sets out:

- Standards which are mandatory compliance elements; and
- **Guidelines** which are non-mandatory elements that provide further information and suggestions to improve design and quality of life.

The Design Standards and Guidelines are technical in nature and it is recommended that you speak to your builder or an Everleigh sales team representative who will be able to guide you through this process.

### The Design Standards and Guidelines consists of three parts as follows:



# AUTHORITY REQUIREMENTS

### Design and Siting Standards

Directs customers to the Approved Plan of Development – Envelope Plan and Design Criteria documents which include the **mandatory design standards for siting your home** to the specific characteristics of your lot. These documents are available in Annexure A and B.



# MIRVAC REQUIREMENTS

# Architectural and Landscape Standards

Provides the **mandatory architectural and landscape design standards** to include in all homes in Everleigh which are essential to making Everleigh a place in which you will be proud to live.



# GOOD PRACTICE

### Sustainable Living Guidelines

Provides **suggestions** to introduce some easy ways to potentially reduce your future ongoing costs and the impact on the environment.

Alternative design solutions may be presented to the Everleigh Design Committee and will be assessed on individual architectural merit. The Design Committee at its absolute discretion may approve alternative design solutions where it is considered that they achieve the overall intent and desired outcomes of the Design Standards & Guidelines.

# Building (a) Everleigh Portal

We understand that keeping track of all this information can be a challenge and have established a web portal to assist.

The **Building @ Everleigh Portal** is a one stop shop for information relating to your lot, including but not limited to the following:

- Residential Design Standards & Guidelines
- Fact Sheets and Manuals
- Approved Plan of Development Envelope Plan
- Approved Plan of Development Design Criteria
- Survey Plans
- Disclosure Plans
- Civil Design Drawings
- Services Location Plan
- As Constructed Drawings
- Compaction Reports
- Acoustic Report
- Bushfire Management Plans

The information available in the **Building @ Everleigh Portal** will help you and your builder make informed decisions regarding the design of your home.

The **Building @ Everleigh Portal** is accessible via the Everleigh website or speak to an Everleigh sales representative.

# The Approval Process

You will need both the Design Approval from the Everleigh Design Committee (Design Committee) and Building Approval from Logan City Council (Council)/ building certifier before you can commence construction.

Mirvac has developed a streamlined process based on previous experience to ensure that you can start building your home and garden as soon as possible



The Design Committee often receives an influx of applications at the time of settlement. To avoid any potential delays to starting the build on your lot, we recommend that your builder submits your application as early as possible to give you a head start on the assessment process.

# YOUR STEPS

It may seem daunting but often your builder has plenty of experience with this process.

atta docui of Covei



Please ensure that your builder attaches all the required documentation listed in the Covenant Application Form as part of the submission.



Be sure to include the proof of bond payment as part of your covenant application to avoid a delay in the assessment and approval process. The bond will be returned after the final inspection (refer Step 9).

Your builder will work with you to design your home to comply with this document. Proceed to Step 2 once you're happy with your design and your builder has drawn up the consolidated set of plans.

Design

# STEP 1



# Submission

Your builder submits your house plans, colour schedules, landscape plans and proof of covenant payment (refer to Step 3) to the Design Committee via the Building @ Everleigh Portal.

# Covenant Bond Payment

Your fully refundable **Covenant Bond** is required to be deposited to the following account to be held in trust.

HWL Ebsworth Lawyers Law Practice Trust Account BSB: 034-003 Acc Number: 246634 Description: "Surname & Lot Number" – Covenant Bond Amount: \$1000

Assessment

The Design Committee will assess your submission for compliance with the Design Standards & Guidelines. During this process we will work with you and your builder if anything needs amendment. In some cases, plans may need to be resubmitted. This process normally takes 2 weeks if all information is provided.

# Building Approval

Once Design Committee approval has been issued, your builder can then make an application to your accredited building certifier/ Council for the **statutory Building Approval.** 



# Construction

Please ensure that your lot is properly maintained to be free of excessive weeds, rubbish or garbage prior to and during the construction phase of your home. This will ensure that the land is safe at all times.

# Call for Inspection

STEP

Ο

••1

Once your house and landscaping is complete, please touch base with us via the **Building @ Everleigh Portal** to **organise your final inspection.** 

> 9 nspecti

STEP

# Inspection & Refund

The covenant bond will then be refunded once **final compliance approval** is issued by the Design Committee and the **return bond form** is completed on the **Building @ Everleigh Portal**.

HOT TIP!

STEF

5

Design

Approval

The Design Committee will

issue an approval when your

submission has been assessed as complying with the Design Standards & Guidelines. Your

stamped approved plans will be provided to you and your builder via the **Building @ Everleigh Portal**.



# Design & Siting Standards

# Approved Plan of Development — Envelope Plan and Design Criteria

We recommend that you speak with your builder or an Everleigh Sales Team representative who will be able to guide you through the Approved Plan of Development – Envelope Plan and the Approved Plan of Development – Design Criteria (PoD documents) and how these relate to your specific lot.


The Approved PoD documents are available in Annexure A and B.

The Design and Siting Standards (Part 1) which includes the approved PoD documents should also be read with the Architectural and Landscape Design Standards (Part 2).

Where compliance with any particular design standard in Part 2 results in non-compliance with Part 1, then the design standard for Part 1 takes precedence. In all other instances, the design standards in Part 2 take precedence.

Provided overleaf is a simple flow chart with instructions on how to navigate the PoD documents should you wish to review and understand these provisions yourself.







# Architectural and Landscape Design Standards

### MINIMUM BUILDING SIZE

• For lots with only one street frontage, the minimum width of your home is to be the lesser of 25m or 75% of the primary street frontage width, measured to the outside of walls.



### ROOFS

- 40 degrees is the maximum pitch for traditional hip and gable roofs.
- Skillion roofs should be proportional to the main body of the home and roof pitches should generally be between 7.5 – 15 degrees.



- All single storey houses are to have a minimum of 450mm eaves to all publicly visible façades.
- All double storey houses are to have a minimum of 450mm eaves to all publicly visible façades on ground level, and a minimum of 450mm eaves must be provided to all elevations on the upper storey. Variations on this (e.g. inclusion of a parapet) may be approved on merit if it achieves a positive addition to the façade of your home.
- Your roof materials are limited to:
  - Corrugated pre-finished metal sheets (e.g. Colorbond).
  - Roof Tiles.
  - Your roof colour must be of a muted / earthy tone (refer to colour palette below for guidance). Harsh colours such as blue, red and black are not permitted.

#### Colorbond references:



Pale Eucalypt

For more information, please visit the Building @ Everleigh Portal.

# **FAÇADE DESIGN**

#### Primary Street Façade Design

- The residential character of your home must be of a contemporary architectural aesthetic or design. It should reflect the characteristics of Everleigh, embracing the natural bushlands and open spaces, with sympathetic colour tones and material palette. No federation or colonial design elements should be included in the design.
- The façade must have variation in the elevation with at least one substantial projecting feature element such as a portico, verandah or feature wall.
- Any entrance portico must be proportional to the façade of the building and is to be a minimum of 4m<sup>2</sup> (including eave overhangs) and 1.5m deep.
- At least 1 habitable room must address the primary street frontage.


- Similar homes with similar façades are not allowed on adjoining lots.
- Obscure windows or windows to toilets and bathrooms should not front the primary street, unless aesthetically screened.
- Walls over 9m in length without windows or articulation are not permitted.
- No garden sheds, air conditioning condensers or clothes lines, etc. can be located between the primary street façade and boundary.

#### Front Entry Door

- Your home's front door must be well defined and/or visible from the primary street.
- The entry door must be:
- nominal 1200mm wide with minimum 20% glazing; or
   nominal 1000mm wide combined with a minimum 200mm wide sidelight
- Other combinations may be approved on merit if they achieve a positive addition to the façade of your home.


#### Garages

- Minimum two car (side by side) internal garage must be provided for lots with frontages of 12.5m or greater.
- Garages must be integrated into the main building and are to be setback 1m behind the front wall of the main building.



11





#### Secondary Street Façade Design

- If your home is on a corner lot, it must be designed to address all streets.
- It must have variation in the secondary street façade with at least one substantial projecting feature element such as a portico, verandah or feature wall.
- Walls over 9m in length without windows or articulation are not permitted.
- At least 1 habitable room should address the secondary street frontage.
- No garden sheds, air conditioning condensers or clothes lines, etc. can be located between the secondary street façade and boundary unless they are screened from view from a Public Area by approved screens or fences.
- Note: Greenbank Road and Teviot Road are not considered a secondary frontage.

#### Glazing to Public Areas

- All façades (excluding the garage door) are to include glazing for a minimum 10% of the façade area to provide surveillance, interest and variation.
- Sliding windows under 1200mm width are not permitted.
- · Reflective glass is not permitted.
- Temporary window treatments or vertical blinds are not permitted.

### **LETTER BOXES**

- The letter box must be complementary to the modern aesthetics of the primary building and fencing..
- The letter box must be installed prior to the occupation of the main building.

# EXTERNAL WALL MATERIALS AND COLOURS

- To give a sense of variety and interest, a mix of materials or colours must be used to all walls of your home facing a street or park frontage.
- A minimum of 2 and a maximum of 3 variations of colour and/ or materials (excluding windows, doors and garage doors) must be incorporated.
- Colour and/or material change should comprise a minimum 10% of façade wall area.

#### **External Wall Materials**

- Face brickwork or split-face block work is not permitted on primary street, secondary street or public open space façades except as a limited feature only.
- Finishes to the Primary Street and or Secondary Street Facade must return back around the other walls and extend back 1m or wherever the side fence meets the house, whichever is the greater.
- Finishes to any non-feature masonry on primary street and secondary street façade must be solid render not 'bag and painting'.
- Double or 1.5 height face brick is not permitted anywhere.
- Finishes to any non-feature masonry on public open space façades may be 'bag and painting' and the finish used on this façade must also be used on the adjoining side and/or rear walls.
- Second hand materials are not permitted unless they are used as highlight architectural elements.

#### External Wall Colours

- Your colour scheme must be primarily muted tones, but limited and controlled feature highlight colours may be approved.
- Each application is to be accompanied by an External Colour Schedule clearly nominating the location and extent of colours and materials.

For more information, please visit the Building @ Everleigh Portal.

#### **DRIVEWAYS & ENTRY PATHS**

- Maximum of 1 driveway per dwelling is permitted under the plan of Development. Hot Tip: Make sure you consider shared driveway to dwelling and shed (or similar).
- Acceptable materials for your driveway include coloured concrete, exposed aggregate concrete, pavers on a concrete base slab and asphalt concrete with concrete edge. Stencil or painted finish are also accepted. These must compliment the external colour scheme of your home. Note plain concrete driveways are prohibited under the Plan of Development.
- The main pedestrian entry path to your home must be from the primary street frontage and must be constructed from a permanent hard surface such as coloured concrete, exposed aggregate, natural stone or concrete pavers on a concrete base. Pebble or decorative gravel are not permitted as materials for the main entry path to your home.
- Side paths must be constructed from similar materials to the main entry path or decorative gravel on compacted road base. Material selection must reflect and integrate with the surrounding landscape.
- It is important that you ensure your builder complies with Council's approval requirements for your driveway as Council may require you to remove it and reconstruct it if it is not constructed correctly.
- No direct access to residential lots is permitted off Teviot Road or Greenbank Road (prohibited under the Approved Masterplan).

### **PRIVACY AND CROSS VIEWING**

Privacy between your home and your neighbours' homes is to be achieved by one or more of the following measures:

- · Obscure glazing to all bathrooms and toilets.
- 1.7m high sill levels above floor level.
- · External screens.

### SECURITY AND INSECT SCREENS

- The style of any screen visible from a Public Area must be of a simple profile. Hexagonal, diamond grill or ornate historical styles are not permitted.
- Frames and screens must match the colour of the door or window frames or be dark grey or black in order to reduce their visual impact.
- Security shutters or security blinds over windows are not permitted if visible from a Public Area.

# EXTERNAL SERVICES AND WASTE RECYCLING

- If you have a rainwater tank it must be located away from or screened from view from all Public Areas.
- If your dwelling requires an on-site sewer treatment system, it
  must be located behind the rear building line, and you should
  consider access (for maintenance), irrigation and impact on
  neighbouring properties
- · Meter boxes must be painted to match the wall colour.
- TV aerials are to be installed inside the roof cavity or designed and located so that they are not visible from Public Areas
- Radio masts or satellite dishes are to be designed and located so that they are not visible from Public Areas.
- Storage tanks for solar hot water systems, roof and wall mounted air conditioning units, clothes drying facilities and service yards are not to be visible from Public Areas.
- Water tanks, if installed, must be located to the side or rear of the building, and appropriately screened from the primary street frontage.
- Garbage bin pads are mandatory and are to be located so that they are not visible from Public Areas.

#### **CONSTRUCTION OBLIGATIONS**

- · Your building site must be clean and safe at all times.
- Your builder must provide a skip bin or enclosure on site to contain rubbish for the duration of the construction period.
- Bins and site facilities must be clear of all neighbouring properties, roads, footpaths, reserves and all other Public Areas at all times.

### **DEVELOPER WORKS**

- Where the Developer has constructed a fence, entry statement or retaining wall, it is to be maintained by the owner to the standard to which it was constructed.
- The road and verge in front of your lot including the concrete footpath and services such as water meters, telecommunication boxes, **street trees**, stormwater drains, manholes, and electrical pillars are assets owned by Council or service authorities. They have been constructed to the required standards and Council and other service authorities have recorded them as correctly constructed prior to your house building commencing.
- These assets cannot be altered, including changing the ground levels, without the correct approval from Council.
   Mirvac inspects these assets at completion of your home to ensure no damage. Any damage caused during construction of a dwelling to any estate infrastructure (e.g. kerbs, grassed verges, street trees, bollards, etc.) is to be repaired by the owner to the standard to which it was constructed.



#### LANDSCAPING

- The landscaping to areas of your lot visible from Public Areas must be approved by the Design Committee.
- The planting theme to be adopted is generally of a native character. All trees, shrubs, and ground covers must be selected for their appropriateness according to their proposed situation.
- Planted garden beds must be provided to a minimum of 50% of the available soft landscaping area forward of the building line on the primary street frontage and 20% of the available soft landscaping area forward of the building line on the secondary street frontage (if applicable), with high quality turf installed to the remainder of soft landscaping areas.
- Generally, a 50/50 ratio of shrubs to ground covers will establish suitable variety and form.
- A minimum of two large canopy trees (minimum size of 100L stock and 2.5m tall at the time of planting) must be provided to the landscape areas between your house and the verge.
- Gardens are to be edged with concrete, galvanized steel, masonry or rectangular shaped treated timber, but not round timber, logs or plastic edging.
- Garden edges with a height exceeding 200mm are considered to be a retaining wall, therefore must be constructed according to the design requirements of a retaining wall.






#### **Retaining Walls**

- A retaining wall is defined as any retaining structure higher than 200mm.
- All retaining walls must be constructed as part of the construction of your home.
- Retaining walls must be tiered 1m vertical and 1m horizontal where forward of the building line to any street, park or lane and visible from Public Areas and must be constructed to match the developer's specification or materials such as stone, masonry, steel or quality hardwood timber. The horizontal section is to comprise a planting zone to soften the visual impact of the retaining wall.



• For sloping lots and where a built to boundary wall is permitted, this wall must be projected to at least 150mm below the likely pad level of the adjacent block. The pad level can be assumed to be the average of the four corners of the adjacent block using the As Built levels. The build down of the build to boundary wall must be in a material consistent with the visible section of the wall immediately above it.



- Retaining wall construction must include a suitable drainage system to deliver sub-surface water below the wall to the local storm water system.
- Retaining walls may need to be certified by a Registered Professional Engineer. You are required to meet the Local Authorities requirements with regard to this matter.
- Please refer to the Retaining Wall Fact Sheet and WRB Retaining Wall Warranty in Annexure E for further detail.

#### Sheds

- · Must be located behind the rear building line.
- Must be painted or stained to suit the colour scheme of the home. Reflective materials are not permitted.
- Must be less than 100m<sup>2</sup>.
- Must be less than 5m in height.
- Multiple sheds are permitted as long as the combined area is no larger than 100m2.
- Your roof colour must be of a muted / earthy tone (refer to colour palette below for guidance). Harsh colours such as blue, red and black are not permitted.



Consider access when locating your shed, noting only one driveway per lot is permitted under the Plan of Development. Driveway will need to provide access to the garage and shed (or similar).

### **FENCES GENERAL**

- All fences to your lot must be approved by the Design Committee.
- Only fence types shown in Annexure C are allowed. No other materials such as bamboo or colorbond are allowed.
- Fences constructed by Mirvac on any lots cannot be removed or altered without written permission from Mirvac. Any damage to these fences must be repaired to the original standard by the land owner(s).
- Fences visible from Public Areas must be maintained on an ongoing basis including recoating with timber treatment if detailed as part of the fence type.
- All lots are required to have front, side & back fences.

#### Fencing facing the Primary Street


- Must be Rural Fence Type A (RFA)
- Maximum 1.2m in height to top rail. (Refer to RFA Fence Detail)
- Must be located a minimum of 1m behind the adjoining front façade wall.
- Fence returns, if any, must be of the same style as RFA.

# Fencing facing the Secondary Street (being Greenbank Road or Teviot Road)

- Must be Rural Fence Type A (RFA)
- Maximum 1.2m in height to top rail. (Refer to RFA Fence Detail)

#### Fencing to Side Boundaries

- Must be Rural Fence Type A (RFA) for the first 40m from front boundary fence.
- Maximum 1.2m in height to top rail (or top wire if RFB).
- Remaining side boundary fence can be Rural Fence Type A
   (RFA) or Rural Fence Type B (RFB)
- Refer to Annexure C for further detail on fence requirements and options for side boundary.






#### GATES

# Gates are not mandatory, although must consider the following if installed:

- Gates can be sliding or hinged. If hinged, they must open inwards
- · Maximum 1.2m in height
- Driveway gates to be a maximum of 6m wide
- Pedestrian gates to be a maximum of 1.2m wide (including side gates)
- No vehicle gates are permitted onto Greenabank Road or Teviot Road (Pedestrian gates are permitted, and to be a maximum of 1.2m wide)
- Gate style must be in keeping with the character of the home



Rural Fence Type B (RFB)



# Sustainable Living Guidelines

Mirvac considers sustainability and innovation to be key components in delivering cohesive communities that are safe, encourage healthy and active lifestyles and result in lower household expenses.

#### **Objectives**

- To set a new benchmark for high-quality sustainable living, and encourage the incorporation of best practice sustainable initiatives
- To provide and encourage opportunities for residents to reduce their environmental impact
- To provide and encourage opportunities for residents to reduce household expenses during operation

#### Energy Consumption and Greenhouse gas-emission reduction

- Mirvac encourages all homes to achieve a 7 Star NatHERS rating. This may be achieved through incorporation of the following elements where necessary –
  - Maximising opportunities for cross ventilation and provide high level operable windows in multi-level homes to allow for heat removal
  - Shading designed to restrict solar access to the living spaces in summer, whilst allowing beneficial solar access in winter.
  - Increased rating of the wall and ceiling insulation to the required specification
  - Treated glazing or double glazing where necessary
  - Draft sealing (weather seals on external doors etc.) where necessary
  - Sealed exhaust fans where necessary

- In addition to achieving a 7 Star rating on the building fabric, Mirvac encourage house designs to include the following energy saving features:
  - Gas boosted solar hot water or electric heat pump hot water systems
  - Gas or induction cook tops
  - LED light fittings throughout the home
  - Exterior lighting fitted with motion sensors
  - Low energy use appliances (aim for energy ratings greater than 4 star)
  - Energy efficient air conditioning systems (aim for a COP greater than 3)
  - Standby 'Green Switch' or Smart home automation to reduce energy whilst the home is unoccupied.
  - Solar photovoltaic electricity systems with battery storage

## Water Conservation and reuse

- To assist in achieving an overall reduction in household water usage, Mirvac recommends that homes incorporate the following measures:
  - Rainwater tanks for toilet flushing and irrigation
  - Dishwasher and washing machines with a 4 Star or greater WELS rating
  - Tapware and toilets with a 4 Star or greater WELS rating
  - Showers with a 3 Star WELS rating
  - Purchasers are encouraged to consider water efficient landscape design, soil mix, and plant selections, with a target of a minimum of 70% of planted species to be drought tolerant

#### Materials and Waste

- Maximise the use of standard sizes of materials wherever possible to minimise wastage
- Mirvac recommends the use of low-impact construction materials
  - For masonry consider low impact options, such as recycled or carbon neutral bricks
  - For lightweight construction, consider the use of natural or innovative materials such as timber, structural insulated panels or Hebel for a reduced environmental impact and good thermal performance qualities.
- Internal Finishes
  - Consider the use of flooring, joinery and plasterboard that is environmentally certified by independent certification schemes such as GECA, EcoSpecifier or the Carpet Institute of Australia
  - Select high quality, durable finishes with long warranty periods

- To reduce the airborne chemicals within your home consider the following products
  - Engineered wood products, such as kitchen cabinetry and wardrobes, with low or zero formaldehyde (rated as E1 or E0)
  - Paints, adhesives and carpets rated to have low levels of volatile organic compounds (VOCs)
- To reduce waste to landfill during the operation of your home, consider
  - Installing a dual bin in the kitchen joinery to make recycling as easy as disposing of general waste
  - The use of a worm farm or composting bin to reduce food waste and provide fertiliser for your gardens.

# Smart Technology

Smart monitoring

Consider the use of smart meters to help track your energy consumption and reduce your bills even further

- Smart home automation
   Consider the use of smart home automation to make your life easier and future proof your home.
   Systems available include:
  - Smart Security systems
  - Smart intercom and access controls
  - Smart controls of lighting, blinds, air conditioning and appliances
  - Audio Visual systems
- If solar electricity and/or batteries are installed, consider a fully electric house to avoid the need for a natural gas connection.

# Landscaping

- The use of permeable surfaces is encouraged to maximise opportunities for natural infiltration and groundwater recharge
- The use of waterwise plant species, waterwise irrigation and mulching of garden beds is encouraged to reduce water use
- The planting of trees offering shade for the house and outdoor living areas and contributing to bird habitat is encouraged
- The use of locally native plant species is encouraged to increase biodiversity
- Consider the use of herbs, vegetables and fruit trees to create a productive garden



Please refer to Annexure D for the Landscaping Design Guidelines including concepts and a recommended planting palette which provide further information on how to achieve a high quality landscape outcome.

# Definitions

## As Constructed Site Level

The existing level of your lot as constructed during the civil works completed by or on behalf of Mirvac.

### Built to Boundary Walls (Zero Lot Boundary)

Refer Plan of Development.

## **Covenant Bond**

A Covenant Bond has been incorporated into the land sales contract for all properties within Everleigh. The fully refundable Covenant Bond serves to ensure that well designed, quality homes are brought to life to make this an attractive community to be proud of.

### **Design Committee**

The entity appointed by Mirvac authorised to approve building applications under these Residential Design Standards & Guidelines.

### Façade

Elevation of a building visible from a Public Area. The primary façade is the elevation facing the primary street.

# Living Areas

The internal part of your home excluding utility areas such as garage, laundry, bathroom, toilet, hall ways and storage areas.

# Local Authority

Logan City Council or the Department of State Development, Manufacturing, Infrastructure and Planning as applicable.

# Plan of Development (POD)

The approved Plan of Development – Envelope Plan and Plan of Development – Design Criteria in Annexure A and B.

# **Primary Street**

The street fronting your lot where the lot has only one street frontage; or for lots with two or more street frontages the street which your home's front door is located.

# Private Open Space

External areas of your lot with an area and dimensions as required by the Plan of Development. Private Open Space areas are not to contain any service items such as bin store, air conditioning condensers or rainwater tanks, etc. It may be roofed or un-roofed.

# **Public Area**

Any land vested to, or under the control of the Logan City Council. E.g. roads, verges /nature strips, parks, public access ways, etc.

# **Public Open Space**

Public Area excluding roads and verges/nature strips.

# **Retaining Wall**

A retaining wall is defined as any retaining structure higher than 200mm.

#### Setback

Refer Plan of Development.

### Site Coverage

Refer Plan of Development.


# **Secondary Street**

Applies to lots with more than one street frontage and is the street(s) which is not the primary street.

Note: for the purpose of these Design Standards and Guidelines, Greenbank Road and Teviot Road are not considered secondary street frontages.

Residential Design Standards & Guidelines 20






PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL Approval no: DEV2016/768 Date: 10 July 2020




# **ROL 1:** PLAN OF DEVELOPMENT - ENVELOPE PLANS

**TEVIOT ROAD, GREENBANK** 


09 JULY 2020










PLAN OF DEVELOPMENT - ROL 1 - ENVELOPE PLAN - SHEET 1 OF 4












# RURAL FENCE TYPE A (RFA) TIMBER HARDWOOD FENCE


# SPECIFICATIONS


- 1200mm sawn (to top rail), dark (stained), natural hardwood timber post & rail style fence
- The proposed specification is 150mm x 150mm HDW posts with 3 x 200mm x 50mm HWD timber rails. Rails to be fully checked in flush to allow for dog mesh. Posts to be concreted a minimum of 600mm in ground
- This fence will be required along the front boundary of the lot, minimum 40m down side boundaries from front boundary fence, and along the rear boundary (and any other fences fronting a road ie Greenbank Road or Teviot Road).
- If owners wish to continue this along the full side boundary they are permitted to do so.
- This style of fence will allow for a dog proof mesh to be fixed to it if required by the owner.
- If owner requires dog proof mesh this is to be 8/115/15 hinge joint mesh with steel strainers (if required).
- Timber to be stained in Jarrah Integrain Timber Oil.



### **RURAL FENCE TYPE A EXAMPLE**

150






# RURAL FENCE TYPE B (RFB) STAR PICKET WITH STEEL STRAINERS


# SPECIFICATIONS

- To be 1200mm (to top wire) star picket fence with 5 strand plain wire.
- 1300mm high black steel star pickets, 5 strand wire (3.15 galvanised wire) medium tensile, tensioned with wire (Gripple) fixings to strainer posts
- Will require steel black steel strainer posts concreted a minimum 700mm in ground
- Stay and star pickets to be black steel material.
- Rural Fence B (RFB) to be used along side boundaries only, for the back 60m measured to the rear boundary, as minimum standard(Intergrain Timber Oil stained in Jarrah).
- Owner has the option of continuing Rural Fence Type A (RFA) style fence for full length of side boundary if preferred.
- If owner requires dog proof mesh this is to be 8/115/15 hinge joint mesh with steel strainers (if required)

## RURAL FENCE TYPE B (RFB) EXAMPLE







# **ROL 1:** PLAN OF DEVELOPMENT - DESIGN CRITERIA

**TEVIOT ROAD, GREENBANK** 

10 NOVEMBER 2020





U.UIII 1.0m 1.5m 0.0m 1.0m 1.0m 2.0m 1.0m 1.0m 1.5m 2.0m 1.0m 1.0m 2.0m 2.01 1.0m 2.0m 2.0m m 2.0m 2.0m 0m 2.0m .0m .5m Om LOT DEPTHS 1.0m ALL LOT DEPTHS ALL LOT DEPTHS 1.0m DEPTHS ←1.0m





# **1.0 APPROVED USES**

#### 1.1 USES EXEMPT IN ACCORDANCE WITH THIS PLAN OF DEVELOPMENT

Uses listed in Table 1 and complying with the relevant Design Criteria (Section 3.0 and Section 4.0) in this Plan of Development and ROL 1: Plan of Development - Envelope Plans document are approved exempt development.

TABLE 1: LAND USES EXEMPT IN ACCORDANCE WITH THIS PLAN OF DEVELOPMENT

#### LAND USES

- Display HomeHouse (detached, attached, or interface lots)
- Park Home Based Business

 Multiple Residential (Up to 3 dwelling units where identified on the ROL 1: Plan of Development - Envelope Plans) Advertising Device

### 1.2 USES SUBJECT TO COMPLIANCE ASSESSMENT

Uses listed in Table 2 and complying with the relevant Design Criteria (Section 3.3, 3.4 and 3.5) in this Plan of Development and ROL 1: Plan of Development Envelope Plans document are approved development subject to Compliance Assessment.

TABLE 2: LAND USES USES SUBJECT TO COMPLIANCE ASSESSMENT & DESIGN CRITERIA

#### LAND USES

Sales Office (up to 400m<sup>2</sup> GFA)

Other Residential (Retirement)
Multiple Residential (4 or more dwelling units where identified on the ROL 1: Plan of Development - Envelope Plans)

### 1.3 DEFINED TERMS

The terms used in this document have a particular meaning as stated in the Greater Flagstone UDA Development Scheme (October 2011) (Development Scheme). The Development Scheme definitions prevail over all other planning instruments to the extent of any inconsistency.

# 2.0 CRITERIA FOR A CHANGE TO APPROVED LAYOUT FOR GREENBANK ROL 1


### 2.1 DESIGN STANDARDS FOR A CHANGE TO APPROVED RECONFIGURING A LOT LAYOUT AND PLAN OF DEVELOPMENT **ENVELOPE PLANS FOR GREENBANK ROL 1**

The following plans and documents can be amended by compliance assessment where generally in accordance with the design standards in Table 3, or as otherwise agreed with the nominated assessing authority.

- ROL 1: Plan of Development Envelope Plans (Envelope Plans) 1.
- ROL 1: Reconfiguration of a Lot Plans (RoL Plans) 2.

Figure 1 below identifies those fixed elements of the Envelope Plans and RoL Plans that cannot be adversely impacted or changed.

#### FIGURE 1: FIXED ELEMENTS - ROL 1



#### TABLE 3: DESIGN STANDARDS


GENERAL	DESIGN STANDARDS
Development Yield	The total development yield is to be between 457 and 559 dwellings (being the originally approved 508 dwellings +/- 10%) where not in conflict with the other requirements of Table 3: Design Standards.
Lot Design	<ul> <li>Size &amp; density</li> <li>no minimum lot size</li> <li>For Residential - Standard Lots, development achieves a minimum net residential density of 15 dwellings per hectare for ROL 1</li> </ul>
	Shape • Width and depth consistent with typical lot dimensions - refer Section 3.0.
	<ul> <li>Slope</li> <li>Unless constructed in an integrated or attached development, the finished slope on a lot less than 450m<sup>2</sup> in area does not exceed:</li> <li>10% side slope</li> <li>5% lengthwise slope</li> <li>Less, if both figures approach the maximum together.</li> <li>Platform construction required when finished slope on lot is 16% or greater</li> </ul>
Block Size	<ul> <li>Length 100-200 metres</li> <li>Mid-block break providing a pedestrian link when blocks are over 130 metres</li> <li>Depth 40-80 metres</li> </ul>
Interface Lots	Minimum lot size of 3,000m <sup>2</sup>
Lot Layout	<ul> <li>No more than eight narrow (less than 10.0 metres) frontage lots in a row.</li> <li>No more than six lots with a width of 7.5 metres to 5.0 metres in a row unless serviced by a rear lane.</li> </ul>
Access	<ul> <li>90% of dwellings must be within 400m of a Neighbourhood Recreation Park or other park providing equivalent informal recreation opportunities.</li> <li>90% of Residential - Standard Lots are within 400 metres of an existing or planned public transport stop.</li> </ul>
Street Network	<ul> <li>Grid pattern or modified grid responsive to site characteristics.</li> <li>Where slope allows, orientation within 15 degrees of north-south or east-west.</li> <li>To minimise cut &amp; fill, streets follow ridges, gullies, and/or are perpendicular to slope.</li> <li>Minimise cul-de-sacs where possible. Where proposed, cul-de-sac length is desirably no greater than 10 lots.</li> </ul>
Typical Road Typologies	<ul> <li>Roads are designed generally in accordance with the approved Context Plan.</li> <li>Street network includes (where relevant):</li> <li>A trunk connector providing access to neighbourhood connector streets;</li> <li>Neighbourhood connector streets providing direct access to properties and connections to neighbourhood destinations;</li> <li>Neighbourhood access streets provide direct access to properties and neighbourhood lanes; and</li> <li>Neighbourhood lanes – provide direct property access either at the front or rear of lots.</li> </ul>
On-Street Car parking	On-street car parking to be provided at a minimum rate of 0.5 spaces per residential lot.
Total Park Area Required	Minimum 2.8 ha

Note: Parks to be provided generally in accordance with the requirements of the Open Space Master Plan Rates of Provision & Accessibility

#### **REFERENCE MATERIAL**

	PDA Guidelines and Practice Notes	<ul> <li>Guideline 1 - Residential 30 (May 2015)</li> <li>Guideline 5 - Neighbourhood Planning and Design (May 2015)</li> <li>Guideline 6 - Street and Movement Network (April 2012)</li> <li>Guideline 7 - Low Rise Buildings (May 2015)</li> <li>Guideline 12 - Park Planning and Design (May 2015)</li> <li>Guideline 13 - Engineering Standards (May 2015)</li> <li>Guideline 18 - Development Interfaces (May 2015)</li> </ul>
--	---	---





# 3.0 DESIGN CRITERIA

### 3.1 HOUSE (DETACHED)

### The following criteria apply to a House (Detached) proposals

#### **Planning Context**

- In accordance with the provisions of the Greater Flagstone Urban Development Area Development Scheme (October 2011) (Development Scheme), building work and operational work are exempt development where in accordance with, or associated with, this Plan of Development (PoD).
- All relevant provisions of this PoD must be satisfied prior to the issuance of a Building Approval.
- The provisions of the Development Scheme will apply where development does not comply with all provisions of the Plan of Development.
- The Development Scheme definitions prevail over all other planning instruments to the extent of any inconsistency

#### General

- All development is to be undertaken in accordance with the Development Approval. <sup>18</sup> Nominated building location envelopes may be constrained by future easements and/or services. 2.
- Where allotments are so marked on ROL 1: Plan of Development Envelope 3 Plans, residential buildings must be designed and constructed to comply with AS3671-1989 Acoustics - Road Traffic Noise Intrusion - Building, Siting and Construction (floor-plan specific acoustic design) or as per acceptable forms of construction from QDC MP4.4 - Buildings in a Transport Noise Corridor. Refer to the approved Noise Impact Assessment for further information.

#### Setbacks

- Setbacks are as per Table 4: Plan of Development Table House (Detached) (Table 4), unless specified otherwise on this sheet.
- The permitted location of built to boundary walls are indicated 5.
- on the ROL 1: Plan of Development Envelope Plans.
- Built to boundary walls are not mandatory. Where built to boundary walls are not adopted, side setbacks shall be in accordance with the requirements 6 of the Non-Built to Boundary Setbacks nominated in Table 4.
- All boundary setbacks are measured to the wall of the structure.
- The dwelling and associated projections (gutters etc.) must be located wholly within the subject lot, unless encroachment rights are secured by way of easement (or other suitable mechanism).
- Other than built to boundary walls, the outside face of the fascia, or the roof structure where there is no fascia, or attached sunhoods or the like (not including retractable blinds, fixed screens, rainwater fittings, or ornamental attachments) is permitted to extend 600mm within the prescribed setback, however cannot encroach closer than 450mm from the boundary.
- 10. The length of the built to boundary wall is not to exceed 50% of the lot depth, or 15.0m, whichever is the greatest.
- For corner lots (excluding a corner intersecting with a laneway), 11. no building or structure over 2m high is built within a 6m x 6m truncation at the corner of two road frontages (refer Table 4).
- The primary street frontage elevation is to be articulated to reduce the mass of the building by one or more of the following a. Windows recessed into the façade

  - b.
  - Balconies, porches or verandahs Window hoods Shadow lines created on the building through mid. nor changes in the façade (100mm minimum)
- 13. Entrance porticoes may be located closer to the property
  - boundary than stated in Table 4, provided that the portico:
    a. Is located no less than 1.4m from the front property boundary,
    b. Does not exceed maximum height of 4.5m,
    c. Does not exceed a width of 3.0m; and
    d. The state of the stat

  - c. d. The portico remains open and not enclosed

# **Building Height**

- 14. The maximum building height is 9.0m.
- 15. Buildings must have no more than 2 storeys

**INDICATIVE ALLOTMENT TYPE** 

FRONT SETBACKS PRIMARY FRONTAGE

For lots with multiple street frontages

SECONDARY FRONTAGE

**REAR SETBACK** Where allotments are so

2.0m total height

For all other lots

SIDE SETBACK

URBIS

frontage

Note: A Pedestrian Link is not a secondary

marked (

Development - Envelope Plan For lots located on the low side

of a retaining wall greater than

a. A lot only has one primary frontage.
 b. The primary frontage for a corner lot is as per the ROL 1: Plan of Development -Building Envelope Plan (if nominated)

- Site Cover
- The maximum Area covered by all buildings and structures roofed with impervious materials, does not exceed the maximum site cover indicated in Table 4, where Area means:
- for enclosed spaces, the area including the outside wall; and a. b. for unenclosed spaces, the area is measured along a

TABLE 4: PLAN OF DEVELOPMENT TABLE - HOUSE (DETACHED)

To Wall (Ground Floor)

To Wall (Ground Floor)

To Wall (First Floor)

To Wall (First Floor)

To Garage Door

Ground Floor

Ground Floor

Ground Floor

nd Eld

First Floor

First Floor

First Floor

Gro

To Garage Door

line 600mm in from the perimeter of the roof.

(PRIMARY REFERENCE FOR ALLOTMENT TYPE IS THE ROL 1: PLAN OF DEVELOPMENT - ENVELOPE PLANS)

**INDICATIVE ALLOTMENT WIDTH (FRONTAGE)** 

### PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL





### 4 March 2021

- Private Open Space and Amenity Each house / dwelling unit has a clearly defined outdoor living space which:
  - Has an area of at least: a.
    - 12 sqm with a minimum dimension of 2.4m for a 3 or more bedroom house ' dwe<sup>i</sup>llina unit 9 sqm with a minimum dimension of 2.4m for a 2 bedroom house / dwelling
      - unit; or
    - 5 sqm with a minimum dimension of 1.2m for a 1 room or 1 bedroom house **Retaining Walls** - 5 sqm with a minimum dimension of 1.2m of a mount of 1 bedroom / dwelling unit.
       Is accessible from a living area; and
       Has a ground slope of not more than 1 in 10;
       Provides visual privacy from outdoor living spaces on adjacent lots.
  - b.

### **Eaves and Roof Pitch**

Eaves, or other architectural features which add visual interest to wall/roof junctions (such as parapets), are required to all walls excluding those built to the boundary. 19 The maximum roof pitch is 40 degrees.

#### Parking and Driveways 20.

- A minimum of two on-site car parking spaces must be provided for each dwelling, one of which must be within a garage.
- Garages
- A single storey dwelling on a lot with a primary frontage equal to or greater than 10m and less than 12.5m must adhere to the following criteria: The front facing building wall, which comprises the garage door, to not exceed an external width of 5.7m The garage door: a.

  - Width does not exceed 4.8m; and
  - Has a minimum 450mm eave above it; and
  - · Setback a minimum of 240mm behind the pillar of the garage door; and
  - Setudate a minimum of 240 min benind the plinar of the garage door, a
     Has a sectional, it or roller door.
     The front façade of the dwelling is to be forward of the alignment of the garage wall, and include the following:
     A front entrance door with glass inserts and / or windows or with a sidelight where the front door is solid. If the front facade includes
  - a habitable room with window, a sidelight is not required; or
     A front verandah, portico or porch located over the front entrance, which extends a minimum of 1600mm forward
- of the entrance door. The verandah, portico or porch is to include front piers with distinct materials and/or colours.
  b. A double storey dwelling on a lot with a primary frontage equal to or great-er than 10m and less than 12.5m must adhere to the following criteria:
  The front facing building wall, which comprises the garage door, to not exceed an external width of 5.7m

  - The garage door: Width does not exceed 4.8m; and

COURTYARD

14m

3.0m

3.0m

5.0m

2.0m

2.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

2.0m

- Width does not exceed 4.8m; and
  Setback a minimum of 240mm behind the pillar of the garage door; and
  Has a sectional, tilt or roller door.
  The front entrance door is to be visible and identifiable from the street.
  A dwelling on lot with a primary frontage of 12.5m or greater must adhere to the following criteria:
  Must have a garage door not exceeding 40% of the lot frontage
  Double garages are to be setback 1.0m behind the main face of the dwelling or two ground floor.
- dwelling at the ground floor.
- 22. For a dwelling on a lot with a primary frontage less than 10.0m the garage door width must not exceed 3.0m.
- The maximum width of a driveway at the lot boundary shall be:

- a. 4.8m for a dwelling with a double garage with a lot frontage of 12.5m or greater;
  b. 3.5m for a dwelling with a double garage with a lot frontage of a dwelling with a double garage with a lot frontage.
  c. 3.0m for a dwelling with single or tandem garage on any lot frontage. Garages are to be located as nominated on the ROL 1: Plan of 24
- Development Envelope Plans, or in an alternate location subject to confirmation that there is no conflict with proposed/existing services
- A maximum of one driveway per dwelling is permitted unless it is a corner lot where a maximum of two driveways are permitted (1 per frontage).
- 26 The driveway finish must not be plain concrete
- Driveways are to be:
- 27 a.

VILLA

10m

3.0m

3.0m

5.0m

1.5m

2.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

2.0m

a minimum distance of 6m from an intersection of one street with another street; and

**PREMIUM VILLA** 

12.5m

3.0m

3.0m

5.0m

2.0m

2.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

2.0m

- b. designed and constructed in accordance with approv-al / permit requirements of Logan City Council.
- 28. Carports are only permitted where:
  - Located behind the façade of the dwelling which fac-es the primary street frontage; and For corner lots, set back a minimum of 3.0m from the secondary street frontage. а.
  - b.

- Other than walls erected by the developer, retaining walls:
- must be tiered 1m vertical and 1m horizontal where forward of the building line to any street, park or lane and visible from the public realm; and a. b. cannot exceed 1.5m in height without stepping elements incorporated. 30. For sloping lots:

PRIMARY FRONTAGE

Min 1

PRIMARY

FRONTAGE

PREMIUM

TRADITIONAL

**20**m

4.5m

4.5m

5.5m

3.0m

3.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

2.0m

1\_0 3

- a. Where a built to boundary wall is permitted, this wall must be prolected to at least 150mm below the likely pad level of the adjacent block. The pad level can be assumed to be the average of the four corners of the adjacent block using the As Built levels. The build down of the build to boundary wall must be in a material consist-ent with the visible section of the wall immediately above it.
- Where on a lot with a rear retaining wall exceeding 2.0m above ground level (or where identified on the Plan of Development
- Envelope Plans), the Rear Setback is as per Table 4.

#### Fencing

Queensland

Government

32. Primary frontage requirements:

on the right).

34. Pedestrian link requirements: a. Fences to pedestrian links:

**Structures and Services** 

Secondary Dwelling

38. A secondary dwelling is only permitted where:

The lot is 400m<sup>2</sup> or more;

37.

a.

b

С.

PREMIUM

COURTYARD

16m

4.0m

4.0m

5.0m

2.0m

2.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

2.0m

- The maximum fence height is 1.8m; а
- b.
- Fences are not permitted along road front-ages forward of the building; and Side boundary fences are to be recessed at с. least 1m behind the wall addressing the pri-
- mary road frontage (as seen on the right). Secondary frontage requirements:
   a. Fences to Secondary Frontages (Side) of

Corner Lots may extend beyond the face of the secondary facade only on the basis the fencing visible from the public area is:

A maximum fence height of 1.8m; Solid up to a height of 1.2m with any fencing above 1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall where the transparency is consistent across the full area of the fence (in transparency be leasted)

the fence (ie. transparent sections cannot be located Solely at ground level); and Does not extend for lengths greater than 10m without a landscaped recess 3m in length and 1m deep (as seen

A maximum fence height of 1.8m; and Solid up to a height of 1.2m with any fencing above 1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall

where the transparency is consistent across the full area of the fence (i.e. transparent sections cannot be located solely at ground level).

All ancillary structures (e.g. garden sheds, gazebos, pools) and services are

36. Screened drying areas are to be located behind the main face of the dwellings.

Rubbish bin areas are to be located behind the main face of the dwellings or stored so as to not be visible from the public realm.

The lot frontage is 12.5m or more; and It complies with the applicable self assessable provi-sions in Schedule 3 of the Development Scheme where

TRADITIONAL

18m

4.5m

4.5m

5.5m

3.0m

3.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m


2.0m

not inconsistent with the provisions of this PoD.

There is to be no more than one secondary dwelling on a lot.

built be suitably located or screened to minimise detrimental visual impact from public spaces or neighbouring residential allotments, with the exception of solar panels and solar hot water systems which may be located where most efficient.

SITE COVER		70%	70%	60%	60%	60%	60%
Non-Built to Boundary	First Floor	0.9m	1.0m	1.0m	1.5m	2.0m	2.0m
SIDE SETBACK	Ground Floor	0.9m	1.0m	1.0m	1.0m	1.5m	1.5m
Built to Boundary	First Floor	0.9m	1.0m	1.0m	1.0m	1.5m	1.5m
SIDE SETBACK	Ground 1 1001	0-0.311	0-0.3111	0-0.3111	0-0.311	0-0.311	0-0.3111



**GREENBANK** 

PROJECT NO: ND1309 DATE: 09.11.2020 DRAWING NO: DC01-1 **REV:** 16

 $(\mathbf{l})$ 

PLAN OF DEVELOPMENT - ROL 1 - DESIGN CRITERIA - SHEET 1 OF 4

# 3.2 HOUSE (ATTACHED)

#### The following criteria apply to House (attached) proposals.

#### **Planning Context**

- In accordance with the provisions of the Greater Flagstone Urban Development Area Development Scheme (October 2011) (Development Scheme), building work and operational work are exempt development where in accordance with, or associated with, this Plan of Development (PoD).
- All relevant provisions of this PoD must be satisfied prior to the issuance of a Building Approval.
- The provisions of the Development Scheme will apply where development does not comply with all provisions of the Plan of Development.
- The Development Scheme definitions prevail over all other planning instruments to the extent of any inconsistency.

#### General

- All development is to be undertaken in accordance with the Development Approval.
- Nominated building location envelopes may be constrained 2. by future easements and/or services
- Where allotments are so marked on ROL 1: Plan of Development Envelope Plans, residential buildings must be designed and constructed to comply with 3 AS3671-1989 Acoustics - Road Traffic Noise Intrusion - Building, Siting and Construction (floor-plan specific acoustic design) or as per acceptable forms of construction from QDC MP4.4 - Buildings in a Transport Noise Corridor. Refer to the approved Noise Impact Assessment for further information.

#### Setbacks

- Setbacks are as per Table 5: Plan of Development Table House (Attached) (Table 5), unless specified otherwise on this sheet.
- The permitted location of built to boundary walls are indicated 5 on the ROL 1: Plan of Development - Envelope Plans.
- Where built to boundary walls are not adopted, side setbacks shall be in 6. accordance with the Non-Built to Boundary Wall setbacks nominated in Table 5.
- Length of Built to Boundary walls shall be no more than:
- 80% for a house on a lot width of 7.5m or less
- 75% for a house on a lot width of 7.5m 9.9m b.
- 70% for a house on a lot width of 10m 12.49m 65% for a house on a lot width of 12.5m 14.9m
- d
- 60% for a house on a lot width of 15m 19.9m 55% for a house on a lot width of 20m or greater
- All boundary setbacks are measured to the wall of the structure.
- 8. The dwelling and associated projections (gutters etc.) must be located wholly within the subject lot, unless encroachment rights are secured by way of easement (or other suitable mechanism). 9
- Other than built to boundary walls, the outside face of the fascia, or the roof structure where there is no fascia, or attached sunhoods or the like (not including retractable blinds, fixed screens, rainwater fittings, or ornamental attachments) of a building is permitted to extend 600mm within the prescribed setback, however cannot encroach closer than 450mm from the boundary.
- 11. For corner lots (excluding a corner intersecting with a laneway), no building or structure over 2m high is built within a 6m x 6m truncation at the corner of two road frontages (refer Table 5)
- The primary street frontage elevation is to be articulated to reduce the mass of the building by one or more of the following: a. Windows recessed into the façade
- b Balconies, porches or verandahs
- Window hoods С

DEVELOPMENT - ENVELOPE PLANS) FRONT SETBACKS **PRIMARY FRONTAGE** 

For lots with multiple street frontages

SECONDARY FRONTAGE

**REAR SETBACK** Where allotments are so

2.0m total height

For all other lots

SIDE SETBACK

Note: A Pedestrian Link is not a secondary frontage

marked (

Development - Envelope Plan. For lots located on the low side

of a retaining wall greater than

a. A lot only has one primary frontage.
 b. The primary frontage for a corner lot is as per the ROL 1: Plan of Development -Building Envelope Plan (if nominated)

- Shadow lines created on the building through mi-nor changes in the façade (100mm minimum). d.
- 13. Entrance porticoes may be located closer to the property boundary than stated in Table 5 provided that the porticoe
- Is located no less than 1.4m from the front property boundary; а.
  - Does not exceed a maximum height of 4.5m; Does not exceed a width of 3.0m; and
- d. The portico remains open and not enclosed.

### PLANS AND DOCUMENTS referred to in the PDA **DEVELOPMENT APPROVAL**

Approval no: DEV2016/768

4 March 2021

#### Date: **Building Height**

- 14. The maximum building height is 9.0m
- 15. Buildings must have no more than 2 storeys

#### Site Cover

- 16. The maximum Area covered by all buildings and structures roofed with impervious materials, does not exceed the maximum site cover indicated in Table 5, where Area means:

  - for enclosed spaces, the area including the outside wall; and for unenclosed spaces, the area is measured along a line 600mm in from the perimeter of the roof.

#### **Private Open Space and Amenity**

- Buildings must ensure the provision of natural light and ventilation to core living areas.
- 18. Each house / dwelling unit has a clearly defined outdoor living space which: a. Has an area of at least:
  - 12 sqm with a minimum dimension of 2.4m for a 3 or more bedroom house
  - / dwelling unit; 9 sqm with a minimum dimension of 2.4m for a 2 bedroom house / dwelling unit; or
  - 5 sqm with a minimum dimension of 1.2m for a 1 room or 1 bedroom house / dwelling unit; and
  - b.
  - Is accessible from a living area; and Has a ground slope of not more than 1 in 10; and Provides visual privacy from outdoor living spaces on adjacent lots

#### Eaves and Roof Pitch

- Eaves. or other architectural features which add visual interest to wall/roof junctions (such as parapets), are required to all walls excluding those built to the boundary.
- The maximum roof pitch is 40 degrees. 20.

#### Parking and Driveways

- A minimum of two on-site car parking spaces must be provided for each dwelling, one of which must be within a garage. 21
- 22. Garages:
  - a. Front loaded attached allotments must adhere to the following criteria: For lot frontages less than 10m, single or tandem garages must be used; For lot frontages equal to or greater than 10m and less than 12.5m, double

    - garages can be used where the garage door width does not exceed 4.8m; For lot frontages greater than 12.5m, single, tandem or double garages may be used where the garage door width does not exceed 40% of the lot frontage; and
  - Double garages are to be setback 1.0m behind the main face of the dwelling, excluding balconies.
- 23. The maximum width of a driveway at the lot boundary shall be:

  - 4.8m for a dwelling with a double garage on a lot with a width of 12.5m or greater.3.5m for a dwelling on a lot with a width between 10m to 12.49m. b 3.0m for a dwelling with a single or tandem garage on any lot
- A maximum of one driveway per dwelling is permitted unless it is a corner lot where a maximum of two driveways are permitted (1 per frontage).
- Where accessed from a laneway, garages are to be paired (built to a common boundary where possible). 25.

- 26. The driveway finish must not be plain concrete.
- Driveways are to be: 27.
  - a. a minimum distance of 6m from an intersec-tion of one street with another street; and

  - b. designed and constructed in accordance with approv-al / permit requirements of Logan City Council.

#### **Retaining Walls**

- 28. Other than walls erected by the developer, retaining walls:
- a. must be tiered 1m vertical and 1m horizontal where forward of the build-
- ing line to any street, park or lane and visible from the public realm; and b. cannot exceed 1.5m in height without stepping elements incorporated.
- 29. For sloping lots:

FRONT LOADED

3.0m

3.0m

5.0m

1.5m

2.0m

N/A

2.5m

2.5m

2.5m

2.5m

1.5m

1.5m

N/A

Where a built to boundary wall is permitted, this wall must be pro-

# TABLE 5: PLAN OF DEVELOPMENT TABLE - HOUSE (ATTACHED) INDICATIVE ALLOTMENT TYPE IPRIMARY REFERENCE FOR ALLOTMENT TYPE IS THE ROL 1: PLAN OF

To Wall (Ground Floor)

To Wall (Ground Floor)

To Wall (First Floor)

To Wall (First Floor)

To Garage Door

To Garage Door

Ground Floor

Ground Floor

Ground Floor

To Garage Door

First Floor

First Floor

First Floor

jected to at least 150mm below the likely pad level of the adjacent block. The pad level can be assumed to be the average of the four corners of the adjacent block using the As Built levels. The build down of the build to boundary wall must be in a material consist-ent with the visible section of the wall immediately above it.

PRIMARY FRONTAGE

PRIMARY

FRONTAGE

30. Where on a lot with a rear retaining wall exceeding 2.0m above ground level (or where identified on the Plan of Development – Envelope Plans), the Rear Setback is as per Table 5.

#### Fencing

Oueensland

- 31. For front loaded lots the Primary Frontage requirements are as follows:
- - b.
- The maximum fence height is 1.8m; Fences are not permitted along road front-ages forward of the building; and Side boundary fences are to be recessed at least 1m behind the wall addressing the C.
- primary road frontage (as seen on the right) For rear loaded lots the Primary Frontage 32.
- requirements are as follows
  - The maximum fence height is 1.2m; b.
  - Fences are permitted along the Pri-mary Frontage and the side boundaries forward of the façade facing the Primary Frontage; and Fences must be at least 50% transparent.
- 33. For all lots the Secondary Frontage requirements are as follows:
- a. Fences may extend beyond the face of the secondary façade only on the basis the fencing visible from the public area is: - A maximum fence height of 1.8m; - Solid up to a height of 1.2m with any fencing above

35. Within laneways, 1.8m high fences are permitted to screen private open space, car parking and servicing areas.

For rear loaded lots, letterboxes for the dwelling shall be located on the primary street or park frontage and not in the laneway.

Rubbish bin areas are to be located behind the main face of the

dwellings or stored so as to not be visible from the public realm.

The lot is 400m or more; The lot frontage is 12.5m or more; and It complies with the applicable self assessable provi-sions in Schedule 3 of the Development Scheme where not inconsistent with the provisions of this PoD.

41. There is to be no more than one secondary dwelling on a lot.

37. All ancillary structures (e.g. garden sheds, gazebos, pools) and services are

to be suitably located or screened to minimise detrimental visual impact from public spaces or neighbouring residential allotments, with the exception of solar

panels and solar hot water systems which may be located where most efficient.

Screened drying areas are to be located behind the main face of the dwellings.

DUAL LOADED

3.0m

3.0m

5.0m

2.0m

2.0m

5.0m

2.5m

2.5m

2.5m

2.5m

1.5m

1.5m

N/A

the transparency is consistent across the full area of the fence (i.e. transparent sections cannot be located

solely at ground level); and Does not extend for lengths greater than 10m without

a landscaped recess 3m in length and 1m deep (as seen

a. Fences to pedestrian links:

A maximum fence height of 1.8m; and
Solid up to a height of 1.2m with any fencing above 1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall where the fence can be at least 10% transparent overall

transparent sections cannot be located solely at ground level).

where the transparency is consistent across the full area of the fence (i.e.

1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall where

on the right).

34. Pedestrian link requirements

**Structures and Services** 

**Secondary Dwelling** 

40. A secondary dwelling is only permitted where:

The lot is 400m<sup>2</sup> or more;

Letterboxes

38.

39.

**REAR LOADED** 

3.0m

3.0m

N/A

1.5m

2.0m

N/A

2.5m

2.5m

2.5m

2.5m

1.5m


1.5m

1.5m

a.

b.

C.



### 3.3 MULTIPLE RESIDENTIAL

The following criteria apply to Multiple Residential Proposals.

### **Planning Context**

- In accordance with the provisions of the Greater Flagstone Urban Development Area Development Scheme (October 2011) (Development Scheme), building work and operational work are exempt development where in accordance with, or associated with, this Plan of Development (PoD).
- All relevant provisions of this PoD must be satisfied prior to the issuance of a Building Approval.
- The provisions of the Development Scheme will apply where development does not comply with all provisions of the Plan of Development.
- The Development Scheme definitions prevail over all other planning instruments to the extent of any inconsistency.

### General

- All development is to be undertaken in accordance with the Development Approval.
- Nominated building location envelopes may be constrained by future easements and/or services
- Where allotments are so marked on ROL 1: Plan of Development 3 - Envelope Plans, residential buildings must be designed and constructed to comply with AS3671-1989 Acoustics - Road Traffic Noise Intrusion - Building, Siting and Construction (floor-plan specific acoustic design) or as per acceptable forms of construction from QDC MP4.4 - Buildings in a Transport Noise Corridor. Refer to the approved Noise Impact Assessment for further information

### Setbacks

- Setbacks are as per Table 6: Plan of Development Table Multiple Residential (Table 6), unless specified otherwise on this sheet
- All boundary setbacks are measured to the wall of the structure.
- The dwelling and associated projections (gutters etc.) must be located wholly within the subject lot, unless encroachment rights are secured by way of easement (or other suitable mechanism)
- Other than built to boundary walls, the outside face of the fascia, or the roof structure where there is no fascia, or attached sunhoods or the like (not including retractable blinds, fixed screens, rainwater to extend 600mm within the prescribed setback, however cannot encroach closer than 450mm from the boundary
- For corner lots (excluding a corner intersecting with a laneway), no building or structure over 2m high is built within a 6m x 6m 8. truncation at the corner of two road frontages (refer Table 6).
- The primary street frontage elevation is to be articulated to reduce the mass of the building by one or more of the following:
- Windows recessed into the facade Balconies, porches or verandahs

PLAN

- Window hoods c. d. Shadow lines created on the building through minor changes in the façade (100mm minimum).
- 10. Entrance porticoes may be located closer to the property
- boundary than stated in the Table 6 provided that the portico:
- Is located no less than 1.4m from the front property boundary;

TABLE 6: PLAN OF DEVELOPMENT TABLE - MULTIPLE RESIDENTIAL

To Garage Door

- b. Does not exceed a maximum height of 4.5m;
- Does not exceed a width of 3.0m; and С.
- d. The portico remains open and not enclosed.

PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

### Approval no: DEV2016/768

#### 4 March 2021 Date: **Building Height**

- 11. The maximum building height is 9.0m
- 12. Buildings must have no more than 2 storeys.

### Site Cover

- 13. The maximum Area covered by all buildings and structures
  - roofed with impervious materials, does not exceed the maximum site cover indicated in Table 6, where Area means:
  - for enclosed spaces, the area including the outside wall; and a.
  - for unenclosed spaces, the area is measured along a line 600mm in from the perimeter of the roof

### **Private Open Space and Amenity**

- 14. Each house / dwelling unit has a clearly defined outdoor living space which: a. Has an area of at least:
  - 12sqm with a minimum dimension of 2.4m for a 3 or more bedroom house / dwelling unit; 9sqm with a minimum dimension of 2.4m for a 2 bedroom house /
  - dwelling unit; or 5sgm with a minimum dimension of 1.2m for a 1 room or 1 bedroom
  - house / dwelling unit.
  - Is accessible from a living area; Has a ground slope of not more than 1 in 10; and b.
- c. d. Provides visual privacy from outdoor living spaces on adjacent lots. Or communal open space is provided which:

  - a. has an area of at least 25% of the area of the lot; and
    b. is of a shape which can include a circle with a 4.0m diameter.
- 15. Buildings must ensure the provision of natural
- light and ventilation to core living areas.

### **Eaves and Roof Pitch**

- 16. Eaves, or other architectural features which add visual interest to
- wall/roof junctions (such as parapets), are required to all walls

### **Parking and Driveways**

- 18. A minimum of two on-site car parking spaces must be provided for each dwelling, one of which must be within a garage
- 19. For all front-loaded attached allotments, garages are not to dominate the streetscape

17. The maximum roof pitch is 40 degrees

- 20. A maximum of one driveway per dwelling permitted.
- 21. Where accessed from a laneway, garages are to be paired where possible.
- 22. The driveway finish must not be plain concrete.
- 23. Driveways are to be:
  - a minimum distance of 6m from an intersec-

  - tion of one street with another street; and b. designed and constructed in accordance with approval / permit requirements of Logan City Council

### **Retaining Walls**

- 24. Other than walls erected by the developer, retaining walls: must be tiered 1m vertical and 1m horizontal where
  - forward of the building line to any street, park or
  - lane and visible from the public realm; and
  - cannot exceed 1.5m in height without stepping elements incorporated


### Fending

Queenslan

Government

- 25. For front loaded dwellings the Primary Frontage requirements are as follows:
  - a. b.

  - The maximum fence height is 1.8m; Fences are not permitted along road front-ages forward of the building; and Side boundary fences are to be setback at least 1m behind the face of the wall addressing the pri-mary road frontage (as seen on the right). C.
- 26. For rear loaded dwellings the Primary Frontage requirements are as follows:
- a. The maximum fence height is 1.2m; b.
  - Fences are permitted along the Primary Frontage and the side boundaries forward of the façade facing the Primary Frontage; and Fences must be at least 50% transparent.
- 27. For all dwellings the Secondary Frontage
  - requirements are as follows:
  - a. Fences may extend beyond the face of the secondary façade only on the basis the fencing visible from the public area is:
    - A maximum fence height of 1.8m;
      Solid up to a height of 1.2m with any fencing above 1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall where the transparency is consistent across the full area of the fence (i.e. transparent sections cannot be located solely at ground level); and



FRONTAGE

PRIMARY FRONTAGE

- Does not extend for lengths greater than 10m without a landscaped recess 3m in length and 1m deep (as seen on the right).
- 28. Pedestrian link requirements:
  - a. Fences to pedestrian links:

  - A maximum fence height of 1.8m; and Solid up to a height of 1.2m with any fencing above 1.2m in height being at least 50% transparent or the fence can be at least 25% transparent overall where the transparency is consistent across the full area of the fence (i.e. transparent sections cannot be located solely at ground level).
- 29. Within laneways, 1.8m high fences are permitted to screen private open space, car parking and servicing areas

#### Letterboxes

30. For rear loaded dwellings, letterboxes shall be located on the primary street or park frontage and not in the laneway

### **Structures and Services**

- 31. All ancillary structures (e.g. garden sheds, gazebos, pools) and services are to be suitably located or screened to minimise detrimental visual impact from public spaces or neighbouring residential allotments, with the exception of solar panels and solar hot water systems which may be located where most efficient
- 32. Screened drying areas are to be located behind the main face of the dwellings.
- Rubbish bin areas are to be located behind the main face of the dwellings or stored so as to not be visible from the public realm.

N/A

PLAN OF DEVELOPMENT TAB	LE - MULTIPLE RESID	ENTIAL		
INDICATIVE ALLOTMENT TYPE (PRIMARY REFERENCE FOR ALLOTMENT TYPE IS DEVELOPMENT - ENVELOPE PLANS)		FRONT LOADED	REAR LOADED	DUAL LOADED
FRONT SETBACKS				
PRIMARY FRONTAGE For lots with multiple street frontages:	To Wall (Ground Floor)	3.0m	3.0m	3.0m
<ul> <li>a. A lot only has one primary frontage.</li> <li>b. The primary frontage for a corner lot is as per the ROL 1: Plan of Development – Build-</li> </ul>	To Wall (First Floor)	3.0m	3.0m	3.0m
ing Envelope Plan (if nominated)	To Garage Door	5.0m	N/A	5.0m
SECONDARY FRONTAGE	To Wall (Ground Floor)	1.5m	1.5m	2.0m
Note: A Pedestrian Link is not a secondary frontage	To Wall (First Floor)	2.0m	2.0m	2.0m
	To Garage Door	N/A	N/A	5.0m
REAR SETBACK				
For lots located on the low side of	Ground Floor	2.5m	2.5m	2.5m
a retaining wall greater than 2.0m total height	First Floor	2.5m	2.5m	2.5m
For all other lots	Ground Floor	1.5m	1.5m	1.5m
	First Floor	1.5m	1.5m	1.5m


SIDE SETBACK SIDE SETBACK Ground Floor 1.0m 1.0m 1.5m

N/A



SITE COVER		75%	75%	70%
Non-Built to Boundary	First Floor	1.0m	1.0m	1.5m

1.5m





### 3.4 SALES OFFICE

The following criteria apply to a Sales Office:

- The hours of operation of the sales office do not commence before 7am or extend later than 6pm.
- · A minimum of 2 on-site car parking spaces are provided.
- Private open space and public frontage are turfed and landscaped.

### 3.5 OTHER RESIDENTIAL

The following criteria apply to Other Residential:

- Development has minimum boundary clearances that comply with Table 7.
- Each dwelling has private open space with direct access from the principal living areas of each dwelling of a shape which can include a circle with 2.4m diameter.
- · An outdoor communal open space area being a minimum 10% of the site area is provided.
- 90% of development is located within 400m of a bus service.

### TABLE 7: PLAN OF DEVELOPMENT TABLE - OTHER RESIDENTIAL

Setbacks		
Front Setback		4.0m
	where the height of that part is 4.5m or less	1.5m
Side Boundary	where the height of that part is greater than 4.5m but not more than 7.5m	2.0m
	where the height is greater than 7.5m	2.0m
Rear Boundary		6.0m
Maximum Buildir	ng Height	9.0m

### 3.6 HOUSE (INTERFACE LOTS)

### **Planning Context**

- In accordance with the provisions of the Greater Flagstone Urban Development Area Development Scheme (October 2011) (Development Scheme), building work and operational work are exempt development where in accordance with, or associated with, this Plan of Development (PoD).
- All relevant provisions of this PoD must be satisfied prior to the issuance of a Building Approval
- The provisions of the Development Scheme will apply where development does not comply with all provisions of the Plan of Development.
- The Development Scheme definitions prevail over all other planning instruments to the extent of any inconsistency.

### General

- All development is to be undertaken in accordance with the Development Approval.
- Nominated building location envelopes may be 2. constrained by future easements and/or services.
- Where allotments are so marked on ROL 1: Plan of Development - Envelope Plans, residential buildings must be designed and constructed to comply with AS3671-1989 Acoustics - Road Traffic Noise Intrusion - Building, Siting and Construction (floor-plan specific acoustic design) or as per acceptable forms of construction from QDC MP4.4 - Buildings in a Transport Noise Corridor. Refer to the approved Noise Impact Assessment for further information

### Setbacks

- Setbacks are as per Table 8: Plan of Development Table House (Interface Lots) (Table 8), unless specified otherwise on this sheet.
- 5 All boundary setbacks are measured to the wall of the structure.
- The dwelling and associated projections (gutters etc.) must be located wholly within the subject lot, unless encroachment rights are secured by way of easement (or other suitable mechanism). 6.

### **Building Height**

- The maximum building height is 9.0m.
- Buildings must have no more than 2 storeys. 8.

### Site Cover

- The maximum Area covered by all buildings and structures roofed with impervious materials, does not exceed site cover of 25% where Area means:
- a. for enclosed spaces, the area including the outside wall; and
  b. for unenclosed spaces, the area is measured along a line 600mm in from the perimeter of the roof.

### Eaves and Roof Pitch

- 10. Eaves, or other architectural features which add visual interest to wall/roof junctions (such as parapets), are required to all walls.
- 11. The maximum roof pitch is 40 degrees.

### **Parking and Driveways**

- 12. A minimum of two on-site car parking spaces must be provided for each dwelling.
- 13. A double garage must be used.
- 14. The maximum width of a driveway at the lot boundary shall be 4.8m.
- 15. A maximum of one driveway per dwelling is permitted.
- 16. The driveway finish must not be plain concrete
- 17. Driveways are to be designed and constructed in accordance with approval / permit requirements of Logan City Council

### **Retaining Walls**

- 18. Other than walls erected by the developer, retaining walls:
  - must be tiered 1m vertical and 1m horizontal where forward of the building line to any street, park or lane and visible from the public realm; and cannot exceed 1.5m in height without stepping elements incorporated.

### Fencing

- 19. The maximum fence height is 1.2m.
- 20. Fences are permitted to all frontages.
- 21. Fences must be at least 50% transparent.

### **Structures and Services**

- 22. All ancillary structures (e.g. garden sheds, gazebos, pools) and services are to be suitably located or screened to minimise detrimental visual impact from public spaces or neighbouring residential allotments, with the exception of solar panels and solar hot water systems which may be located where most efficient.
- 23. Screened drying areas are to be located behind
- the main face of the dwellings. 24. Rubbish bin areas are to be located behind the main face of the dwellings or stored so as to not be visible from the public realm.

### Secondary Dwelling

- 25. A secondary dwelling is only permitted where:
  - The lot is 400m<sup>2</sup> or more;
  - The lot frontage is 12.5m or more; and It complies with the applicable self assessable provisions in Schedule 3 of the Development Scheme where not
- inconsistent with the provisions of this PoD 26. There is to be no more than one secondary dwelling on a lot.


PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL



Approval no: DEV2016/768 4 March 2021 Date:

### TABLE 8: PLAN OF DEVELOPMENT TABLE - HOUSE (INTERFACE LOTS)

Setbacks		
Front Setback		6.0m
Side Boundary	Ground Floor	1.5m
Side Boundary	First Floor	2.0m
Rear Boundary		40m (Note that acoustic attenuation may be required where structures are built within 40-60m of the rear boundary)





- Buildings require Acoustic Design to the upper floor only (40-60m from the  $\sum$ Greenbank Road Boundary)
- Maximum Building Location Envelope (Ground Floor)
- -- Maximum Building Location Envelope (First Floor)



### 4.0 ADVERTISING DEVICES

Advertising Devices in accordance with the controls on this sheet are exempt in accordance with this Plan of Development.



### Notes

### **Currency period**

- Unless otherwise agreed to in writing, all advertising devices nominated on this plan are not permitted to remain longer than 20 years from either the date that approval is granted for the last lot or once the last residential lot is sold within the estate, whichever is the earliest
- 2. After these times, the Advertising Devices must be removed.

### Construction

Construction of Advertising Devices is limited З. to 6:30am – 6:30pm Monday to Saturday, and may not occur outside of these hours, on Sundays or on public holidays

### Visual amenity and safety of movement

- An advertising device is not to be animated or revolve or flash
  - The advertising devices are to be treated 5. to reduce glare and reflectivity

### Standards for signs

- A Banner Sign is permitted where complying with the following criteria:
- a. Does not exceed a maximum sign face area of 2.5m<sup>2</sup>
- b. Where a flag on a flagpole:Does not exceed a maximum height of 9m;
  - Is set a minimum of 2.4m from ground level;
- and
- Is limited to 1 flag per 10m of street front boundary.
- Building / Structure Façade Sign is permitted
- where complying with the following criteria:
- a. The sign is painted on, attached to or otherwise incorporated into a wall of a building / strucure does not project above the wall of the building / structure; b.
- The sign is painted on, attached to or otherwise incorporated into a window of a building is limited to a window on the ground floor of the building; The sign is painted on, attached to or otherwise
- C. incorporated into the fascia of a building:Does not prejudice above or below the fascia
- of the building; Has a maximum height of 30% of the height of
- the building / structure; and Has a maximum total face of 25% of the
- building façade.
- Directional Sign is permitted where complying with the following criteria

8.

9.

- a. Has a maximum height of 1.2m above ground level: and
- b. Has a maximum total face area of 1m<sup>2</sup>
- Free Standing Sign is permitted where complying with the following Criteria:
- Has a maximum height of 8m;
- Has a maximum height of 8m; Has a maximum width of 6m per advertising face; Being a pole, pylon or billboard sign or v sign, has a minimum clearance above ground level of 2.4m where pedestrian access is to occur under C.
- the Free Standing Sign;d. For billboard and v signs, avoids visual clutter by adhering to the following: - No more than 2 billboard or v signs are erected
- per 100m of road frontage to the site; A separation of at least 60m from another billboard or v sign on the same road frontage or 200m if either sign has an electronic component; and Does not include bunting.
- 10.
- Sales Office Sign is permitted where complying with the following criteria
- a. Is located on premises lawfully operating as a Sales Office;
- b. Limited to 1 per road frontage; and
  c. Has a maximum face area of 5m<sup>2</sup>
- A Third Party Sign is permitted to be erected on 11 land owned or under the control of Mirvac, and intended to advertise the emerging community.

### **Definitions:**

### Advertising Device

Any permanent structure, device, sign or the like intended for advertising purposes. It includes any framework, supporting structure or building feature that is provided exclusively or mainly as part of the advertisement.

#### Banner Sign A device that

- a. comprises only cloth, paper, flexible plastic, fabric or other non-rigid material; and
- b. is suspended from a structure or pole with or without supporting framework.

### Building / Structure Façade Sign

A sign which is painted on, attached to or otherwise incorporated into the wall, window, canopy or fascia of a building or structure.

- Note-Examples of a building façade sign: Awning fascia sign being an advertising device painted on, attached to or incorporated into the fascia of an awning, balcony or veranda.Canopy sign being an advertising device painted on
- or otherwise incorporated into a canopy of a building. Hamper sign being an advertising device painted of on, attached to or otherwise incorporated into the area between a door head and the
- underside of an awning, balcony or veranda.Building name sign being an advertising device
- painted on, attached to or otherwise incorporated into the wall of a building naming or identifying a building by the use of a logo or the like. Wall sign being an advertising device painted
- on, attached to or otherwise incorporated into a wall of a building or structure (fence).
- Window sign being an advertising device painted on, attached to or otherwise incorporated into a window of a building.

### Directional Sign

A sign providing information in respect of the operation of an activity on the premises

Note-Examples of a directional sign:

- entrance sign; parking sign;
- menu board

### Face Area


In relation to an advertising device, where the advertising device has:

- a. only one face, the greater of the area of: the advertisement panel or board as installed; or a rectangular figure best enclosing the
- advertising message, logo or figure; b. more than one face, the sum of the area of each of the faces where each is calculated separately in accordance with paragraph (a).


### Free Standing Sign

A sign permanently attached to the ground on its supportive structure independent of any building.

- Note—Examples of a freestanding sign A billboard sign being an advertising device the width of which is greater than the height and which may be positioned on the ground or mounted on one or many vertical supports;
- A v sign being an advertising device the width of which is greater than the height and which may be positioned on the ground or mounted on one or many vertical supports where the two advertising faces are arranged at an angle to each other addressing the road frontage; A ground sign being an advertising device which
- in effect sits on or rises out of the ground;A pole sign being an advertising device which may be positioned on the ground or mounted on one or more supports;
- A vertical banner free standing sign being an advertising device of non-rigid material normally fixed at the top and bottom to brackets extending from a freestanding pole.



### FIGURE 2: INDICATIVE LOCATIONS OF PRIMARY ADVERTISING DEVICES



# Everleigh Landscape Design Guidelines

### The following planting plans present typical garden layouts.

Plans require customisation to suit the unique site conditions.

Designs must meet requirements outlined in the Part 2: Architectural and Landscape Design Standards of the Everleigh Residential Design Standards & Guidelines.

Refer to the plant palette for recommended species list.


Be sure to seek advice from your engineer for any retaining walls or fencing requirements.

HOT TIP

### General Landscape Design Notes

Give consideration to the following:


- Protect and enhance favourable existing views and vistas through considerate placement of trees and shrubs
- Locate trees and shrubs to provide adequate privacy between
   neighbours and the public realm
- Provide a balance of sun penetration, shading and wind screening
- Consider the location of windows and the mature heights of shrubs when planting around the house perimeter to preserve views into the garden and prevent overshading of the interior
- Consider service locations and potential conflicts with trees
- · Provide safe and comfortable access to gates and doorways
- Ensure pathways and pavements are stable, even and non-slip in all weather conditions with adequate crossfalls to prevent ponding of water
- Do not plant spiky plants next to pathways
- Maintain adequate sightlines for drivers and pedestrians in the vicinity of driveways and ensure plants with a mature height of under 500mm are chosen for ciritical locations
- Manage site water to ensure stormwater runs off away from buildings and waterlogging is minimised
- Consider the site's aspect and predict the amount of sun and shade plants will likely receive when selecting species from the plant palette



Landscape Design Guidelines

Everleig





### Legend

- 1 Driveway - 6.0m max width
- 2 Gates H1.2m (Inward swing only or slide)
- 3 Side access 3.5m min. width
- 4 Shed
- 5 Pedestrian gate H1.2m
- 6 Overland Flow (Where applicable) 7 Front yard landscaping 8 Feature tree (Recommended) 9 Vegetative screen 10 Buffer planting (Desireable)
- 11 Lawn

- 12 Side fences + gate H1.2m (Optional)
- 13 Garden bed
- 14 Pedestrian path
- 15 Post and rail fence (RFA)
- 16 Post and wire fence (RFB) (or RFA if desired)

### LANDSCAPE PLAN: TYPICAL LOT - WITH

### **DRIVE THROUGH GARAGE**



### Legend

 Driveway - 6.0m max width
 Gates H1.2m - Inward swing only or slide (Optional)
 Side access 3.5m min. width
 Shed
 Pedestrian gate H1.2m

6	Overland Flow (Where applicable)	12
7	Front yard landscaping	13
8	Feature tree (Recommended)	14
9	Vegetative screen	15
10	Buffer planting (Desireable)	16
11	Lawn	de

- 2 Side fences + gate H1.2m (Optional)
- Garden bed
- 14 Pedestrian path
- 5 Post and rail fence (RFA)
- Post and wire fence (RFB) (or RFA if desired)

LANDSCAPE PLAN: TYPICAL LOT – WITHOUT DRIVE THROUGH

GARAGE (SIDE ACCESS)

### PROPOSED PLANTING GUIDELINE: TREES

(+) Tree or feature plant

	PLANT SP	PECIES	SIZE		LIGHT	REQUIREN	IENTS	WILDLI	FE ATTRA	CTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
	Scientific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY Size	Full Sun	Part Sun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
1	Atractocarpus fitzalanii	Native Gardenia	8m x 3m	45L	Х	х		Х	Х	Х	Х		Х	Х					Х	х
2	Buckinghamia celsissima	Ivory Curl	8m x 3m	45L	х	х		х	Х	Х		х			х			Х	х	
3	Callistemon 'White Anzac'	Bottlebrush	0.5-1.5m x 05-3m	45L	х	х		х	Х	Х				Х	х			Х		
4	Corymbia 'Summer Red'	Flowering Gum	3-5m x 3-4m	45L	х	х		Х	Х	Х		Х			х			Х		х
5	Cupaniopsis anacardioides	Tuckeroo	5-8m X 5-7m	45L	х	х		х				Х		Х		Х			Х	
6	Grevillea baileyana	Brown Silk Oak	5-10m x 3-4m	45L	Х	х		х		Х		Х			х			Х		
7	Grevillea 'Honey Gem'	Honey Gem	5m x 3m	45L	Х			х				Х		Х			х	Х		
8	Grevillea 'Robyn Gordon'	Grevillea	1-1.5m x 0.5-1.5m	45L	х	х		х	Х	Х		Х		х			х	Х		
9	Lophostemon confertus	Queensland Brush Box	10-25m x 5-15m	45L				х	Х	Х		Х		х	х			Х		х
10	Michelia figo	Port Wine Magnolia	2.5m x 1.5m	45L	х	х					х	Х	х	Х	х				х	х
11	Magnolia grandiflora 'Little Gem'	Magnolia 'Little Gem'	4-5m x 2-3m	45L	х	х		х		Х			х		х	х				Х
12	Melaleuca bracteata	Honey Myrtle	3-4m x 1.5-2m	45L	Х	х		Х	х	Х		Х			х			Х		х
13	Melaleuca leucadendra	Weeping Paperbark	10-14m x 8-10m	45L	Х			х				Х		Х	Х			Х		
14	Peltophorum pterocarpum	Yellow Poinciana	8-15m x 5-10m	45L	Х	х			Х	Х		Х		Х	Х					х
15	Tristaniopsis laurina	Water Gum	5-8m x 5-10m	45L	Х			х	Х	Х		Х		Х	Х					х
16	Waterhousea floribunda	Weeping Lilli Pilli	4-5m X 2-3m	45L	х	х		х			Х				Х					х



### PLANTING PALETTE: TREES



### PROPOSED PLANTING GUIDELINE: FEATURE PLANTS (INCLUDING VINES & CLIMBERS)

(+) Tree or feature plant

	PLANT SF	PECIES	SIZE		LIGHT	REQUIRE	MENTS	WILDLI	FE ATTRA	CTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
	Scientific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY SIZE	Full Sun	Part Sun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
	Alcantarea extensa	White Empress	1.5m x 1.5M	140mm	Х	Х						Х	х						Х	
	Doryanthes excelsa	Gymea lily	2-4m x 2-3m	140mm	Х			Х	Х	Х		х		Х	Х				Х	х
	Furcraea Foetida 'Variegata'	Mauritius Hemp	1.2-1.5m x 1-1.8m	140mm	Х	Х						х	х						Х	
	Pandorea jasminoides	Bower Vine	To 5m	140mm	Х	Х						Х	х					Х		х
5	Trachelospermum jasminoides	Star Jasmine	5m - 7m	140mm	Х	Х			Х	Х		Х		Х	Х			Х	Х	х
6	Yucca elephantipes	Soft Tipped Yucca	2m x 15m	140mm	Х	Х						х		Х	Х				Х	х
7	Zamia furfuracea	Cardboard Palm	1m x 1.5-2m	140mm	Х	Х						Х							Х	



### PLANTING PALETTE: FEATURE PLANTS (INCLUDING VINES & CLIMBERS)







46 **Everleigh –** Precinct 1.5 Acreage Lots

### **PROPOSED PLANTING GUIDELINE: LARGE SCREENING PLANTS & HEDGING SHRUBS**

High shrubs

	PLANT SPECIES		SIZE		LIGHT	REQUIRE	MENTS	WILDL	IFE ATTR/	ACTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
	Scientific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY SIZE	Full Sun	Part Sun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
	Banksia integrifolia	Coastal Banksia	4-15m x 1-6m	140mm	Х	Х		х						х		Х	Х	Х		
2	Callistemon 'Captain Cook'	Bottlebrush Captain Cook	2m x 1.5m	140mm														Х		
3	Callistemon viminalis	Weeping Bottlebrush	5-8m x 3-4m	140mm	х	х		Х						х	х			х		
4	Metrosideros thomasii	New Zealand Christmas Bush	4m x 2m	140mm	Х			х	х	Х	Х	Х		х	Х			Х		х
5	Syzygium 'Resilience'	Lilly Pilly Resilience	5m x 2m	140mm	Х	Х		х	х	Х	Х		Х	х				Х		х



### PLANTING PALETTE: LARGE SCREENING PLANTS & HEDGING SHRUBS





### **PROPOSED PLANTING GUIDELINE: MEDIUM SCREENING PLANTS & HEDGING SHRUBS**

L-M Low-medium shrubs

	PLANT S	PECIES	SIZE		LIGHT	REQUIRE	MENTS	WILDLI	FE ATTR/	ACTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
	Scientific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY SIZE	Full Sun	Part Sun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
1	Alpinia caerulea	Native Ginger	1.5m x 1m	140mm		х		х					х		х			х		
2	Babingtonia virgata	Heath Myrtle	2-4m x 2-3m	140mm	Х	Х		Х	Х	Х					Х					Х
3	Banksia robur	Swamp Banksia	2 x 2m	140mm	х			х	х	х			х			х		Х		
	Grevillea rosmarinifolia	Rosemary Grevillea	2m x 2m	140mm	Х	Х		Х				Х		Х			Х	Х		
5	Leptospermum 'Cardwell'	Cardwell	2m x 1.5m	140mm	х			х	х	х		х	Х	Х			Х	Х		Х
6	Melaleuca 'Claret Tops'	Claret Tops	1.5m x 1m	140mm	Х							Х						Х		х
7	Strelitzia reginae	Bird of Paradise	1-2m x 1.5m	140mm	x							х		Х	Х	х	Х		х	Х
8	Westringia 'Wynyabbie Gem'	Native Rosemary	1.5m x 1.5m	140mm	Х	Х			Х	Х	х	Х		Х				Х		х
9	Westringia 'Zena'	Native Rosemary	1m x 1m	140mm	Х	Х			Х	Х	х	х		Х				Х		х
10	Xerochrysum bracteatum	Everlasting Daisy	0.2-0.5m x 0.2-0.5m	140mm	Х	Х			Х	Х		Х		Х	Х	х		Х		Х



### PLANTING PALETTE: MEDIUM SCREENING PLANTS & HEDGING SHRUBS





50 **Everleigh –** Precinct 1.5 Acreage Lots

### PROPOSED PLANTING GUIDELINE: LOW SCREENING PLANTS & HEDGING SHRUBS

L-M Low-medium shrubs

	PLANT SI	PECIES	SIZE		LIGHT	REQUIRE	MENTS	WILDLI	FE ATTR/	ACTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
Scie	entific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY SIZE	Full Sun	PartSun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
	eckea virgata Petite'	La Petite	1m x 1m	140mm	Х	Х			Х	х	х		х		Х			Х		х
	listemon tle John'	Little John	1 x 1m	140mm	х			х				х			х	х		Х		х
	oporum pticum	Coastal Myoporum	0.5m x 2m	140mm	Х	Х						х		х	Х			Х		х
	lodendron nadu'	Xanadu	0.75m x 1m	140mm	Х	Х							Х						Х	
	stringia ticosa	Coastal Rosemary	2m x 4m	140mm	Х	Х		Х	Х	Х	х	Х		Х	Х			Х		х



### PLANTING PALETTE: LOW SCREENING PLANTS & HEDGING SHRUBS





### PROPOSED PLANTING GUIDELINE: GRASSES AND GROUNDCOVER

GC Ground cover / grasses

	PLANT SI	PECIES	SIZE		LIGHT	REQUIREI	MENTS	WILDLI	FE ATTR/	ACTING		ENANCE REQUIRE			FLOV	VERS			STYLE	
	Scientific Name	Common Name	Height x Spread at Maturity (m)	MIN. SUPPLY SIZE	Full Sun	Part Sun	Full Shade	Birds	Butterfly	Bees/Insects	Prune for Hedge	Drought Tolerant	Moist Soil – Well Mulched	Spring	Summer	Autumn	Winter	Native	Tropical	Traditional
1	Brachyscome multifida	Cut Leaf Daisy	0.5m x 0.8m	140mm	х	х			х	x		х		Х	Х			Х		х
2	Casuarina 'Cousin It'	Cousin It	0.15-0.3 x 1.5-3m	140mm	Х	Х						Х		Х	Х					
3	Chrysocephalum apiculatum	Everlasting Buttons	0.3 x 0.5-3m	140mm	Х	Х		Х	Х	х										
4	Cordyline fruticosa 'Pink Diamond'	Cordyline Pink Diamond	2-3m x 1m	140mm	Х	х						Х	х						х	
5	Dietes bicolor	Wild Iris	1 x 1m	140mm	Х							Х		Х	Х					Х
6	Dietes grandiflora	Wild Iris	1 x 1m	140mm	х							Х		Х	х					х
7	Gazania rigens	Gazania	0.3 – 0.5m	140mm	х							х		Х	х			х		х
8	Grevillea 'Poorinda Royal Mantle'	Grevillea	0.1-0.2m x 3-8m	140mm	Х	х		х	х	х								Х		
9	Liriope muscari 'Evergreen Giant'	Liriope Evergreen Giant	0.75 x 0.3m	140mm	х							Х			Х	х			х	х
10	Lomandra hystrix	Slender Mat Rush	1.5m x 1.5m	140mm	Х							Х		Х	Х			Х		
11	Myoporum parvifolium	Creeping Boobialla	0.1-0.5m x 1-3m	140mm	Х	Х						Х		Х	Х			Х		
12	Russelia equisetiformis	Coral Plant	1m x 4m	140mm	Х	Х		Х	Х			Х							Х	
13	Viola hederacea	Native Violet	0.15 x 0.2m	140mm		Х	Х					Х	Х	Х				Х	Х	х



### PLANTING PALETTE: GRASSES AND GROUNDCOVER





# Annexure E

Retaining Wall Fact Sheet & WRB Retaining Wall Warranty

# Everleigh

# Retaining Wall Fact Sheet and Owner Obligations

The Everleigh team have carefully considered and prepared your land during the civil works to ensure the best outcome for your future build. This fact sheet outlines some key ongoing owner obligations to ensure that your retaining walls are well maintained throughout the life of the property.

### When designing retaining walls, Mirvac prefer the use of either:

- Boulders, stone or masonry, usually for areas facing the street areas to maximise street appeal, or
- Concrete sleeper panel walls to minimise the impact the structure has on useable land and to reduce maintenance costs because of the robust nature of concrete.


As these retaining walls are contained within private property the land owner owns them and has a responsibility to monitor and maintain the retaining walls. At Everleigh, retaining walls between private lots are located on the common boundary, and hence adjoining landowners share a responsibility to maintain the wall. The following information is provided to assist all homeowners and their builders.

### The retaining walls have been designed in accordance with:

- All relevant Australian Standards
- Applicable Logan City Council approvals
- A 5kPa surcharge loading above the retaining wall
- Maximum 1 in 10 back slope above concrete sleeper retaining wall
- Existing site soil properties

In order to avoid adversely affecting the structural integrity of the retaining wall, each land owner has a responsibility to ensure the following (including making builders or tenants aware):

- That works adjacent to the retaining wall structure complies with the design parameters noted above
- That no open excavations, alterations or modifications are permitted within the zone of influence without Engineering assessment. Refer to sketch for definition of 'zone of influence'
- That no structures or trees are installed within the zone of influence (both above and below the retaining wall) without Engineering assessment
- Water is not permitted to pond within the zone of influence above or below the wall
- Any site works within any individual allotment must not disrupt the wall drainage including limiting discharge from the retaining wall



- No machinery is to be used above the retaining wall where it would result in a load more than the 5kPa limit noted above as this may cause deformation of the wall components
- The wall height is not to be raised by any method, including bolting on or constructing an additional retaining wall above, without obtaining an engineering assessment of the effects on the wall

Installation of a solid 1.8m boundary fence on or adjacent to the wall (depending on boundary location and/or agreement with neighbour) is acceptable provided the consideration given to the items raised above. As with all fences, design and construction of the fence is the owner's responsibility.


## **Zone of Influence**

The following information is provided as a general guide. If you are unsure you should consult with a suitably qualified engineer to confirm the actual extent of the zone of influence.

For example, if the wall height (H) is 1.6m then:


For the Lower Lot the Zone of Influence extends from the base of the wall for H x 1.25 or  $1.6m \times 1.25 = 2m$ 

For the Upper Lot the Zone of Influence extends from the base of the wall for H x 1.25 or  $1.6m \times 1.25 = 2m$ 



# Typical Retaining Wall Subsoil Outlet on Relevant Low Side Allotments

Installed in the rear corner of relevant allotments located on the low side of a retaining wall.







Visit the sales office open daily 10am – 5pm 56 Kessels Boulevard, Greenbank Call 07 3859 5960 or visit everleigh.mirvac.com



### **Product Warranty**

**TO: Warranty Holder** 

### **Retaining Wall Warranty**

WRB Group Holdings Pty Ltd (QBCC Licence No. 15065209) ABN 47 620 599 377 (WRB) warrants that if the structural integrity of the retaining wall supplied and installed by WRB for the Project, fails as a direct result of it not having been reasonably fit for its purpose at the time of its installation, WRB will for the term of 15 years commencing from the Installation Date, repair the retaining wall or compensate the Warranty Holder in accordance with the following terms and conditions:

### Subject Retaining Walls

This warranty is provided only for retaining walls constructed by WRB in accordance with records maintained by WRB. Details for retaining walls constructed by WRB on a specific lot can be obtained from WRB on request by a Warranty Holder. The retaining wall warranty does not extend to cover any liability, loss or damage, consequential or otherwise however suffered or incurred as a direct or indirect result of the supply or installation of the retaining wall by WRB. This product warranty is in addition to other rights and remedies under the consumer law (see additional benefit).

### <u>Claim</u>

You must make a claim under this product warranty within 3 months of becoming aware, or when you should reasonably have become aware, of the failure in the structural integrity of the retaining wall by providing WRB with written details of:

- (a) the failure sufficient to enable WRB to assess the claim;
- (b) the name of the estate, lot number and street address where the failure occurred; and
- (c) your name, street address, email address, daytime telephone number and interest in the land,

by email to admin@wrbconstruction.com.au or post to PO Box 4411, Gumdale QLD 4154.

### Assessment

WRB will assess your claim within a reasonable time, and give you written notice of WRB's assessment of your claim.

If in assessing your claim, WRB requires you to make the retaining wall available for inspection, you will make it available for inspection by WRB within a reasonable time.

07 3890 2811

wrbconstruction.com.au

84 INGLESTON ROAD WAKERLEY, QLD 4154

admin@wrbconstruction.com.au



If WRB assesses that failure in the structural integrity of the retaining wall has occurred as a direct result of it not having been reasonably fit for its intended purpose at the time of its installation, WRB will take one of the following actions (the election of which will be made by WRB in WRB's absolute discretion) within 28 days after giving you written notice of WRB's assessment of your claim:

(a) repair the retaining wall; or

(b) compensate you for the reasonable cost to repair the retaining wall.

### **Exclusions & Limitations**

WRB will not have any liability to you under this product warranty if:

(a) the retaining wall is altered, modified or damaged by any person, thing or weather event outside of the Design Scope after the Installation Date.

(b) the retaining wall is not reasonably maintained, and failure of the retaining wall is accelerated as a result. To avoid any doubt, the Warranty Holder's obligations include but are not limited to ensuring that:

- no open excavations, alterations or modifications are permitted within the zone of influence without Engineering assessment in writing.
- no structures or trees are installed within the zone of influence (both above and below the retaining wall) without Engineering assessment in writing
- water is not permitted to pond within the zone of influence above or below the wall
- any site works within any individual allotment must not disrupt the wall drainage including limiting discharge from the retaining wall
- no machinery is to be used above the retaining wall where it would result in a load more than the 5kPa as this may cause deformation of the wall components
- the wall height is not to be raised by any method, including bolting on or constructing an additional retaining wall above, without obtaining an Engineering assessment of the effects on the wall (noting that installation of a solid 1.8m boundary fence on or adjacent to the wall (depending on boundary location and/or agreement with neighbour) is acceptable provided consideration is given to the items raised above).

### (c) you are not the Warranty Holder;

(d) you fail to make a claim under this product warranty strictly within 3 months of becoming aware, or when you should reasonably have become aware, of the failure in the structural integrity of the retaining wall.

Transfer of warranty

6 07 3890 2811

wrbconstruction.com.au

admin@wrbconstruction.com.au



The benefit of this warranty may be transferred to a new land owner if the property is sold subject to:

- The Warranty Holder making a written request to WRB; and
- WRB agreeing in writing to transfer the benefit of the warranty (acting reasonably).

### Additional Benefit

The benefits provided to you under this product warranty are in addition to other rights and remedies, including any right or remedy under the Australian Consumer Law, you may have at law, in equity or under statute.

### **Definitions**

Developer means Mirvac Queensland Pty Limited

Warranty Holder means the lawful owner of the land where the owner:

- is the Developer;
- is the first transferee when the Developer transfers ownership of the land <u>(subject to</u> <u>the first transferee registering the warranty with WRB within 3 months of transfer of</u> <u>the land</u>; or
- has WRB's written confirmation that the warranty has been validly transferred to them.

**Installation Date** *means* the date on which the relevant Form 16 is signed. **Zone of Influence** *means* the area adjacent to the retaining wall within which any changes to ground conditions may have an impact on the performance of the retaining wall. **Design Scope** means the codes which are outlined in the Form 15 to identify how the retaining wall has been designed.

**Project** *means* the Everleigh subdivision development undertaken by the Developer at Teviot Road, Greenbank in the State of Queensland.



wrbconstruction.com.au

admin@wrbconstruction.com.au

# Everleigh

Residential Design Standards and Guidelines Precinct 1.5 Acreage Lots

### **REVISIONS SCHEDULE**

REVISION	DATE	CHANGES MADE
A	17.11.2020	First Copy
В	27.01.2021	Final