


# EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT TEVIOT ROAD, GREENBANK FOR MIRVAC QLD PTY LTD



LOCALITY PLAN  
Scale 1:5000



SHEET LIST TABLE	
SHEET NO.	SHEET TITLE
C001	COVER SHEET
C002	SURVEY SETOUT PLAN
C003	OVERALL SERVICES LAYOUT
C004	SAFETY IN DESIGN
C100	ROADWORKS AND DRAINAGE LAYOUT
C201	BULK EARTHWORKS LAYOUT
C210	BULK EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2
C211	BULK EARTHWORKS NOTES AND DETAILS - SHEET 2 OF 2
C300	ROADWORKS NOTES AND DETAILS
C310	AMBER CIRCUIT LONGITUDINAL SECTION
C311	AMBER CIRCUIT CROSS SECTIONS
C312	MOSS STREET LONGITUDINAL SECTIONS
C313	MOSS STREET CROSS SECTIONS - SHEET 1 OF 2
C314	MOSS STREET CROSS SECTIONS - SHEET 2 OF 2
C315	BAMBOO ROAD LONGITUDINAL SECTION
C316	BAMBOO ROAD CROSS SECTIONS
C317	DRIVEWAY 3 LONG & CROSS SECTIONS
C330	INTERSECTION DETAILS LAYOUT
C340	PAVEMENT MARKINGS AND SIGNAGE LAYOUT
C350	ACOUSTIC FENCE LAYOUT PLAN
C400	STORMWATER CATCHMENT LAYOUT
C410	STORMWATER DRAINAGE LONG SECTIONS - SHEET 1 OF 2
C411	STORMWATER DRAINAGE LONG SECTIONS - SHEET 2 OF 2
C420	STORMWATER DRAINAGE NOTES AND DETAILS
C430	STORMWATER DRAINAGE NOTES AND DETAILS
C440	STORMWATER CALCULATIONS 39% AEP STORM
C441	STORMWATER CALCULATIONS 1% AEP STORM
C500	SEWERAGE LOCALITY PLAN & NOTES
C510	SEWERAGE LAYOUT PLAN
C520	SEWERAGE LONG SECTIONS - SHEET 1 OF 3
C521	SEWERAGE LONG SECTIONS - SHEET 2 OF 3
C522	SEWERAGE LONG SECTIONS - SHEET 3 OF 3
C530	SEWERAGE NOTES AND DETAILS
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C610	WATER RETICULATION LAYOUT PLAN
C611	WATER RETICULATION LIVE CONNECTION DETAILS
C700	EROSION AND SEDIMENT CONTROL LAYOUT - BULK EARTHWORKS PHASE
C701	EROSION AND SEDIMENT CONTROL - STABILISATION PHASE
C710	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1 OF 2
C711	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2 OF 2
C900	TEMPORARY WORKS - ROADWORKS AND DRAINAGE

### GENERAL NOTES

- ALL DIMENSIONS GIVEN ON THESE DRAWINGS ARE IN METRES UNLESS NOTED OTHERWISE.
- ALL NEW WORK AND MATERIALS SHALL COMPLY CURRENT RELEVANT COUNCIL STANDARDS AND SPECIFICATIONS.
- ALL WORK SHALL BE JOINED NEATLY TO EXISTING CONSTRUCTION.
- THE CONTRACTOR IS TO LOCATE, IDENTIFY AND ESTABLISH THE CONNECTIVITY OF ALL EXISTING SERVICES WITHIN THE LIMITS OF PROPOSED WORKS AND CONFIRM THIS INFORMATION WITH THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MEASURING DEVICES, SAFETY EQUIPMENT AND MACHINERY REQUIRED TO CARRY OUT INSPECTIONS/MEETINGS AS SPECIFIED OR REQUESTED BY THE ENGINEER.
- CONSTRUCTION CERTIFICATION REQUIREMENTS SUCH AS PAVEMENT PROOF ROLLS ETC. ARE TO BE AS PER THE LOGAN CITY COUNCIL SPECIFICATION.
- THESE NOTES SHALL APPLY TO ALL PORTIONS OF WORK.
- THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATIONS. ANY POINT OF CONFLICT WILL BE RESOLVED BY THE SUPERINTENDENT.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A CONSTRUCTION MANAGEMENT PLAN FOR THE SITE TO BE ACCEPTED BY EDQ. THIS PLAN IS TO INCLUDE ALL ITEMS AS LISTED IN THE DECISION NOTICE AS A MINIMUM.

### NOISE

- ALL PLANT AND EQUIPMENT SHALL BE CONTROLLED TO MINIMISE NOISE EMISSION IN ACCORDANCE WITH AS2436 (GUIDE TO NOISE CONTROL ON CONSTRUCTION, MAINTENANCE AND DEMOLITION). THE SITE WORKING HOURS SHOULD BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS. WHERE NOT SPECIFIED THE HOURS SHALL BE:

MONDAY - SATURDAY 7:00am to 6:00pm  
SUNDAY OR PUBLIC HOLIDAY NO WORK PERMITTED

### PRE-CONSTRUCTION & APPROVALS

- NO LOCATING/ POTHOLING OF EXISTING SERVICES HAS BEEN CARRIED OUT. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND DEPTH OF ALL EXISTING SERVICES WHICH AFFECT THE WORKS AND REPORT ANY POTENTIAL CLASHES TO THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORKS.
- THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING WITH THE APPROPRIATE AUTHORITY FOR LOCATING EXISTING SERVICES AND FOR ANY MODIFICATIONS TO EXISTING SERVICES REQUIRED AS A RESULT OF THE WORKS.
- THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL EXISTING SERVICES FROM DAMAGE.
- ANY WORKS DAMAGED AS A RESULT OF CONSTRUCTION ARE TO BE REINSTATED TO RELEVANT AUTHORITY'S REQUIREMENTS AT THE CONTRACTORS COST.
- FINISHED SURFACE LEVELS ARE TO BE GRADED UNIFORMLY BETWEEN LEVELS INDICATED ON THE DRAWINGS.

### WORKPLACE HEALTH & SAFETY

- THE CONTRACTOR SHALL BE THE PRINCIPAL CONTRACTOR AS DESIGNATED BY THE WORK HEALTH AND SAFETY ACT (2011).
- THE CONTRACTOR SHALL PREPARE AND IMPLEMENT A WORKPLACE HEALTH AND SAFETY PLAN AS REQUIRED BY THE WORK HEALTH AND SAFETY ACT (2011).

### SETOUT NOTES

- CO-ORDINATE SETOUT PROVIDED ON THESE DRAWINGS IS BASED ON A CO-ORDINATE BASE PROVIDED ON THE DETAIL SURVEY DRAWING 7598 S 02 DTH, PREPARED BY SAUNDERS HAVILL GROUP. REFERENCE MARKS AND CORRESPONDING CO-ORDINATES ARE PROVIDED ON DRAWING C002.
- THE LEVEL DATUM FOR WORKS IS A.H.D (AUSTRALIAN HEIGHT DATUM).

FOR CONSTRUCTION



**BRISBANE OFFICE**  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au


DESIGNED  
K KIWANG  
CHECKED  
A LANGDON  
PROJECT MANAGER  
S STEINHOFER  
PROJECT DIRECTOR  
*Patrick Brady*  
PATRICK BRADY RPEQ 7112

SCALE  
0 100 200 300m  
SCALE 1:5000 (A1)  
ORIGINAL SHEET SIZE A1

CLIENT  
MIRVAC QLD PTY LTD  
PROJECT  
EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
LOCATION  
TEVIOT ROAD, GREENBANK  
SHEET TITLE  
COVER SHEET

JOB CODE  
MIR009-01  
SHEET NUMBER  
C001  
REV  
B

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**LEGEND**

- PROPOSED ROAD CENTRELINE
- STAGE BOUNDARY

**INDEMNITY - EXISTING SERVICES**

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

**LEVEL DATUM: AHD (DERIVED)**

ORIGIN - PM61308  
 RL OF ORIGIN - 54.660m A.H.D

**ORIGIN OF COORDINATES: STATION C1 (PM 73506)**

PROJECT COORDINATES - STN C1, 8792.646 E, 32093.723 N

FOR FURTHER DETAILS REFER TO DETAIL SURVEY DRAWING 7598 S 02 DT H PREPARED BY SAUNDERS HAVILL GROUP.

**SITE AREA**

36,378m<sup>2</sup>

**REAL PROPERTY DESCRIPTION**

LOT 2 on SP297192

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
05/09/2021	A	ORIGINAL ISSUE	KK	PB
			REC	APP




**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
 CHECKED  
**A LANGDON**  
 PROJECT MANAGER  
**S STEINHOFER**  
 PROJECT DIRECTOR  
  
**PATRICK BRADY** RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**SURVEY SETOUT PLAN**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C002**  
 REV  
**B**



**LEGEND - PROPOSED**


- D—D—D— STORMWATER
- S—S—S— GRAVITY SEWER
- RM—RM—RM— SEWER RISING MAIN
- TS—TS—TS— TRUNK SEWER
- W—W—W— WATER
- E—E—E— ELECTRICITY

**LEGEND - EXISTING**

- - - D - - - D - - - STORMWATER
- - - S - - - S - - - GRAVITY SEWER
- - - RM - - - RM - - - SEWER RISING MAIN
- - - TS - - - TS - - - TRUNK SEWER
- - - W - - - W - - - WATER
- - - E - - - E - - - ELECTRICITY

**LEGEND - PROPERTY SERVICE CONNECTIONS**

- W **WATER** - POLY SERVICE FROM WATER MAIN, METER BOX & COVER INSTALLED. BUILDER TO MAKE APPLICATION TO LOGAN CITY COUNCIL FOR METER ASSEMBLY SUPPLY AND INSTALLATION. WHERE WATER METER IS LOCATED BEHIND RETAINING WALL, 25mm POLYPIPE WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "WATER".
- **SEWER** - CAPPED Ø100 PVC PIPE (BURIED MAX 1.5m). MARKED WITH 40Ø ORANGE PVC CONDUIT SECURELY TAPED TO H.W. STAKE AT SURFACE (BURIED TO CAPPED PIPE). CONDUIT LABELLED "SEWER."
- RW **ROOFWATER** - CONNECTION LOCATION CAN BE EITHER FRONT OF LOT VIA KERB ADAPTOR OUTLET TO ROAD, OR REAR OF LOT INTO ROOFWATER DRAINAGE PIPE VIA PIT. CAPPED PVC Ø100 PIPES (BURIED MAX 1.5m) MARKED WITH 900x50x25 HW STAKE LABELLED "ROOFWATER."
- SSD **RETAINING WALL SUB-SOIL DRAINAGE** - OUTLET POINT TO LOT FOR RETAINING WALL SUB-SOIL DRAINAGE TO BE CONNECTED TO YARD DRAINAGE BY BUILDER. Ø100 NON-SLOTTED AGG PIPE CAPPED AND TERMINATED 200m ABOVE SURFACE. PVC DUCT TAPED TO 900x50x25 HW STAKE LABELLED "RETAINING WALL SUBSOIL OUTLET".
- T **TELECOMMUNICATIONS/NBN** - PVC CONDUIT (BURIED APPROX 300mm). MARKED WITH 900x50x25 HW STAKE LABELLED "TELECOMMS".
- **ELECTRICITY** - ELECTRICITY PILLAR EXISTS IN ROAD VERGE. BUILDER TO MAKE APPLICATION WITH ENERGY PROVIDER FOR SERVICE INSTALLATION TO LOT. WHERE ELECTRICITY PILLAR IS LOCATED BEHIND RETAINING WALL, CONDUIT WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "ELECTRICITY".
- G **GAS** - GAS MAIN EXISTS IN ROAD VERGE. BUILDER/HOME OWNER TO MAKE APPLICATION TO GAS PROVIDER FOR SERVICE INSTALLATION TO LOT.
- - - **RETAINING WALL**
- ⊗ ⊠ **SERVICE TERMINATION POINT MARKER.** 900x50x25 HW STAKE, OR 40Ø ORANGE PVC CONDUIT STAKE



TYPICAL PROPERTY SERVICES CONNECTIONS DETAIL  
NTS


**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**BRISBANE OFFICE**  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
*[Signature]*  
**PATRICK BRADY** RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**OVERALL SERVICES LAYOUT**

JOB CODE <b>MIR009-01</b>	
SHEET NUMBER <b>C003</b>	REV <b>B</b>



**DESIGN HAZARD NOTES:**

- PREMISE, HAVING BEEN COMMISSIONED TO CARRY OUT DETAILED DESIGN AND DOCUMENTATION OF THESE WORKS, CONFIRM THAT THE PREMISE DRAWING SET HAS BEEN INTERNALLY REVIEWED FOR DESIGN SAFETY IN ACCORDANCE WITH SECTION 22 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD.
- THIS REPORT SUMMARISES AN INTERNAL REVIEW OF PREMISE'S DETAILED DESIGN DRAWINGS FOR DESIGN SAFETY.
- THIS REPORT IN NO WAY RELIEVES THE PRINCIPAL, CONTRACTOR OR ANY OTHER PARTY OF THEIR OWN OBLIGATIONS AND RESPONSIBILITIES UNDER THE WORK HEALTH AND SAFETY ACT 2011 QLD, INCLUDING (BUT NOT LIMITED TO) CONSULTATION WITH THE DESIGNER UNDER SECTION 294 OF THE ACT, THE PREPARATION OF SATISFACTORY SAFE WORK METHOD STATEMENTS AND DUTIES OF CARE.
- IT IS A REQUIREMENT UNDER SECTION 296 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD, THAT A COPY OF THIS REPORT BE PROVIDED TO THE CONTRACTOR BY THE ENTITY COMMISSIONING THE WORK SHOWN OF THE PREMISE DRAWINGS.
- AS PER THE DEPARTMENT OF JUSTICE AND THE ATTORNEY-GENERAL- WORKPLACE HEALTH AND SAFETY QUEENSLAND, A WRITTEN REPORT IS NOT REQUIRED FOR DESIGNS THAT HAVE TYPICAL FEATURES.

CONSEQUENCE TABLE		
LEVEL	CONSEQUENCE	COST/TIME
5 - CATASTROPHIC	FATALITY OR MULTIPLE PERSONS ONSITE WITH LIFE THREATENING HEALTH EFFECT OR INABILITY TO CONTINUE	HUGE FINANCIAL OR TIME LOSS
4 - MAJOR	EXTENSIVE INJURIES, OR ONSET OF SEVERE OR LIFE THREATENING HEALTH EFFECT TO SINGLE PERSON ONSITE. MULTIPLE PERSONS WITH ONSET OF IRREVERSIBLE HEALTH EFFECTS. PERMANENT INJURY TO PERSON ONSITE.	MAJOR FINANCIAL OR TIME LOSS
3 - MODERATE	MEDICAL TREATMENT REQUIRED. IRREVERSIBLE HEALTH EFFECT TO A SINGLE PERSON. MULTIPLE PERSONS ONSITE WITH REVERSIBLE HEALTH EFFECTS.	HIGH FINANCIAL OR TIME LOSS
2 - MINOR	FIRST AID, SINGLE OR MULTIPLE INJURIES AMONGST PERSONS ONSITE. SINGLE PERSON ONSITE WITH MODERATE SHORT TERM REVERSIBLE HEALTH EFFECTS.	MEDIUM FINANCIAL OR TIME LOSS
1 - INSIGNIFICANT	NO INJURIES. OVER EXPOSURE TO A SINGLE PERSON ONSITE, BUT NO REPORTED HEALTH EFFECTS.	LOW FINANCIAL OR TIME LOSS

**CONSTRUCTION HAZARD NOTES:**

- UNDER THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011, THE WORK HEALTH AND SAFETY REGULATION 2011 AND OTHER LEGISLATION AND GUIDELINES, THE PRINCIPAL CONTRACTOR HAS SPECIFIC OBLIGATIONS IN RELATION TO THE SAFE OPERATION OF THE SITE AND OF THE WORKS. TO ASSIST THE PRINCIPAL CONTRACTOR IN COMPLYING WITH THESE OBLIGATIONS THE PROJECT DESIGNERS HAVE IDENTIFIED BY DRAWING NOTES, AREAS WHERE POTENTIAL HAZARDS MAY ARISE. THESE NOTES OR ADVICE, SHALL NOT NECESSARILY BE CONSIDERED COMPLETE AND ARE BASED UPON THE DESIGNERS' UNDERSTANDING OF THE SAFETY RISKS ASSOCIATED WITH THE WORKS. THESE NOTES OR ADVICE SHALL NOT RELIEVE THE PRINCIPAL CONTRACTOR OF ANY OBLIGATION UNDER THE RELEVANT LEGISLATION OR GUIDELINE. THE PRINCIPAL CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE PREPARATION OF AN APPROPRIATE WORK HEALTH SAFETY MANAGEMENT PLAN AND SAFE WORK METHOD STATEMENTS FOR THE SITE.
- PURSUANT TO THE WORK HEALTH AND SAFETY ACT 2011 WE HEREBY ADVISE THAT OUR DESIGN SAFETY REVIEW HAS IDENTIFIED UNUSUAL OR ATYPICAL DESIGN FEATURES THAT MAY PRESENT ADDITIONAL HAZARDS OR RISKS DURING THE CONSTRUCTION PHASE AND THESE ARE LISTED IN THE CONSTRUCTION HAZARD SCHEDULE.

RISK ANALYSIS MATRIX						
		1 - INSIGNIFICANT	2 - MINOR	3 - MODERATE	4 - MAJOR	5 - CATASTROPHIC
LIKELIHOOD	A - ALMOST CERTAIN	MODERATE	HIGH	EXTREME	EXTREME	EXTREME
	B - LIKELY	MODERATE	HIGH	HIGH	EXTREME	EXTREME
	C - POSSIBLE	LOW	MODERATE	HIGH	EXTREME	EXTREME
	D - UNLIKELY	LOW	LOW	MODERATE	HIGH	EXTREME
	E - RARE	LOW	LOW	MODERATE	HIGH	HIGH

RISK EVALUATION TABLE	
RISK LEVEL	ACTION REQUIRED
EXTREME	UNACCEPTABLE RISK. RE-DESIGN REQUIRED. DO NOT PROCEED WITHOUT ADDITIONAL CONTROLS.
HIGH	UNACCEPTABLE RISK. ADDITIONAL CONTROLS NEEDED. CONSIDER FURTHER REVIEW AND CONSIDER RE-DESIGN
MODERATE	RISK MAY BE ACCEPTABLE. MANAGEMENT TO DETERMINE ACTIONS REQUIRED
LOW	ACCEPTABLE. MANAGE RISK THROUGH ROUTINE PROCEDURES AND OTHER ADMINISTRATIVE CONTROLS

LIKELIHOOD TABLE		
LEVEL	DESCRIPTION	QUANTIFICATION GUIDE
A - ALMOST CERTAIN	THE EVENT <u>IS</u> EXPECTED TO OCCUR IN MOST CERTAIN CIRCUMSTANCES	MORE THAN ONCE PER YEAR
B - LIKELY	THE EVENT <u>WILL</u> PROBABLY OCCUR IN MOST CIRCUMSTANCES	AT LEAST ONCE IN 5 YEARS
C - POSSIBLE	THE EVEN T <u>SHOULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 10 YEARS
D - UNLIKELY	THE EVENT <u>COULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 30 YEARS
E - RARE	THE EVENT <u>MAY</u> OCCUR IN EXCEPTIONAL CIRCUMSTANCES	LESS THAN ONCE IN 30 YEARS


DESIGN HAZARD SCHEDULE					
ITEM	DESIGN HAZARD	POTENTIAL HAZARD	RISK	ELIMINATION / MINIMISATION OF HAZARD / RISK	RESIDUAL RISK
D1	URBAN LAYOUT HAZARD	THE URBAN LAYOUT IS DESIGNED AROUND A PARTICULAR HAZARD :- - INTERSECTION IS UNCLEAR WHICH ROAD HAS PRIORITY	HIGH	THE HAZARD HAS BEEN REDUCED/ELIMINATED BY:- - LINE MARKED INTERSECTION TO ENSURE IT IS CLEAR WHICH ROAD HAS PRIORITY - DESIGN VEHICLE SWEEP PATH CHECKED FOR COMPLIANCE	LOW
D2	EXISTING UNDERGROUND / OVERHEAD SERVICES HAZARD	EXISTING UNDERGROUND AND/OR OVERHEAD SERVICES HAZARD EXIST ON SITE AND NEEDS TO BE REMOVED AND RELOCATED.	HIGH	THE DESIGN OF THE PROJECT HAS INCORPORATED THE RELOCATION OF THESE EXISTING SERVICES AND THE CONTRACTOR IS TO BE MADE AWARE OF THESE EXISTING SERVICES AND TAKE ALL ACTIONS NECESSARY TO MITIGATE THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D3	DEEP EXCAVATION HAZARD	DEEP EXCAVATION IS REQUIRED TO INSTALL SEWER TO SERVICE STRUCTURE.	HIGH	THE DEEP EXCAVATION HAZARD CANNOT BE AVOIDED AND THE CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D4	HIGH RETAINING WALLS	SOME AREAS OF WORKS CONTAIN HIGH RETAINING WALLS WHERE LAND MORPHOLOGY DICTATES.	HIGH	HIGH RETAINING WALLS CANNOT BE AVOIDED DUE TO EXISTING LAND MORPHOLOGY. SINGLE TIER WALLS HAVE LIMITED TO A MAX HEIGHT OF 2m. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEIDUM
D5	WATER BODIES	PROPOSED CONSTRUCTION WATER DAMS WILL BE PRESENT ON SITE.	MEDIUM	PROPOSED WATER BODIES HAVE BEEN LOCATED AWAY FROM PUBLIC ACCESS AREAS. ACCESS TO THESE LOCATION WILL BE RESTRICTED FROM THE PUBLIC. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	LOW

CONSTRUCTION HAZARD SCHEDULE		
ITEM	POTENTIAL HAZARD	POSSIBLE PREVENTATIVE ACTION
C1	DEEP EXCAVATION HAZARD	ALL STEPS MUST BE TAKEN TO OBTAIN CURRENT UNDERGROUND SERVICES INFORMATION BEFORE EXCAVATION WORKS COMMENCE. EXCAVATION WORK MUST BE UNDERTAKEN BY APPROPRIATELY EXPERIENCED AND QUALIFIED PERSONNEL. EXCAVATIONS SHALL BE ADEQUATELY SHORED AND APPROPRIATE BARRICADES AND SIGNAGE ERECTED, IF REQUIRED.
C2	OVERHEAD POWER HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF LIVE OVERHEAD CABLES. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING EARTHWORKS AND ANY OTHER HIGH RISK WORKS, IF REQUIRED.
C3	UNDERGROUND ELECTRICAL, TELECOMMUNICATION, GAS AND WATER MAIN HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF THE EXISTING SERVICE. THE SERVICE SHALL BE IDENTIFIED AND MARKED BY THE SUPPLY AUTHORITY PRIOR TO THE COMMENCEMENT OF EXCAVATION. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING THE EXCAVATION WORK, IF REQUIRED.
C4	WORKS NEAR RAIL, AIRPORTS AND ROADS HAZARD	ALL REQUIRED PERMITS, APPROVALS AND SAFETY REQUIREMENTS FROM THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHALL REMAIN ON SITE DURING CONSTRUCTION WHILE THE HAZARD REMAINS.
C5	PEDESTRIAN ACCESS HAZARD	WORK WITHIN OR ADJACENT TO AREAS WHICH THE PUBLIC REQUIRES PEDESTRIAN ACCESS MUST HAVE APPROPRIATE BARRICADES AND SIGNAGE ERECTED AT ALL TIMES.
C6	POTENTIAL VEHICLE HAZARD	SITE PERSONNEL SHALL BE ADVISED OF THE POTENTIAL HAZARDS AND THE APPROPRIATE PROCEDURES FOR WORKING ADJACENT TO OPERATING PUBLIC ROADS. APPROPRIATE SAFETY CLOTHING SHALL BE WORN AND THE REQUIRED SIGNAGE SHALL BE ERECTED. THE WORKS SHALL BE UNDERTAKEN IN A MANNER WHICH DOES NOT COMPROMISE THE SAFETY OF THE VEHICLE OCCUPANTS OR THE SITE PERSONNEL.
C7	DEMOLITION AND CLEARING HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE DEMOLITION AND CLEARING WORKS FOR THE PROJECT AT ALL TIMES. THE CONTRACTORS WORK METHOD STATEMENT SHALL ALSO GIVE CONSIDERATION TO FALLING DEBRIS, COLLAPSE AND DANGEROUS AIRBORNE AGENTS.
C8	TRAFFIC MANAGEMENT HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC THROUGH THE PROJECT AT ALL TIMES. THE CONTRACTOR SHALL DEVELOP A TRAFFIC MANAGEMENT PLAN (TMP) FOR THE PROJECT TO ESTABLISH APPROPRIATE CONTROLS IN ACCORDANCE WITH THE MANUAL FOR UNIFORM TRAFFIC CONTROL.
C9	ASBESTOS HAZARD	ALL PERSONNEL SHOULD BE ADVISED OF THE POTENTIAL PRESENCE OF ASBESTOS AND AN IDENTIFICATION AND ACTION PLAN SHALL BE PUT IN PLACE. SAMPLING AND IDENTIFICATION IS TO BE UNDERTAKEN IN ACCORDANCE WITH WORKPLACE HEALTH AND SAFETY REGULATIONS. IF SAMPLING CONFIRMS THE PRESENCE OF ASBESTOS THEN THE ACTION PLAN IS TO BE IMPLEMENTED TO REMEDIATE THE SITE.
C10	POTENTIAL ROCK FALL	LAND ABOVE THE SITE HAS BEEN CLEARED AND SOME EARTHWORKS HAS BEEN UNDERTAKEN CREATING A POTENTIAL ROCK FALL HAZARD. SUITABLE PERSONNEL SHALL BE RESPONSIBLE FOR IDENTIFYING ANY POTENTIAL HAZARD AND THE CONTRACTOR SHALL TAKE APPROPRIATE ACTION TO ELIMINATE THE HAZARD.

FOR CONSTRUCTION					
DATE	REV	DESCRIPTION	KK	PB	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB	
05/09/2021	A	ORIGINAL ISSUE	KK	PB	

**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au



DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112
























SCALE  
 ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC GROUP**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**SAFETY IN DESIGN**










JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C004**  
 REV  
**B**



LEGEND - PROPOSED

-  PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
-  PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
-  PROPOSED IPWEA TYPE 'B2' KERB. REFER IPWEA STD DWG RS-080.
-  PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
-  PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
-  PROPOSED 1.5m WIDE (U.N.O.) CONCRETE FOOTPATH. REFER LCC STD DWGS.
-  PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
-  DURATHEM THRESHOLD TREATMENT. REFER TO LANDSCAPE PLANS FOR COLOUR AND PATTERN.
-  PROPOSED STORMWATER
-  PROPOSED STORMWATER STRUCTURE No.
-  ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C420.
-  ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C420.
-  ROOFWATER DRAINAGE KERB ADAPTORS & PROPERTY PIT. REFER DETAIL ON DWG C420.
-  PROPOSED ROOFWATER HOUSE CONNECTION (150 Ø uPVC)
-  PROPOSED RETAINING WALL
-  ZERO LOT BOUNDARY
-  PROPOSED FUTURE DRIVEWAY LOCATION
-  PROPOSED SEWER
-  PROPOSED WATER
-  PROPOSED WATER CONDUIT
-  PAD MOUNTED TRANSFORMER
-  PROPOSED LANDSCAPING WITHIN VERGE. CONCRETE EDGE RESTRAINT BY LANDSCAPING CONTRACTOR. CIVIL CONTRACTOR TO COORDINATE WITH LANDSCAPING CONTRACTOR TO CARRY OUT THEIR WORKS. REFER TO LANDSCAPE DRAWINGS FOR FURTHER DETAIL.
-  PROPOSED TREE LOCATION

LEGEND - EXISTING

-  EXISTING STORMWATER
-  EXISTING SEWER
-  EXISTING WATER
-  EXISTING ELECTRICAL
-  EXISTING TELSTRA
-  EXISTING GAS
-  EXISTING RISING MAIN
-  EXISTING RETAINING WALL
-  EXISTING STORMWATER STRUCTURE No.

PAVEMENT SUBGRADE GUARANTEE:

CONTRACTOR SHALL UNDERTAKE EARTHWORKS REQUIRED IN EITHER CUT OR FILL TO ENSURE THE SUBGRADE QUALITY IS AT CBR10 OR GREATER. CONTRACTOR TO LIAISE WITH OWN GEOTECHNICAL ENGINEER TO ACHIEVE REQUIREMENT.


STORMWATER TRENCH BACKFILL NOTE:

ALL STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

FOR TYPICAL SECTIONS AND NOTES REFER TO

DRAWING No. C300 - ROADWORKS TYPICAL SECTIONS AND NOTES, AND DRAWING No. C400 - STORMWATER DRAINAGE DETAILS AND NOTES.

CONTRACTOR TO ENSURE TEVIOT ROAD VERGE ADJACENT TO DEVELOPMENT LOTS GRADE TOWARDS THE ROAD. SUPERINTENDENT TO CONFIRM AND CONTACT DESIGNER IF GRADING VERGE TO ROAD IS UNFEASIBLE.





FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION		KK	PB
05/09/2021	A	ORIGINAL ISSUE		KK	PB



**BRISBANE OFFICE**  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWIANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**ROADWORKS AND DRAINAGE LAYOUT**

JOB CODE  
**MIR009-01**

SHEET NUMBER	REV
<b>C100</b>	<b>B</b>





**NOTES**

- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- EARTHWORKS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL LAYOUT PLANS AND EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
- ALL EARTHWORKS TO BE CARRIED OUT UNDER 'LEVEL ONE' GEOTECHNICAL CONTROL IN ACCORDANCE WITH LOCAL AUTHORITIES AND AS3798.
- EXCESS CUT TO BE STOCKPILED IN THE LOCATION SHOWN OR AS DIRECTED ON SITE.
- ALL BATTERS ARE 1 IN 4 UNLESS SHOWN OTHERWISE.
- CONTRACTOR TO INSTALL TEMPORARY CONSTRUCTION FENCING ALONG THE FULL PERIMETER BOUNDARY INCLUDING APPROPRIATE SIGNAGE.

**TESTING**

- THE SUPERINTENDENT MAY ORDER ADDITIONAL TESTS. REFER TO THE LOCAL AUTHORITIES SPECIFICATION FOR STANDARDS OF COMPACTION AND MATERIAL STANDARDS. FAILED TESTS WILL BE AT THE CONTRACTOR'S EXPENSE.

**EARTHWORKS TESTING**

- COMPACTION TESTS

LOCATION	AREA PER TEST
FINISHED LEVEL OR ROAD SUBGRADE (IN CUT OR FILL)	REFER TO THE LOCAL AUTHORITY SPECIFICATION
LOWEST TWO LEVELS OF EMBANKMENT (PER LAYER)	
OTHER LAYERS OF EMBANKMENT	
PREPARED NATURAL GROUND UNDER EMBANKMENT	

- QUALITY TESTS  
QUALITY TESTS OF IMPORTED MATERIAL ARE REQUIRED AS SET OUT BY LOCAL AUTHORITY.
- SUBGRADE TESTS  
THE NUMBER AND LOCATION OF PAVEMENT SUBGRADE TESTS SHALL BE IN ACCORDANCE WITH LOGAN CITY COUNCIL SPECIFICATION REQUIREMENTS.

**DUST**

- NO VISIBLE DUST EMISSIONS MUST OCCUR AT THE BOUNDARIES OF THE SITE DURING EARTHWORKS AND CONSTRUCTION ACTIVITIES ON THE SITE. DUST CONTROL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH AS/NZS3580.10.1:2003. DUST CONTROL SHALL COMPLY WITH THE NSW DEPARTMENT OF ENVIRONMENT AND CONSERVATION REPORT 'APPROVED METHODS & GUIDANCE FOR THE MODELLING AND ASSESSMENT OF AIR POLLUTANTS IN NSW.'
- THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN CONTROLS TO ACHIEVE THE REQUIREMENTS OF ITEM 1 ABOVE.

**FILL MANAGEMENT**

- ALL FILL MATERIAL WILL BE PLACED IN ACCORDANCE WITH THE FILL SPECIFICATION PROVIDED ON THIS SHEET, OR WHERE PROVIDED, THE REQUIREMENTS OF THE GEOTECHNICAL REPORT SPECIFIC TO THIS CONTRACT.
- THE FILL MATERIAL WILL COMPRISE ONLY OF NATURAL EARTH AND ROCK AND SHALL BE FREE OF ALL CONTAMINATES, NOXIOUS, HAZARDOUS, DELETERIOUS AND ORGANIC MATERIAL.
- ALL SITE PREPARATION WORK SHOULD GENERALLY BE CARRIED OUT IN ACCORDANCE WITH AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS'.
- THE SITE SHOULD BE STRIPPED OF ANY TOPSOIL FROM CUT AND FILL AREAS, ROAD ALIGNMENTS AND CARPARKING AREAS, AND STOCKPILED FOR LATER USE.
- PRIOR TO THE PLACEMENT OF ANY STRUCTURAL FILL THE SITE SHOULD BE PROOF ROLLED USING A MINIMUM 10 TONNE (STATIC WEIGHT) PADFOOT ROLLER. ANY LOOSE OR SOFT AREAS SHOULD BE REMOVED AND RECOMPACTED OR REPLACED USING A COMPACTED SELECT FILL.
- DEPRESSIONS FORMED BY THE REMOVAL OR VEGETATION, EXISTING STRUCTURES, UNDERGROUND SERVICES ETC., SHOULD HAVE ALL DISTURBED SOIL CLEANED OUT AND BE BACKFILLED WITH COMPACTED SELECT FILL MATERIAL.
- ALL COMPLIANCE TESTING SHALL BE CARRIED OUT BY THE GEOTECHNICAL ENGINEER WHO WILL BE ENGAGED BY THE PRINCIPAL CONTRACTOR. ANY/ALL TESTING NECESSARY FOR GUIDANCE OR RE-TESTS WILL BE AT THE COST OF THE CONTRACTOR.
- THE PLACEMENT OF FILL TO BE EXECUTED SUCH THAT TO BE FREE DRAINING AT ALL TIMES AND NOT TO BE A NUISANCE OR PONDING TO ADJOINING PROPERTY OR ROADS.
- NO DEMOLITION MATERIAL TO BE USED AS FILL MATERIAL.
- WHERE UNSUITABLE MATERIAL IN AREAS OF FILL IS ENCOUNTERED, THIS WILL BE TREATED AS SET OUT IN THE EARTHWORK SPECIFICATION.
- ALL VEHICLES EXITING FROM THE SITE TO BE CLEAN TO PREVENT MATERIAL BEING TRACKED OR DEPOSITED ON THE ADJOINING PUBLIC ROADS, REFER ENVIRONMENTAL MANAGEMENT NOTES ON THE EROSION AND SEDIMENT CONTROL DRAWINGS.
- SITE ACCESS TO AND ACROSS THE SITE ARE SUBJECT TO SUPERINTENDENT APPROVAL.

**TOPSOIL RESPREAD REQUIREMENTS**

TOPSOIL RESPREAD THICKNESS SHALL BE AS SPECIFIED BELOW IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TOPSOIL RESPREAD LOCATIONS AND THICKNESS.

**TURF**

CONTRACTOR SHALL SUPPLY AND LAY TURF AS SPECIFIED IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TURF SUPPLY AND LAY AREAS.

**TRENCH SPOIL**

EXCESS TRENCH SPOIL MATERIAL GENERATED BY THIS CONTRACT SHALL BE PLACED EITHER WITHIN THE FILL ZONE NOMINATED ON THE EARTHWORKS DRAWINGS OR WITHIN A FILL ZONE NOMINATED BY THE SUPERINTENDENT THAT SHALL BE CONFIRMED PRIOR TO CONSTRUCTION COMMENCEMENT. FILL TO BE PLACED UNDER LEVEL 1 SUPERVISION AND IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION.

**TRENCH BACKFILL**

CBR15 STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

**EXCAVATION IN ROCK**

CONTRACT SHALL INCLUDE TREATING, SIZING, CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED TO ENSURE THAT FILL SPECIFICATION AND LEVEL ONE CERTIFICATION IS ACHIEVED.

**EVERLEIGH EARTHWORKS TOLERANCE TABLE**

ITEM	TOLERANCE
EARTHWORKS IN ALLOTMENTS AND VERGES <sup>(a)</sup>	EWL or FSL +/- 50mm
CUT BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 150mm <sup>(b)</sup>
FILL BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 300mm <sup>(b)</sup>
EARTHWORKS IN PARKS	EWL or FSL +/- 50mm

<sup>(a)</sup> TOLERANCE IS -0mm / +50mm WHERE ADJACENT DRAINAGE ELEMENT.  
<sup>(b)</sup> MEASURED FROM THE AVERAGE SLOPE PLANE.

**TOLERANCE NOTES**

- EARTHWORKS LEVEL (EWL) IS 100mm BELOW FINISHED SURFACE LEVEL (FSL) ON ALLOTMENTS (TOPSOIL RESPREAD THICKNESS).
- FINISHED SURFACE LEVEL (FSL) IS TOP OF TURF / STABILISED TOPSOIL LEVEL.
- ROADWORKS SUBGRADE, PAVEMENT, ASPHALT CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
- STORMWATER DRAINAGE CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
- SEWER AND WATER RETICULATION CONSTRUCTION LEVEL TOLERANCES AS PER SEQ D&C CODE.

**DISPERSIVE SOILS MANAGEMENT NOTES**

- DISPERSIVE SOIL TREATMENT MEASURES IN THE FOLLOWING AREAS SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE REQUIREMENTS OF THE EVERLEIGH DISPERSIVE SOIL MANAGEMENT:
  - WITHIN SERVICE TRENCHES
  - SURFACE AREAS SURROUNDING STORMWATER HEADWALLS
  - TURF/LANDSCAPED AREAS SUBJECT TO WATER FLOW
  - TURF/LANDSCAPED AREAS SUBJECT TO WATER PONDING
- STABILISATION OF DISTURBED AREAS AND MANAGEMENT OF EROSION AND SEDIMENT SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLANS IN THIS DRAWING SET.
- CONTRACTOR MUST CONSTRUCT AND ESTABLISH THE EROSION AND SEDIMENT CONTROL DEVICES, CONSTRUCTION WATER HOLDING DAM AND HES BASIN PRIOR TO COMMENCING EARTHWORKS OPERATION.
- ALL DISTURBED AREAS SHALL BE STABILISED AS SOON AS PRACTICABLE (BUT NOT MORE THAN 10 DAYS) FOLLOWING FINALISATION OF LEVELS. STABILISATION TO BE IN ACCORDANCE WITH EROSION & SEDIMENT CONTROL - STABILISATION PHASE.

**TOPSOIL AMELIORATION**

ONSITE STRIPPED TOPSOIL SHALL BE AMELIORATED PRIOR TO RESPREAD. THE FOLLOWING AMELIORATION SPECIFICATIONS SHALL APPLY:

**A-GRADE QUALITY TOPSOIL AMELIORATION:**

- SCREEN STRIPPED TOPSOIL
- ON-SITE COMPOST INCORPORATION (0.15kg/m<sup>3</sup> OF TOPSOIL)
- DOLOMITE (15kg/m<sup>3</sup> OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m<sup>3</sup> OF TOPSOIL)
- FERTILISER (0.4kg/m<sup>3</sup> OF TOPSOIL)

**B-GRADE QUALITY TOPSOIL AMELIORATION:**

- SCREEN STRIPPED TOPSOIL
- DOLOMITE (15kg/m<sup>3</sup> OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m<sup>3</sup> OF TOPSOIL)
- FERTILISER (0.4kg/m<sup>3</sup> OF TOPSOIL)

**ROCK TREATMENT IN ALLOTMENTS**

WHERE ALLOTMENTS ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 500mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL), AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

ALL CUT LOTS WHICH ARE NOT LOCATED IN ROCK MUST ACHIEVE 100kPa BEARING CAPACITY. WHERE THIS CAN'T BE ACHIEVED, THE CONTRACTOR SHALL RECTIFY THE SUBGRADE IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION TO ACHIEVE A 100kPa BEARING CAPACITY.

**ROCK TREATMENT IN VERGES**

WHERE ROAD RESERVES ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 1000mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL) AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

**EARTHWORKS SPECIFICATION**

SPECIFICATION	DEPTH RANGE (m)				PAVEMENT SUBGRADE	TRENCH BACKFILL
	0.0 - 0.6	0.6 - 3.00	3.00 - 5.00	> 5.00		
CBR %	-	-	-	-	10	15
LAYER THICKNESS (mm)	300	300	300	300	BETWEEN SUBGRADE AND 0.3m BELOW	300
MAXIMUM PARTICLE SIZE (mm)	200	500	500	500	200	200
% PASSING 37.5mm	80% MIN	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES
% PASSING 0.075mm	30% MIN	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES AND AS3798
COMPACTION	95% STD	95% STD	95% STD	95% STD	100% STD	95% MOD IN ROADS AND 95% STD OUTSIDE ROADS
MOISTURE	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	60% - 90% OF OMC	+/- 2% OMC

**NOTES:**

- OMC - OPTIMUM MOISTURE CONTENT
- LAYER OF THICKNESS IS LIMITED TO 300mm TO ALLOW IDENTIFICATION OF LARGER PARTICLES AND ALLOW EVERY CHANCE OF BREAK DOWN IN FILLING OR REMOVAL.
- TREATMENT OF ROCK TO SIZES ABOVE SHOULD BE CARRIED OUT IN CUT PRIOR TO LOADING TO FILL AREAS. TREATED ROCK TO BE APPROVED BY GITA PRIOR TO TRANSPORTING.
- UPPER 0.6m, (PARTICULARLY IN AREAS OF DEEP FILL), OF THE FILL PROFILE TO BE RELATIVELY IMPERMEABLE HENCE INCREASE IN FINES COMPONENT.
- PROOF ROLL TESTING ON EACH COMPACTED LAYER USING RUBBER WHEELED PLANT SUCH AS LOADED ADT'S OR LOADED SCRAPERS. UNFAVOURABLE DEFORMATION OF THE COMPACTED SURFACE UNDER LOAD OF ADT'S OR SCRAPERS WILL REQUIRE REPAIR PRIOR TO ADDITIONAL PLACEMENT.
- MECHANICAL INTERLOCK METHODOLOGY IS NOT APPROPRIATE DUE TO POOR DURABILITY OF SITE WON SANDSTONE. FILL COMPOSITION IS REQUIRED TO INCLUDE AN APPROPRIATE SAND GRAVEL AND FINES COMPONENT CONFORMING TO THE REQUIREMENTS OF AS798.

**KEY OUTCOMES FOR EARTHWORKS OPERATIONS**

- DELIVER RESIDENTIAL LOTS WITH FAVOURABLE LOT CLASSIFICATIONS - I.E - NO P CLASSIFICATIONS
- FILL THICKNESS DOES NOT VARY MORE THAN 2m OVER A DISTANCE OF 10m
- CONSTRUCT FILL AND LIMIT LONG TERM CREEP SETTLEMENTS TO WITHIN 0.5% TO 1.0% OF THE FILL THICKNESS
- BUILDING PLATFORM THAT ALLOWS BUILDERS TO CONSTRUCT SLAB ON GROUND RAFTS USING LIGHT EARTHMOVING EQUIPMENT
- MATERIAL WON FROM CUTS AND USED IN FILL WITH REQUIRE
  - CUTS IN ROCK AS WELL AS BLENDED WITH
  - CUTS IN FINER MATERIALS SUCH AS SANDS AND CLAYS
- CREATING A FILL PLATFORM THAT IS ABLE TO BE TESTED IN ACCORDANCE WITH AS3798 AND AS1289

FOR CONSTRUCTION					
DATE	REV	DESCRIPTION	REC	APP	REVISIONS
05/11/2021	B	ISSUED FOR CONSTRUCTION			
05/09/2021	A	ORIGINAL ISSUE			

**Premise**  
**BRISBANE OFFICE**  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**

CHECKED  
**A LANGDON**

PROJECT MANAGER  
**S STEINHOFER**

PROJECT DIRECTOR  
**PATRICK BRADY**

RPEQ 7112

SCALE

ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**


SHEET TITLE  
**BULK EARTHWORKS NOTES AND DETAILS - SHEET 1 OF 2**

JOB CODE  
**MIR009-01**

SHEET NUMBER  
**C210**


REV  
**B**






SHALL BE INSTALLED FOR ALL RETAINING WALLS LOCATED ON INTERALLOTMENT BOUNDARIES.

**TYPICAL RETAINING WALL SUBSOIL OUTLET TO ROAD**  
N.T.S.




SHALL BE INSTALLED IN REAR CORNER OF ALL ALLOTMENTS LOCATED BELOW A RETAINING WALL.


**TYPICAL RETAINING WALL SUBSOIL OUTLET TO ALLOTMENTS**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT 0.4m-2m MAX HIGH**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL ROAD ADJACENT TO LOT WHERE ROAD LEVEL IS HIGHER**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL ROAD ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT 2m-3m MAX HIGH**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL PARK ADJACENT TO LOT WHERE PARK LEVEL IS HIGHER**  
N.T.S.




**TYPICAL RETAINING WALL DETAIL PARK ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER**  
N.T.S.



**TYPICAL INTER ALLOTMENT RETAINING WALL TOP OF WALL SETOUT AND END DETAIL**  
N.T.S.



**TYPICAL RETAINING WALL TOP AND BOTTOM FINISHING LEVEL DETAIL**  
N.T.S.



**TYPICAL SECTION FOR BATTERS BETWEEN LOTS**  
SCALE 1:20

**RETAINING WALL DESIGN:**

- ALL RETAINING WALLS SHALL BE DESIGNED & CONSTRUCTED IN ACCORDANCE WITH THE "DESIGN AND CONSTRUCTION RETAINING WALL SPECIFICATION" PREPARED BY PREMISE ENGINEERING.
- RETAINING WALLS ARE TO BE DESIGNED TO ACHIEVE A MINIMUM OF 50 YEAR DESIGN LIFE.
- RETAINING WALLS ARE TO BE DESIGNED IN ACCORDANCE WITH THE AS4678- EARTH RETAINING STRUCTURES AND RELEVANT MATERIAL STANDARDS (E.G AS3600- CONCRETE STRUCTURES).

**RETAINING WALL SUBSOIL DRAINAGE OUTLET DESIGN:**

RETAINING WALL SUBSOIL DRAINAGE PIPE OUTLET LOCATIONS SHALL BE IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION. THE PRINCIPAL CIVIL CONTRACTOR SHALL DETERMINE THE LOCATION OF RETAINING WALL SUBSOIL DRAINAGE PIPES IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION AND PROVIDE PROPOSAL TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION.

**RETAINING WALL SHOP DRAWINGS**

CONTRACTOR MUST PREPARE RETAINING WALL SHOP DRAWINGS FOR APPROVAL BY SUPERINTENDENT PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION. SHOP DRAWINGS ARE TO DETAIL THE FOLLOWING ELEMENTS:

- ELEVATIONS OF ALL PROPOSED RETAINING WALLS AND ACOUSTIC FENCES
- TOP AND BOTTOM RLS TO SLEEPER/PANEL
- FINISHED PAD/ROAD SURFACE LEVELS
- DIMENSIONS OF RETAINING WALL END FINISHING CONFIGURATION, OFFSETS FROM BOUNDARIES
- POST DETAILS FOR INTRICATE INTERSECTION POINTS

**PROPERTY SERVICES UNDER RETAINING WALLS:**

CONTRACTOR SHALL REFER TO ALL LATEST SERVICE DRAWINGS TO ENSURE PROVISIONS ARE MADE FOR ALL PROPERTY SERVICE CONNECTIONS UNDER RETAINING WALLS.

**PAD MOUNTED TRANSFORMER NOTE**

- RETAINING WALLS AND THEIR FOOTINGS SHALL NOT ENCOACH INTO THE PMT SITE (AS PER RETAINING WALLS LOCATED ADJACENT ROAD RESERVES DETAIL) UNLESS THE RETAINING WALL SPECIFIED IS AN ENERGEX STANDARD MASONRY WALL.
- RETAINING WALL DESIGN SHALL CONSIDER ENERGEX REQUIREMENT WHERE RETAINING WALLS ARE LOCATED WITHIN 2m OF PMT SITE.

**RETAINING WALL TYPE**

**PRIVATE FACING RETAINING WALLS:**  
CONCRETE SLEEPER RETAINING WALL. TIMBER TEXTURED SLEEPERS AND 2 COAT PAINT (COLOUR WARM GREY 10C). DESIGN SPECIFICATION BY MANUFACTURER.

**PUBLIC FACING RETAINING WALLS:**  
CONCRETE PANEL RETAINING WALL. 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER.

**FENCE BRACKETS**

PROVIDE FENCE BRACKETS TO ALL RETAINING WALLS. NO BRACKETS TO BE PROVIDED WITHIN THE FIRST 5m FROM FRONT BOUNDARY FOR INTER-ALLOTMENT RETAINING WALLS.

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	C	ISSUED FOR CONSTRUCTION	KK	PB
15/10/2021	B	UPDATED RETAINING WALL NOTE	AL	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB

**Premise**  
BRISBANE OFFICE  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
**PATRICK BRADY** RPEQ 7112

SCALE  
NTS  
ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**  
PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
LOCATION  
**TEVIOT ROAD, GREENBANK**  
SHEET TITLE  
**BULK EARTHWORKS NOTES AND DETAILS - SHEET 2 OF 2**

JOB CODE  
**MIR009-01**  
SHEET NUMBER  
**C211**  
REV  
**C**

**NOTES**

- ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARD DRAWINGS AND METHODS (U.N.O.).
- NOTWITHSTANDING THE LIMITS OF CUTTING AND FILLING SHOWN ON THE DRAWINGS, THE ACTUAL LIMITS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT DURING CONSTRUCTION AND SIMILARLY THE FINISHED SURFACE CONTOURS MAY BE ADJUSTED BY WRITTEN DIRECTION OF THE SUPERINTENDENT DURING CONSTRUCTION.
- THE CONTRACTOR IS TO ASCERTAIN THE EXACT LOCATION OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE COST OF RECTIFICATION OF ANY DAMAGES TO EXISTING SERVICES WHICH MAY OCCUR. THE LOCATION OF EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY.
- SUBGRADE TEST RESULTS TO BE FORWARDED TO SUPERINTENDENT FOR DETERMINATION OF BOX DEPTHS PRIOR TO EXCAVATION. TESTS SHALL INCLUDE SOAKED CBR AND/OR OTHER TESTS AS REQUESTED BY THE SUPERINTENDENT.
- ALLOTMENT FILLING TO BE COMPACTED TO 95% (min) OF THE R.D.D. (AS 1289 - TESTS E1.1, E4.1).
- LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.
- LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS APPROVED BY THE SUPERINTENDENT TO ACHIEVE SATISFACTORY CONNECTION TO THE EXISTING WORKS.
- SIDE DRAINS AND MITRE DRAINS TO BE CONSTRUCTED ADJACENT TO ALL KERB AND CHANNEL.
- PROVIDE FLUSH POINTS TO SUBSOIL DRAINS, LOCATIONS TO BE CONFIRMED ON SITE.
- ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION. ALL PIPES ARE 375mm DIAMETER U.N.O.
- GULLIES AND GULLY GRATES SHALL BE TO STD. DRGS BSD-8051 - BSD-8059.
- KACEY GALV. STEEL KERB ADAPTORS ARE TO BE INSTALLED TO THE REQUIREMENTS OF THE LOCAL COUNCILS STANDARD DRAWINGS AND SPECIFICATIONS.
- ALL LOTS SHOWN BOXED TO HAVE ROOFWATER FOOTPATH CROSSINGS TO KERB. CROSSINGS ARE TO BE 88.9 DIA. GALV. CHS. TO KACEY KERB ADAPTOR.
- ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
- ROOFWATER PITS ARE TO BE 600mm DIAMETER FOR DEPTHS LESS THAN 750mm, 900mm DIAMETER FOR DEPTHS BETWEEN 750mm AND 1500mm DEEP AND 1050mm DIAMETER FOR DEPTHS GREATER THAN 1500mm.
- ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- HAZARD MARKERS (D4-4A) TO BE PLACED AT THE END OF NEW WORKS AS DIRECTED BY SUPERINTENDENT.
- SITE CBR VALUE AND PAVEMENT DESIGN AND DEPTHS TO BE VERIFIED WITH CBR TESTS PRIOR TO CONSTRUCTION.
- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- TO BE READ IN CONJUNCTION WITH ALL STORMWATER DRAINAGE LAYOUT PLANS & ROADWORKS DETAILS.

**ROADWORKS NOTES**

- GEOTECHNICAL TESTING FOR PAVEMENT CONSTRUCTION IS TO BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT SPECIFICATION. TEST CERTIFICATES ARE TO BE PREPARED BY A REGISTERED N.A.T.A. LABORATORY AT THE CONTRACTORS COST AND SHALL BE PROVIDED TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS. THE CONTRACTOR IS TO NOTIFY THE ENGINEER OF ANY NON-CONFORMANCES. ALL NON CONFORMING WORK IS TO BE RECTIFIED AS DIRECTED BY THE ENGINEER.
- FULL DEPTH PAVEMENT CONSTRUCTION SHALL EXTEND BEHIND ALL KERB AND CHANNEL FOR A DISTANCE WHICH IS THE GREATER OF 150mm FROM THE BACK OF KERB OR ACROSS TO THE OUTER LIMIT OF SIDE DRAIN FILTER MATERIAL.
- TRANSITION KERB AND CHANNEL TO BARRIER KERB SMOOTHLY OVER MIN. 1.0m LENGTH.
- PAVEMENT THICKNESSES NOMINATED ON THESE DRAWINGS ARE PROVISIONAL ONLY AND MAY BE VARIED BY THE SUPERINTENDENT SUBJECT TO INSITU PAVEMENT SUBGRADE TESTING. PAVEMENT SUBGRADES ARE TO BE INITIALLY CONSTRUCTED TO THE UNDERSIDE OF THE NOMINATED LOWER SUBBASE COURSE WITHIN FILL AREAS, AND TO THE UNDERSIDE OF THE NOMINATED UPPER SUBBASE COURSE WITHIN CUT AREAS. INSITU SUBGRADE CBR TESTING AS SPECIFIED FOR PAVEMENT DESIGN VERIFICATION IS TO BE CARRIED OUT AT THESE LEVELS.
- REPAIR ANY DAMAGE TO EXISTING KERB AND CHANNEL, FOOTPATH OR ROADWAY (INCLUDING REMOVAL OF CONCRETE SLURRY FROM FOOTPATHS, ROADS, KERB AND CHANNEL AND STORMWATER GULLIES AND SIDEDRAINS) THAT MAY OCCUR DURING ANY WORKS CARRIED OUT.

**CONCRETE PAVEMENT**

- THE CONCRETE PAVEMENT HAS BEEN DESIGNED BASED ON A CBR 5 AND IS SUBJECT TO CONFIRMATION UPON RECEIPT OF CBR TEST RESULT AT TIME OF CONSTRUCTION.
- CONCRETE PAVEMENT SPECIFICATION:

COMPRESSION STRENGTH: 25 MPa @ 28 DAYS  
 FLEXURAL STRENGTH: 3.5 MPa @ 28 DAYS  
 MAXIMUM AGGREGATE SIZE: 20mm  
 SLUMP: 80mm+15mm  
 MESH: SL72, 50 TOP COVER  
 BEDDING: 100mm MIN CBR 15 BEDDING


- MATERIALS AND WORKMANSHIP SHALL COMPLY WITH AS1379, AS3600 AND AS3610.
- PROJECT ASSESSMENT OF STRENGTH IN ACCORDANCE WITH AS3600 SHALL BE ADOPTED FOR SAMPLING AND TESTING. THE CONTRACTOR SHALL PAY ALL TESTING COSTS.
- CONSTRUCTION JOINTS SHALL BE MADE ONLY AT APPROVED LOCATIONS.
- ALL JOINTS ARE TO BE SEALED JUST PRIOR TO HANDOVER WITH DOW CORNING '888' SEALANT INSTALLED IN ACCORDANCE WITH MANUFACTURING RECOMMENDATIONS.
- JOINTS ARE TO BE INSPECTED AND SEALANT REGULARLY REPLACED IF REQUIRED.
- DIMENSIONAL TOLERANCES OF AS3600, MODIFIED BY AS3610, SHALL APPLY UNLESS OTHERWISE NOTED. SLAB SURFACE FLATNESS TOLERANCE SHALL BE 5mm MAXIMUM DEVIATION FOR A 3m STRAIGHT EDGE.
- CONCRETE PAVEMENTS ARE TO BE BROOM FINISHED. SLAB THICKNESSES NOTED ARE EXCLUSIVE OF APPLIED FINISHES
- CURE ALL CONCRETE BY AN APPROVED METHOD FOR 7 DAYS AFTER HARDENING. PVA AND RESIN BASED CURING COMPOUNDS SHALL NOT BE USED.

**CONCRETE PAVEMENT MAINTENANCE NOTES**


- NOTE THAT UPKEEP AND REPLACEMENT OF SEALANTS IS PART OF THE ONGOING MAINTENANCE REQUIREMENTS FOR THIS SITE.
- NOTE THAT SHRINKAGE CRACKS OF WIDTH < 1.5mm MAY OCCUR IN CONCRETE PAVEMENTS WITHIN 12 MONTHS OF INITIAL CASTING.
- NOTE THAT THE PAVEMENT WILL NOT BE MAINTENANCE FREE FOR ITS DESIGN LIFE.
- INSPECT FLUSH SIDE DRAINS AND SUBSOIL DRAINS EVERY 12 MONTHS.

**CONCRETE REQUIREMENTS**

ITEM	28 DAY STRENGTH	CONCRETE CYLINDER TEST	TESTING FREQUENCY
KERB & CHANNEL	N32	REQUIRED	1 TEST PER 300m
VEHICULAR CROSSINGS	N25	REQUIRED	1 TEST PER CROSSING
BIKEWAYS	N25	REQUIRED	1 TEST PER 300m
FOOTPATHS	N25	REQUIRED	1 TEST PER 300m
CONCRETE CHANNELS	N25	REQUIRED	1 TEST PER 150m <sup>2</sup>
STRUCTURES	AS DESIGN	REQUIRED	AS DIRECTED
ROOFWATER MH'S	N20	NOT REQUIRED	
STORMWATER MH'S	N25	NOT REQUIRED	
PRECAST MANHOLE ROOF SLABS	N40	NOT REQUIRED	
GULLY PITS			
.. PRECAST LINTEL	N30	NOT REQUIRED	
.. OTHER	N25	NOT REQUIRED	




**SAWCUT JOINT (S.J.)**




**TYPICAL PAVEMENT CUT-BACK DETAIL**

N.T.S




**TYPICAL KERB RECESS / END DETAIL**


NOTE: REFER LAYOUT PLAN FOR TRANSITION RECESS & KERB END LOCATIONS & LENGTHS



PLAN



**KERB END DETAIL**



**TYPICAL FUTURE ROADS BOX-OUT TREATMENT**

SCALE 1:20


**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED: K KIWANG  
 CHECKED: A LANGDON  
 PROJECT MANAGER: S STEINHOFER  
 PROJECT DIRECTOR: Patrick Brady  
 RPEQ 7112




CLIENT: **MIRVAC GROUP**  
 PROJECT: **EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION: **TEVIOT ROAD, GREENBANK**  
 SHEET TITLE: **ROADWORKS NOTES AND DETAILS**

JOB CODE: **MIR009-01**  
 SHEET NUMBER: **C300**  
 REV: **B**

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- AMBER CIRCUIT
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 <sup>5</sup>
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

\* REFER TO INTERSECTION DETAILS PLANS



Horiz Curve Data  
Vertical Geometry Grade (%)  
Vertical Grade Length (m)  
Vertical Curve Length (m)  
Vertical Curve Radius (m)

DATUM R.L.62.0

CUT (-)/FILL DEPTH	LHS LIP LEVEL	RHS LIP LEVEL	DESIGN SURFACE	NATURAL SURFACE	CHAINAGE
0.000			68.429	68.429	-0.00
-0.000			68.335	68.336	3.75
-0.000			68.222	68.222	12.86
0.000	68.168	68.168	68.255	68.255	17.75
0.000	68.198	68.198	68.285	68.285	20.00
0.000	68.466	68.466	68.553	68.553	40.00
0.000	68.678	68.678	68.765	68.765	55.78
0.000	68.733	68.733	68.820	68.820	60.00
0.000	68.754	68.754	68.841	68.841	61.75
0.000	68.932	68.932	69.019	69.019	80.00
0.000	68.956	68.956	69.043	69.043	83.35
0.000	68.972	68.972	69.059	69.059	85.78
0.000	69.059	69.059	69.146	69.146	100.00
0.000	69.129	69.129	69.216	69.216	111.35
0.355	69.182	69.182	69.269	68.934	120.00
0.355	69.305	69.305	69.392	69.057	140.00
0.355	69.427	69.427	69.514	69.179	160.00
0.355	69.550	69.550	69.637	69.302	180.00
0.355	69.673	69.673	69.760	69.425	200.00
0.355	69.680	69.680	69.767	69.432	201.18
0.355	69.721	69.721	69.808	69.473	207.88
0.355	69.847	69.847	69.934	69.599	220.00
0.355	69.890	69.890	69.977	69.642	222.78
0.355	70.219	70.219	70.306	69.971	237.88
0.355	70.276	70.276	70.363	70.028	240.00
0.355	70.817	70.817	70.904	70.569	260.00
0.355	70.921	70.921	71.008	70.673	263.82
0.355	*	*	71.372	71.037	277.82
0.355			71.427	71.092	280.00
0.355			71.466	71.131	281.57
0.355					281.57


AMBER CIRCUIT LONGITUDINAL SECTION  
SCALE 1:1000(H) 1:100(V)

FOR CONSTRUCTION



BRISBANE OFFICE  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
K KIWANG  
CHECKED  
A LANGDON  
PROJECT MANAGER  
S STEINHOFER  
PROJECT DIRECTOR  
PATRICK BRADY  
RPEQ 7112





CLIENT  
MIRVAC QLD PTY LTD  
PROJECT  
EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
LOCATION  
TEVIOT ROAD, GREENBANK  
SHEET TITLE  
AMBER CIRCUIT LONGITUDINAL SECTION

JOB CODE  
MIR009-01  
SHEET NUMBER  
C310  
REV  
B

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
05/09/2021	A	ORIGINAL ISSUE	KK	PB






**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**AMBER CIRCUIT CROSS SECTIONS**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C311**  
 REV  
**B**

PAVEMENT DESIGN (PRELIMINARY)	
ROADS	- MOSS STREET
CLASS	- ACCESS STREET (TYPICAL)
ESA's	- 5.90 x 10 <sup>5</sup>
SURFACE	- 35mm AC of 10mm MIX
PRIMER TYPE	- PRIME
CBR 80	- 150mm
CBR 45	- 150mm
TOTAL BOX	- 335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

\* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

Vertical Geometry Grade (%)

Vertical Grade Length (m)


Vertical Curve Length (m)

Vertical Curve Radius (m)

DATUM R.L.56.0

CHAINAGE	NATURAL SURFACE	DESIGN SURFACE	RHS LIP LEVEL	LHS LIP LEVEL	CUT (-)/FILL DEPTH
0.00	62.505	62.505			0.000
3.75	62.440	62.411			-0.029
10.47	62.263	62.327			0.064
17.75	62.426	62.426		62.339	0.000
20.00	62.487	62.487		62.400	0.000
26.20	62.655	62.655		62.568	0.000
40.00	62.992	62.992		62.905	0.000
56.20	63.295	63.295		63.208	0.000
60.00	63.354	63.354		63.267	0.000
66.26	63.452	63.452		63.365	0.000
80.00	63.702	63.686		63.599	-0.016
100.00	64.101	64.101		64.014	0.000
106.26	64.249	64.249		64.162	0.000
120.00	64.583	64.583		64.496	0.000
140.00	65.068	65.068		64.981	0.000
160.00	65.554	65.554		65.467	0.000
180.00	66.039	66.039		65.952	0.000
200.00	66.525	66.525		66.438	0.000
215.00	66.889	66.889		66.802	0.000
218.45	66.973	66.973		66.886	0.000
220.00	67.010	67.010		66.923	0.000
220.87	67.031	66.944		66.944	0.000
233.66	67.370	67.370		67.283	0.000
237.11	67.471	67.471		67.384	0.000
240.00	67.558	67.558		67.471	0.000
250.87	67.913	67.913		67.826	0.000
260.00	68.227	68.227		68.140	0.000
280.00	68.917	68.917		68.830	0.000
300.00	69.589	69.589		69.502	0.000
307.61	69.843	69.843		69.756	0.000
315.46	69.770	70.105		70.018	0.335
320.00	69.914	70.249		70.162	0.335
340.00	70.360	70.695		70.608	0.335
345.46	70.429	70.764		70.677	0.335
360.00	70.583	70.918		70.831	0.335
380.00	70.795	71.130		71.043	0.335
400.00	71.007	71.342		71.255	0.335
400.69	71.014	71.349		71.262	0.335
403.96	71.048	71.383		71.296	0.335
404.54	71.055	71.390		71.303	0.335
418.94	71.207	71.542		71.455	0.335
419.52	71.213	71.548		71.461	0.335
420.00	71.218	71.553		71.466	0.335
422.80	71.248	71.583		71.496	0.335
428.73	71.311	71.646		71.559	0.335
440.00	71.430	71.765		71.694	0.335
450.54	71.541	71.876		71.819	0.335
460.00	71.642	71.977		71.915	0.335
462.62	71.670	72.005		71.943	0.335
466.87	71.719	72.054		71.992	0.335
480.00	71.872	72.207		72.149	0.335
500.00	72.104	72.439		72.382	0.335
520.00	72.337	72.672		72.614	0.335
540.00	72.569	72.904		72.847	0.335
552.90	72.719	73.054		72.992	0.335
560.00	72.802	73.137		73.080	0.335
575.00	72.976	73.311		73.254	0.335
580.00	73.035	73.370		73.312	0.335
600.00	73.267	73.602		73.545	0.335

EXISTING PRECINCT 1.1      EXISTING PRECINCT 12.1      EXISTING PRECINCT 12.2      PRECINCT 9.1      FUTURE PRECINCT




FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB





**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWIANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
 PATRICK BRADY RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**MOSS STREET LONGITUDINAL SECTIONS**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C312**  
 REV  
**B**



**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB

**Premise**  
 BRISBANE OFFICE  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
 PATRICK BRADY  
 RPEQ 7112


SCALE  
 0 2 4 6m  
 SCALE 1:100 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**MOSS STREET CROSS SECTIONS - SHEET 1 OF 2**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C313**  
 REV  
**B**



\* FOR SURFACE STABILISATION TREATMENT OF WORKS OUTSIDE OF PRECINCT 9.1, REFER TO MIR-012-01 DRAWING C730 - EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE




**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au


DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
 PATRICK BRADY  
 RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**MOSS STREET CROSS SECTIONS - SHEET 2 OF 2**


JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C314**  
 REV  
**B**






CHAINAGE 80

DATUM R.L. 66.00




CHAINAGE 60

DATUM R.L. 67.00




CHAINAGE 40

DATUM R.L. 67.00




CHAINAGE 20

DATUM R.L. 68.00




CHAINAGE 160

DATUM R.L. 62.00




CHAINAGE 140

DATUM R.L. 63.00



CHAINAGE 120

DATUM R.L. 64.00



CHAINAGE 100


DATUM R.L. 65.00

**FOR CONSTRUCTION**



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
 CHECKED  
**A LANGDON**  
 PROJECT MANAGER  
**S STEINHOFER**  
 PROJECT DIRECTOR  
*Patrick Brady*  
**PATRICK BRADY** RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**BAMBOO ROAD CROSS SECTIONS**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C316**  
 REV  
**B**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	DRIVEWAY 3
CLASS	-	REAR ACCESS DRIVEWAY
ESA's	-	1.10 x 10 <sup>5</sup>
SURFACE	-	35mm AC of 10mm MIX
CBR 80	-	PRIME
CBR 45	-	150mm
CBR 15	-	100mm
TOTAL BOX	-	285mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

\* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data

Vertical Geometry Grade (%)	Vertical Grade Length (m)	Vertical Curve Length (m)	Vertical Curve Radius (m)
-2.55%	2.7m	0.78m	0.00
36.23%	0.27m	0.17m	0.00
-7.41%	0.05m	0.12m	0.00
10%	0.89m	2.77m	0.00
3.82%	32.78m		0.00
0.63%			0.00



DATUM R.L.63.0

CUT (-)/FILL DEPTH	LHS LIP LEVEL	RHS LIP LEVEL	DESIGN SURFACE	NATURAL SURFACE	CHAINAGE
0.535	69.943	70.055	69.850	69.515	0.00
0.285	69.943	70.079	69.998	69.713	8.28
0.285	69.987	70.108	70.042	69.757	15.26
0.285	70.017	70.108	70.071	69.786	20.00
0.278	70.115	70.206	70.169	69.891	35.62

DRIVEWAY 3 LONGITUDINAL SECTION

SCALE 1:1000H 1:100V

INT. AMBER CIRCUIT CH.10  
IP CH. 2.70 RL.69.785  
IP CH. 3.47 RL.69.763  
IP CH. 3.74 RL.69.743  
IP CH. 4.03 RL.69.848  
IP CH. 4.03 RL.69.848  
IP CH. 4.03 RL.69.848  
IP CH. 6.83 RL.69.960  
IP CH. 7.74 RL.69.994  
IP CH. 4.08 RL.69.848  
SAG CH. 4.08 RL.69.848



DRIVEWAY 3 CROSS SECTIONS

SCALE 1:100


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION		KK	PB
05/09/2021	A	ORIGINAL ISSUE		KK	PB




**BRISBANE OFFICE**  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED <b>K KIWANG</b>	 PATRICK BRADY RPEQ 7112
CHECKED <b>A LANGDON</b>	
PROJECT MANAGER <b>S STEINHOFER</b>	
PROJECT DIRECTOR	




CLIENT <b>MIRVAC GROUP</b>	JOB CODE <b>MIR009-01</b>
PROJECT <b>EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT</b>	SHEET NUMBER <b>C317</b>
LOCATION <b>TEVIOT ROAD, GREENBANK</b>	REV <b>B</b>
SHEET TITLE <b>DRIVEWAY 3 LONG &amp; CROSS SECTIONS</b>	



INTERSECTION AMBER CIRCUIT & MOSS STREET

INTERSECTION MOSS STREET AND BAMBOO ROAD



INTERSECTION DRIVEWAY 3 & AMBER CIRCUIT

**LEGEND**

- 12.0 — FINISHED MAJOR CONTOURS (0.50m)
- — — FINISHED MINOR CONTOURS (0.10m)
- ▬▬▬▬▬ PROPOSED 1.5m WIDE CONCRETE FOOTPATH. (UNO) REFER CONC. REQUIREMENTS ON DRG. No. C300
- ▬▬▬▬▬ PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
- ▬▬▬▬▬ PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- ▬▬▬▬▬ PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- ▬▬▬▬▬ PROPOSED IPWEA TYPE 'B2' KERB ONLY. REFER IPWEA STD DWG RS-080.
- ▬▬▬▬▬ PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
- ▬▬▬▬▬ PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
- 12.497 LIP OF KERB LEVEL
- TRANSITION IN KERB AND CHANNEL TYPE
- D — PROPOSED STORMWATER
- S — PROPOSED SEWER
- W — PROPOSED WATER

**EXISTING - LEGEND**

- D --- D --- EXISTING STORMWATER
- S --- S --- EXISTING SEWER
- W --- W --- EXISTING WATER
- E --- E --- EXISTING ELECTRICAL
- T --- T --- EXISTING TELSTRA
- G --- G --- EXISTING GAS
- RM --- RM --- EXISTING SEWER RISING MAIN

**NOTE**  
LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**Premise**  
BRISBANE OFFICE  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
**PATRICK BRADY** RPEQ 7112

SCALE  
0 5 10 15m  
SCALE 1:250 (A1)  
ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**  
PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
LOCATION  
**TEVIOT ROAD, GREENBANK**  
SHEET TITLE  
**INTERSECTION DETAILS LAYOUT**

JOB CODE  
**MIR009-01**  
SHEET NUMBER  
**C330**  
REV  
**B**



### LINEMARKING NOTES

- PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD, QUEENSLAND DEPARTMENT OF MAIN ROADS) AND THE SPECIFIC REQUIREMENTS OF REFERENCE SPECIFICATION S150 ROADWORKS. BRISBANE CITY COUNCILS SPECIFIC REQUIREMENTS ARE DETAILED ON STANDARD DRAWINGS BSD-3151 TO BDS-3163.
- ALL INTERNAL LINE MARKING TO CONSIST OF LINES 100mm WIDE WITH 2 COATS OF PAINT TO MANUFACTURERS SPECIFICATIONS.
- EXTENT OF LINEMARKING SHALL BE VERIFIED ON SITE PRIOR TO INSTALLATION.
- ALL PAINTED MARKINGS SHALL BE APPROVED REFLECTORISED U.N.O.
- ANY EXISTING LINE MARKINGS DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED.
- EXISTING CONFLICTING LINE MARKINGS ARE TO BE GROUND OFF BY METHODS APPROVED BY THE DISTRICT ENGINEER.
- RETRO-REFLECTIVE RAISED PAVEMENT MARKERS (RRPM'S) SHALL BE PLACED 25mm TO 50mm FROM THE PAINTED LINEMARKING AND ORIENTATED SO THAT FULL REFLECTIVE EFFECT IS ACHIEVED BY AIMING THE REFLECTIVE FACE IN THE DIRECTION OF APPROACHING TRAFFIC.
- GENERALLY THE NORMAL SPACING BETWEEN RRPM'S IS TO BE 12.0m U.N.O.
- ANY EXISTING LINEMARKING NOT SHOWN ON THIS PLAN WHICH CONFLICTS OR IS INCOMPATIBLE WITH THE PROPOSED LINEMARKING SHALL BE REMOVED BY THE CONTRACTOR.
- NOSE OF ISLANDS TO BE PAINTED WHITE WITH GLASS BEADS.
- ALL STREET LIGHTING IN ACCORDANCE WITH AS1158.

### SIGNAGE NOTES

- LOCATION OF SIGNS SHOWN INDICATED ON THIS PLAN ARE INDICATIVE ONLY. CARE AND CONSIDERATION IS TO BE GIVEN TO ON SITE CONDITIONS TO AVOID ANY VISUAL OBSTRUCTION OF THE SIGN ALONG THE INTENDED COURSE OF APPROACHING TRAFFIC. EXACT LOCATION OF ALL SIGNS SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.
- SIGNS SHOULD BE ORIENTATED AT APPROXIMATELY RIGHT ANGLES TO, AND FACING THE TRAFFIC THEY ARE INTENDED TO SERVE.
- SIGNAGE SHALL BE IN ACCORDANCE WITH:
  - AS1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
  - AS1743 ROAD SIGNS SPECIFICATION
  - AS4049.1 PAVEMENT MARKING MATERIALS
- STREET NAME SIGNS ARE TO BE INSTALLED WITH THE RELEVANT HOUSE NUMBERS IN ACCORDANCE WITH THE RELEVANT LOCAL COUNCIL STANDARD DRAWINGS.

### REQUIRED SIGNS



### LEGEND

AC SURFACE DRIVEWAY

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK PB
05/09/2021	A	ORIGINAL ISSUE	KK PB

**BRISBANE OFFICE**  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**

CHECKED  
**A LANGDON**

PROJECT MANAGER  
**S STEINHOFER**

PROJECT DIRECTOR  
*Patrick Brady*  
**PATRICK BRADY**

RPEQ 7112

SCALE

SCALE 1:500 (A1)

ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**


PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**


SHEET TITLE  
**PAVEMENT MARKINGS AND SIGNAGE LAYOUT**

JOB CODE  
**MIR009-01**


SHEET NUMBER	REV
<b>C340</b>	<b>B</b>



LAYOUT PLAN  
SCALE: 1:500



B SECTION  
SCALE 1:50



A SECTION  
SCALE 1:50

LEGEND - PROPOSED

- 1.8m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- 2.4m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- 2.5m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- 2.6m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.
- H1.80 TOTAL HEIGHT FROM TOP OF FENCE TO LOWEST POINT ON EITHER SIDE OF ACOUSTIC FENCE

LEGEND - EXISTING

- 1.8m HIGH MODULAR WALLS, ACOUSTIC FENCE OR APPROVED EQUIVALENT.

**NOTE:**  
\* ACOUSTIC FENCE WALL HEIGHTS TO BE COORDINATED WITH EXISTING ACOUSTIC FENCE HEIGHTS. REFER RETAINING WALL SHOP DRAWINGS FOR FURTHER DETAIL. EXISTING WALLS ARE TO BE INCLUDED IN THE RETAINING WALL SHOP DRAWINGS AND TO BE REVIEWED BY THE SUPERINTENDENT AS PART OF THE REVIEW PROCESS.

**NOTE:**  
THESE ACOUSTIC FENCE PLANS SHOULD BE READ IN CONJUNCTION WITH THE C200 SERIES EARTHWORKS DRAWINGS.

THESE DRAWINGS HAVE BEEN PREPARED IN ACCORDANCE WITH THE ATP CONSULTING ENGINEERS NOISE IMPACT ASSESSMENT, DOCUMENT NO. ATP170617-R-TNIA-04\_RoL 5 DATED AUGUST 2021.

THE PROPOSED ACOUSTIC FENCE SHALL BE CONSTRUCTED AS FOLLOWS:

- THE ACOUSTIC FENCE SHOULD BE CONSTRUCTED TO COMPLY WITH TMR'S ROAD TRAFFIC NOISE MANAGEMENT: CODE OF PRACTICE.
- MATERIAL WITH MINIMUM SURFACE DENSITY OF 15kg/m<sup>2</sup>, E.G. TIMBER PALINGS WITH MINIMUM THICKNESS 20mm; FIBRE-CEMENT SHEETING WITH MINIMUM THICKNESS OF 12mm; MASONRY; AND AERATED CONCRETE.
- THE NOISE BARRIER SHOULD BE FREE OF ANY GAPS. IF THE NOISE BARRIER IS CONSTRUCTED OF TIMBER PALINGS, PLANKS SHOULD HAVE MINIMUM 35mm OVERLAP.
- NO GAPS SHALL BE LEFT BETWEEN THE FENCE AND THE GROUND.
- THE NOISE BARRIER SHOULD BE OF DURABLE CONSTRUCTION.
- ACOUSTIC FENCE SHOULD BE PAINTED TO MATCH RETAINING WALLS.
- THE ACOUSTIC FENCE IS AS PER SLIM WALL SPECIFICATIONS FROM MODULAR WALLS.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION		KK	PB
05/09/2021	A	ORIGINAL ISSUE		KK	PB

**Premise**  
BRISBANE OFFICE  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au


DESIGNED  
K KIWIANG  
CHECKED  
A LANGDON  
PROJECT MANAGER  
S STEINHOFER  
PROJECT DIRECTOR  
PATRICK BRADY  
RPEQ 7112

SCALE  
0 10 20 30m  
SCALE 1:500 (A1)  
0 1 2 3m  
SCALE 1:50 (A1)  
ORIGINAL SHEET SIZE A1

CLIENT  
MIRVAC QLD PTY LTD  
PROJECT  
EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
LOCATION  
TEVIOT ROAD, GREENBANK  
SHEET TITLE  
ACOUSTIC FENCE LAYOUT PLAN

JOB CODE  
MIR009-01  
SHEET NUMBER  
C350  
REV  
B





**LEGEND**

- PROPOSED STORMWATER CATCHMENT BOUNDARY.
- 1/A 0.2311ha STORMWATER CATCHMENT NUMBER AND AREA
- PROPOSED STORMWATER LINE
- EXISTING STORMWATER LINE
- FINISHED CONTOURS (0.50m)
- FINISHED CONTOURS (0.25m)
- EXISTING CONTOURS (0.50m)

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REVISIONS
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK PB
03/09/2021	A	ORIGINAL ISSUE	KK PB
			REC APP



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWIANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**


PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**STORMWATER CATCHMENT LAYOUT**

JOB CODE		<b>MIR009-01</b>
SHEET NUMBER	REV	
<b>C400</b>	<b>B</b>	

STRUCTURE NAME	1/502	2/502	3/502	4/502	5/502
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1050mm DIA




PIPE SIZE (mm)	375	375	375	375
PIPE CLASS	2	2	2	2
PIPE GRADE (%)	1.26%	1.53%	1.10%	1.45%
PIPE SLOPE (1 in X)	79.5	65.2	90.8	68.9
FULL PIPE VELOCITY (m/s)	0.35	0.58	0.68	1.39
PART FULL VELOCITY (m/s)	1.39	1.71	1.58	2.09
PIPE FLOW (cumecs)	0.039	0.064	0.075	0.154
PIPE CAPACITY AT GRADE (cumecs)	0.197	0.217	0.184	0.211
DATUM RL	55.0			

WSE IN STRUCTURE	71.326	70.951	70.498	69.689	68.986
HGL IN PIPE	71.281	70.919	70.486	69.689	68.986
DEPTH OF INVERT BELOW FSL	1.255	1.286	1.455	1.480	1.354
INVERT LEVEL	71.139	70.756	70.235	69.305	68.684
FINISHED (& EXISTING) SURFACE LEVEL	72.394 (75.254)	72.042 (74.060)	71.689 (72.771)	70.786 (74.459)	70.038 (73.534)
CHAINAGE	0.000	30.473	32.625	63.098	84.383

LINE 502

STRUCTURE NAME	1/503	4/502	1/504	5/502	1/505	5/502
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1050mm DIA	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1050mm DIA




PIPE SIZE (mm)	375	375	375	375	375	375
PIPE CLASS	2	2	2	2	2	2
PIPE GRADE (%)	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
PIPE SLOPE (1 in X)	100.0	99.8	100.0	100.0	100.0	100.0
FULL PIPE VELOCITY (m/s)	0.61	0.37	0.33	0.33	0.33	0.33
PART FULL VELOCITY (m/s)	1.48	1.29	1.25	1.25	1.25	1.25
PIPE FLOW (cumecs)	0.068	0.041	0.036	0.036	0.036	0.036
PIPE CAPACITY AT GRADE (cumecs)	0.175	0.176	0.175	0.175	0.175	0.175
DATUM RL	55.0	55.0	55.0	55.0	55.0	55.0

WSE IN STRUCTURE	70.077	69.689	69.122	69.089	69.089	69.089
HGL IN PIPE	69.891	69.778	69.055	69.035	69.035	69.035
DEPTH OF INVERT BELOW FSL	1.115	1.169	1.116	1.115	1.115	1.115
INVERT LEVEL	69.702	69.617	68.910	68.898	68.898	68.898
FINISHED (& EXISTING) SURFACE LEVEL	70.817 (74.649)	70.786 (74.459)	70.025 (73.594)	70.013 (73.627)	70.013 (73.534)	70.013 (73.534)
CHAINAGE	0.000	8.515	2.746	5.520	5.520	5.520

LINE 503

STRUCTURE NAME	1/506	2/506	3/506	4/506	5/506	TE/506
STRUCTURE DESCRIPTION	IPWEA MANHOLE 1050mm DIA	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1050mm DIA	IPWEA MANHOLE 1200mm DIA	EXISTING PIPE END




PIPE SIZE (mm)	375	375	375	450	450
PIPE CLASS	2	2	2	2	2
PIPE GRADE (%)	2.36%	1.30%	0.67%	0.55%	0.42%
PIPE SLOPE (1 in X)	42.4	76.9	149.5	181.0	239.9
FULL PIPE VELOCITY (m/s)	0.09	0.27	0.93	0.99	1.60
PART FULL VELOCITY (m/s)	1.16	1.31	1.41	1.46	1.60
PIPE FLOW (cumecs)	0.010	0.030	0.102	0.157	0.254
PIPE CAPACITY AT GRADE (cumecs)	0.269	0.200	0.143	0.212	0.184
DATUM RL	53.0				

WSE IN STRUCTURE	69.053	68.916	68.889	68.649	68.423	68.259
HGL IN PIPE	69.053	68.916	68.889	68.649	68.423	68.259
DEPTH OF INVERT BELOW FSL	1.136	1.433	1.379	1.456	1.487	1.484
INVERT LEVEL	68.983	68.540	68.302	68.239	68.175	68.175
FINISHED (& EXISTING) SURFACE LEVEL	70.119 (69.839)	69.973 (70.468)	69.681 (70.961)	69.695 (71.215)	69.304 (72.835)	69.212 (72.979)
CHAINAGE	0.000	18.804	16.709	35.513	64.62	123.223

LINE 506

STRUCTURE NAME	1/513	4/506	1/514	5/506
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1050mm DIA	IPWEA KERB INLET L.L.I.; 2.4m Lintel	IPWEA MANHOLE 1200mm DIA



PIPE SIZE (mm)	375	375	375	375
PIPE CLASS	2	2	2	2
PIPE GRADE (%)	1.00%	1.00%	1.00%	1.00%
PIPE SLOPE (1 in X)	100.0	100.0	100.0	100.0
FULL PIPE VELOCITY (m/s)	0.50	0.37	0.37	0.37
PART FULL VELOCITY (m/s)	1.40	1.29	1.29	1.29
PIPE FLOW (cumecs)	0.055	0.041	0.041	0.041
PIPE CAPACITY AT GRADE (cumecs)	0.175	0.175	0.175	0.175
DATUM RL	53.0	54.0	54.0	54.0

WSE IN STRUCTURE	68.855	68.649	68.490	68.423
HGL IN PIPE	68.713	68.649	68.423	68.423
DEPTH OF INVERT BELOW FSL	1.115	1.211	1.115	1.115
INVERT LEVEL	68.543	68.484	68.144	68.088
FINISHED (& EXISTING) SURFACE LEVEL	69.658 (71.347)	69.695 (71.215)	69.259 (73.012)	69.304 (72.835)
CHAINAGE	0.000	5.839	5.536	5.536

LINE 513


**FOR CONSTRUCTION**

05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB
DATE	REV	DESCRIPTION	REC	APP



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au


DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**STORMWATER DRAINAGE LONG SECTIONS - SHEET 1 OF 2**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C410**  
 REV  
**B**

STRUCTURE NAME	1/515	5/506
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA MANHOLE 1200mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	0.99%
PIPE SLOPE (1 in X)	101.5
FULL PIPE VELOCITY (m/s)	0.58
PART FULL VELOCITY (m/s)	1.46
PIPE FLOW (cumecs)	0.065
PIPE CAPACITY AT GRADE (cumecs)	0.174
DATUM RL	54.0

WSE IN STRUCTURE	68.592	68.423
HGL IN PIPE	68.423	68.423
DEPTH OF INVERT BELOW FSL	1.130	1.211
INVERT LEVEL	68.139	68.093
FINISHED (& EXISTING) SURFACE LEVEL	69.269 (71.688)	69.304 (71.835)
CHAINAGE	0.000	4.699

LINE 515

1/524	2/524	3/524	4/524	TE/524
IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA KERB INLET L.I.L., 2.4m Lintel	EXISTING PIPE END




PIPE SIZE (mm)	375	375	375	450
PIPE CLASS	2	2	2	2
PIPE GRADE (%)	3.40%	3.19%	4.33%	4.91%
PIPE SLOPE (1 in X)	29.4	31.4	23.1	20.4
FULL PIPE VELOCITY (m/s)	0.08	0.56	1.24	1.34
PART FULL VELOCITY (m/s)	1.26	2.21	3.07	3.58
PIPE FLOW (cumecs)	0.009	0.062	0.137	0.213
PIPE CAPACITY AT GRADE (cumecs)	0.323	0.313	0.365	0.632
DATUM RL	54.0			

WSE IN STRUCTURE	69.973	69.717	68.700	66.564
HGL IN PIPE	69.970	69.717	68.700	66.564
DEPTH OF INVERT BELOW FSL	1.344	1.415	1.249	1.400
INVERT LEVEL	69.905	69.463	68.307	66.139
FINISHED (& EXISTING) SURFACE LEVEL	71.249 (76.051)	70.878 (76.384)	69.577 (75.851)	67.551 (70.819)
CHAINAGE	0.000	12.981	35.000	47.981

LINE 524

1/525	3/524
IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA KERB INLET L.I.L., 2.4m Lintel




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.33
PART FULL VELOCITY (m/s)	1.25
PIPE FLOW (cumecs)	0.036
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	56.0

WSE IN STRUCTURE	68.753	68.700
HGL IN PIPE	68.699	68.700
DEPTH OF INVERT BELOW FSL	1.237	1.115
INVERT LEVEL	68.562	68.461
FINISHED (& EXISTING) SURFACE LEVEL	69.799 (76.010)	69.577 (75.851)
CHAINAGE	0.000	10.066

LINE 525

1/526	4/524
IPWEA KERB INLET L.I.L., 2.4m Lintel	IPWEA KERB INLET L.I.L., 2.4m Lintel



PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	3.00%
PIPE SLOPE (1 in X)	33.3
FULL PIPE VELOCITY (m/s)	0.86
PART FULL VELOCITY (m/s)	2.43
PIPE FLOW (cumecs)	0.095
PIPE CAPACITY AT GRADE (cumecs)	0.304
DATUM RL	52.0

WSE IN STRUCTURE	67.376	67.113
HGL IN PIPE	67.149	67.113
DEPTH OF INVERT BELOW FSL	1.398	1.390
INVERT LEVEL	66.536	66.162
FINISHED (& EXISTING) SURFACE LEVEL	67.934 (71.968)	67.551 (70.819)
CHAINAGE	0.000	12.487

LINE 526


**FOR CONSTRUCTION**

05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB
DATE	REV	DESCRIPTION	REC	APP



**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
 PATRICK BRADY  
 RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**STORMWATER DRAINAGE LONG SECTIONS - SHEET 2 OF 2**


JOB CODE  
**MIR009-01**

SHEET NUMBER  
**C411**

REV  
**B**

**STORMWATER DRAINAGE NOTES**

- ALL STORMWATER DRAWINGS ARE TO BE READ IN CONJUNCTION WITH DRAWING C001, STORMWATER LAYOUT PLANS, NOTES AND DETAILS.
- STORMWATER PITS ARE TO BE CONSTRUCTED INSITU IN ACCORDANCE WITH DRAWINGS OR AS VARIED AS NOTED ON THE DRAWING. PREFABRICATED STORMWATER PITS CAN BE USED SUBJECT TO WRITTEN APPROVAL FROM THE SUPERINTENDENT. CLASS D HEAVY DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN TRAFFIC AREAS, CLASS B LIGHT DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN LANDSCAPE AREAS UNLESS NOTED OTHERWISE.
- ALL DRAINAGE EXCAVATION AND CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3500 AND THE APPLICABLE LOCAL AUTHORITY SPECIFICATIONS AND STANDARD DETAILS.
- ALL MATERIALS SHALL MEET THE REQUIREMENTS OF AS1254 & AS1273.
- ALL uPVC PIPES SHALL BE CLASS 'SN8' FOR DN150 & DN225, AND CLASS 'SN6' FOR DN100 UNLESS NOTED OTHERWISE.
- PIPES SHALL BE LAID AT MIN. 1% GRADE UNLESS NOTED OTHERWISE.
- CONTRACTOR MUST VERIFY THAT ALL PIPE LEVELS AND GRADES CAN BE ACHIEVED PRIOR TO CONSTRUCTING DRAIN LINES. ANY CONFLICT SHALL BE REPORTED TO THE SUPERINTENDENT FOR ANY NECESSARY ALTERATIONS PRIOR TO ANY CONSTRUCTION OF CONNECTING PIPEWORK.
- WHERE PIPES ARE TO BE LAID WITHIN THE ZONE OF INFLUENCE OF STRUCTURAL LOADINGS (e.g. BUILDING FOOTINGS, RETAINING WALLS...etc). THE BUILDER SHALL PROVIDE ADEQUATE BRIDGING / PROTECTION. WHERE ANY DOUBT MAY EXIST REFERENCE SHALL BE MADE TO THE DESIGNER OF THE STRUCTURE.
- BENCHING OF PIT STRUCTURES SHALL HAVE A SMOOTH FINISHED SURFACE, AND PIPES SHALL NOT PROJECT INSIDE THE SHAFT OF THE PIT.
- WHERE RECTANGULAR PIT STRUCTURES ARE USED, PIPES MUST NOT CONNECT TO THE PIT AT CORNERS.
- ALL CONSTRUCTION AND EXCAVATIONS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT REQUIREMENTS OF THE WORK HEALTH AND SAFETY ACT 2011 AND SUBSEQUENT AMENDMENTS.
- ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION.
- ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
- ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- INSTALL 150mm DIAMETER PVC ROOFWATER HOUSE CONNECTION STUB INTO ROOFWATER PITS. INSTALL AT 750mm DEPTH TYPICAL OR 50mm FROM THE BASE OF PIT (WHICHEVER IS SHALLOWER).




**TYPICAL ROOFWATER KERB ADAPTOR OUTLET DETAIL**  
N.T.S.

**REFERENCE POINT LOCATION FOR DRAINAGE STRUCTURES**


STRUCTURE TYPE	HORIZONTAL CONTROL POINT [REFERENCE POINT LOCATION]	VERTICAL CONTROL REFERENCE LEVEL
MANHOLE	CENTRELINE OF MAIN SHAFT	FINISHED SURFACE LEVEL AT CENTRE OF MAIN SHAFT
GULLY PIT OVER MANHOLE	CENTRE OF GULLY PIT	LIP LEVEL
GULLY PIT (LIP IN LINE)	CENTRE OF GULLY PIT	LIP LEVEL
HEADWALL	INTERSECTION OF HEADWALL FACE AND PIPE CENTRE LINE	INVERT LEVEL
FIELD INLET	CENTRE OF PIT	TOP OF CONCRETE PIT
ROOFWATER PIT	CENTRE OF PIT	TOP OF GRATE

**EXCAVATION IN ROCK NOTE:**  
CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

**TRENCH SPOIL NOTE:**  
SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.



**TYPICAL ROOFWATER PROPERTY PIT TO KERB ADAPTOR OUTLET DETAIL**  
N.T.S.



**TYPICAL DETAIL**  
GRATED PIT IN CONCRETE PAVEMENT  
SCALE 1:20

FOR CONSTRUCTION				
DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
05/09/2021	A	ORIGINAL ISSUE	KK	PB


**Premise**  
BRISBANE OFFICE  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
**PATRICK BRADY**


SCALE  
NTS  
ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC GROUP**  
PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
LOCATION  
**TEVIOT ROAD, GREENBANK**  
SHEET TITLE  
**STORMWATER DRAINAGE NOTES AND DETAILS**

JOB CODE  
**MIR009-01**  
SHEET NUMBER  
**C420**  
REV  
**B**



5/506  
IPWEA MANHOLE  
1200mm DIA



5/502  
IPWEA MANHOLE  
1050mm DIA


**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB



**BRISBANE OFFICE**  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
*Patrick Brady*  
**PATRICK BRADY** RPEQ 7112



CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**STORMWATER DRAINAGE NOTES AND DETAILS**

JOB CODE  
**MIR009-01**

SHEET NUMBER	REV
<b>C430</b>	<b>B</b>








# EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT

## TEVIOT ROAD, GREENBANK

### FOR MIRVAC QLD PTY LTD

#### SEWERAGE



### LOCALITY PLAN

#### REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844  
 LOT 9 on S312355

NAME OF ESTATE	EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT	
SUBDIVIDER	Mirvac QLD Pty Ltd	
APPLICATION No.	-	
SP DELEGATE APPROVAL DATE	-	
COUNCIL DA APPROVAL No.	-	
DRAWING/PLAN No.	C510	
No. OF ALLOTMENTS	63	
AREA ha	3.64	
LENGTH OF SEWERS	DN150 uPVC SN8	845m
	DN225 uPVC SN8	

SHEET LIST TABLE	
SHEET NO.	SHEET TITLE
C500	SEWERAGE LOCALITY PLAN & NOTES
C510	SEWERAGE LAYOUT PLAN
C520	SEWERAGE LONG SECTIONS - SHEET 1 OF 3
C521	SEWERAGE LONG SECTIONS - SHEET 2 OF 3
C522	SEWERAGE LONG SECTIONS - SHEET 3 OF 3
C530	SEWERAGE NOTES AND DETAILS

#### GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND SEWERAGE CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- THE CONSTRUCTION OF THE SEWERAGE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. SEWERAGE WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER SEWERAGE SYSTEM.
- ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE CONTRACTOR UNDER LOGAN WATER SUPERVISION AT THE DEVELOPER'S COST.
- ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE "ACCEPTED PRODUCTS AND MATERIALS" LIST.
- EACH ALLOTMENT SHALL BE SERVED BY A DN100 PROPERTY CONNECTION. FOR ALLOTMENTS OTHER THAN SINGLE RESIDENTIAL, A DN150 PROPERTY CONNECTION SHALL BE PROVIDED.
- PROPERTY CONNECTIONS SHALL BE LOCATED WITHIN THE PROPERTY AS SHOWN IN THE DRAWINGS.
- PROPERTY CONNECTION BRANCHES SHALL EXTEND INTO THE PROPERTY A MINIMUM OF 300mm AND A MAXIMUM OF 750mm.
- WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE CARRIED OUT IN LAYERS NOT EXCEEDING 300mm (LOOSE) IN DEPTH AND SHALL BE COMPACTED UNTIL THE COMPACTION IS NOT LESS THAN 95% OF THE MATERIALS MAXIMUM COMPACTION WHEN TESTED IN ACCORDANCE WITH A.S. 1289 (MODIFIED COMPACTION). TESTING SHALL BE CARRIED OUT AFTER EACH ALTERNATE LAYER. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED SEWERS WILL NOT BE ISSUED BY THE SEQ SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED.
- WHERE SEWERS HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SEQ SEWER CODE.
- THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
- SEWERS SHALL BE DISUSED /ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ SEWER CODE.
- BENCH MARK AND LEVELS TO AHD.
- REFER TO BULK EARTHWORKS DRAWINGS FOR FINISHED SURFACE LEVELS.
- ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT. FOR INFORMATION PHONE: 1300 369 915.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS TO ALLOW CONSTRUCTION OF THE SEWER SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE FOR EXCAVATION AND SAFE SHORING TO ALLOW SEWER MAINTENANCE SECTION TO CARRY OUT LIVE SEWER WORK.
- CONSTRUCT TRENCHES TO SEQ-SEW-1200-2, WITH EMBEDMENT TYPE 3 SUPPORT MINIMUM TO SEQ-SEW-1201-1, AND ROAD CROSSINGS TO SEQ-SEW-1205-1 AND LCC STANDARDS.
- CONSTRUCT PROPERTY CONNECTIONS TO SEQ-SEW-1100 SERIES.
- CONSTRUCT MAINTENANCE STRUCTURES TO SEQ-SEW-1300 SERIES.
- CONSTRUCT BULKHEADS TO SEQ-SEW-1206-1.
- INSTALL DETECTABLE MARKER TAPE ON ALL MAINS AND PROPERTY CONNECTIONS.
- CALCAREOUS CONCRETE IN MAINTENANCE HOLES REQUIRED IN ACCORDANCE WITH SEQ WS&S D&C CODE REQUIREMENTS.
- CCTV OF SEWER TO BE UNDERTAKEN AND SUPPLIED TO SUPERINTENDENT PRIOR TO, BUT NO GREATER THAN 2 WEEKS BEFORE, THE ON-SITE INSPECTION FOR OFF MAINTENANCE.

#### VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST

#### SOIL

- TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.
- IF ACID SULPHATE SOILS EXIST IN THE WORKS AREA, ACID SULPHATE SOILS ARE TO MANAGED IN ACCORDANCE WITH AN APPROVED ACID SULPHATE SOIL MANAGEMENT PLAN.

#### CREEK CROSSINGS

- SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

#### REHABILITATION

- PREDISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- PREDISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED.

#### SAFETY

- THE DESIGN AND CONSTRUCTION OF THE WORKS SHALL COMPLY WITH ALL QUEENSLAND LEGISLATION.

#### INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORKPLACE HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 369 915

CONTACT "DIAL BEFORE YOU DIG" ON 1100 FOR LOCATION OF EXISTING PUBLIC SERVICES PRIOR TO EXCAVATION.

#### TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

#### EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

#### FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
07/05/2021	A	ORIGINAL ISSUE	KK	

**Premise**  
 BRISBANE OFFICE  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au



DESIGNED  
K KIWANG  
 CHECKED  
A LANGDON  
 PROJECT MANAGER  
S STEINHOFER  
 PROJECT DIRECTOR  
  
 PATRICK BRADY RPEQ 7112

SCALE  
  
 SCALE 1:10000 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**SEWERAGE LOCALITY PLAN & NOTES**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C500**  
 REV  
**B**





**LEGEND - PROPOSED**

- GRAVITY SEWER
- Ø100mm PROPERTY CONNECTION, 7.5m OFFSET FROM SIDE BODY WITH DWAY, 1.2m OFFSET FROM SIDE BODY WITHOUT DWAY, TYPICAL U.N.O.
- MAINTENANCE STRUCTURE
- PROPOSED MAINTENANCE HOLE OR MAINTENANCE SHAFT NUMBER. REFER LONG SECTION DRAWINGS FOR STRUCTURE DETAILS.
- HORIZONTAL BEND (3m RADIUS).
- 38** LOT NUMBER
- STORMWATER DRAINAGE
- DRINKING WATER MAIN
- ELECTRICAL (PROPOSED)
- FINISHED CONTOURS (0.50m)
- ZERO LOT LINE
- FUTURE DRIVEWAY LOCATION
- PROPOSED RETAINING WALL
- PROPOSED CONCRETE FOOTPATH & KERB RAMP
- STAGE BOUNDARY

**LEGEND - EXISTING**

- Ø100mm EXISTING PROPERTY CONNECTION
- STORMWATER DRAINAGE
- GRAVITY SEWER
- SEWER RISING MAIN
- SEWER TRUNK MAIN
- DRINKING WATER MAIN
- EXISTING CONTOURS (0.50m)

PROPERTY CONNECTIONS HAVE BEEN DESIGNED TO CONTROL THE REQUIRED SERVICE AREA OF EACH LOT AT A GRADE OF 1:60 AND A MAXIMUM DEPTH TO INVERT OF PROPERTY CONNECTION AT 1.5m, UNLESS OTHERWISE STATED.

ALL PROPERTY CONNECTIONS DIA 100 PVC UNLESS OTHERWISE DENOTED.

FOR SEWERAGE RETICULATION NOTES REFER DWG No. C500.

CONTRACTOR TO ENSURE THAT ALL SLOPED PROPERTY CONNECTIONS LOCATED AT REAR OF LOTS SHALL TERMINATE AT SHORTEST LENGTH POSSIBLE FROM THE JUNCTION WITH THE SEWER MAIN.

CONTRACTOR TO CONSTRUCT PROPOSED SEWER MANHOLES WITH SUFFICIENT NECK HEIGHT SHOULD FUTURE LAND OWNER REQUIRE ADJUSTMENT TO LID LEVEL TO SUIT POTENTIAL DRIVEWAY.

**EXISTING HOUSE CONNECTION DETAILS**

LOT #	INVERT LEVEL	DEPTH
3001	68.066	1.250
3025	68.853	1.250
3040	68.843	1.250
3041	68.426	1.250
3042	68.009	1.250
3043	67.529	1.250
3044	64.773	1.250
3065	65.158	1.250
3066	64.341	1.250

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REVISIONS	REC	APP
05/11/2021	C	ISSUED FOR CONSTRUCTION		KK	PB
03/09/2021	B	REMOVED PLAN SEALING HATCH ON PRECINCT 9.1B AND 9.1C, ADDED ELECTRICAL		KK	PB
07/05/2021	A	ORIGINAL ISSUE		KK	PB

**Premise**

**BRISBANE OFFICE**  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
K KIWANG

CHECKED  
A LANGDON

PROJECT MANAGER  
S STEINHOFER

PROJECT DIRECTOR  
PATRICK BRADY

RPEQ 7112

SCALE

SCALE 1:500 (A1)

ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**SEWERAGE LAYOUT PLAN**

JOB CODE  
**MIR009-01**

SHEET NUMBER  
**C510**

REV  
**C**





MAINTENANCE HOLE / SHAFT NO.

MH / MS COVER TYPE	B
MH / MS TYPE	HTP
MH DROP TYPE	V
LINE NO.	28
PROPERTY CONNECTION DEPTH	1.250
PROPERTY CONNECTION INVERT LEVEL	70.923
PROPERTY CONNECTION TYPE	B
LOT NO.	3031

	6/28	7/28
	TE1/30	1/30
	2/30	
	B	B
	J	J
	V	V
	30	
	1.250	
	68.074	
	B	
	3024	

	TE1/31	3/31
	B	B
	J	J
	V	V
	1.250	
	69.275	
	B	
	3026	

	9/24	E/33
	B	B
	A	A
	V	V
	33	24
	1.350	1.400
	68.775	68.826
	B	B
	3009	3010

	10/24	1/34	2/34
	B	B	B
	A	J	J
	V	V	V
	34	24	34
	1.250	1.250	1.250
	68.827	69.173	69.552
	B	B	B
	3016	3017	3018

	TE1/40	2/40
	B	B
	J	J
	V	V
	1.250	1.250
	65.874	66.385
	B	B
	3064	3065

LEGEND

RR DENOTES ROAD RESERVE  
PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.00
B	CONCRETE MANHOLE 1.20
C	CONCRETE MANHOLE 1.50
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
HB	HORIZONTAL BEND (3m HORIZ. RADIUS)
HTP	HORIZONTAL BEND TANGENT POINT

LID TYPES	
B	CLASS B NON TRAFFICABLE CONCRETE IN FILL
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CONCRETE IN FILL

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL
D(E)	TYPE D - EXTENDED VERTICAL REFER DWG C530

- NOTES:
- EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
  - DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

DATUM RL	61.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	100 85
LENGTH	86.154 21.403
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.529 2.673 2.643 2.642
INVERT LEVEL (IL)	69.602 70.464 70.494 70.745
FINISHED SURFACE LEVEL (FSL)	72.132 73.137 70.494 73.587
EXISTING SURFACE LEVEL (ESL)	73.867 76.885 77.670
CHAINAGE (CH)	TP 141.536 227.710 249.113

DATUM RL	58.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	100 100
LENGTH	10.548 55.297
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.278 2.235 2.215 2.002
INVERT LEVEL (IL)	66.983 67.088 67.108 67.661
FINISHED SURFACE LEVEL (FSL)	69.261 69.324 73.179 69.663
EXISTING SURFACE LEVEL (ESL)	72.891 73.179 74.188 72.171
CHAINAGE (CH)	0.000 10.548 65.845

DATUM RL	59.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	57
LENGTH	54.297
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.581
INVERT LEVEL (IL)	67.555 68.501
FINISHED SURFACE LEVEL (FSL)	70.136 71.083
EXISTING SURFACE LEVEL (ESL)	73.541 74.188
CHAINAGE (CH)	0.000 54.297

DATUM RL	56.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	34
LENGTH	23.500
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.597 2.567 2.000
INVERT LEVEL (IL)	67.498 67.528 68.226
FINISHED SURFACE LEVEL (FSL)	70.095 70.226 70.226
EXISTING SURFACE LEVEL (ESL)	70.299 69.551
CHAINAGE (CH)	0.000 23.500

DATUM RL	58.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	99 40
LENGTH	12.927 43.000
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.224 2.144 2.054 2.034 2.048
INVERT LEVEL (IL)	67.812 67.892 68.023 68.043 69.131
FINISHED SURFACE LEVEL (FSL)	70.037 70.077 70.077 68.043 71.179
EXISTING SURFACE LEVEL (ESL)	70.791 71.380 70.077 72.888
CHAINAGE (CH)	0.000 12.927 55.927

DATUM RL	57.000
PROPERTY DESCRIPTION	RR
PIPE SIZE (mm), CLASS	DN150 uPVC SN8
GRADE (1 IN X)	21
LENGTH	109.200
EMBEDMENT TYPE	TYPE 3
DEPTH OF INVERT BELOW FSL	2.485
INVERT LEVEL (IL)	65.974 69.271
FINISHED SURFACE LEVEL (FSL)	66.460 71.182
EXISTING SURFACE LEVEL (ESL)	67.575 76.411
CHAINAGE (CH)	0.000 109.200

**HORIZONTAL BEND NOTE:**  
DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).

**PROPERTY CONNECTION NOTE:**  
CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.

**MANHOLE COVER NOTE:**  
ALL MANHOLE COVERS IN VERGE WITHOUT FOOTPATH TO HAVE CONCRETE SURROUND.

FOR CONSTRUCTION

05/11/2021	C	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	B	AMENDMENT TO NOTES AND ADDED MANHOLE COVER NOTE	KK	PB
07/05/2021	A	ORIGINAL ISSUE	KK	
DATE	REV	DESCRIPTION	REC	APP

**Premise**  
BRISBANE OFFICE  
LEVEL 1, 100 BRUNSWICK STREET  
PO BOX 361  
FORTITUDE VALLEY, QLD 4006  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
K KIWIANG  
CHECKED  
A LANGDON  
PROJECT MANAGER  
S STEINHOFER  
PROJECT DIRECTOR  
PATRICK BRADY  
RPEQ 7112

SCALE  
HORIZONTAL 1:1000 (A1)  
VERTICAL 1:100 (A1)  
ORIGINAL SHEET SIZE A1

CLIENT  
MIRVAC QLD PTY LTD  
PROJECT  
EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
LOCATION  
TEVIOT ROAD, GREENBANK  
SHEET TITLE  
SEWERAGE LONG SECTIONS - SHEET 2 OF 3

JOB CODE  
MIR009-01  
SHEET NUMBER  
C521  
REV  
C




**LIVE SEWER WORKS**


No.	DESCRIPTION	DIA. SEWER	MH NO.	MH TYPE	COVER TYPE	LOT NO.	F.S.L.	E.S.L.	I.L.	DEPTH
1(A)	0.5m FROM STUB END CAP TE2/24, CONSTRUCTOR TO LAY NEW LINE 24. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE2/24	END	-	3001	69.322	72.869	66.766	2.556
1(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 24 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
2(A)	0.5m FROM STUB END CAP TE1/30, CONSTRUCTOR TO LAY NEW LINE 30. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/30	END	-	3001	69.261	72.891	66.983	2.278
2(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 30 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
3(A)	0.5m FROM STUB END CAP TE1/31, CONSTRUCTOR TO LAY NEW LINE 31. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/31	END	-	3025	70.136	73.541	67.555	2.581
3(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 31 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
4(A)	0.5m FROM STUB END CAP TE2/28, CONSTRUCTOR TO LAY NEW LINE 28. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE2/28	END	-	3040	70.126	73.446	67.864	2.262
4(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 28 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
5(A)	0.5m FROM STUB END CAP TE3/42, CONSTRUCTOR TO LAY NEW LINE 42. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE3/42	END	-	3044	66.074	66.499	63.458	2.617
5(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 42 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
6(A)	0.5m FROM STUB END CAP TE1/40, CONSTRUCTOR TO LAY NEW LINE 40. AFTER CLEANSING, TESTING AND INSPECTING, NOTIFY AGENCY.	150	TE1/40	END	-	3065	66.460	67.575	63.974	2.485
6(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 40 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									

LEVELS IN THE LIVE SEWER TABLE ARE DESIGN LEVELS. AS CONSTRUCTED INFORMATION TO BE ADDED WHEN AVAILABLE.


CONSULTING ENGINEERS ARE TO CONTACT PRIOR TO COMMENCEMENT OF CONSTRUCTION TO ARRANGE FOR THIS WORK TO BE CARRIED OUT. (EXCAVATION, SAFE-SHORTING AND ASSOCIATED WORK BY CONTRACTOR). EXCAVATION WORKS CARRIED OUT BY CONTRACTORS AT DEPTH OF 1.5m OR GREATER MUST PROVIDE A "SAFE WORK PLAN" AS PER WORKPLACE HEALTH AND SAFETY LEGISLATION TO SEQ-SPS PRIOR TO SEQ-SPS COMMENCING ANY WORK. IT IS THE DEVELOPER'S RESPONSIBILITY TO ENSURE ALL LIVE SEWER WORKS ARE COMPLETE BEFORE ALLOWING PRIVATE DRAINAGE TO BE CONNECTED.




**EXTENDED PROPERTY CONNECTION WHERE PROPERTY CONNECTION CROSSES RETAINING WALL OR DN200 OR LARGER WATERMAIN - TYPE D (E)**



**SEWER LINE CROSSING CONCRETE SLEEPER RETAINING WALL BRIDGING SLAB DETAIL**




**TYPICAL MAINTENANCE STRUCTURE IN CONCRETE FOOTPATH DETAIL**




**CONCRETE STORMWATER SUPPORT TYPICAL DETAIL**

- GENERAL CONCRETE STORMWATER SUPPORT NOTES:**
- SUPPORTS TO BE INSTALLED WHERE STORMWATER PIPE DIAMETER IS EQUAL TO OR GREATER THAN 600mm.
  - 3m MAX DEPTH OF CONCRETE STORMWATER SUPPORT 'D'
  - DESIGN BASED ON ACHIEVING 100kPa OF ULTIMATE LIMIT STATE BEARING CAPACITY. TO BE CONFIRMED BY CONTRACTOR DURING CONSTRUCTION.
  - 0.300m\* WIDTH UP TO 1050 RCP CLASS 2
  - 0.500m\* WIDTH BETWEEN 1050 AND 1800 RCP CLASS 2


- CONCRETE STORMWATER SUPPORT IN ROCK NOTES**
- WHERE BRIDGING STRUCTURE IS LOCATED IN ROCK SUBGRADE, CONTRACTOR SHALL PROVIDE GEOTECHNICAL ADVICE TO SUPERINTENDENT ADVISING IF SUITABLE SUBGRADE BEARING CAPACITY CAN BE ACHIEVED TO FACILITATE THIS SUPPORT TYPE.



**ELEVATION**



**SERVICE LINE CROSSING BOULDER OR BLOCK RETAINING WALL BRIDGING SLAB DETAIL**



**CONCRETE STORMWATER SUPPORT IN ROCK SUBGRADE DETAIL**

STRUCTURAL DETAILS APPROVED DATE  
 05/11/2021  
 BRIONY HOOPER RPEQ 10854

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	C	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	B	AMENDED LIVE SEWER WORKS NUMBERS	KK	PB
07/05/2021	A	ORIGINAL ISSUE	KK	PB

**Premise**

**BRISBANE OFFICE**  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
 CHECKED  
**A LANGDON**  
 PROJECT MANAGER  
**S STEINHOFER**  
 PROJECT DIRECTOR  
**Patrick Brady**  
 RPEQ 7112

SCALE  
 0 0.8 1.6 2.4m  
 SCALE 1:40 (A1)  
 0 0.4 0.8 1.2m  
 SCALE 1:20 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION  
**TEVIOT ROAD, GREENBANK**

SHEET TITLE  
**SEWERAGE NOTES AND DETAILS**

JOB CODE  
**MIR009-01**

SHEET NUMBER  
**C530**


REV  
**C**



# EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT

## TEVIOT ROAD, GREENBANK FOR MIRVAC QLD PTY LTD

### WATER RETICULATION



#### LOCALITY PLAN

#### REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844  
LOT 9 on S312355

#### SHEET LIST TABLE

SHEET NO.	SHEET TITLE
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C610	WATER RETICULATION LAYOUT PLAN
C611	WATER RETICULATION LIVE CONNECTION DETAILS

#### GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- ADOPT LIP OF KERB OR SHOULDER OF ROAD AS PERMANENT LEVEL. COVER OF MAIN FROM PERMANENT LEVEL TO BE AS SHOWN IN SEQ-WAT-1200-2.
- CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD DRAWINGS.
- ALL MATERIALS USED IN THE WORKS SHALL COMPLY WITH SEQ-SP'S ACCEPTED PRODUCTS AND MATERIALS LIST OR BE APPROPRIATELY SHOWN, LISTED AND DEFINED IN THE ENGINEERING SUBMISSION SO THAT THE ALTERNATIVE PRODUCT OR MATERIAL CAN BE ASSESSED AND IF APPROPRIATE, APPROVED BY SEQ-SP'S
- ALL CONCRETE FOOTPATHS TO BE CLEAR OF WATER MAINS, WHERE POSSIBLE
- CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT TO THE RETICULATION SYSTEM.
- ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128.
- CONSTRUCT THRUST BLOCKS ON ALL BENDS, TEES, TAPERS AND DEAD ENDS IN ACCORDANCE WITH SEQ-WAT-1205-1, AND SEQ-WAT-1206-1.
- CONSTRUCT TRENCHES IN ACCORDANCE WITH SEQ-WAT-1200-2, PIPE EMBEDMENT TO SEQ-WAT-1201-1 (TYPE C SUPPORT) AND ROAD CROSSINGS TO SEQ-WAT-1204-1 AND LCC STANDARDS.
- INSTALL SCOURS IN ACCORDANCE WITH SEQ-WAT-1307-3.
- INSTALL DETECTABLE MARKER TAPE ON ALL WATER MAINS AND PROPERTY SERVICES.
- INSTALL HYDRANTS IN ACCORDANCE WITH SEQ-WAT-1302-1, SEQ-WAT-1303-1
- INSTALL PAVEMENT MARKERS IN ACCORDANCE WITH SEQ-WAT-1300-1 & 2.

#### VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED, IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST.

#### SOIL

- TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.

#### CREEK CROSSINGS

- SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

#### REHABILITATION

- PRE-DISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- PRE-DISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED, ALL DISTURBED AREAS ASSOCIATED WITH CONSTRUCTION SHALL BE REHABILITATED, HEAVILY COMPACTED AREAS SHOULD BE RIPPED PRIOR TO TREATMENT.
- ALL DISTURBED AREAS ARE TO BE LEFT IN STABLE CONDITION.
- ALL PLANTING/RE-VEGETATION WILL NEED TO BE MAINTAINED THROUGHOUT THE MAINTENANCE PERIOD.

#### CONSTRUCTION REQUIREMENTS

- LIVE WATER CONNECTIONS TO BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH A VALID NETWORK ACCESS PERMIT UNDER LOGAN WATER SUPERVISION AT DEVELOPERS EXPENSE AT LOCATION MARKED.
- PRIOR TO ANY EXCAVATION, CONTRACTOR IS TO LOCATE ACTUAL POSITIONS OF PUBLIC SERVICE UTILITIES BY POT HOLES.
- UPON COMPLETION OF ALL WORKS, CONTRACTORS SHALL SUPPLY THE SUPERVISING RPEQ DETAILED "AS CONSTRUCTED" INFORMATION OF THE WORK. "AS CONSTRUCTED" INFORMATION SHALL COMPLY WITH CURRENT SEQ CODE OR LOCAL AUTHORITY STANDARDS FOR PLAN AND DIGITAL INFORMATION.
- CONTRACTOR IS TO BE RESPONSIBLE FOR ARRANGING ALL LOGAN WATER CONNECTIONS AND PAYMENTS OF CONNECTION FEES.

#### TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

#### EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

#### INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

#### RPEQ CERTIFICATION

THE CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO LOGAN WATER RETICULATION SYSTEM. ALL RPEQ CERTIFIED DRAWINGS COMPLY WITH SEQ CODE AND LOGAN WATER REQUIREMENTS.

#### INSPECTION REQUIREMENTS

PRIOR TO COMMENCEMENT OF WORKS, CONTACT PREMISE (07) 3253 2222 AND LOGAN WATER TO CONFIRM INSPECTION REQUIREMENTS INCLUDING LIVE CONNECTIONS.

A MINIMUM 48 HOURS NOTICE IS REQUIRED.

INSPECTIONS ARE REQUIRED TO BE ORGANIZED WITH PREMISE AND LOGAN WATER. ANY COSTS ASSOCIATED WITH ENGAGING LOGAN WATER TO UNDERTAKE INSPECTIONS OUTSIDE OF THE FEE PAID SHALL BE BORNE BY THE CONTRACTOR.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128

#### SEQ CODE STD DRAWING SCHEDULE

SOIL CLASSIFICATION	SEQ-WAT-1200-1
EMBEDMENT AND TRENCH FILL	SEQ-WAT-1200-2
THRUST BLOCK DETAILS	SEQ-WAT-1205-1
VALVE THRUST BLOCKS	SEQ-WAT-1206-1
IDENTIFICATION MARKERS	SEQ-WAT-1300-1,2



#### FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
07/05/2021	A	ORIGINAL ISSUE	KK	





**BRISBANE OFFICE**  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
CHECKED  
**A LANGDON**  
PROJECT MANAGER  
**S STEINHOFER**  
PROJECT DIRECTOR  
*[Signature]*  
**PATRICK BRADY** RPEQ 7112

SCALE  
0 200 400 600m  
SCALE 1:10000 (A1)  
ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC QLD PTY LTD**  
PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
LOCATION  
**TEVIOT ROAD, GREENBANK**  
SHEET TITLE  
**WATER RETICULATION LOCALITY PLAN & NOTES**

JOB CODE  
**MIR009-01**  
SHEET NUMBER  
**C600**  
REV  
**B**



**LEGEND - PROPOSED**

- POTABLE WATERMAIN
- POTABLE WATER RETICULATION CONDUIT
- WATER SERVICES & WATER METER BOX POINT. METER BY OTHERS
- SLUICE VALVE
- FIRE HYDRANT
- TEST POINT
- DEAD END
- DEFLECTION
- TRUNCATIONS 5 DEGREES OR LESS
- LOT NUMBER
- STORMWATER
- GRAVITY SEWER
- SEWER RISING MAIN
- ELECTRICITY
- ZERO LOT BOUNDARY
- PREFERRED DRIVEWAY LOCATION (BY OTHERS)
- SITE BOUNDARY
- PROPOSED RETAINING WALL
- PAD MOUNTED TRANSFORMER

**LEGEND - EXISTING**

- WATER
- SLUICE VALVE
- FIRE HYDRANT
- TEST POINT
- SCOUR BRANCH
- DEAD END
- WATER METER
- STORMWATER
- GRAVITY SEWER
- SEWER RISING MAIN
- ELECTRICAL
- TELSTRA
- GAS

- LIVE CONNECTION NOTES:**
- LIVE CONNECTIONS BY LOGAN WATER
  - LIVE CONNECTION IN ACCORDANCE WITH SEQ-WAT-1303-1
  - THRUST BLOCKS NOT SHOWN FOR CLARITY.
  - PRE-CHLORINATION FITTINGS AS REQUIRED.

**INDEMNITY - EXISTING SERVICES**

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

AS CONSTRUCTED DETAILS FOR AMEND.

I CERTIFY THAT THE 'AS CONSTRUCTED' DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS

SIGNED: \_\_\_\_\_ DATE: \_\_\_\_\_

NAME OF SIGNATORY: \_\_\_\_\_

RPEQ No. or LICENCE: \_\_\_\_\_

COMPANY NAME: \_\_\_\_\_

START DATE: \_\_\_\_\_

**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	REC	APP
05/11/2021	C	ISSUED FOR CONSTRUCTION	KK	PB
15/10/2021	B	UPDATED WATER MAIN SIZE ADJACENT LOTS 3009 & 3010	AL	PB
07/05/2021	A	ORIGINAL ISSUE	KK	PB

**BRISBANE OFFICE**  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED: K KIWANG  
 CHECKED: A LANGDON  
 PROJECT MANAGER: S STEINHOFER  
 PROJECT DIRECTOR: PATRICK BRADY  
 RPEQ 7112

SCALE: 0 10 20 30m  
 SCALE 1:500 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT: **MIRVAC QLD PTY LTD**

PROJECT: **EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**

LOCATION: **TEVIOT ROAD, GREENBANK**




SHEET TITLE: **WATER RETICULATION LAYOUT PLAN**

JOB CODE: **MIR009-01**

SHEET NUMBER: **C610**

REV: **C**






- LIVE CONNECTION NOTES:**
1. LIVE CONNECTIONS BY LOGAN WATER
  2. LIVE CONNECTION IN ACCORDANCE WITH SEQ-WAT-1303-1
  3. THRUST BLOCKS NOT SHOWN FOR CLARITY.
  4. PRE-CHLORINATION FITTINGS AS REQUIRED.

AS CONSTRUCTED DETAILS FOR AMEND.  
I CERTIFY THAT THE 'AS CONSTRUCTED' DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS  
SIGNED: \_\_\_\_\_ DATE: \_\_\_\_\_  
NAME of SIGNATORY: \_\_\_\_\_  
RPEQ No. or LICENCE: \_\_\_\_\_  
COMPANY NAME: \_\_\_\_\_  
START DATE: \_\_\_\_\_

FOR CONSTRUCTION				
DATE	REV	DESCRIPTION	REC	APP
05/11/2021		ISSUED FOR CONSTRUCTION	KK	
07/05/2021	A	ORIGINAL ISSUE	KK	


**Premise**  
BRISBANE OFFICE  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
K KIWANG  
CHECKED  
A LANGDON  
PROJECT MANAGER  
S STEINHOFER  
PROJECT DIRECTOR  
PATRICK BRADY  
RPEQ 7112



CLIENT  
MIRVAC QLD PTY LTD  
PROJECT  
EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
LOCATION  
TEVIOT ROAD, GREENBANK  
SHEET TITLE  
WATER RETICULATION LIVE CONNECTION DETAILS

JOB CODE  
MIR009-01  
SHEET NUMBER  
C611  
REV  
A



**NOTE**  
PRIOR TO FORECAST RAIN EVENTS INSTALL TEMPORARY BERMS, AS REQUIRED BASED ON EARTHWORK LEVELS TO REDUCE SLOPE GRADE AND LENGTH WITHIN LOTS AND ROAD BOX

**LEGEND - PROPOSED**

- EXTENT OF CUT
- EXTENT OF FILL
- GULLY INLET PROTECTION. REFER DETAIL IECA DRAWING ESC-03 FOR DETAILS.
- FIELD INLET PROTECTION. REFER DETAIL IECA DRAWING ESC-02 FOR DETAILS.
- FLOW DIRECTION OR RUNOFF
- MULCH BERM
- SEDIMENT FENCE REFER IECA DRAWING SF-01 & SF-02 FOR DETAILS.
- CLEAN WATER DIVERSION BUND
- DIRTY WATER DIVERSION BUND
- FINISHED MAJOR CONTOURS (0.50m)
- FINISHED MINOR CONTOURS (0.25m)

**LEGEND - EXISTING**

- 12.0 MAJOR CONTOURS (1.00m)
- MINOR CONTOURS (0.50m)
- EXISTING MULCH BUND. BUILT DURING CLEARING AND GRUBBING PHASE
- EXISTING DIRTY WATER DIVERSION BUND. BUILT DURING CLEARING AND GRUBBING PHASE
- VEGETATION CLEARING EXTENT
- EXISTING RETAINING WALL TO PREVENT FLOW TO CONSTRUCTED PRECINCT. CONTRACTOR TO MONITOR DURING EARTHWORKS PHASE

**INSTALLATION SEQUENCE EARTHWORKS**

- STEP 1**  
PERFORM EARTHWORKS ON LEADS CUT TO FILL ON SITE IN ACCORDANCE WITH THE CIVIL EARTHWORKS DRAWINGS.
- STEP 2**  
ONCE FINAL CUT AND FILL BATTER LEVELS HAVE BEEN ACHIEVED, REMOVE REQUIRED TOPSOIL FROM STOCKPILED AREAS AND PLACE ON BATTERS AND OTHER DISTURBED AREAS AS DIRECTED BY THE SITE SUPERINTENDENT.
- STEP 3**  
AS SOON AS POSSIBLE AFTER TOPSOIL HAS BEEN PLACED ON BATTERS AND OTHER DISTURBED AREAS, THESE AREAS SHOULD BE STABILISED PER FINAL DESIGN TREATMENT (REFER DRAWING C701) WITHIN TIMEFRAMES PER 'MAX DAYS TO STABILISATION' BASED ON EROSION RISK (REFER DRAWING C710). IF A RAINFALL EVENT IS FORECAST WHICH IS LIKELY TO CAUSE RUNOFF PRIOR TO DISTURBED OR EXPOSED AREAS BEING STABILISED, A COMBINATION OF MULCH, BINDER OR BIDUM IS TO BE USED TO COVER EXPOSED AREAS. INSTALLATION OF TEMPORARY EROSION CONTROL TO ACTIVE OR INACTIVE WORK AREAS, PRIOR TO RAINFALL EVENTS UNTIL FINAL DESIGN TREATMENT (STABILISATION PER DRAWING C701) IS CRITICAL GIVEN INABILITY TO INSTALL TYPE 1 CONTROLS.
- STEP 4**  
ALL SEDIMENT AND EROSION CONTROL MEASURES ARE TO REMAIN IN PLACE AND BE MONITORED UNTIL CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED. ADDITIONAL EROSION CONTROLS ARE TO BE ERECTED AS REQUIRED BY THE SUPERINTENDENT.

**NOTES**

1. REFER EROSION AND SEDIMENT CONTROL NOTES AND DETAILS DRAWINGS.
2. ALL FOOTPATHS RELEVANT TO PROPOSED SUB-PRECINCT ARE TO BE FULLY TURFED AS SOON AS PRACTICAL.
3. ALL CLEAN AND DIRTY WATER CATCH DRAINS ARE TO HAVE ROCK CHECK DAMS PLACED IN ACCORDANCE WITH IECA STD DWG RCD-01.
4. CONTRACTOR TO ENSURE STORMWATER DRAINAGE IS COVERED AT ALL TIMES DURING EARTHWORKS PHASE.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

*T. Clark*  
TERRY CLARK (CPESC 6089)

FOR CONSTRUCTION			
DATE	REV	DESCRIPTION	REVISIONS
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK PB
03/09/2021	A	ORIGINAL ISSUE	KK PB
			REC APP

**Premise**


**BRISBANE OFFICE**  
LEVEL 11, 300 ADELAIDE STREET  
BRISBANE, QLD 4000  
PH: (07) 3253 2222  
WEB: www.premise.com.au

DESIGNED  
**K KIWANG**

CHECKED  
**A LANGDON**

PROJECT MANAGER  
**S STEINHOFER**

PROJECT DIRECTOR  
*Patrick Brady*  
**PATRICK BRADY RPEQ 7112**



CLIENT  
**MIRVAC QLD PTY LTD**

PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**







LOCATION  
**TEVIOT ROAD, GREENBANK**





SHEET TITLE  
**EROSION AND SEDIMENT CONTROL LAYOUT - EARTHWORKS PHASE**

JOB CODE <b>MIR009-01</b>	
SHEET NUMBER <b>C700</b>	REV <b>B</b>



**NOTE**  
 CONTRACTOR TO ENSURE THAT ALL DISTURBED AREAS ARE REINSTATED WITH 50mm TOPSOIL AND DRILL SEEDING AND HYDROMULCH SPRAY ESPECIALLY ON AREAS ADJACENT PRECINCT 9.1 DISTURBED AREA.

- LEGEND - PROPOSED**
-  PROPOSED STORMWATER
  -  100mm THICK TOPSOIL RESPREAD AND DRILL SEEDING. HYDROMULCH TO BE SPRAYED IMMEDIATELY AFTER.
  -  100mm THICK TOPSOIL AND TURF
  -  50mm THICK TOPSOIL DRILL SEEDING. HYDROMULCH TO BE SPRAYED IMMEDIATELY AFTER.
  -  FINISHED MAJOR CONTOURS (0.50m)
  -  FINISHED MINOR CONTOURS (0.25m)

- LEGEND - EXISTING**
-  MAJOR CONTOURS (1.00m)
  -  MINOR CONTOURS (0.50m)
  -  EXISTING DIRTY WATER DIVERSION BUND.
  -  VEGETATION CLEARING EXTENT

**SERVICE TRENCH AND ROAD CONSTRUCTION SEQUENCE**

- STEP 6**  
 PRIORITY SHOULD BE GIVEN TO PLACEMENT OF GRAVELS WITHIN ROAD AS A MEANS TO REDUCE EROSION RISK  
 PAVEMENT CONSTRUCTION  
 MAINTAIN SILT FENCES, AND CATCH DRAINS WHICH CONTROL SEDIMENTATION AND EROSION DURING PAVEMENT CONSTRUCTION  
 GULLY INLET CONTROLS TO BE REINSTATED DURING PAVEMENT AND STORMWATER CONSTRUCTION AND MAINTAINED UNTIL ENTIRE UPSLOPE CATCHMENT HAS BEEN STABILISED.
- STEP 7**  
 MAINTENANCE PERIOD  
 MAINTAIN CONTROL AND ESC AND VEGETATIVE TREATMENTS WHICH CONTROL SEDIMENTATION AND EROSION PRIOR TO THE ESTABLISHMENT OF STABILIZED GRASS COVER.
- STEP 8**  
 REMOVE CONSTRUCTION ENTRANCES.
- ADDITIONAL EROSION CONTROLS ARE TO BE ERECTED AND MONITORED AS REQUIRED BY THE SUPERINTENDENT

- NOTES**
- REFER EROSION AND SEDIMENT CONTROL NOTES AND DETAILS DRAWINGS.
  - ALL FOOTPATHS ARE TO BE FULLY TURFED AS SOON AS PRACTICAL.
  - CONTRACTOR TO ENSURE THAT GRASS SEEDED AREAS SHOWN ON THIS PLAN ACHIEVE SUFFICIENT STRIKE AND COVERAGE IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARDS.
  - FOR STABILISATION MEASURES OF FUTURE PRECINCTS, REFER TO M1012-01 - C730 EROSION AND SEDIMENT CONTROL LAYOUT - STABILISATION PHASE.

**TURFING AND TOPSOIL NOTE**  
 CONTRACTOR SHALL RESPREAD AMELIORATED TOPSOIL (AMELIORATION REQUIREMENTS AS DIRECTED BY SUPERINTENDENT) TO VERGES AT A THICKNESS OF 100mm. TURFING TO VERGES WITHIN PRECINCT 12.3 WORKS SHALL BE UNDERTAKEN BY THE CIVIL CONTRACTOR.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

*T. Clark*  
 TERRY CLARK (CPESC 6089)

**NOTE**  
 STABILISATION MEASURES TO BE APPLIED WITHIN TIMEFRAMES PER 'MAX DAYS TO STABILISATION' BASED ON EROSION RISK (REFER DRAWING C710). IF A DELAY IN APPLICATION OR INSTALLATION WILL OCCUR THEN TEMPORARY EROSION CONTROL (MULCH, BINDER OR BIDUM) MUST BE UTILISED TO EFFECTIVELY STABILISE ALL EXPOSED OR DISTURBED AREAS UNTIL FINAL TREATMENT IS APPLIED.



**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB
			REC	APP

**Premise**  
 BRISBANE OFFICE  
 LEVEL 11, 300 ADELAIDE STREET  
 BRISBANE, QLD 4000  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
 K KIWANG  
 CHECKED  
 A LANGDON  
 PROJECT MANAGER  
 S STEINHOFER  
 PROJECT DIRECTOR  
 PATRICK BRADY RPEQ 7112

SCALE  
 0 10 20 30m  
 SCALE 1:500 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT  
 MIRVAC QLD PTY LTD  
 PROJECT  
 EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT  
 LOCATION  
 TEVIOT ROAD, GREENBANK  
 SHEET TITLE  
 EROSION AND SEDIMENT CONTROL - STABILISATION PHASE


JOB CODE  
 M1009-01  
 SHEET NUMBER  
 C701  
 REV  
 B

**EROSION & SEDIMENT CONTROL NOTES**


- LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- REFER EARTHWORKS DRAWINGS FOR ADDITIONAL NOTES.
- ALL TRENCHES, FOOTPATH EXCAVATIONS & STOCKPILES TO BE PROTECTED BY TEMPORARY SEDIMENT FENCES UNTIL 80% GRASS COVERAGE IS ACHIEVED TO DISTURBED AREAS.
- EVERY PRECAUTION IS TO BE TAKEN TO PREVENT THE TRANSPORT OF SILT INTO THE NEWLY LAID STORMWATER PIPES THAT ARE CONNECTED TO THE DOWNSTREAM PIPE SYSTEMS, AND ANY EXISTING OPEN CHANNELS.
- THESE NOTES SHALL BE READ IN CONJUNCTION WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- THE EROSION AND SEDIMENT CONTROL WORKS SHALL COMPLY WITH THE REQUIREMENTS OF THE LOCAL AUTHORITIES EROSION AND SEDIMENT CONTROL STANDARDS.
- THE CONTRACTOR SHALL TAKE ALL REASONABLE AND PRACTICABLE MEASURES TO:
  - ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON EROSION FLOW VELOCITIES;
  - MINIMISE SOIL EROSION FROM WATER AND WIND;
  - MINIMISE ADVERSE EFFECTS OF SEDIMENT RUN-OFF;
  - MINIMISE OR PREVENT ENVIRONMENTAL HARM ASSOCIATED WITH DISCHARGES FROM THE SITE (E.G. THE EFFECTS OF SEDIMENTATION ON THE ENVIRONMENTAL VALUES OF RECEIVING WATERS); AND
  - ENSURE THAT THE VALUE AND USE OF RESIDENTIAL PROPERTIES ADJACENT TO THE DEVELOPMENT (SUCH AS DRAINAGE AND ROADS) ARE NOT DIMINISHED AS A RESULT OF THE MIGRATION OF SEDIMENT FROM THE DEVELOPMENT.
- THE CONTRACTOR SHALL APPOINT AN APPROPRIATELY EXPERIENCED PERSON TO BE MADE RESPONSIBLE FOR IMPLEMENTATION OF THE ESC.
- ALL ESC MEASURES SHALL BE INSPECTED:
  - AT LEAST DAILY (WHEN WORK IS OCCURRING ON SITE).
  - AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON SITE).
  - WITHIN 24 HOURS OF EXPECTED RAINFALL.
  - WITHIN 18 HOURS OF RAINFALL OCCURRING.
- MAINTENANCE OF ESC MEASURES SHALL OCCUR TO ENSURE THEY ARE OPERATING EFFICIENTLY AND IN ACCORDANCE WITH THE FOLLOWING SCHEDULE:

ESC MEASURES	MAINTENANCE TRIGGER	TIME FRAME FOR UNDERTAKING MAINTENANCE
ESC MEASURES	WHEN SETTLED SEDIMENT VOLUME EXCEEDS 25% OF THE CAPACITY OF THE ESC MEASURE	BY THE END OF THE DAY


- INSTALL DIVERSION CATCH DRAINS UPSTREAM OF, AND SILT FENCE DOWNSTREAM OF, STOCKPILES.
- STOCKPILES ARE TO BE LOCATED AWAY FROM EROSION HAZARD AREAS SUCH AS DRAINAGE LINES AND STEEP SLOPES.
- STOCKPILES ARE TO BE PROTECTED FROM EROSION BY THE WIND.
- ADEQUATE SUPPLIES OF EMERGENCY MAINTENANCE MATERIALS, INCLUDING (BUT NOT LIMITED TO) TIE WIRE, STAKES, FILTER CLOTH, WIRE MESH AND CLEAN GRAVEL SHOULD BE AVAILABLE ON-SITE.
- ESC MAINTENANCE ACTIVITIES ARE TO BE RECORDED IN AN ON-SITE REGISTER. THE REGISTER IS TO BE MAINTAINED FOR THE DURATION OF THE WORKS AND IS TO BE MADE AVAILABLE TO THE SUPERINTENDENT.
- DISTURBED AREA ARE TO BE STABILISED AS SOON AS POSSIBLE ON COMPLETION OF BULK EARTHWORKS. LOTS TO BE STABILISED FOLLOWING RESPREADING OF TOPSOIL.
- SUPPLEMENTARY ESC MEASURES SHALL BE DIRECTED BY THE SUPERINTENDENT.




(a) Rock entry/exit pad for construction sites (refer to Standard Drawing Exit-03 for building sites)



(c) Alternative low maintenance arrangement (still under development)



(b) Rock pad sloping away from road



(d) Rock pad sloping towards the road

**CONSTRUCTION ENTRANCE DETAIL**

- MATERIALS**
- COMPOSTS MUST COMPLY WITH THE REQUIREMENTS OF AS4454.
- (i) WELL-DECOMPOSED 100% ORGANIC MATTER PRODUCED BY CONTROLLED AEROBIC (BIOLOGICAL) DECOMPOSITION.
  - (ii) MAXIMUM OF 1% OF INERT MATERIAL.
  - (iii) MAXIMUM SOLUBLE SALT CONCENTRATION OF 5ds/m, AND pH RANGE OF 5.0 TO 8.5.
  - (iv) MOISTURE CONTENT OF 30 TO 50% PRIOR TO APPLICATION.
- INSTALLATION**
- REFER TO APPROVED PLANS FOR LOCATION AND EXTENT. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, EXTENT, MATERIAL TYPE, OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.
  - WHEN SELECTING THE LOCATION OF A COMPOST FILTER BERM, TO THE MAXIMUM DEGREE PRACTICABLE, ENSURE THE BERM IS LOCATED:
    - (i) TOTALLY WITHIN THE PROPERTY BOUNDARIES;
    - (ii) ALONG A LINE OF CONSTANT ELEVATION (PREFERRED, BUT NOT ALWAYS PRACTICAL);
    - (iii) AT LEAST 1m, IDEALLY 3m, FROM THE TOE OF A FILL EMBANKMENT;
    - (iv) AWAY FROM AREAS OF CONCENTRATED FLOW.
  - ENSURE THE BERM IS INSTALLED IN A MANNER THAT AVOIDS THE
- REMOVAL (IF REQUIRED)**
- WHEN DISTURBED AREAS UP-SLOPE OF THE BERM ARE SUFFICIENTLY STABILISED TO RESTRAIN EROSION, THE BERM MAYBE REMOVED.
  - REMOVE ANY COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.
  - REHABILITATE/REVEGETATE THE DISTURBED GROUND AS NECESSARY TO MINIMISE THE EROSION HAZARD.
- MAINTENANCE**
- DURING THE CONSTRUCTION PERIOD, INSPECT THE BERM AT LEAST WEEKLY AND AFTER ANY SIGNIFICANT RAIN. MAKE NECESSARY REPAIRS IMMEDIATELY.
  - REPAIR OR REPLACE ANY DAMAGED SECTIONS.
  - WHEN MAKING REPAIRS, ALWAYS RESTORE THE SYSTEM TO ITS ORIGINAL CONFIGURATION UNLESS AN AMENDED LAYOUT IS REQUIRED OR SPECIFIED.
  - REMOVE ACCUMULATED SEDIMENT IF THE SEDIMENT DEPOSIT EXCEEDS A DEPTH OF 100mm OR 1/3 THE HEIGHT OF THE BERM.
  - DISPOSE OF SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.




Figure 1 - Typical profile of a compost filter berm

**MULCH BUND DETAIL**

EROSION RISK RATING												
BASED ON AVERAGE MONTHLY RAINFALL (SOURCE TABLE 4.4.2 IECA 2008)												
MONTHLY DATA	JAN.	FEB.	MAR.	APR.	MAY	JUN.	JUL.	AUG.	SEPT.	OCT.	NOV.	DEC.
MEAN RAINFALL	101.00	79.50	130.90	535.50	33.50	67.80	19.80	24.50	23.40	35.80	109.10	75.500
EROSION RISK	HIGH	MODERATE	HIGH	MODERATE	LOW	MODERATE	VERY LOW	VERY LOW	VERY LOW	LOW	HIGH	MODERATE
	VERY LOW RISK: 0 TO 30mm											
	LOW RISK: 30+ TO 45mm											
	MODERATE RISK: 45+ TO 100mm											
	HIGH RISK: 100+ TO 225mm											
	EXTREME RISK: >225mm											

**EROSION RISK RATING**

APPLICABLE MONTH	EROSION RISK RATING	ADVANCE LAND CLEARING ALLOWED (WEEKS WORK)	MAX DAYS TO STABILISATION	STAGED CONSTRUCTION AND STABILISATION OF EARTH BATTERS > 6H : 1V	STOCKPILES STABILISED
	VERY LOW	8	30 (60%)		
OCTOBER	LOW	8	30 (70%)		
	MODERATE	6	20 (70%)	X	
NOVEMBER	HIGH	4	10 (75%)	X	X
	EXTREME	2	10 (80%)	X	X

**NOTE:**  
FOR DISPERSIVE SOILS MANAGEMENT NOTES, REFER TO DRAWINGS C210.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

Terry Clark (CPESC 6089)

<b>FOR CONSTRUCTION</b>			<p><b>BRISBANE OFFICE</b> LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au</p>	DESIGNED K KIWANG CHECKED A LANGDON PROJECT MANAGER S STEINHOFER PROJECT DIRECTOR P. Brady	SCALE	CLIENT MIRVAC QLD PTY LTD PROJECT EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK SHEET TITLE EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 1 OF 2	JOB CODE MIR009-01 SHEET NUMBER C710 REV B
05/11/2021 B ISSUED FOR CONSTRUCTION KK PB 05/09/2021 A ORIGINAL ISSUE KK PB DATE REV DESCRIPTION REVISIONS REC APP	ORIGINAL SHEET SIZE A1						

## ROLES AND RESPONSIBILITIES

ROLE	RESPONSIBILITY
PROJECT MANAGER	<ul style="list-style-type: none"> <li>• OVERALL RESPONSIBILITY OF ESC IMPLEMENTATION</li> <li>• NOTIFY THE ENVIRONMENTAL MANAGER IMMEDIATELY OF ANY NON-COMPLIANCE WITH ESCP</li> <li>• ENSURE THE PROMPT IMPLEMENTATION OF MEASURES TO MITIGATE EROSION AND SEDIMENT GENERATION</li> </ul>
SITE SUPERVISOR / FOREMEN	<ul style="list-style-type: none"> <li>• MONITOR DAILY RAINFALL</li> <li>• NOTIFY ENVIRONMENTAL ADVISOR/CONSULTANT WHEN RUNOFF GENERATING RAINFALL OCCURS IN THE PREVIOUS 24 HOURS</li> <li>• MAINTAIN CURRENT RECORDS OF RAINFALL, STORAGE VOLUMES, WATER QUALITY, TREATMENT PRACTICES, DISCHARGE VOLUMES (AS APPROPRIATE)</li> <li>• INSTALLATION AND MAINTENANCE OF ESC</li> </ul>
ENVIRONMENTAL MANAGER	<ul style="list-style-type: none"> <li>• PROVIDE DESIGN INFORMATION AS REQUIRED</li> <li>• CONDUCT IN-SITU MONITORING (AS REQUIRED)</li> <li>• COLLECT AND SUBMIT SAMPLES TO LABORATORY (AS REQUIRED)</li> <li>• COLLATE RESULTS AND PREPARE REPORTS (AS REQUIRED)</li> <li>• CONDUCT SITE INSPECTIONS AND AUDITS (AS REQUIRED)</li> <li>• INSPECT ESC INSTALLATION AND MAINTENANCE</li> <li>• INSPECT OFFSITE IMPACTS AND MANAGEMENT</li> <li>• PROVIDE ADVICE REGARDING ESC SITE IMPROVEMENT (AS REQUIRED)</li> </ul>
ALL PERSONNEL	<ul style="list-style-type: none"> <li>• REPORT ANY DAMAGE TO ESC DEVICES AND ANY POTENTIAL OR ACTUAL ENVIRONMENTAL HARM IN LINE WITH DUTY TO NOTIFY UNDER THE REQUIREMENTS OF THE ENVIRONMENTAL PROTECTION ACT 1994</li> </ul>

## CORRECTIVE AND PREVENTATIVE ACTION

AN ENVIRONMENTAL INCIDENT WITH RESPECT TO THE ESCP IS DEFINED AS ANY OCCURRENCE WHERE SEDIMENT IS RELEASED FROM THE SITE, WHETHER CONTROLLED OR UNCONTROLLED, OR WHERE STORM WATER IS RELEASED (CONTROLLED) FROM SITE WHICH DOES NOT MEET THE WATER QUALITY REQUIREMENTS.

ALL INCIDENTS AND NON-CONFORMANCES ARE TO BE REPORTED, INVESTIGATED AND CORRECTED IN ACCORDANCE WITH THE ESCP TO ENSURE EFFECTIVE SOIL AND WATER QUALITY MANAGEMENT PRACTICES AT ALL TIMES.

BEST PRACTICE SITE MANAGEMENT REQUIRES ALL ESC MEASURES TO BE INSPECTED BY THE CONTRACTORS NOMINATED REPRESENTATIVE AT LEAST DAILY WHEN RAIN IS OCCURRING, WITHIN 24 HOURS PRIOR TO EXPECTED RAINFALL, AND WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE ONSITE RUNOFF (IECA, 2008). SUCH INSPECTIONS MUST CHECK:

- **DAILY SITE INSPECTIONS** (DURING PERIODS OF RUNOFF PRODUCING RAINFALL)
  - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
  - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
  - ALL SITE DISCHARGE POINTS (INCLUDING DEWATERING ACTIVITIES AS APPROPRIATE)
- **WEEKLY SITE INSPECTIONS** (EVEN IF WORK IS NOT OCCURRING ON-SITE)
  - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
  - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
  - OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.
  - LITTER AND WASTE RECEPTORS
  - OIL, FUEL AND CHEMICALS STORAGE FACILITIES
- **PRIOR TO ANTICIPATED RUNOFF PRODUCING RAINFALL**
  - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
  - ALL TEMPORARY FLOW DIVERSION AND DRAINAGE WORKS
- **FOLLOWING RUNOFF PRODUCING RAINFALL**
  - ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES
  - OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)
  - OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.



I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

*Terry Clark*


TERRY CLARK (CPESC 6089)

FOR CONSTRUCTION				<p><b>BRISBANE OFFICE</b> LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au</p>	DESIGNED <b>K KIWANG</b> CHECKED <b>A LANGDON</b> PROJECT MANAGER <b>S STEINHOFER</b> PROJECT DIRECTOR <i>Patrick Brady</i>	SCALE	CLIENT <b>MIRVAC QLD PTY LTD</b>	JOB CODE <b>MIR009-01</b>
05/11/2021    B    ISSUED FOR CONSTRUCTION    KK    PB 03/09/2021    A    ORIGINAL ISSUE    KK    PB DATE    REV    DESCRIPTION    REC    APP	REVISIONS	PROJECT <b>EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT</b> LOCATION <b>TEVIOT ROAD, GREENBANK</b> SHEET TITLE <b>EROSION AND SEDIMENT CONTROL NOTES AND DETAILS - SHEET 2 OF 2</b>	ORIGINAL SHEET SIZE A1 SHEET NUMBER <b>C711</b> REV <b>B</b>					





**NOTE**  
 CONTRACTOR TO ENSURE THAT THE SURFACE WATER IN TURNAROUND IS DIRECTED TO KERB AND CHANNEL AND OVERLAND FLOW PATHS ARE CONSIDERED. CONTRACTOR TO NOTIFY SUPERINTENDENT SHOULD THIS CRITERIA NOT BE MET.



**FOR CONSTRUCTION**

DATE	REV	DESCRIPTION	KK	PB
05/11/2021	B	ISSUED FOR CONSTRUCTION	KK	PB
03/09/2021	A	ORIGINAL ISSUE	KK	PB
			REC	APP

**Premise**  
 BRISBANE OFFICE  
 LEVEL 1, 100 BRUNSWICK STREET  
 PO BOX 361  
 FORTITUDE VALLEY, QLD 4006  
 PH: (07) 3253 2222  
 WEB: www.premise.com.au

DESIGNED  
**K KIWANG**  
 CHECKED  
**A LANGDON**  
 PROJECT MANAGER  
**S STEINHOFER**  
 PROJECT DIRECTOR  
**Patrick Brady**  
 RPEQ 7112

SCALE  
 0 10 20 30m  
 SCALE 1:500 (A1)  
 0 5 10 15m  
 SCALE 1:250 (A1)  
 ORIGINAL SHEET SIZE A1

CLIENT  
**MIRVAC GROUP**  
 PROJECT  
**EVERLEIGH PRECINCT 9.1 SUBDIVISION DEVELOPMENT**  
 LOCATION  
**TEVIOT ROAD, GREENBANK**  
 SHEET TITLE  
**TEMPORARY WORKS - ROADWORKS AND DRAINAGE**

JOB CODE  
**MIR009-01**  
 SHEET NUMBER  
**C900**  
 REV  
**B**