

		PRI		ICT 9.3		
		I EVIO I ROAD				
	N	F	TES			
	 This plan has been prepared from preliminary survey plan (SP331503) and engineering plans provided on the 13/12/2021 by Premise Engineering Pty Ltd. Development approval was granted for this subdivision (DEV2020/1160) by the Minister for Economic Development Queensland on 26th of August 2021. The relevant authorities have granted operational works approval, for the proposed lot. The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot. Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company. All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007. Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished 					
	level between allotments is less than 0.5m.					
		No.	by	Date	Chkd	Description
	senes	A	TBG	10/03/22	CU	Original Issue
	Issl					
1503					Or	vel Datum: AHD der. igin of Levels: PSM 203673 . of Origin: 54.070 intour Interval: 0.25m

Scale @A3 1:200 Dwg No. 7598 S 45 DP A 3164