



NOTES

This plan has been prepared from preliminary survey plan (SP338104) and engineering plans provided on the 14/09/2022 by Premise Engineering Pty Ltd.

Development approval was granted for this subdivision (DEV2020/1160) by the Minister for Economic Development Queensland on 26th of August 2021.

for the proposed lot.

The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.

All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.

Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company.

Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.

Issues	No.	by	Date	Chkd	Description
	Α	TBG	13/10/22	PS	Original Issue



phone 1300 123 SHG web www.saundershavill.com

unless otherwise stated, and therefore is subject to final survey and construction of operational works.

Locality of Greenbank (Logan City Council)

Level Datum: AHD der.

Origin of Levels: PSM 203673 RL of Origin: 54.070 Contour Interval: 0.25m

Scale @A3 1: 200

Dwg No. 7598 S 49 DP A 3257