




## Everleigh

0.62m

0.00m

RL 51.00



#### **NOTES**

This plan has been prepared from preliminary survey plan (SP348245) and engineering plans provided on the 11/07/2024 by Premise Civil Engineering Pty Ltd.

The current development approval was granted for this subdivision (DEV2022/1277/7) by the Minister for Economic Development Queensland on 15th of December 2023.

The relevant authorities have granted operational works approval, for the proposed lot.

The purchaser should refer to the applicable development approvals for building and/or other requirements that may be applicable to the lot.

Extent of retaining walls shown indicatively only. Retaining walls may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.

Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company.

### Chkd Description No. by Date A MS 01/08/24 PS Original Issue

# MERLOTLANE Retaining Wall on Boundary (Front of Lot Transition) Max Height: Min Height: Average Height: 0.31m 4380 391 m2 RL 50:90 4379 RL 51.10 RL 50.25

This Disclosure Plan is prepared for the sole purpose of satisfying the disclosure requirements of the Land Sales Act and SHOULD NOT be used for any other purpose, particularly as-constructed purposes. This information is compiled from design plans only, unless otherwise stated, and therefore is subject to final survey and construction of operational works.

لسينسيا 0

2

#### Disclosure Plan for Proposed Lot 4380 on SP348245

16

14

9003 (Pt)

RL 51.10

0.90m

Retaining Wall on Boundary

SCALE @A3 1:200 - LENGTHS ARE IN METRES

12

Average Height: 0.90m

Max Height: Min Height:

Existing Title Reference: 51351694

Locality of Greenbank (Logan City Council)

	<b>sa</b> unders
5	havill group

the lot shown hereon)

LEGEND

Area of Fill

Area of Cut **Design Contours** Depth of Fill Contours

Retaining Wall

Tiered Retaining Wall

Finished Pad Design Level

XX.XX Finished Surface Design Level

(Not all items in this legend may be relevant to

Saunders Havill Group Pty Ltd ABN 24 144 972 949 Brisbane / Springfield head office 9 Thompson St Bowen Hills Q 4006 phone 1300 123 SHG web www.saundershavill.com

ø surveying ø town planning ø urban design ø environmental management ø landscape architecture

Described as part of Lot 9003 on SP348213

RL of Origin: 54.070 Contour Interval: 0.25m Scale @A3 1: 200

Level Datum: AHD der.

Dwg No. 7598 S 68 DP A 4380

Origin of Levels: PSM 203673