

gh	PRECINCT 8.2						
	Extent of retaining walls shown indicatively only. Retaining wa may not extend the full length of a lot boundary where finished level between allotments is less than 0.5m.					ngth of a lot boundary where finished	
	Parts of this lot may be subject to rip and re-compact earthwork procedures as determined by site conditions. This process may be completed in cut locations to assist the house pad construction. Any re-compaction will comply with AS3798 requirements and certified by a third party company. All fill shall be placed and compacted in a controlled manner so that Level 1 level of responsibility may be achieved and certified as per AS3798-2007.						
	-	No.	by	Date	Chkd	Description	
	les	A	MS	05/09/24	PS	Original Issue	
	lssues						
2 24							
SP348262					Level Datum: AHD der. Origin of Levels: PSM 203673 RL of Origin: 54.070 Contour Interval: 0.25m		
					Scale @A3_1:200		
					Dw	/g No. 7598 S 70 DP A 4268	