

SHEET LIST TABLE			
SHEET NO.	SHEET TITLE		
C001	COVER SHEET		
C002	SURVEY SETOUT PLAN		
C003	OVERALL SERVICES LAYOUT		
C004	SAFETY IN DESIGN		
C100	ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 1		
C101	ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 2		
C200	BULK EARTHWORKS LAYOUT PLAN - SHEET 1		
C201	BULK EARTHWORKS LAYOUT PLAN - SHEET 2		
C210	BULK EARTHWORKS NOTES AND DETAILS - SHEET 1		
C211	BULK EARTHWORKS NOTES AND DETAILS - SHEET 2		
C220	EARTHWORKS SUBGRADE ROCK PREPARATION DETAILS		
C230	RETAINING WALL SUBSOIL DRAINAGE PLAN - SHEET 1		
C231	RETAINING WALL SUBSOIL DRAINAGE PLAN - SHEET 2		
C300	ROADWORKS NOTES AND DETAILS		
C310	ROAD 115 LONG AND CROSS SECTIONS		
C311	ROAD 117 LONG AND CROSS SECTIONS		
C312	ROAD 119 LONG AND CROSS SECTIONS		
C313	ROAD 120 LONG AND CROSS SECTIONS		
C314	ROAD 121 LONG AND CROSS SECTIONS		
C315	ROAD 122 LONG SECTION		
C316	ROAD 122 CROSS SECTIONS - SHEET 1		
C317	ROAD 122 CROSS SECTIONS - SHEET 2		
C318	ROAD 122 CROSS SECTIONS - SHEET 3		
C319	DRIVEWAY 10 LONG SECTION AND CROSS SECTIONS		
C320	INTERSECTION DETAILS LAYOUT - SHEET 1		
C321	INTERSECTION DETAILS LAYOUT - SHEET 2		
C330	PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN - SHEET 1		
C331	PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN - SHEET 2		
C400	STORMWATER CATCHMENT LAYOUT PLAN		
C410	STORMWATER DRAINAGE LONG SECTIONS - SHEET 1		
C411	STORMWATER DRAINAGE LONG SECTIONS - SHEET 2		
C412	STORMWATER DRAINAGE LONG SECTIONS - SHEET 3		
C420	STORMWATER DRAINAGE NOTES AND DETAILS		
C430	STORMWATER DRAINAGE STRUCTURE DETAILS - SHEET 1		
C431	STORMWATER DRAINAGE STRUCTURE DETAILS - SHEET 2		
C440	STORMWATER CALCULATIONS 39% AEP STORM - SHEET 1		
C441	STORMWATER CALCULATIONS 39% AEP STORM - SHEET 2		
C442	STORMWATER CALCULATIONS 1% AEP STORM - SHEET 1		
C443	STORMWATER CALCULATIONS 1% AEP STORM - SHEET 2		
C500	SEWERAGE LOCALITY PLAN & NOTES		
C510	SEWERAGE LAYOUT PLAN - SHEET 1		
C511	SEWERAGE LAYOUT PLAN - SHEET 2		
C520	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 1		
C521	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 2		
C522	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 3		
C523	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 4		
C524	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 5		
C530	SEWERAGE NOTES AND DETAILS		
C600	WATER RETICULATION LOCALITY PLAN & NOTES		
C610	WATER RETICULATION LAYOUT PLAN - SHEET 1		
C611	WATER RETICULATION LAYOUT PLAN- SHEET 2		
C620	WATER LIVE CONNECTION AND TYPICAL DETAILS		
C700	OVERALL EROSION & SEDIMENT CONTROL KEY PLAN		
C701	EROSION AND SEDIMENT CONTROL - BULK EARTHWORKS PHASE		
C702	EROSION AND SEDIMENT CONTROL - STABILISATION PHASE		
C710	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS		
C900	TEMPORARY WORKS - ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 1		
C901	TEMPORARY WORKS - ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 2		

EVERLEIGH PRECINCT 8.2

SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK

FOR MIRVAC QLD PTY LTD

GENERAL NOTES

- ALL DIMENSIONS GIVEN ON THESE DRAWINGS ARE IN METRES UNLESS NOTED OTHERWISE.
- ALL NEW WORK AND MATERIALS SHALL COMPLY WITH CURRENT RELEVANT COUNCIL STANDARDS AND SPECIFICATIONS.
- ALL WORK SHALL BE JOINED NEATLY TO EXISTING CONSTRUCTION.
- THE CONTRACTOR IS TO LOCATE, IDENTIFY AND ESTABLISH THE CONNECTIVITY OF ALL EXISTING SERVICES WITHIN THE LIMITS OF PROPOSED WORKS AND CONFIRM THIS INFORMATION WITH THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MEASURING DEVICES, SAFETY EQUIPMENT AND MACHINERY REQUIRED TO CARRY OUT INSPECTIONS/MEETINGS AS SPECIFIED OR REQUESTED BY THE ENGINEER.
- CONSTRUCTION CERTIFICATION REQUIREMENTS SUCH AS PAVEMENT PROOF ROLLS ETC. ARE TO BE AS PER THE LOGAN CITY COUNCIL SPECIFICATION.
- THESE NOTES SHALL APPLY TO ALL PORTIONS OF WORK.
- THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATIONS. ANY POINT OF CONFLICT WILL BE RESOLVED BY THE SUPERINTENDENT.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A CONSTRUCTION MANAGEMENT PLAN FOR THE SITE TO BE ACCEPTED BY EDQ. THIS PLAN IS TO INCLUDE ALL ITEMS AS LISTED IN THE DECISION NOTICE AS A MINIMUM.

NOISE

- ALL PLANT AND EQUIPMENT SHALL BE CONTROLLED TO MINIMISE NOISE EMISSION IN ACCORDANCE WITH AS2436 (GUIDE TO NOISE CONTROL ON CONSTRUCTION, MAINTENANCE AND DEMOLITION). THE SITE WORKING HOURS SHOULD BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS. WHERE NOT SPECIFIED THE HOURS SHALL BE:

MONDAY - SATURDAY 7:00am to 6:00pm
SUNDAY OR PUBLIC HOLIDAY NO WORK PERMITTED

PRE-CONSTRUCTION & APPROVALS

- NO LOCATING/ POTHOLING OF EXISTING SERVICES HAS BEEN CARRIED OUT. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND DEPTH OF ALL EXISTING SERVICES WHICH AFFECT THE WORKS AND REPORT ANY POTENTIAL CLASHES TO THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORKS.
- THE CONTRACTOR IS RESPONSIBLE FOR ARRANGING WITH THE APPROPRIATE AUTHORITY FOR LOCATING EXISTING SERVICES AND FOR ANY MODIFICATIONS TO EXISTING SERVICES REQUIRED AS A RESULT OF THE WORKS.
- THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL EXISTING SERVICES FROM DAMAGE.
- ANY WORKS DAMAGED AS A RESULT OF CONSTRUCTION ARE TO BE REINSTATED TO RELEVANT AUTHORITY'S REQUIREMENTS AT THE CONTRACTORS COST.
- FINISHED SURFACE LEVELS ARE TO BE GRADED UNIFORMLY BETWEEN LEVELS INDICATED ON THE DRAWINGS.

WORKPLACE HEALTH & SAFETY

- THE CONTRACTOR SHALL BE THE PRINCIPAL CONTRACTOR AS DESIGNATED BY THE WORK HEALTH AND SAFETY ACT (2011).
- THE CONTRACTOR SHALL PREPARE AND IMPLEMENT A WORKPLACE HEALTH AND SAFETY PLAN AS REQUIRED BY THE WORK HEALTH AND SAFETY ACT (2011).

SETOUT NOTES

- CO-ORDINATE SETOUT PROVIDED ON THESE DRAWINGS IS BASED ON A CO-ORDINATE BASE PROVIDED ON THE DETAIL SURVEY DRAWING 7598 S 02 DTH, PREPARED BY SAUNDERS HAVILL GROUP. REFERENCE MARKS AND CORRESPONDING CO-ORDINATES ARE PROVIDED ON DRAWING C002.
- THE LEVEL DATUM FOR WORKS IS A.H.D (AUSTRALIAN HEIGHT DATUM).



LOCALITY PLAN

Scale 1:5000



FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR PATRICK BRADY

SCALE
0 100 200 300m
SCALE 1:5000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	COVER SHEET

JOB CODE	MIR-0802
SHEET NUMBER	C001
REV	B



LEGEND

- PROPOSED ROAD CENTRELINE
- STAGE BOUNDARY

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

LEVEL DATUM: AHD (DERIVED)

ORIGIN - PM61308
RL OF ORIGIN - 54.660m A.H.D

ORIGIN OF COORDINATES: STATION C1 (PM 73506)

PROJECT COORDINATES - STN C1, 8792.646 E, 32093.723 N

FOR FURTHER DETAILS REFER TO DETAIL SURVEY DRAWING 7598 S 02 DT H PREPARED BY SAUNDERS HAVILL GROUP.

SITE AREA

39.906m²

REAL PROPERTY DESCRIPTION

LOT 2 on SP297192

LAYOUT PLAN

SCALE 1:1000

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112


SCALE
0 20 40 60m
SCALE 1:1000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD	JOB CODE	MIR-0802
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER	C002
LOCATION	TEVIOT ROAD, GREENBANK	REV	B
SHEET TITLE	SURVEY SETOUT PLAN		



LEGEND - PROPERTY SERVICE CONNECTIONS

- W** **WATER** - POLY SERVICE FROM WATER MAIN, METER BOX & COVER INSTALLED. BUILDER TO MAKE APPLICATION TO LOGAN CITY COUNCIL FOR METER ASSEMBLY SUPPLY AND INSTALLATION. WHERE WATER METER IS LOCATED BEHIND RETAINING WALL, 25mm POLYPIPE WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "WATER".
- S** **SEWER** - CAPPED Ø100 PVC PIPE (BURIED MAX 1.5m). MARKED WITH 400 ORANGE PVC CONDUIT SECURELY TAPED TO H.W. STAKE AT SURFACE (BURIED TO CAPPED PIPE). CONDUIT LABELLED "SEWER".
- RW** **ROOFWATER** - CONNECTION LOCATION CAN BE EITHER FRONT OF LOT VIA KERB ADAPTOR OUTLET TO ROAD, OR REAR OF LOT INTO ROOFWATER DRAINAGE PIPE VIA PIT. CAPPED PVC Ø100 PIPES (BURIED MAX 1.5m) MARKED WITH 900x50x25 HW STAKE LABELLED "ROOFWATER".
- SSD** **RETAINING WALL SUB-SOIL DRAINAGE** - OUTLET POINT TO LOT FOR RETAINING WALL SUB-SOIL DRAINAGE TO BE CONNECTED TO YARD DRAINAGE BY BUILDER. Ø100 NON-SLOTTED AGG PIPE CAPPED AND TERMINATED 200m ABOVE SURFACE. PVC DUCT TAPED TO 900x50x25 HW STAKE LABELLED "RETAINING WALL SUBSOIL OUTLET".
- T** **TELECOMMUNICATIONS/NBN** - PVC CONDUIT (BURIED APPROX 300mm). MARKED WITH 900x50x25 HW STAKE LABELLED "TELECOMMS".
- E** **ELECTRICITY** - ELECTRICITY PILLAR EXISTS IN ROAD VERGE. BUILDER TO MAKE APPLICATION WITH ENERGY PROVIDER FOR SERVICE INSTALLATION TO LOT. WHERE ELECTRICITY PILLAR IS LOCATED BEHIND RETAINING WALL, CONDUIT WILL BE SUPPLIED UNDER WALL INTO LOT AND WILL BE MARKED WITH 900x50x25 HW STAKE LABELLED "ELECTRICITY".
- G** **GAS** - GAS MAIN EXISTS IN ROAD VERGE. BUILDER/HOME OWNER TO MAKE APPLICATION TO GAS PROVIDER FOR SERVICE INSTALLATION TO LOT.
- RETAINING WALL**
- SERVICE TERMINATION POINT MARKER. 900x50x25 HW STAKE, OR 400 ORANGE PVC CONDUIT STAKE**



LAYOUT PLAN
SCALE 1:1000

LEGEND - PROPOSED

- SW** STORMWATER
- W** WATER
- S** GRAVITY SEWER

LEGEND - CONSTRUCTED

- SW** STORMWATER
- S** GRAVITY SEWER
- W** WATER
- RM** SEWER RISING MAIN

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 20 40 60m
SCALE 1:1000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD	JOB CODE	MIR-0802
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER	C003
LOCATION	TEVIOT ROAD, GREENBANK	REV	B
SHEET TITLE	OVERALL SERVICES LAYOUT		

DESIGN HAZARD NOTES:

1. PREMISE, HAVING BEEN COMMISSIONED TO CARRY OUT DETAILED DESIGN AND DOCUMENTATION OF THESE WORKS, CONFIRM THAT THE PREMISE DRAWING SET HAS BEEN INTERNALLY REVIEWED FOR DESIGN SAFETY IN ACCORDANCE WITH SECTION 22 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD.
2. THIS REPORT SUMMARISES AN INTERNAL REVIEW OF PREMISE'S DETAILED DESIGN DRAWINGS FOR DESIGN SAFETY.
3. THIS REPORT IN NO WAY RELIEVES THE PRINCIPAL, CONTRACTOR OR ANY OTHER PARTY OF THEIR OWN OBLIGATIONS AND RESPONSIBILITIES UNDER THE WORK HEALTH AND SAFETY ACT 2011 QLD, INCLUDING (BUT NOT LIMITED TO) CONSULTATION WITH THE DESIGNER UNDER SECTION 294 OF THE ACT, THE PREPARATION OF SATISFACTORY SAFE WORK METHOD STATEMENTS AND DUTIES OF CARE.
4. IT IS A REQUIREMENT UNDER SECTION 296 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD, THAT A COPY OF THIS REPORT BE PROVIDED TO THE CONTRACTOR BY THE ENTITY COMMISSIONING THE WORK SHOWN OF THE PREMISE DRAWINGS.
5. AS PER THE DEPARTMENT OF JUSTICE AND THE ATTORNEY-GENERAL- WORKPLACE HEALTH AND SAFETY QUEENSLAND, A WRITTEN REPORT IS NOT REQUIRED FOR DESIGNS THAT HAVE TYPICAL FEATURES.

CONSEQUENCE TABLE		
LEVEL	CONSEQUENCE	COST/TIME
5 - CATASTROPHIC	FATALITY OR MULTIPLE PERSONS ONSITE WITH LIFE THREATENING HEALTH EFFECT OR INABILITY TO CONTINUE	HUGE FINANCIAL OR TIME LOSS
4 - MAJOR	EXTENSIVE INJURIES, OR ONSET OF SEVERE OR LIFE THREATENING HEALTH EFFECT TO SINGLE PERSON ONSITE. MULTIPLE PERSONS WITH ONSET OF IRREVERSIBLE HEALTH EFFECTS. PERMANENT INJURY TO PERSON ONSITE.	MAJOR FINANCIAL OR TIME LOSS
3 - MODERATE	MEDICAL TREATMENT REQUIRED. IRREVERSIBLE HEALTH EFFECT TO A SINGLE PERSON. MULTIPLE PERSONS ONSITE WITH REVERSIBLE HEALTH EFFECTS.	HIGH FINANCIAL OR TIME LOSS
2 - MINOR	FIRST AID, SINGLE OR MULTIPLE INJURIES AMONGST PERSONS ONSITE. SINGLE PERSON ONSITE WITH MODERATE SHORT TERM REVERSIBLE HEALTH EFFECTS.	MEDIUM FINANCIAL OR TIME LOSS
1 - INSIGNIFICANT	NO INJURIES. OVER EXPOSURE TO A SINGLE PERSON ONSITE, BUT NO REPORTED HEALTH EFFECTS.	LOW FINANCIAL OR TIME LOSS

CONSTRUCTION HAZARD NOTES:

1. UNDER THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011, THE WORK HEALTH AND SAFETY REGULATION 2011 AND OTHER LEGISLATION AND GUIDELINES, THE PRINCIPAL CONTRACTOR HAS SPECIFIC OBLIGATIONS IN RELATION TO THE SAFE OPERATION OF THE SITE AND OF THE WORKS.
TO ASSIST THE PRINCIPAL CONTRACTOR IN COMPLYING WITH THESE OBLIGATIONS THE PROJECT DESIGNERS HAVE IDENTIFIED BY DRAWING NOTES, AREAS WHERE POTENTIAL HAZARDS MAY ARISE. THESE NOTES OR ADVICE, SHALL NOT NECESSARILY BE CONSIDERED COMPLETE AND ARE BASED UPON THE DESIGNERS' UNDERSTANDING OF THE SAFETY RISKS ASSOCIATED WITH THE WORKS.
THESE NOTES OR ADVICE SHALL NOT RELIEVE THE PRINCIPAL CONTRACTOR OF ANY OBLIGATION UNDER THE RELEVANT LEGISLATION OR GUIDELINE. THE PRINCIPAL CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE PREPARATION OF AN APPROPRIATE WORK HEALTH SAFETY MANAGEMENT PLAN AND SAFE WORK METHOD STATEMENTS FOR THE SITE.
2. PURSUANT TO THE WORK HEALTH AND SAFETY ACT 2011 WE HEREBY ADVISE THAT OUR DESIGN SAFETY REVIEW HAS IDENTIFIED UNUSUAL OR ATYPICAL DESIGN FEATURES THAT MAY PRESENT ADDITIONAL HAZARDS OR RISKS DURING THE CONSTRUCTION PHASE AND THESE ARE LISTED IN THE CONSTRUCTION HAZARD SCHEDULE.

RISK ANALYSIS MATRIX						
		1 - INSIGNIFICANT	2 - MINOR	3 - MODERATE	4 - MAJOR	5 - CATASTROPHIC
LIKELIHOOD	A - ALMOST CERTAIN	MODERATE	HIGH	EXTREME	EXTREME	EXTREME
	B - LIKELY	MODERATE	HIGH	HIGH	EXTREME	EXTREME
	C - POSSIBLE	LOW	MODERATE	HIGH	EXTREME	EXTREME
	D - UNLIKELY	LOW	LOW	MODERATE	HIGH	EXTREME
	E - RARE	LOW	LOW	MODERATE	HIGH	HIGH

RISK EVALUATION TABLE	
RISK LEVEL	ACTION REQUIRED
EXTREME	UNACCEPTABLE RISK. RE-DESIGN REQUIRED. DO NOT PROCEED WITHOUT ADDITIONAL CONTROLS.
HIGH	UNACCEPTABLE RISK. ADDITIONAL CONTROLS NEEDED. CONSIDER FURTHER REVIEW AND CONSIDER RE-DESIGN
MODERATE	RISK MAY BE ACCEPTABLE. MANAGEMENT TO DETERMINE ACTIONS REQUIRED
LOW	ACCEPTABLE. MANAGE RISK THROUGH ROUTINE PROCEDURES AND OTHER ADMINISTRATIVE CONTROLS

LIKELIHOOD TABLE		
LEVEL	DESCRIPTION	QUANTIFICATION GUIDE
A - ALMOST CERTAIN	THE EVENT <u>IS</u> EXPECTED TO OCCUR IN MOST CERTAIN CIRCUMSTANCES	MORE THAN ONCE PER YEAR
B - LIKELY	THE EVENT <u>WILL</u> PROBABLY OCCUR IN MOST CIRCUMSTANCES	AT LEAST ONCE IN 5 YEARS
C - POSSIBLE	THE EVEN T <u>SHOULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 10 YEARS
D - UNLIKELY	THE EVENT <u>COULD</u> OCCUR AT SOME TIME	AT LEAST ONCE IN 30 YEARS
E - RARE	THE EVENT <u>MAY</u> OCCUR IN EXCEPTIONAL CIRCUMSTANCES	LESS THAN ONCE IN 30 YEARS


DESIGN HAZARD SCHEDULE					
ITEM	DESIGN HAZARD	POTENTIAL HAZARD	RISK	ELIMINATION / MINIMISATION OF HAZARD / RISK	RESIDUAL RISK
D1	URBAN LAYOUT HAZARD	THE URBAN LAYOUT IS DESIGNED AROUND A PARTICULAR HAZARD :- - INTERSECTION IS UNCLEAR WHICH ROAD HAS PRIORITY	HIGH	THE HAZARD HAS BEEN REDUCED/ELIMINATED BY:- - LINE MARKED INTERSECTION TO ENSURE IT IS CLEAR WHICH ROAD HAS PRIORITY - DESIGN VEHICLE SWEEP PATH CHECKED FOR COMPLIANCE	LOW
D2	EXISTING UNDERGROUND / OVERHEAD SERVICES HAZARD	EXISTING UNDERGROUND AND/OR OVERHEAD SERVICES HAZARD EXIST ON SITE AND NEEDS TO BE REMOVED AND RELOCATED.	HIGH	THE DESIGN OF THE PROJECT HAS INCORPORATED THE RELOCATION OF THESE EXISTING SERVICES AND THE CONTRACTOR IS TO BE MADE AWARE OF THESE EXISTING SERVICES AND TAKE ALL ACTIONS NECESSARY TO MITIGATE THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D3	DEEP EXCAVATION HAZARD	DEEP EXCAVATION IS REQUIRED TO INSTALL SEWER TO SERVICE STRUCTURE.	HIGH	THE DEEP EXCAVATION HAZARD CANNOT BE AVOIDED AND THE CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEDIUM
D4	HIGH RETAINING WALLS	SOME AREAS OF WORKS CONTAIN HIGH RETAINING WALLS WHERE LAND MORPHOLOGY DICTATES.	HIGH	HIGH RETAINING WALLS CANNOT BE AVOIDED DUE TO EXISTING LAND MORPHOLOGY. SINGLE TIER WALLS HAVE LIMITED TO A MAX HEIGHT OF 2m. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	MEIDUM
D5	WATER BODIES	PROPOSED CONSTRUCTION WATER DAMS WILL BE PRESENT ON SITE.	MEDIUM	PROPOSED WATER BODIES HAVE BEEN LOCATED AWAY FROM PUBLIC ACCESS AREAS. ACCESS TO THESE LOCATION WILL BE RESTRICTED FROM THE PUBLIC. CONTRACTOR WILL NEED TO TAKE ALL ACTIONS NECESSARY TO ADDRESS THIS HAZARD DURING CONSTRUCTION.	LOW

CONSTRUCTION HAZARD SCHEDULE		
ITEM	POTENTIAL HAZARD	POSSIBLE PREVENTATIVE ACTION
C1	DEEP EXCAVATION HAZARD	ALL STEPS MUST BE TAKEN TO OBTAIN CURRENT UNDERGROUND SERVICES INFORMATION BEFORE EXCAVATION WORKS COMMENCE. EXCAVATION WORK MUST BE UNDERTAKEN BY APPROPRIATELY EXPERIENCED AND QUALIFIED PERSONNEL. EXCAVATIONS SHALL BE ADEQUATELY SHORED AND APPROPRIATE BARRICADES AND SIGNAGE ERECTED, IF REQUIRED.
C2	OVERHEAD POWER HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF LIVE OVERHEAD CABLES. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING EARTHWORKS AND ANY OTHER HIGH RISK WORKS, IF REQUIRED.
C3	UNDERGROUND ELECTRICAL, TELECOMMUNICATION, GAS AND WATER MAIN HAZARD	WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF THE EXISTING SERVICE. THE SERVICE SHALL BE IDENTIFIED AND MARKED BY THE SUPPLY AUTHORITY PRIOR TO THE COMMENCEMENT OF EXCAVATION. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING THE EXCAVATION WORK, IF REQUIRED.
C4	WORKS NEAR RAIL, AIRPORTS AND ROADS HAZARD	ALL REQUIRED PERMITS, APPROVALS AND SAFETY REQUIREMENTS FROM THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHALL REMAIN ON SITE DURING CONSTRUCTION WHILE THE HAZARD REMAINS.
C5	PEDESTRIAN ACCESS HAZARD	WORK WITHIN OR ADJACENT TO AREAS WHICH THE PUBLIC REQUIRES PEDESTRIAN ACCESS MUST HAVE APPROPRIATE BARRICADES AND SIGNAGE ERECTED AT ALL TIMES.
C6	POTENTIAL VEHICLE HAZARD	SITE PERSONNEL SHALL BE ADVISED OF THE POTENTIAL HAZARDS AND THE APPROPRIATE PROCEDURES FOR WORKING ADJACENT TO OPERATING PUBLIC ROADS. APPROPRIATE SAFETY CLOTHING SHALL BE WORN AND THE REQUIRED SIGNAGE SHALL BE ERECTED. THE WORKS SHALL BE UNDERTAKEN IN A MANNER WHICH DOES NOT COMPROMISE THE SAFETY OF THE VEHICLE OCCUPANTS OR THE SITE PERSONNEL.
C7	DEMOLITION AND CLEARING HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE DEMOLITION AND CLEARING WORKS FOR THE PROJECT AT ALL TIMES. THE CONTRACTORS WORK METHOD STATEMENT SHALL ALSO GIVE CONSIDERATION TO FALLING DEBRIS, COLLAPSE AND DANGEROUS AIRBORNE AGENTS.
C8	TRAFFIC MANAGEMENT HAZARD	SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC THROUGH THE PROJECT AT ALL TIMES. THE CONTRACTOR SHALL DEVELOP A TRAFFIC MANAGEMENT PLAN (TMP) FOR THE PROJECT TO ESTABLISH APPROPRIATE CONTROLS IN ACCORDANCE WITH THE MANUAL FOR UNIFORM TRAFFIC CONTROL.
C9	ASBESTOS HAZARD	ALL PERSONNEL SHOULD BE ADVISED OF THE POTENTIAL PRESENCE OF ASBESTOS AND AN IDENTIFICATION AND ACTION PLAN SHALL BE PUT IN PLACE. SAMPLING AND IDENTIFICATION IS TO BE UNDERTAKEN IN ACCORDANCE WITH WORKPLACE HEALTH AND SAFETY REGULATIONS. IF SAMPLING CONFIRMS THE PRESENCE OF ASBESTOS THEN THE ACTION PLAN IS TO BE IMPLEMENTED TO REMEDIATE THE SITE.
C10	POTENTIAL ROCK FALL	LAND ABOVE THE SITE HAS BEEN CLEARED AND SOME EARTHWORKS HAS BEEN UNDERTAKEN CREATING A POTENTIAL ROCK FALL HAZARD. SUITABLE PERSONNEL SHALL BE RESPONSIBLE FOR IDENTIFYING ANY POTENTIAL HAZARD AND THE CONTRACTOR SHALL TAKE APPROPRIATE ACTION TO ELIMINATE THE HAZARD.

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB	
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB	
DATE	REV	DESCRIPTION	REC	APP	

REVISIONS




BRISBANE OFFICE

LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR

PATRICK BRADY

KPEQ 7112

SCALE

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD

PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT


LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
SAFETY IN DESIGN

JOB CODE
MIR-0801

SHEET NUMBER
C004

REV
B



LAYOUT PLAN
SCALE 1:500

PAVEMENT SUBGRADE GUARANTEE:
CONTRACTOR SHALL UNDERTAKE EARTHWORKS REQUIRED IN EITHER CUT OR FILL TO ENSURE THE SUBGRADE QUALITY IS AT CBR10 OR GREATER. CONTRACTOR TO LIAISE WITH OWN GEOTECHNICAL ENGINEER TO ACHIEVE REQUIREMENT.

STORMWATER TRENCH BACKFILL NOTE:
ALL STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

• FOR TYPICAL SECTIONS AND NOTES REFER TO DRAWING No. C300 - ROADWORKS TYPICAL SECTIONS AND NOTES, AND DRAWING No. C420 - STORMWATER DRAINAGE DETAILS AND NOTES.

LEGEND - PROPOSED

- PAVEMENT (ASPHALT)
- PAVEMENT (CONCRETE)
- PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'B2' KERB. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED 1.5m WIDE (U.N.O.) CONCRETE FOOTPATH. REFER LCC STD DWGS.
- PROPOSED CONCRETE LANDSCAPING FOOTPATH. REFER LANDSCAPING DRAWINGS FOR DETAILS.
- PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
- PROPOSED STORMWATER
- PROPOSED STORMWATER STRUCTURE No.
- ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C420.
- ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C420.
- PROPOSED ROOFWATER HOUSE CONNECTION (150 Ø uPVC)
- PROPOSED CONCRETE SLEEPER RETAINING WALL
- PROPOSED CONCRETE PANEL RETAINING WALL
- PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
- ZERO LOT BOUNDARY
- PROPOSED FUTURE DRIVEWAY LOCATION
- PROPOSED SEWER
- PROPOSED WATER
- PROPOSED WATER CONDUIT
- STAGE BOUNDARY
- PROPOSED LANDSCAPING. CIVIL CONTRACTOR TO COORDINATE WITH LANDSCAPING CONTRACTOR TO CARRY OUT THEIR WORKS. REFER TO LANDSCAPE DRAWINGS FOR FURTHER DETAIL.
- TREES
- PMT PADMOUNT TRANSFORMER

LEGEND - CONSTRUCTED

- ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C420.
- ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C420.
- STORMWATER
- SEWER
- WATER
- SEWER RISING MAIN
- RETAINING WALL
- STORMWATER STRUCTURE No.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 1


JOB CODE
MIR-0802
SHEET NUMBER
C100
REV
B

LEGEND - PROPOSED

- PAVEMENT (ASPHALT)
- PAVEMENT (CONCRETE)
- PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'B2' KERB. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
- PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
- PROPOSED 1.5m WIDE (U.N.O.) CONCRETE FOOTPATH. REFER LCC STD DWGS.
- PROPOSED CONCRETE LANDSCAPING FOOTPATH. REFER LANDSCAPING DRAWINGS FOR DETAILS.
- PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
- PROPOSED STORMWATER
- PROPOSED STORMWATER STRUCTURE No.
- ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C420.
- ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C420.
- PROPOSED ROOFWATER HOUSE CONNECTION (150 Ø uPVC)
- PROPOSED CONCRETE SLEEPER RETAINING WALL
- PROPOSED CONCRETE PANEL RETAINING WALL
- PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
- ZERO LOT BOUNDARY
- PROPOSED FUTURE DRIVEWAY LOCATION
- PROPOSED SEWER
- PROPOSED WATER
- PROPOSED WATER CONDUIT
- STAGE BOUNDARY
- PROPOSED LANDSCAPING. CIVIL CONTRACTOR TO COORDINATE WITH LANDSCAPING CONTRACTOR TO CARRY OUT THEIR WORKS. REFER TO LANDSCAPE DRAWINGS FOR FURTHER DETAIL.
- TREES
- PMT
- PADMOUNT TRANSFORMER

LEGEND - CONSTRUCTED

- ROOFWATER DRAINAGE KERB ADAPTORS WITH TWIN 125x75 GALVANISED RHS. REFER DETAIL ON DWG C420.
- ROOFWATER DRAINAGE KERB ADAPTORS. REFER DETAIL ON DWG C420.
- STORMWATER
- SEWER
- WATER
- SEWER RISING MAIN
- RETAINING WALL
- STORMWATER STRUCTURE No.



LAYOUT PLAN
SCALE 1:500

PAVEMENT SUBGRADE GUARANTEE:

CONTRACTOR SHALL UNDERTAKE EARTHWORKS REQUIRED IN EITHER CUT OR FILL TO ENSURE THE SUBGRADE QUALITY IS AT CBR10 OR GREATER. CONTRACTOR TO LAISE WITH OWN GEOTECHNICAL ENGINEER TO ACHIEVE REQUIREMENT.

STORMWATER TRENCH BACKFILL NOTE:

ALL STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

- FOR TYPICAL SECTIONS AND NOTES REFER TO DRAWING No. C300 - ROADWORKS TYPICAL SECTIONS AND NOTES, AND DRAWING No. C420 - STORMWATER DRAINAGE DETAILS AND NOTES.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C101
REV
B



LAYOUT PLAN
SCALE 1:500

LEGEND - PROPOSED

- NO CHANGES TO BULK EARTHWORKS. EARTHWORKS DONE AS PART OF PRECINCT 10.2, 10.4 & 8.1 EARTHWORKS PACKAGES
- EXTENT OF CUT
- EXTENT OF FILL
- 12.0 FINISHED MAJOR CONTOURS (0.50m)
- FINISHED MINOR CONTOURS (0.25m)
- 51.65 FINISHED SURFACE LEVEL
- PROPOSED CONCRETE SLEEPER RETAINING WALL (AND HEIGHT). TIMBER TEXTURED SLEEPERS AND 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED CONCRETE PANEL RETAINING WALL (AND HEIGHT). 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED TERRACE LOT FRONTING PARK BY OTHERS RETAINING WALL (AND HEIGHT). RETAINING WALL TYPE TBC.
- FEATURE FENCE BY LANDSCAPER
- FOOTPATH SPOT LEVEL
- ZERO LOT LINE
- PROPOSED FUTURE DRIVEWAY LOCATION
- STAGE BOUNDARY
- 1m WIDE, 200mm HIGH STEP TERRACE LOTS STAIRS FRONTING PARK

LEGEND - CONSTRUCTED

- RETAINING WALL
- CONTOURS (0.50m)
- STORMWATER
- SEWER
- WATER
- SEWER RISING MAIN

NOTES

- REFER TO BULK EARTHWORKS NOTES & DETAILS DRAWINGS FOR:
 - EARTHWORKS NOTES AND DETAILS
 - RETAINING WALL NOTES AND DETAILS
- PROPOSED SERVICES ARE WITHIN THE VICINITY OF RETAINING WALLS. REFER SERVICE DRAWINGS FOR SERVICE LOCATIONS AND DETAILS.
- EXISTING DWELLINGS, FENCES ETC TO BE DEMOLISHED AND REMOVED OFF SITE BY OTHERS (UNLESS NOTED OTHERWISE)
- FINAL RETAINING WALL TYPES AND FINISHES SHALL BE CONFIRMED WITH THE SUPERINTENDENT PRIOR TO CONSTRUCTION.

EARTHWORKS FOR LOTS 4011-4012, 4017-4018, 4039-4044 & 4076-4094 COMPLETED AS PART OF PRECINCT 9 & 10.1 WORKS

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION - ADDED WALL BETWEEN LOTS 4172 AND 4173	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
DATE	REV	DESCRIPTION	REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
BULK EARTHWORKS LAYOUT PLAN - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C200
REV
B



LAYOUT PLAN
SCALE 1:500

EARTHWORKS FOR LOTS 4011-4012, 4017-4018, 4039-4044 & 4076-4094 COMPLETED AS PART OF PRECINCT 9 & 10.1 WORKS

LEGEND - PROPOSED

- NO CHANGES TO BULK EARTHWORKS. EARTHWORKS DONE AS PART OF PRECINCT 10.2, 10.4 & 8.1 EARTHWORKS PACKAGES
- EXTENT OF CUT
- EXTENT OF FILL
- FINISHED MAJOR CONTOURS (0.50m)
- FINISHED MINOR CONTOURS (0.25m)
- FINISHED SURFACE LEVEL
- PROPOSED CONCRETE SLEEPER RETAINING WALL (AND HEIGHT). TIMBER TEXTURED SLEEPERS AND 2 COAT PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED CONCRETE PANEL RETAINING WALL (AND HEIGHT). 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER
- PROPOSED TERRACE LOT FRONTING PARK BY OTHERS RETAINING WALL (AND HEIGHT). RETAINING WALL TYPE TBC.
- FEATURE FENCE BY LANDSCAPER
- FOOTPATH SPOT LEVEL
- ZERO LOT LINE
- PROPOSED FUTURE DRIVEWAY LOCATION
- STAGE BOUNDARY
- 1m WIDE, 200mm HIGH STEP TERRACE LOTS STAIRS FRONTING PARK

LEGEND - CONSTRUCTED

- RETAINING WALL
- CONTOURS (0.50m)
- STORMWATER
- SEWER
- WATER
- SEWER RISING MAIN

NOTES

- REFER TO BULK EARTHWORKS NOTES & DETAILS DRAWINGS FOR:
 - EARTHWORKS NOTES AND DETAILS
 - RETAINING WALL NOTES AND DETAILS
- PROPOSED SERVICES ARE WITHIN THE VICINITY OF RETAINING WALLS. REFER SERVICE DRAWINGS FOR SERVICE LOCATIONS AND DETAILS.
- EXISTING DWELLINGS, FENCES ETC TO BE DEMOLISHED AND REMOVED OFF SITE BY OTHERS (UNLESS NOTED OTHERWISE)
- FINAL RETAINING WALL TYPES AND FINISHES SHALL BE CONFIRMED WITH THE SUPERINTENDENT PRIOR TO CONSTRUCTION.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
BULK EARTHWORKS LAYOUT PLAN - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C201
REV
B

NOTES

1.

LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
2.

EARTHWORKS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL LAYOUT PLANS AND EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
3.

ALL EARTHWORKS TO BE CARRIED OUT UNDER 'LEVEL ONE' GEOTECHNICAL CONTROL IN ACCORDANCE WITH LOCAL AUTHORITIES AND AS3798.
4.

EXCESS CUT TO BE STOCKPILED IN THE LOCATION SHOWN OR AS DIRECTED ON SITE.
5.

ALL BATTERS ARE 1 IN 4 UNLESS SHOWN OTHERWISE.
6.

CONTRACTOR TO INSTALL TEMPORARY CONSTRUCTION FENCING ALONG THE FULL PERIMETER BOUNDARY INCLUDING APPROPRIATE SIGNAGE.

TESTING

1.

THE SUPERINTENDENT MAY ORDER ADDITIONAL TESTS. REFER TO THE LOCAL AUTHORITIES SPECIFICATION FOR STANDARDS OF COMPACTION AND MATERIAL STANDARDS. FAILED TESTS WILL BE AT THE CONTRACTOR'S EXPENSE.

EARTHWORKS TESTING

1.

COMPACTION TESTS

LOCATION	AREA PER TEST
FINISHED LEVEL OR ROAD SUBGRADE (IN CUT OR FILL)	REFER TO THE LOCAL AUTHORITY SPECIFICATION
LOWEST TWO LEVELS OF EMBANKMENT (PER LAYER)	
OTHER LAYERS OF EMBANKMENT	
PREPARED NATURAL GROUND UNDER EMBANKMENT	
2.

QUALITY TESTS

QUALITY TESTS OF IMPORTED MATERIAL ARE REQUIRED AS SET OUT BY LOCAL AUTHORITY.
3.

SUBGRADE TESTS

THE NUMBER AND LOCATION OF PAVEMENT SUBGRADE TESTS SHALL BE IN ACCORDANCE WITH LOGAN CITY COUNCIL SPECIFICATION REQUIREMENTS.

DUST

1.

NO VISIBLE DUST EMISSIONS MUST OCCUR AT THE BOUNDARIES OF THE SITE DURING EARTHWORKS AND CONSTRUCTION ACTIVITIES ON THE SITE. DUST CONTROL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH AS/NZS3580.10.1:2003. DUST CONTROL SHALL COMPLY WITH THE NSW DEPARTMENT OF ENVIRONMENT AND CONSERVATION REPORT 'APPROVED METHODS & GUIDANCE FOR THE MODELLNG AND ASSESSMENT OF AIR POLLUTANTS IN NSW'.
2.

THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN CONTROLS TO ACHIEVE THE REQUIREMENTS OF ITEM 1 ABOVE.

FILL MANAGEMENT

1.

ALL FILL MATERIAL WILL BE PLACED IN ACCORDANCE WITH THE FILL SPECIFICATION PROVIDED ON THIS SHEET, OR WHERE PROVIDED, THE REQUIREMENTS OF THE GEOTECHNICAL REPORT SPECIFIC TO THIS CONTRACT.
2.

THE FILL MATERIAL WILL COMPRISE ONLY OF NATURAL EARTH AND ROCK AND SHALL BE FREE OF ALL CONTAMINATES, NOXIOUS, HAZARDOUS, DELETERIOUS AND ORGANIC MATERIAL.
3.

ALL SITE PREPARATION WORK SHOULD GENERALLY BE CARRIED OUT IN ACCORDANCE WITH AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS'.
4.

THE SITE SHOULD BE STRIPPED OF ANY TOPSOIL FROM CUT AND FILL AREAS, ROAD ALIGNMENTS AND CARPARKING AREAS, AND STOCKPILED FOR LATER USE.
5.

PRIOR TO THE PLACEMENT OF ANY STRUCTURAL FILL THE SITE SHOULD BE PROOF ROLLED USING A MINIMUM 10 TONNE (STATIC WEIGHT) PADFOOT ROLLER. ANY LOOSE OR SOFT AREAS SHOULD BE REMOVED AND RECOMPACTED OR REPLACED USING A COMPACTED SELECT FILL.
6.

DEPRESSIONS FORMED BY THE REMOVAL OR VEGETATION, EXISTING STRUCTURES, UNDERGROUND SERVICES ETC., SHOULD HAVE ALL DISTURBED SOIL CLEANED OUT AND BE BACKFILLED WITH COMPACTED SELECT FILL MATERIAL.
7.

ALL COMPLIANCE TESTING SHALL BE CARRIED OUT BY THE GEOTECHNICAL ENGINEER WHO WILL BE ENGAGED BY THE PRINCIPAL CONTRACTOR. ANY/ALL TESTING NECESSARY FOR GUIDANCE OR RE-TESTS WILL BE AT THE COST OF THE CONTRACTOR.
8.

THE PLACEMENT OF FILL TO BE EXECUTED SUCH THAT TO BE FREE DRAINING AT ALL TIMES AND NOT TO BE A NUISANCE OR PONDING TO ADJOINING PROPERTY OR ROADS.
9.

NO DEMOLITION MATERIAL TO BE USED AS FILL MATERIAL.
10.

WHERE UNSUITABLE MATERIAL IN AREAS OF FILL IS ENCOUNTERED, THIS WILL BE TREATED AS SET OUT IN THE EARTHWORK SPECIFICATION.
11.

ALL VEHICLES EXITING FROM THE SITE TO BE CLEAN TO PREVENT MATERIAL BEING TRACKED OR DEPOSITED ON THE ADJOINING PUBLIC ROADS, REFER ENVIRONMENTAL MANAGEMENT NOTES ON THE EROSION AND SEDIMENT CONTROL DRAWINGS.
12.

SITE ACCESS TO AND ACROSS THE SITE ARE SUBJECT TO SUPERINTENDENT APPROVAL.

TOPSOIL RESPREAD REQUIREMENTS

TOPSOIL RESPREAD THICKNESS SHALL BE AS SPECIFIED BELOW IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TOPSOIL RESPREAD LOCATIONS AND THICKNESS.

TURF

CONTRACTOR SHALL SUPPLY AND LAY TURF AS SPECIFIED IN THE FOLLOWING AREAS:

- REFER TO EROSION & SEDIMENT CONTROL - STABILISATION PHASE DRAWING FOR TURF SUPPLY AND LAY AREAS.

TRENCH SPOIL

EXCESS TRENCH SPOIL MATERIAL GENERATED BY THIS CONTRACT SHALL BE PLACED EITHER WITHIN THE FILL ZONE NOMINATED ON THE EARTHWORKS DRAWINGS OR WITHIN A FILL ZONE NOMINATED BY THE SUPERINTENDENT THAT SHALL BE CONFIRMED PRIOR TO CONSTRUCTION COMMENCEMENT. FILL TO BE PLACED UNDER LEVEL 1 SUPERVISION AND IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION.

TRENCH BACKFILL

CBR15 STORMWATER TRENCH BACKFILL MATERIAL SHALL BE SOURCED FROM ON SITE EXCAVATED MATERIAL.

EXCAVATION IN ROCK

CONTRACT SHALL INCLUDE TREATING, SIZING, CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED TO ENSURE THAT FILL SPECIFICATION AND LEVEL ONE CERTIFICATION IS ACHIEVED.

EVERLEIGH EARTHWORKS TOLERANCE TABLE

ITEM	TOLERANCE
EARTHWORKS IN ALLOTMENTS AND VERGES ^(a)	EWL or FSL +/- 50mm
CUT BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 150mm ^(b)
FILL BATTERS (OTHER THAN IN LOTS)	EWL or FSL +/- 300mm ^(b)
EARTHWORKS IN PARKS	EWL or FSL +/- 50mm

^(a) TOLERANCE IS -0mm / +50mm WHERE ADJACENT DRAINAGE ELEMENT.
^(b) MEASURED FROM THE AVERAGE SLOPE PLANE.

TOLERANCE NOTES

1.

EARTHWORKS LEVEL (EWL) IS 100mm BELOW FINISHED SURFACE LEVEL (FSL) ON ALLOTMENTS (TOPSOIL RESPREAD THICKNESS).
2.

FINISHED SURFACE LEVEL (FSL) IS TOP OF TURF / STABILISED TOPSOIL LEVEL.
3.

ROADWORKS SUBGRADE, PAVEMENT, ASPHALT CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
4.

STORMWATER DRAINAGE CONSTRUCTION LEVEL TOLERANCES AS PER LCC PSP No. 5.
5.

SEWER AND WATER RETICULATION CONSTRUCTION LEVEL TOLERANCES AS PER SEQ D&C CODE.

DISPERSIVE SOILS MANAGEMENT NOTES

1.

GYPSTUM TREATMENT FOR DISPERSIVE SOILS SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE EVERLEIGH DISPERSIVE SOIL MANAGEMENT PLAN (REPORT #GE20.042.R1). AREAS THAT REQUIRED TREATMENT REGARDLESS OF NOMINATING ON PLANS ARE:
 - ALL SERVICE TRENCHES BELOW AND ABOVE BEDDING MATERIAL, INCLUDING STRUCTURES, E.G. MANHOLES.
 - UNDER AND SURROUNDING STORMWATER HEADWALLS
 - TURF/LANDSCAPED AREAS SUBJECT TO DIRECTED WATER FLOWS. TREATMENT AT FINISHED EARTHWORKS PRIOR TO TOPSOIL PLACEMENT/FINISH LANDSCAPE SURFACE.
 - TURF/LANDSCAPED AREAS SUBJECT TO WATER PONDING. TREATMENT AT FINISHED EARTHWORKS PRIOR TO TOPSOIL PLACEMENT/FINISH LANDSCAPE SURFACE.
 - TREATMENT TO INSITU/UNTOUCHED ROCK IS NOT REQUIRED.
2.

STABILISATION OF DISTURBED AREAS AND MANAGEMENT OF EROSION AND SEDIMENT SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLANS IN THIS DRAWING SET. THE CONTRACTOR IS TO REVIEW THE PROPOSED DRAINS AND DETERMINE IF TREATMENT TO ANY DIVERSION DRAIN IS REQUIRED BASED ON TIME IN USE ON DURING WORKS. TREATMENT TO BE IN ACCORDANCE WITH THE DSMP.
3.

CONTRACTOR MUST CONSTRUCT AND ESTABLISH THE EROSION AND SEDIMENT CONTROL DEVICES, CONSTRUCTION WORK HOLDING DAM AND HES BASIN PRIOR TO COMMENCING EARTHWORKS OPERATION. TREATMENT TO THE SURFACE OF ANY WATER RETAINING BODY SHALL BE IN ACCORDANCE WITH THE DSMP
4.

ALL DISTURBED AREAS SHALL BE STABILISED AS SOON AS PRACTICABLE (BUT NOT MORE THAN 10 DAYS) FOLLOWING FINALISATION OF LEVELS. STABILISATION TO BE IN ACCORDANCE WITH EROSION & SEDIMENT CONTROL - STABILISATION PHASE.

TOPSOIL AMELIORATION

ONSITE STRIPPED TOPSOIL SHALL BE AMELIORATED PRIOR TO RESPREAD. THE FOLLOWING AMELIORATION SPECIFICATIONS SHALL APPLY:

A-GRADE QUALITY TOPSOIL AMELIORATION:

- SCREEN STRIPPED TOPSOIL
- ON-SITE COMPOST INCORPORATION (0.15kg/m³ OF TOPSOIL)
- DOLOMITE (15kg/m³ OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m³ OF TOPSOIL)
- FERTILISER (0.4kg/m³ OF TOPSOIL)

B-GRADE QUALITY TOPSOIL AMELIORATION:

- SCREEN STRIPPED TOPSOIL
- DOLOMITE (15kg/m³ OF TOPSOIL)
- GRANULAR WETTING AGENT (0.5kg/m³ OF TOPSOIL)
- FERTILISER (0.4kg/m³ OF TOPSOIL)

ROCK TREATMENT IN ALLOTMENTS

WHERE ALLOTMENTS ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 500mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL), AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

ALL CUT LOTS WHICH ARE NOT LOCATED IN ROCK MUST ACHIEVE 100kPa BEARING CAPACITY. WHERE THIS CAN'T BE ACHIEVED, THE CONTRACTOR SHALL RECTIFY THE SUBGRADE IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION TO ACHIEVE A 100kPa BEARING CAPACITY.

ROCK TREATMENT IN VERGES

WHERE ROAD RESERVES ARE LOCATED IN CUT, THE CONTRACTOR SHALL OVER-EXCAVATE A MINIMUM 1000mm DEPTH BELOW DESIGN EARTHWORKS LEVEL (EWL) AND RECOMPACT IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND LEVEL ONE SUPERVISION.

EARTHWORKS SPECIFICATION

SPECIFICATION	DEPTH RANGE (m)				PAVEMENT SUBGRADE	TRENCH BACKFILL
	0.0 - 0.6	0.6 - 3.00	3.00 - 5.00	> 5.00		
CBR %	-	-	-	-	10	15
LAYER THICKNESS (mm)	300	300	300	300	BETWEEN SUBGRADE AND 0.3m BELOW	300
MAXIMUM PARTICLE SIZE (mm)	200	500	500	500	200	200
% PASSING 37.5mm	80% MIN	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES	REFER NOTES AND KEY OUTCOMES
% PASSING 0.075mm	30% MIN	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES	REFER NOTES AND AS3798
COMPACTION	95% STD	95% STD	95% STD	95% STD	100% STD	95% MOD IN ROADS AND 95% STD OUTSIDE ROADS
MOISTURE	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	+/- 2% OMC	60% - 90% OF OMC	+/- 2% OMC
NOTES: <div>1. OMC - OPTIMUM MOISTURE CONTENT</div> <div>2. LAYER OF THICKNESS IS LIMITED TO 300mm TO ALLOW IDENTIFICATION OF LARGER PARTICLES AND ALLOW EVERY CHANCE OF BREAK DOWN IN FILLING OR REMOVAL.</div> <div>3. TREATMENT OF ROCK TO SIZES ABOVE SHOULD BE CARRIED OUT IN CUT PRIOR TO LOADING TO FILL AREAS. TREATED ROCK TO BE APPROVED BY GITA PRIOR TO TRANSPORTING.</div> <div>4. UPPER 0.6m, (PARTICULARLY IN AREAS OF DEEP FILL), OF THE FILL PROFILE TO BE RELATIVELY IMPERMEABLE HENCE INCREASE IN FINES COMPONENT.</div> <div>5.PROOF ROLL TESTING ON EACH COMPACTED LAYER USING RUBBER WHEELED PLANT SUCH AS LOADED ADT'S OR LOADED SCRAPERS. UNFAVOURABLE DEFORMATION OF THE COMPACTED SURFACE UNDER LOAD OF ADT'S OR SCRAPERS WILL REQUIRE REPAIR PRIOR TO ADDITIONAL PLACEMENT.</div> <div>6. MECHANICAL INTERLOCK METHODOLOGY IS NOT APPROPRIATE DUE TO POOR DURABILITY OF SITE WON SANDSTONE. FILL COMPOSITION IS REQUIRED TO INCLUDE AN APPROPRIATE SAND GRAVEL AND FINES COMPONENT CONFORMING TO THE REQUIREMENTS OF AS798.</div>						
KEY OUTCOMES FOR EARTHWORKS OPERATIONS <div>1. DELIVER RESIDENTIAL LOTS WITH FAVOURABLE LOT CLASSIFICATIONS - I.E - NO P CLASSIFICATIONS</div> <div>2. FILL THICKNESS DOES NOT VARY MORE THAN 2m OVER A DISTANCE OF 10m</div> <div>3. CONSTRUCT FILL AND LIMIT LONG TERM CREEP SETTLEMENTS TO WITHIN 0.5% TO 1.0% OF THE FILL THICKNESS</div> <div>4. BUILDING PLATFORM THAT ALLOWS BUILDERS TO CONSTRUCT SLAB ON GROUND RAFTS USING LIGHT EARTHMOVING EQUIPMENT</div> <div>5. MATERIAL WON FROM CUTS AND USED IN FILL WITH REQUIRE<ul style="list-style-type: none">CUTS IN ROCK AS WELL AS BLENDED WITHCUTS IN FINER MATERIALS SUCH AS SANDS AND CLAYS</div> <div>6. CREATING A FILL PLATFORM THAT IS ABLE TO BE TESTED IN ACCORDANCE WITH AS3798 AND AS1289</div>						

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au


DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR PATRICK BRADY

PKB
NPEQ 7112


SCALE
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	BULK EARTHWORKS NOTES AND DETAILS - SHEET 1


JOB CODE	MIR-0802
SHEET NUMBER	C210
REV	B




TYPICAL RETAINING WALL SUBSOIL
OUTLET TO ROAD
N.T.S.




TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT
0.4m-2m MAX HIGH
N.T.S.




TYPICAL RETAINING WALL DETAIL
ROAD ADJACENT TO LOT WHERE ROAD LEVEL IS HIGHER
N.T.S.




TYPICAL RETAINING WALL DETAIL
ROAD ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER
N.T.S.




TYPICAL RETAINING WALL SUBSOIL
OUTLET TO ALLOTMENTS
N.T.S.




TYPICAL RETAINING WALL DETAIL INTER ALLOTMENT
2m-2.5m MAX HIGH
N.T.S.




TYPICAL RETAINING WALL DETAIL
PARK ADJACENT TO LOT WHERE PARK LEVEL IS HIGHER
N.T.S.




TYPICAL RETAINING WALL DETAIL
PARK ADJACENT TO LOT WHERE LOT LEVEL IS HIGHER
N.T.S.



TYPICAL INTER ALLOTMENT RETAINING WALL
TOP OF WALL SETOUT AND END DETAIL
N.T.S.



TYPICAL RETAINING WALL TOP AND BOTTOM
FINISHING LEVEL DETAIL
N.T.S.



TYPICAL SECTION FOR
BATTERS BETWEEN LOTS
SCALE 1:20

RETAINING WALL DESIGN:

- ALL RETAINING WALLS SHALL BE DESIGNED & CONSTRUCTED IN ACCORDANCE WITH THE "DESIGN AND CONSTRUCTION RETAINING WALL SPECIFICATION" PREPARED BY PREMISE ENGINEERING.
- RETAINING WALLS ARE TO BE DESIGNED TO ACHIEVE A MINIMUM OF 50 YEAR DESIGN LIFE.
- RETAINING WALLS ARE TO BE DESIGNED IN ACCORDANCE WITH THE AS4678- EARTH RETAINING STRUCTURES AND RELEVANT MATERIAL STANDARDS (E.G AS3600- CONCRETE STRUCTURES).

RETAINING WALL SUBSOIL DRAINAGE OUTLET DESIGN:

RETAINING WALL SUBSOIL DRAINAGE PIPE OUTLET LOCATIONS SHALL BE IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION. THE PRINCIPAL CIVIL CONTRACTOR SHALL DETERMINE THE LOCATION OF RETAINING WALL SUBSOIL DRAINAGE PIPES IN ACCORDANCE WITH THE EVERLEIGH RETAINING WALL DESIGN SPECIFICATION AND PROVIDE PROPOSAL TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION.

RETAINING WALL SHOP DRAWINGS

CONTRACTOR MUST PREPARE RETAINING WALL SHOP DRAWINGS FOR APPROVAL BY SUPERINTENDENT PRIOR TO COMMENCING RETAINING WALL CONSTRUCTION. SHOP DRAWINGS ARE TO DETAIL THE FOLLOWING ELEMENTS:

- ELEVATIONS OF ALL PROPOSED RETAINING WALLS AND ACOUSTIC FENCES
- TOP AND BOTTOM RLS TO SLEEPER/PANEL
- FINISHED PAD/ROAD SURFACE LEVELS
- DIMENSIONS OF RETAINING WALL END FINISHING CONFIGURATION, OFFSETS FROM BOUNDARIES
- POST DETAILS FOR INTRICATE INTERSECTION POINTS

PROPERTY SERVICES UNDER RETAINING WALLS:

CONTRACTOR SHALL REFER TO ALL LATEST SERVICE DRAWINGS TO ENSURE PROVISIONS ARE MADE FOR ALL PROPERTY SERVICE CONNECTIONS UNDER RETAINING WALLS.

PAD MOUNTED TRANSFORMER NOTE

- RETAINING WALLS AND THEIR FOOTINGS SHALL NOT ENCRANCH INTO THE PMT SITE (AS PER RETAINING WALLS LOCATED ADJACENT ROAD RESERVES DETAIL) UNLESS THE RETAINING WALL SPECIFIED IS AN ENERGEX STANDARD MASONRY WALL.
- RETAINING WALL DESIGN SHALL CONSIDER ENERGEX REQUIREMENT WHERE RETAINING WALLS ARE LOCATED WITHIN 2m OF PMT SITE.

RETAINING WALL TYPE

PRIVATE FACING RETAINING WALLS:
CONCRETE SLEEPER RETAINING WALL. TIMBER TEXTURED SLEEPERS AND 2 COAT PAINT (COLOUR WARM GREY 10C). DESIGN SPECIFICATION BY MANUFACTURER.

PUBLIC FACING RETAINING WALLS:
CONCRETE PANEL RETAINING WALL. 2 COAT TEXTURED PAINT. DESIGN SPECIFICATION BY MANUFACTURER.

FENCE BRACKETS

PROVIDE FENCE BRACKETS TO ALL RETAINING WALLS. NO BRACKETS TO BE PROVIDED WITHIN THE FIRST 5m FROM FRONT BOUNDARY FOR INTER-ALLOTMENT RETAINING WALLS.



LEGEND - PROPOSED

- NO CHANGES TO BULK EARTHWORKS. EARTHWORKS DONE AS PART OF PRECINCT 10.2, 10.4 & 8.1 EARTHWORKS PACKAGES
- EXTENT OF CUT
- EXTENT OF FILL
- TREES
- BOLLARD
- STREET TREE / PLANTING AREA. CONTRACTOR TO ENSURE AREA IS FREE OF ROCK UP TO A DEPTH OF 1.5M BELOW DESIGN FSL (I.E. ENSURE AREA IS EASY DIGGING FOR THE INSTALLATION OF TREES AND PLANTING). CONTRACTOR TO ALSO ENSURE THESE AREAS ARE CONNECTED INTO THE NEAREST STORMWATER STRUCTURE AND MADE FREE DRAINING VIA SLOTTED AGI PIPE.

ALLOTMENT PREPARATION REQUIREMENT:

CONTRACTOR SHALL ENSURE THAT ALL ALLOTMENTS WHERE LOCATED IN CUT WITHIN ROCK, SHALL BE OVER-EXCAVATED A MINIMUM 500mm DEPTH BELOW DESIGN EARTHWORKS LEVEL AND RECOMPACTED TO LEVEL ONE CERTIFICATION.

LAYOUT PLAN
SCALE 1:750

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	KK	PB
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 15 30 45m
SCALE 1:750(A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
EARTHWORKS SUBGRADE ROCK PREPARATION DETAILS

JOB CODE
MIR-0802
SHEET NUMBER
C220
REV
B



LEGEND - PROPOSED

- PROPOSED RETAINING WALL SUBSOIL DRAINAGE
- PROPOSED STORMWATER
- RETAINING WALL SUBSOIL OUTLET TO ALLOTMENT
REFER DRAWING C211 FOR TYPICAL DETAILS
- RETAINING WALL SUBSOIL STUB
- PROPOSED RETAINING WALL
- PROPOSED SEWER
- PROPOSED WATER
- STAGE BOUNDARY

LEGEND - CONSTRUCTED

- RETAINING WALL
- STORMWATER
- SEWER
- WATER
- SEWER RISING

LAYOUT PLAN
SCALE 1:500

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
DATE	REV	DESCRIPTION	REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
RETAINING WALL SUBSOIL DRAINAGE PLAN - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C230
REV
B



LEGEND - PROPOSED

- PROPOSED RETAINING WALL SUBSOIL DRAINAGE
- PROPOSED STORMWATER
- RETAINING WALL SUBSOIL OUTLET TO ALLOTMENT
REFER DRAWING C211 FOR TYPICAL DETAILS
- RETAINING WALL SUBSOIL STUB
- PROPOSED RETAINING WALL
- PROPOSED SEWER
- PROPOSED WATER
- STAGE BOUNDARY

LEGEND - CONSTRUCTED

- RETAINING WALL
- STORMWATER
- SEWER
- WATER
- SEWER RISING

LAYOUT PLAN
SCALE 1:500


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112




CLIENT	MIRVAC QLD PTY LTD	JOB CODE	MIR-0802
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER	C231
LOCATION	TEVIOT ROAD, GREENBANK	REV	B
SHEET TITLE	RETAINING WALL SUBSOIL DRAINAGE PLAN - SHEET 2		

NOTES

- 1. ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARD DRAWINGS AND METHODS (U.N.O.).
- 2. NOTWITHSTANDING THE LIMITS OF CUTTING AND FILLING SHOWN ON THE DRAWINGS, THE ACTUAL LIMITS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT DURING CONSTRUCTION AND SIMILARLY THE FINISHED SURFACE CONTOURS MAY BE ADJUSTED BY WRITTEN DIRECTION OF THE SUPERINTENDENT DURING CONSTRUCTION.
- 3. THE CONTRACTOR IS TO ASCERTAIN THE EXACT LOCATION OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE COST OF RECTIFICATION OF ANY DAMAGES TO EXISTING SERVICES WHICH MAY OCCUR. THE LOCATION OF EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY.
- 4. SUBGRADE TEST RESULTS TO BE FORWARDED TO SUPERINTENDENT FOR DETERMINATION OF BOX DEPTHS PRIOR TO EXCAVATION. TESTS SHALL INCLUDE SOAKED CBR AND/OR OTHER TESTS AS REQUESTED BY THE SUPERINTENDENT.
- 5. ALLOTMENT FILLING TO BE COMPACTED TO 95% (min) OF THE R.D.D. (AS 1289 - TESTS E1.1, E4.1).
- 6. LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.
- 7. LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS APPROVED BY THE SUPERINTENDENT TO ACHIEVE SATISFACTORY CONNECTION TO THE EXISTING WORKS.
- 8. SIDE DRAINS AND MITRE DRAINS TO BE CONSTRUCTED ADJACENT TO ALL KERB AND CHANNEL.
- 9. PROVIDE FLUSH POINTS TO SUBSOIL DRAINS, LOCATIONS TO BE CONFIRMED ON SITE.
- 10. ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION. ALL PIPES ARE 375mm DIAMETER U.N.O.
- 11. GULLIES AND GULLY GRATES SHALL BE TO STD. DRGs BSD-8051 - BSD-8059.
- 12. KACEY GALV. STEEL KERB ADAPTORS ARE TO BE INSTALLED TO THE REQUIREMENTS OF THE LOCAL COUNCILS STANDARD DRAWINGS AND SPECIFICATIONS.
- 13. ALL LOTS SHOWN BOXED TO HAVE ROOFWATER FOOTPATH CROSSINGS TO KERB. CROSSINGS ARE TO BE 88.9 DIA. GALV. CHS.TO KACEY KERB ADAPTOR.
- 14. ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
- 15. ROOFWATER PITS ARE TO BE 600mm DIAMETER FOR DEPTHS LESS THAN 750mm, 900mm DIAMETER FOR DEPTHS BETWEEN 750mm AND 1500mm DEEP AND 1050mm DIAMETER FOR DEPTHS GREATER THAN 1500mm.
- 16. ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
- 17. HAZARD MARKERS (D4-4A) TO BE PLACED AT THE END OF NEW WORKS AS DIRECTED BY SUPERINTENDENT.
- 18. SITE CBR VALUE AND PAVEMENT DESIGN AND DEPTHS TO BE VERIFIED WITH CBR TESTS PRIOR TO CONSTRUCTION.
- 19. LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 20. TO BE READ IN CONJUNCTION WITH ALL STORMWATER DRAINAGE LAYOUT PLANS & ROADWORKS DETAILS.


ROADWORKS NOTES

- 1. GEOTECHNICAL TESTING FOR PAVEMENT CONSTRUCTION IS TO BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT SPECIFICATION. TEST CERTIFICATES ARE TO BE PREPARED BY A REGISTERED N.A.T.A. LABORATORY AT THE CONTRACTORS COST AND SHALL BE PROVIDED TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS. THE CONTRACTOR IS TO NOTIFY THE ENGINEER OF ANY NON-CONFORMANCES. ALL NON CONFORMING WORK IS TO BE RECTIFIED AS DIRECTED BY THE ENGINEER.
- 2. FULL DEPTH PAVEMENT CONSTRUCTION SHALL EXTEND BEHIND ALL KERB AND KERB AND CHANNEL FOR A DISTANCE WHICH IS THE GREATER OF 150mm FROM THE BACK OF KERB OR ACROSS TO THE OUTER LIMIT OF SIDE DRAIN FILTER MATERIAL.
- 3. TRANSITION KERB AND CHANNEL TO BARRIER KERB SMOOTHLY OVER MIN. 1.0m LENGTH.
- 4. PAVEMENT THICKNESSES NOMINATED ON THESE DRAWINGS ARE PROVISIONAL ONLY AND MAY BE VARIED BY THE SUPERINTENDENT SUBJECT TO INSITU PAVEMENT SUBGRADE TESTING. PAVEMENT SUBGRADES ARE TO BE INITIALLY CONSTRUCTED TO THE UNDERSIDE OF THE NOMINATED LOWER SUBBASE COURSE WITHIN FILL AREAS, AND TO THE UNDERSIDE OF THE NOMINATED UPPER SUBBASE COURSE WITHIN CUT AREAS. INSITU SUBGRADE CBR TESTING AS SPECIFIED FOR PAVEMENT DESIGN VERIFICATION IS TO BE CARRIED OUT AT THESE LEVELS.
- 5. REPAIR ANY DAMAGE TO EXISTING KERB AND CHANNEL, FOOTPATH OR ROADWAY (INCLUDING REMOVAL OF CONCRETE SLURRY FROM FOOTPATHS, ROADS, KERB AND CHANNEL AND STORMWATER GULLIES AND SIDEDRAINS) THAT MAY OCCUR DURING ANY WORKS CARRIED OUT.



TYPICAL PAVEMENT CUT-BACK DETAIL

N.T.S



TYPICAL FUTURE ROADS BOX-OUT TREATMENT

NOTE: CONTRACTOR TO PROVIDE BOX-OUT TREATMENT ON ROAD BOXES OF FUTURE ROADS UPSTREAM OF ADJOINING COMPLETED ROADS.

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB	
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB	
DATE	REV	DESCRIPTION	REC	APP	

REVISIONS



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR PATRICK BRADY

KPEQ 7112



SCALE
0 0.4 0.8 1.2m
SCALE 1:20 (A1)
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	ROADWORKS NOTES AND DETAILS

JOB CODE	MIR-0802
SHEET NUMBER	C300
REV	B

PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	ROAD 115 (CH.677.70-CH.755.20)
CLASS	-	ACCESS STREET (PARK)
ESA's	-	5.90 x 10 ⁵
SURFACE	-	35mm AC of 10mm MIX
PRIMER TYPE	-	PRIME
CBR 80	-	150mm
CBR 45	-	150mm
TOTAL BOX	-	335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.



FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112


SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 115 LONG AND CROSS SECTIONS


JOB CODE
MIR-0802
SHEET NUMBER
C310
REV
B

PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	ROAD 117 (CH.163.02-CH.260.00)
CLASS	-	ACCESS STREET (TYPICAL)
ESA's	-	5.90 x 10 ⁵
SURFACE	-	35mm AC of 10mm MIX
PRIMER TYPE	-	PRIME
CBR 80	-	150mm
CBR 45	-	150mm
TOTAL BOX	-	335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.



ROAD 117 LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



ROAD 117 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112


SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 117 LONG AND CROSS SECTIONS


JOB CODE
MIR-0802
SHEET NUMBER
C311
REV
B

PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	ROAD 119 (CH.0.00-CH.42.78)
CLASS	-	ACCESS STREET (TYPICAL)
ESA's	-	5.90 x 10 ⁵
SURFACE	-	35mm AC of 10mm MIX
PRIMER TYPE	-	PRIME
CBR 80	-	150mm
CBR 45	-	150mm
TOTAL BOX	-	335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.



ROAD 119 LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				

 **BRISBANE OFFICE**
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 119 LONG AND CROSS SECTIONS

JOB CODE
MIR-0802
SHEET NUMBER
C312
REV
B

PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	ROAD 120 (CH.0.00-CH.42.75)
CLASS	-	ACCESS STREET (TYPICAL)
ESA's	-	5.90 x 10 ⁵
SURFACE	-	35mm AC of 10mm MIX
PRIMER TYPE	-	PRIME
CBR 80	-	150mm
CBR 45	-	150mm
TOTAL BOX	-	335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.

* REFER TO INTERSECTION DETAILS PLANS

Horiz Curve Data



Vertical Geometry Grade (%)
Vertical Grade Length (m)

Vertical Curve Length (m)
Vertical Curve Radius (m)


DATUM R.L.50.0

CUT (-)/FILL DEPTH	0.367	0.045	-0.167	-0.152	-0.242	-0.255
LHS LIP LEVEL	*	56.353	56.466	57.470	57.608	
RHS LIP LEVEL	*	56.353	56.466	57.470	57.608	
DESIGN SURFACE	56.357	56.264	56.206	56.440	56.553	57.557
NATURAL SURFACE	55.897	56.161	56.607	56.706	57.799	57.951
CHAINAGE	0.00	3.75	8.40	17.75	20.00	40.00


ROAD 120 LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



CHAINAGE 40



CHAINAGE 20



CHAINAGE 13.75

ROAD 120 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112


SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 120 LONG AND CROSS SECTIONS

JOB CODE
MIR-0802
SHEET NUMBER
C313
REV
B


PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	ROAD 121 (CH.0.00-CH.48.30)
CLASS	-	ACCESS STREET (TYPICAL)
ESA's	-	5.90 x 10 ⁵
SURFACE	-	35mm AC of 10mm MIX
PRIMER TYPE	-	PRIME
CBR 80	-	150mm
CBR 45	-	150mm
TOTAL BOX	-	335mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.



DATUM R.L.56.0	
CUT (-)/FILL DEPTH	-1.219 -1.308 -1.576 -1.598 -1.849 -1.954 -1.993 -1.981
LHS LIP LEVEL	* 62.760 62.760 62.711 62.416 62.372 62.262 62.050
RHS LIP LEVEL	* 62.760 62.760 62.711 62.416 62.372 62.262 62.050
DESIGN SURFACE	63.271 63.177 62.847 62.798 62.503 62.409 62.349 62.137
NATURAL SURFACE	64.489 64.485 64.424 64.395 64.352 64.363 64.342 64.118
CHAINAGE	0.00 3.75 17.75 20.00 33.32 37.46 40.00 48.30

ROAD 121 LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



ROAD 121 CROSS SECTION
SCALE 1:100

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				

 **BRISBANE OFFICE**
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112




SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1



CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 121 LONG AND CROSS SECTIONS

JOB CODE
MIR-0802
SHEET NUMBER
C314
REV
B

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.



<h1>FOR CONSTRUCTION</h1>				 <div> <p>BRISBANE OFFICE</p> <p>LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000</p> <p>PH: (07) 3253 2222</p> <p>WEB: www.premise.com.au</p> </div>		DESIGNED KLYNT KIWANG		SCALE 		CLIENT MIRVAC QLD PTY LTD		JOB CODE MIR-0802	
						CHECKED ANDREW LANGDON				PROJECT EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT		SHEET NUMBER C315	
PROJECT MANAGER NICK SOMERVILLE		LOCATION TEVIOT ROAD, GREENBANK		REV B									
PROJECT DIRECTOR  PATRICK BRADY		SHEET TITLE ROAD 122 LONG SECTION											
19/07/2024 B ISSUED FOR CONSTRUCTION KK PB 28/05/2024 A ISSUED FOR APPROVAL KK PB DATE REV DESCRIPTION REC APP REVISIONS													



ROAD 122 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB





BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 122 CROSS SECTIONS - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C316
REV
B



ROAD 122 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au



DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
SCALE 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
ROAD 122 CROSS SECTIONS - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C317
REV
B

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



ROAD 122 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG


CHECKED
ANDREW LANGDON


PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR

PATRICK BRADY

KPEQ 7112

SCALE


HORIZONTAL 1:1000 (A1)


VERTICAL 1:100 (A1)

SCALE 1:100 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD

PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
ROAD 122 CROSS SECTIONS - SHEET 3


JOB CODE
MIR-0802

SHEET NUMBER
C318


REV
B

PAVEMENT DESIGN (PRELIMINARY)		
ROADS	-	DRIVEWAY 10
CLASS	-	REAR ACCESS DRIVEWAY
ESA's	-	1.1 x 10 ⁵
SURFACE	-	150mm CONCRETE PAVEMENT + SL82
CBR 45	-	100mm
TOTAL BOX	-	250mm

CONTRACTOR SHALL GUARANTEE CBR10 SUBGRADE OR GREATER. CBR TESTING SHALL BE CARRIED OUT BY CONTRACTOR IN ACCORDANCE WITH LOGAN CITY COUNCIL REQUIREMENTS AND RESULTS SHALL BE PRESENTED TO SUPERINTENDENT FOR APPROVAL PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION. ASSUMED CBR 10 SUBGRADE PRIOR TO TESTING.



DWAY 10 LONGITUDINAL SECTION
SCALE 1:1000(H) 1:100(V)



DWAY 10 CROSS SECTIONS
SCALE 1:100

FOR CONSTRUCTION


19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB	
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB	
DATE	REV	DESCRIPTION	REC	APP	
REVISIONS					

 **BRISBANE OFFICE**
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR

PATRICK BRADY KPEQ 7112

SCALE

HORIZONTAL 1:1000 (A1)

VERTICAL 1:100 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD

PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT


LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
DRIVEWAY 10 LONG SECTION AND CROSS SECTIONS


JOB CODE
MIR-0802

SHEET NUMBER
C319


REV
B



SCALE 1:250



SCALE 1:250


	PAVEMENT (ASPHALT)
	PAVEMENT (CONCRETE)
	PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
	PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
	PROPOSED IPWEA TYPE 'B2' KERB. REFER IPWEA STD DWG RS-080.
	PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
	PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
	FINISHED MAJOR CONTOURS (0.20m)
	FINISHED MINOR CONTOURS (0.10m)
	PROPOSED 1.5m WIDE CONCRETE FOOTPATH. (UNO) REFER CONC. REQUIREMENTS ON DRG. No. C300
	PROPOSED CONCRETE LANDSCAPING FOOTPATH. REFER LANDSCAPING DRAWINGS FOR DETAILS.
	PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
	LIP OF KERB LEVEL
	TRANSITION IN KERB AND CHANNEL TYPE
	PROPOSED STORMWATER
	PROPOSED SEWER
	PROPOSED WATER
	PROPOSED CONCRETE SLEEPER RETAINING WALL
	PROPOSED CONCRETE PANEL RETAINING WALL
	PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS

— — — SW — — — SW —	EXISTING STORMWATER
— — — S — — — S —	EXISTING SEWER
— — — W — — — W —	EXISTING WATER
— — — E — — — E —	EXISTING ELECTRICAL
— — — T — — — T —	EXISTING TELSTRA
— — — G — — — G —	EXISTING GAS

LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
		REVISIONS		



DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR  PATRICK BRADY

RPEU 7112

SCALE

0 5 10 15m

SCALE 1:250 (A1)




ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	INTERSECTION DETAILS LAYOUT - SHEET 1

JOB CODE
MIR-0802

SHEET NUMBER
C320

REV
B



- LEGEND - PROPOSED**
- PAVEMENT (ASPHALT)
 - PAVEMENT (CONCRETE)
 - PROPOSED IPWEA TYPE 'M3' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
 - PROPOSED IPWEA TYPE 'B1' KERB & CHANNEL. REFER IPWEA STD DWG RS-080.
 - PROPOSED IPWEA TYPE 'B2' KERB. REFER IPWEA STD DWG RS-080.
 - PROPOSED IPWEA TYPE 'ER1' EDGE RESTRAINT. REFER IPWEA STD DWG RS-080.
 - PROPOSED IPWEA TYPE 'INV' CHANNEL. REFER IPWEA STD DWG RS-080.
 - FINISHED MAJOR CONTOURS (0.20m)
 - FINISHED MINOR CONTOURS (0.10m)
 - PROPOSED 1.5m WIDE CONCRETE FOOTPATH. (UNO) REFER CONC. REQUIREMENTS ON DRG. No. C300
 - PROPOSED CONCRETE LANDSCAPING FOOTPATH. REFER LANDSCAPING DRAWINGS FOR DETAILS.
 - PROPOSED KERB RAMP. REFER IPWEA STD DWG RS-090.
 - LIP OF KERB LEVEL
 - TRANSITION IN KERB AND CHANNEL TYPE
 - PROPOSED STORMWATER
 - PROPOSED SEWER
 - PROPOSED WATER
 - PROPOSED CONCRETE SLEEPER RETAINING WALL
 - PROPOSED CONCRETE PANEL RETAINING WALL
 - PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS

- LEGEND - CONSTRUCTED**
- EXISTING STORMWATER
 - EXISTING SEWER
 - EXISTING WATER
 - EXISTING ELECTRICAL
 - EXISTING TELSTRA
 - EXISTING GAS

NOTE
LEVELS AND SETOUT INFORMATION FOR KERB AND CHANNEL CONSTRUCTION IS GIVEN TO LIP OF KERB.

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP

BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR
PATRICK BRADY

SCALE
0 5 10 15m
SCALE 1:250 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD

PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT


LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
INTERSECTION DETAILS LAYOUT - SHEET 2

JOB CODE
MIR-0802

SHEET NUMBER
C321

REV
B



LINEMARKING NOTES

- PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD, QUEENSLAND DEPARTMENT OF MAIN ROADS) AND THE SPECIFIC REQUIREMENTS OF REFERENCE SPECIFICATION S150 ROADWORKS. BRISBANE CITY COUNCILS SPECIFIC REQUIREMENTS ARE DETAILED ON STANDARD DRAWINGS BSD-3151 TO BDS-3163.
- ALL INTERNAL LINE MARKING TO CONSIST OF LINES 100mm WIDE WITH 2 COATS OF PAINT TO MANUFACTURERS SPECIFICATIONS. EXTENT OF LINEMARKING SHALL BE VERIFIED ON SITE PRIOR TO INSTALLATION.
- ALL PAINTED MARKINGS SHALL BE APPROVED REFLECTORISED U.N.O.
- ANY EXISTING LINE MARKINGS DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED.
- EXISTING CONFLICTING LINE MARKINGS ARE TO BE GROUND OFF BY METHODS APPROVED BY THE DISTRICT ENGINEER.
- RETRO-REFLECTIVE RAISED PAVEMENT MARKERS (RRPM's) SHALL BE PLACED 25mm TO 50mm FROM THE PAINTED LINEMARKING AND ORIENTATED SO THAT FULL REFLECTIVE EFFECT IS ACHIEVED BY AIMING THE REFLECTIVE FACE IN THE DIRECTION OF APPROACHING TRAFFIC. GENERALLY THE NORMAL SPACING BETWEEN RRPM's IS TO BE 12.0m U.N.O.
- ANY EXISTING LINEMARKING NOT SHOWN ON THIS PLAN WHICH CONFLICTS OR IS INCOMPATIBLE WITH THE PROPOSED LINEMARKING SHALL BE REMOVED BY THE CONTRACTOR.
- NOSE OF ISLANDS TO BE PAINTED WHITE WITH GLASS BEADS.
- ALL STREET LIGHTING IN ACCORDANCE WITH AS1158.




SIGNAGE NOTES

- LOCATION OF SIGNS SHOWN INDICATED ON THIS PLAN ARE INDICATIVE ONLY. CARE AND CONSIDERATION IS TO BE GIVEN TO ON SITE CONDITIONS TO AVOID ANY VISUAL OBSTRUCTION OF THE SIGN ALONG THE INTENDED COURSE OF APPROACHING TRAFFIC. EXACT LOCATION OF ALL SIGNS SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.
- SIGNS SHOULD BE ORIENTATED AT APPROXIMATELY RIGHT ANGLES TO, AND FACING THE TRAFFIC THEY ARE INTENDED TO SERVE.
- SIGNAGE SHALL BE IN ACCORDANCE WITH:
 - AS1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
 - AS1743 ROAD SIGNS SPECIFICATION
 - AS4049.1 PAVEMENT MARKING MATERIALS
- STREET NAME SIGNS ARE TO BE INSTALLED WITH THE RELEVANT HOUSE NUMBERS IN ACCORDANCE WITH THE RELEVANT LOCAL COUNCIL STANDARD DRAWINGS.


PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN
SCALE 1:500

REQUIRED SIGNS



FOR CONSTRUCTION				 BRISBANE OFFICE LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au		DESIGNED KLYNT KIWANG CHECKED ANDREW LANGDON PROJECT MANAGER NICK SOMERVILLE PROJECT DIRECTOR  PATRICK BRADY KPEQ 7112		SCALE  SCALE 1:500 (A1) ORIGINAL SHEET SIZE A1		CLIENT MIRVAC QLD PTY LTD PROJECT EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT LOCATION TEVIOT ROAD, GREENBANK SHEET TITLE PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN - SHEET 1		JOB CODE MIR-0802 SHEET NUMBER C330 REV B	
19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB								
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB								
DATE	REV	DESCRIPTION		REC	APP								
REVISIONS													

JOINS SHEET 1



PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN
SCALE 1:500


REQUIRED SIGNS



R1-2A

TYPICAL LINEMARKING LEGEND

N.T.S.



LINEMARKING NOTES

- PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD, QUEENSLAND DEPARTMENT OF MAIN ROADS) AND THE SPECIFIC REQUIREMENTS OF REFERENCE SPECIFICATION S150 ROADWORKS. BRISBANE CITY COUNCILS SPECIFIC REQUIREMENTS ARE DETAILED ON STANDARD DRAWINGS BSD-3151 TO BDS-3163.
- ALL INTERNAL LINE MARKING TO CONSIST OF LINES 100mm WIDE WITH 2 COATS OF PAINT TO MANUFACTURERS SPECIFICATIONS. EXTENT OF LINEMARKING SHALL BE VERIFIED ON SITE PRIOR TO INSTALLATION.
- ALL PAINTED MARKINGS SHALL BE APPROVED REFLECTORISED U.N.O.
- ANY EXISTING LINE MARKINGS DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED.
- EXISTING CONFLICTING LINE MARKINGS ARE TO BE GROUND OFF BY METHODS APPROVED BY THE DISTRICT ENGINEER.
- RETRO-REFLECTIVE RAISED PAVEMENT MARKERS (RRPM's) SHALL BE PLACED 25mm TO 50mm FROM THE PAINTED LINEMARKING AND ORIENTATED SO THAT FULL REFLECTIVE EFFECT IS ACHIEVED BY AIMING THE REFLECTIVE FACE IN THE DIRECTION OF APPROACHING TRAFFIC. GENERALLY THE NORMAL SPACING BETWEEN RRPM's IS TO BE 12.0m U.N.O.
- ANY EXISTING LINEMARKING NOT SHOWN ON THIS PLAN WHICH CONFLICTS OR IS INCOMPATIBLE WITH THE PROPOSED LINEMARKING SHALL BE REMOVED BY THE CONTRACTOR.
- NOSE OF ISLANDS TO BE PAINTED WHITE WITH GLASS BEADS.
- ALL STREET LIGHTING IN ACCORDANCE WITH AS1158.

SIGNAGE NOTES

- LOCATION OF SIGNS SHOWN INDICATED ON THIS PLAN ARE INDICATIVE ONLY. CARE AND CONSIDERATION IS TO BE GIVEN TO ON SITE CONDITIONS TO AVOID ANY VISUAL OBSTRUCTION OF THE SIGN ALONG THE INTENDED COURSE OF APPROACHING TRAFFIC. EXACT LOCATION OF ALL SIGNS SHALL BE CONFIRMED ON SITE PRIOR TO INSTALLATION.
- SIGNS SHOULD BE ORIENTATED AT APPROXIMATELY RIGHT ANGLES TO, AND FACING THE TRAFFIC THEY ARE INTENDED TO SERVE.
- SIGNAGE SHALL BE IN ACCORDANCE WITH:
 - AS1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
 - AS1743 ROAD SIGNS SPECIFICATION
 - AS4049.1 PAVEMENT MARKING MATERIALS
- STREET NAME SIGNS ARE TO BE INSTALLED WITH THE RELEVANT HOUSE NUMBERS IN ACCORDANCE WITH THE RELEVANT LOCAL COUNCIL STANDARD DRAWINGS.


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
DATE	REV	DESCRIPTION	REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112



CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
PAVEMENT MARKINGS AND SIGNAGE LAYOUT PLAN - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C331
REV
B



LEGEND

- 1/A
0.2311ha
- STORMWATER CATCHMENT BOUNDARY
- STORMWATER CATCHMENT NUMBER AND AREA
- SW

SW
- PROPOSED STORMWATER LINE
- SW

SW
- CONSTRUCTED STORMWATER LINE
- 12.0

12.0
- FINISHED CONTOURS (0.50m)
- 12.0

12.0
- EXISTING CONTOURS (1.00m)

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB	
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB	
DATE	REV	DESCRIPTION	REC	APP	
REVISIONS					



BRISBANE OFFICE

LEVEL 11, 300 ADELAIDE STREET

BRISBANE, QLD 4000


PH: (07) 3253 2222

WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR

PATRICK BRADY

RPEQ 7112

SCALE

0204060m

SCALE 1:1000 (A1)

ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD

PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK


SHEET TITLE
STORMWATER CATCHMENT LAYOUT PLAN

JOB CODE
MIR-0802

SHEET NUMBER
C400

REV
B

STRUCTURE NAME	TE1/5
STRUCTURE DESCRIPTION	TEMPORARY HEADWALL
	6/5
	7/5
	8/5
	9/5
	10/5
	11/5
	12/5
	13/5



PIPE SIZE (mm)	525	600	675	675	750	750	750	1050
PIPE CLASS	2	2	2	2	2	2	2	2
PIPE GRADE (%)	4.27%	1.00%	1.30%	1.61%	1.00%	2.43%	3.00%	2.78%
PIPE SLOPE (1 in X)	23.4	100.0	76.9	62.0	100.0	41.1	33.3	36.0
FULL PIPE VELOCITY (m/s)	1.38	1.37	1.71	1.82	1.86	2.07	2.25	1.46
PART FULL VELOCITY (m/s)	3.70	2.30	2.84	3.13	2.76	3.98	4.40	4.50
PIPE FLOW (cumecs)	0.298	0.389	0.612	0.651	0.821	0.913	0.993	1.267
PIPE CAPACITY AT GRADE (cumecs)	0.889	0.614	0.959	1.068	1.114	1.737	1.929	4.551
DATUM RL	37.0							
WSE IN STRUCTURE	57.183	54.922	54.884	54.195	53.428	52.808	51.442	49.460
HGL IN PIPE	57.183	54.922 54.892	54.876 54.698	54.236 54.158	53.428 53.387	52.808 52.755	51.442 51.377	50.145 50.134
DEPTH OF INVERT BELOW FSL	1.767	1.806 1.881	1.953 2.028	1.815 2.015	1.952 1.952	1.848 1.868	1.704 1.724	2.244 2.544
INVERT LEVEL	56.812	54.416 54.341	54.275 54.200	53.844 53.644	52.845 52.825	52.184 52.164	50.783 50.763	49.795 49.495
FINISHED (& EXISTING) SURFACE LEVEL	58.580 (59.051)	56.221 (55.883)	56.228 (55.485)	55.659 (54.295)	54.777 (52.645)	54.032 (51.757)	52.487 (50.447)	52.039 (49.953)
CHAINAGE	0.000	56.105	62.679	90.052	139.608	203.673	260.453	292.727

LINE 5

FOR CONSTRUCTION				
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR

PATRICK BRADY

RPEQ 7112


SCALE

HORIZONTAL 1:1000 (A1)
0 20 40 60m

VERTICAL 1:100 (A1)
0 4 8m

ORIGINAL SHEET SIZE A1


1/64	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel
2/64	IPWEA KERB INLET L.L.I.; 2.4m Lintel ON 1050mm DIA MANHOLE
3/64	IPWEA KERB INLET (SAG) L.L.I.; 4.8m Lintel ON 1050mm DIA MANHOLE
13/5	



	450	525	600
	2	2	2
	1.00%	1.20%	2.00%
	100.0	83.3	50.0
	0.16		0.54
	1.10		2.31
	0.025	0.074	
	0.285	0.471	
34.0			
50.677	50.665	50.683	50.655
	1.333	1.460	1.493
50.559	50.508	50.476	50.332
50.202	51.969	50.239	50.312
5.085	5.085	12.002	17.087
			15.844
			32.931
			50.028
			49.995
			1.711

64


1/65	IPWEA KERB INLET (SAG) L.L.I.; 2.4m Lintel
12/5	IPWEA MANHOLE 1500mm DIA



	375
	2
	1.00%
	100.0
	0.34
	1.26
	0.037
	0.175
34.0	
50.770	50.713
	1.324
50.574	50.577
50.271	50.459
11.519	52.039
	49.953
	49.495
	2.544

65


4/66	TEMPORARY HEADWALL
5/66	IPWEA MANHOLE 1050mm DIA
12/5	IPWEA MANHOLE 1500mm DIA



	375	450
	2	2
	4.22%	2.59%
	23.7	38.7
	1.43	1.65
	3.15	2.98
	0.158	0.263
	0.360	0.459
35.0		
52.941	52.864	51.590
	1.388	1.453
52.571	51.268	51.553
53.037	51.182	51.193
30.911	52.721	50.534
	51.182	50.778
		50.145
		49.495
		2.544

66

1/67	FUTURE IPWEA KERB INLET L.L.I.; 2.4m Lintel
5/66	IPWEA MANHOLE 1050mm DIA



	375
	2
	3.08%
	32.4
	0.44
	2.03
	0.048
	0.308
36.0	
51.928	51.834
	1.349
51.675	51.590
53.024	51.353
10.440	52.721
	51.182
	51.193
	1.528

67

CLIENT
MIRVAC QLD PTY LTD


PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
STORMWATER DRAINAGE LONG SECTIONS - SHEET 1

JOB CODE MIR-0802	
SHEET NUMBER C410	REV B

STRUCTURE NAME	1/68
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.I.L.: 2.4m Lintel
	IPWEA MANHOLE 1050mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.56
PART FULL VELOCITY (m/s)	1.45
PIPE FLOW (cumecs)	0.061
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	35.0

WSE IN STRUCTURE	51.739		51.590
HGL IN PIPE	51.586		51.590
DEPTH OF INVERT BELOW FSL	1.315	1.348	1.528
INVERT LEVEL	51.406	51.374	51.193
FINISHED (& EXISTING) SURFACE LEVEL	52.721 (51.232)	52.721 (51.182)	
CHAINAGE	0.000	3.180	3.180

LINE 68

1/69	IPWEA KERB INLET L.I.L.: 2.4m Lintel
11/5	IPWEA MANHOLE 1350mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	2.70%
PIPE SLOPE (1 in X)	37.0
FULL PIPE VELOCITY (m/s)	0.51
PART FULL VELOCITY (m/s)	2.02
PIPE FLOW (cumecs)	0.056
PIPE CAPACITY AT GRADE (cumecs)	0.288
DATUM RL	35.0

WSE IN STRUCTURE	51.678		51.442
HGL IN PIPE	51.587		51.442
DEPTH OF INVERT BELOW FSL	1.340	1.388	1.724
INVERT LEVEL	51.415	51.099	50.763
FINISHED (& EXISTING) SURFACE LEVEL	52.756 (51.011)	52.487 (50.447)	
CHAINAGE	0.000	11.690	11.690

LINE 69

1/69A	IPWEA KERB INLET L.I.L.: 2.4m Lintel
11/5	IPWEA MANHOLE 1350mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	0.40%
PIPE SLOPE (1 in X)	249.8
FULL PIPE VELOCITY (m/s)	0.41
PART FULL VELOCITY (m/s)	0.95
PIPE FLOW (cumecs)	0.045
PIPE CAPACITY AT GRADE (cumecs)	0.111
DATUM RL	35.0

WSE IN STRUCTURE	51.528		51.442
HGL IN PIPE	51.444		51.442
DEPTH OF INVERT BELOW FSL	1.315	1.349	1.724
INVERT LEVEL	51.161	51.138	50.763
FINISHED (& EXISTING) SURFACE LEVEL	52.476 (50.204)	52.487 (50.447)	
CHAINAGE	0.000	5.740	5.740

LINE 69A

1/70	IPWEA KERB INLET L.I.L.: 2.4m Lintel
10/5	IPWEA MANHOLE 1350mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.46
PART FULL VELOCITY (m/s)	1.37
PIPE FLOW (cumecs)	0.051
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	36.0

WSE IN STRUCTURE	52.945		52.808
HGL IN PIPE	52.841		52.808
DEPTH OF INVERT BELOW FSL	1.315	1.407	1.868
INVERT LEVEL	52.678	52.625	52.164
FINISHED (& EXISTING) SURFACE LEVEL	53.993 (51.626)	54.032 (51.757)	
CHAINAGE	0.000	5.282	5.282

LINE 70

1/71	IPWEA KERB INLET L.I.L.: 2.4m Lintel
10/5	IPWEA MANHOLE 1350mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.62%
PIPE SLOPE (1 in X)	61.9
FULL PIPE VELOCITY (m/s)	0.60
PART FULL VELOCITY (m/s)	1.76
PIPE FLOW (cumecs)	0.066
PIPE CAPACITY AT GRADE (cumecs)	0.223
DATUM RL	36.0

WSE IN STRUCTURE	53.103		52.808
HGL IN PIPE	52.925		52.808
DEPTH OF INVERT BELOW FSL	1.335	1.396	1.868
INVERT LEVEL	52.737	52.636	52.164
FINISHED (& EXISTING) SURFACE LEVEL	54.072 (51.897)	54.032 (51.757)	
CHAINAGE	0.000	6.255	6.255

LINE 71

1/72	IPWEA KERB INLET L.I.L.: 2.4m Lintel
9/5	IPWEA MANHOLE 1800mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.50
PART FULL VELOCITY (m/s)	1.40
PIPE FLOW (cumecs)	0.055
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	37.0

WSE IN STRUCTURE	53.733		53.428
HGL IN PIPE	53.611		53.512
DEPTH OF INVERT BELOW FSL	1.355	1.409	1.952
INVERT LEVEL	53.442	53.368	52.825
FINISHED (& EXISTING) SURFACE LEVEL	54.797 (52.768)	54.777 (52.645)	
CHAINAGE	0.000	7.356	7.356

LINE 72

1/73	TEMPORARY HEADWALL
2/73	IPWEA KERB INLET L.I.L.: 2.4m Lintel
9/5	IPWEA MANHOLE 1800mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	5.32%
PIPE SLOPE (1 in X)	18.8
FULL PIPE VELOCITY (m/s)	0.27
PART FULL VELOCITY (m/s)	2.15
PIPE FLOW (cumecs)	0.030
PIPE CAPACITY AT GRADE (cumecs)	0.405
DATUM RL	39.0

WSE IN STRUCTURE	57.066		53.428
HGL IN PIPE	57.039		53.428
DEPTH OF INVERT BELOW FSL	1.170	1.416	1.640
INVERT LEVEL	56.914	54.253	53.137
FINISHED (& EXISTING) SURFACE LEVEL	58.084 (57.524)	55.669 (54.288)	54.777 (52.645)
CHAINAGE	0.000	50.000	86.546

LINE 73

1/74	IPWEA KERB INLET L.I.L.: 2.4m Lintel
9/5	IPWEA MANHOLE 1800mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.14
PART FULL VELOCITY (m/s)	0.98
PIPE FLOW (cumecs)	0.015
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	37.0

WSE IN STRUCTURE	53.434		53.428
HGL IN PIPE	53.424		53.428
DEPTH OF INVERT BELOW FSL	1.324	1.581	1.952
INVERT LEVEL	53.296	53.197	52.825
FINISHED (& EXISTING) SURFACE LEVEL	54.620 (52.842)	54.777 (52.645)	
CHAINAGE	0.000	9.943	9.943

LINE 74

1/75	IPWEA KERB INLET (SAG) L.I.L.: 2.4m Lintel
9/5	IPWEA MANHOLE 1800mm DIA




PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	100.0
FULL PIPE VELOCITY (m/s)	0.44
PART FULL VELOCITY (m/s)	1.35
PIPE FLOW (cumecs)	0.048
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	37.0

WSE IN STRUCTURE	53.591		53.428
HGL IN PIPE	53.497		53.428
DEPTH OF INVERT BELOW FSL	1.316	1.594	1.952
INVERT LEVEL	53.339	53.183	52.825
FINISHED (& EXISTING) SURFACE LEVEL	54.655 (53.191)	54.777 (52.645)	
CHAINAGE	0.000	15.560	15.560

LINE 75

1/76	IPWEA FIELD INLET (ON GRADE) 900x600 H.D. GRATE
2/76	IPWEA FIELD INLET (ON GRADE) 900x600 H.D. GRATE
3/76	IPWEA FIELD INLET (ON GRADE) 900x600 H.D. GRATE
4/76	IPWEA FIELD INLET (ON GRADE) 900x600 H.D. GRATE
8/5	IPWEA MANHOLE 1050mm DIA



PIPE SIZE (mm)	375
PIPE CLASS	2
PIPE GRADE (%)	1.00%
PIPE SLOPE (1 in X)	99.9
FULL PIPE VELOCITY (m/s)	0.12
PART FULL VELOCITY (m/s)	0.95
PIPE FLOW (cumecs)	0.013
PIPE CAPACITY AT GRADE (cumecs)	0.175
DATUM RL	38.0

WSE IN STRUCTURE	55.125		54.986		54.844		54.582		54.195
HGL IN PIPE	55.120		54.986		54.844		54.582		54.307
DEPTH OF INVERT BELOW FSL	1.315	1.305	1.325	1.316	1.336	1.428	1.448	1.457	2.015
INVERT LEVEL	55.039	54.889	54.869	54.719	54.699	54.439	54.419	54.202	53.644
FINISHED (& EXISTING) SURFACE LEVEL	56.354 (54.745)	56.194 (54.129)	56.035 (53.725)	55.867 (53.967)	55.659 (54.295)				
CHAINAGE	0.000	15.000	15.000	30.000	15.741	45.741	9.563		

LINE 76

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR PATRICK BRADY

RPEQ 7112

SCALE
HORIZONTAL 1:1000 (A1)
VERTICAL 1:100 (A1)
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD	JOB CODE	MIR-0802
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT	SHEET NUMBER	C411
LOCATION	TEVIOT ROAD, GREENBANK	REV	B
SHEET TITLE	STORMWATER DRAINAGE LONG SECTIONS - SHEET 2		

STRUCTURE NAME	1/77	2/77	3/77	4/77	7/5
STRUCTURE DESCRIPTION	IPWEA KERB INLET L.I.L.: 2.4m Lintel	IPWEA KERB INLET L.I.L.: 2.4m Lintel	IPWEA KERB INLET L.I.L.: 2.4m Lintel	IPWEA KERB INLET L.I.L.: 2.4m Lintel	IPWEA MANHOLE 1050mm DIA

PIPE SIZE (mm)	375	375	375	450
PIPE CLASS	2	2	2	2
PIPE GRADE (%)	4.08%	5.72%	4.28%	4.00%
PIPE SLOPE (1 in X)	24.5	17.5	23.4	25.0
FULL PIPE VELOCITY (m/s)	0.53	0.97	1.45	1.41
PART FULL VELOCITY (m/s)	2.37	3.18	3.18	3.37
PIPE FLOW (cumecs)	0.059	0.108	0.160	0.225
PIPE CAPACITY AT GRADE (cumecs)	0.354	0.420	0.363	0.570

DATUM RL	42.0				
WSE IN STRUCTURE	60.786				54.884
HGL IN PIPE	60.685	59.431	59.330	56.861	54.876
DEPTH OF INVERT BELOW FSL	1.349	1.328	1.348	1.415	2.028
INVERT LEVEL	60.510	59.108	59.088	56.404	54.806
FINISHED (& EXISTING) SURFACE LEVEL	61.859 (62.246)	60.437 (59.562)	59.108	56.404 (57.393)	54.806 (55.454)
CHAINAGE	0.000	34.369	46.924	81.292	121.341

LINE 77

1/78	IPWEA KERB INLET (SAG) L.I.L.: 2.4m Lintel
6/5	IPWEA MANHOLE 1350mm DIA

375	2	1.00%	100.0	0.41	1.33	0.045	0.175
SEWER 150mm IL 54.142 CLR 0.472	39.0						

55.079	54.996	54.843	54.841	54.841	54.841	54.841	54.841
56.159	54.996	54.843	54.841	54.841	54.841	54.841	54.841
8.793							

LINE 78

1/79	IPWEA KERB INLET L.I.L.: 2.4m Lintel
6/5	IPWEA MANHOLE 1350mm DIA

375	2	1.00%	100.0	0.49	1.40	0.054	0.175
SEWER 150mm IL 53.979 CLR 0.626	39.0						

55.117	55.009	54.841	54.841	54.841	54.841	54.841	54.841
56.192	55.009	54.841	54.841	54.841	54.841	54.841	54.841
9.571							

LINE 79

8/82	TEMPORARY HEADWALL
9/82	IPWEA MANHOLE 1200mm DIA
10/82	IPWEA MANHOLE 1200mm DIA
11/82	TEMPORARY HEADWALL

675	2	0.90%	111.1	2.15	2.54	0.769	0.798
SEWER 150mm IL 62.626 CLR 0.324	47.0						

64.405	64.312	63.639	63.639	63.639	63.639	63.639	63.639
65.735	64.312	63.639	63.639	63.639	63.639	63.639	63.639
39.275							

LINE 82

1/113	IPWEA KERB INLET L.I.L.: 2.4m Lintel
10/82	IPWEA MANHOLE 1200mm DIA

375	2	1.00%	99.7	0.20	1.08	0.022	0.176
IPWEA KERB INLET	47.0						

63.586	63.567	63.463	63.463	63.463	63.463	63.463	63.463
64.779	63.567	63.463	63.463	63.463	63.463	63.463	63.463
5.200							

LINE 113

1/114	IPWEA KERB INLET L.I.L.: 2.4m Lintel
10/82	IPWEA MANHOLE 1200mm DIA

375	2	0.40%	249.4	0.41	0.96	0.046	0.111
IPWEA KERB INLET	47.0						

63.634	63.550	63.583	63.583	63.583	63.583	63.583	63.583
64.699	63.550	63.583	63.583	63.583	63.583	63.583	63.583
5.513							

LINE 114

TE/115	PIPE END JOIN TO EXISTING PIPE
9/82	IPWEA MANHOLE 1200mm DIA

375	2	6.00%	16.7	0.69	2.93	0.076	0.430
PIPE END	49.0						

65.730	65.730	65.529	65.529	65.529	65.529	65.529	65.529
67.173	65.730	65.529	65.529	65.529	65.529	65.529	65.529
34.138							

LINE 115

FOR CONSTRUCTION


DATE	REV	DESCRIPTION	KK	PB
19/07/2024	B	ISSUED FOR CONSTRUCTION		
28/05/2024	A	ISSUED FOR APPROVAL		



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR PATRICK BRADY

KPEQ 7112



CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	STORMWATER DRAINAGE LONG SECTIONS - SHEET 3

JOB CODE	MIR-0802
SHEET NUMBER	C412
REV	B

1. ALL STORMWATER DRAWINGS ARE TO BE READ IN CONJUNCTION WITH DRAWING C001, STORMWATER LAYOUT PLANS, NOTES AND DETAILS.
2. STORMWATER PITS ARE TO BE CONSTRUCTED INSITU IN ACCORDANCE WITH DRAWINGS OR AS VARIOUS AS NOTED ON THE DRAWING. PREFABRICATED STORMWATER PITS CAN BE USED SUBJECT TO WRITTEN APPROVAL FROM THE SUPERINTENDENT. CLASS D HEAVY DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN TRAFFIC AREAS, CLASS B LIGHT DUTY GALVANIZED STEEL GRATES ARE TO BE FITTED IN LANDSCAPE AREAS UNLESS NOTED OTHERWISE.
3. ALL DRAINAGE EXCAVATION AND CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3500 AND THE APPLICABLE LOCAL AUTHORITY SPECIFICATIONS AND STANDARD DETAILS.
4. ALL MATERIALS SHALL MEET THE REQUIREMENTS OF AS1254 & AS1273.
5. ALL uPVC PIPES SHALL BE CLASS 'SN8' FOR DN150 & DN225, AND CLASS 'SN6' FOR DN100 UNLESS NOTED OTHERWISE.
6. PIPES SHALL BE LAID AT MIN. 1% GRADE UNLESS NOTED OTHERWISE.
7. CONTRACTOR MUST VERIFY THAT ALL PIPE LEVELS AND GRADES CAN BE ACHIEVED PRIOR TO CONSTRUCTING DRAIN LINES. ANY CONFLICT SHALL BE REPORTED TO THE SUPERINTENDENT FOR ANY NECESSARY ALTERATIONS PRIOR TO ANY CONSTRUCTION OF CONNECTING PIPEWORK.
8. WHERE PIPES ARE TO BE LAID WITHIN THE ZONE OF INFLUENCE OF STRUCTURAL LOADINGS (e.g. BUILDING FOOTINGS, RETAINING WALLS...etc). THE BUILDER SHALL PROVIDE ADEQUATE BRIDGING / PROTECTION. WHERE ANY DOUBT MAY EXIST REFERENCE SHALL BE MADE TO THE DESIGNER OF THE STRUCTURE.
9. BENCHING OF PIT STRUCTURES SHALL HAVE A SMOOTH FINISHED SURFACE, AND PIPES SHALL NOT PROJECT INSIDE THE SHAFT OF THE PIT.
10. WHERE RECTANGULAR PIT STRUCTURES ARE USED, PIPES MUST NOT CONNECT TO THE PIT AT CORNERS.
11. ALL CONSTRUCTION AND EXCAVATIONS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT REQUIREMENTS OF THE WORK HEALTH AND SAFETY ACT 2011 AND SUBSEQUENT AMENDMENTS.
12. ALL STORMWATER PIPES SHALL BE CLASS '2' (UNO) R.C. PIPES UNLESS AN ALTERNATIVE IS APPROVED BY THE SUPERINTENDENT PRIOR TO CONSTRUCTION.
13. ALL TEMPORARY ROOFWATER OUTLETS TO BE EXCAVATED AT 1 IN 200 TO NATURAL SURFACE.
14. ALL ROOFWATER PIPES CROSSING CONCRETE FOOTPATHS ARE TO BE INSTALLED PRIOR TO CONSTRUCTION OF CONCRETE FOOTPATHS.
15. INSTALL 150mm DIAMETER PVC ROOFWATER HOUSE CONNECTION STUB INTO ROOFWATER PITS. INSTALL AT 750mm DEPTH TYPICAL OR 50mm FROM THE BASE OF PIT (WHICHEVER IS SHALLOWER).









STRUCTURE TYPE	HORIZONTAL CONTROL POINT [REFERENCE POINT LOCATION]	VERTICAL CONTROL REFERENCE LEVEL
MANHOLE	 CENTRELINE OF MAIN SHAFT	FINISHED SURFACE LEVEL AT CENTRE OF MAIN SHAFT
GULLY PIT OVER MANHOLE	 CENTRE OF GULLY PIT	LIP LEVEL
GULLY PIT (LIP IN LINE)	 CENTRE OF GULLY PIT	LIP LEVEL
HEADWALL	 INTERSECTION OF HEADWALL FACE AND PIPE CENTRE LINE	INVERT LEVEL
FIELD INLET	 CENTRE OF PIT	TOP OF CONCRETE PIT
ROOFWATER PIT	 CENTRE OF PIT	TOP OF GRATE

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

SPOILAGE OF EXCESS MATERIAL TO BE PLACED INTO THE SOUTHERN DAM
 REHABILITATION AREA INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS
 AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION
 AND ALL LOCAL AUTHORITY STANDARDS. AND SHALL BE FREE DRAINING.

STORMWATER DRAINAGE LONG SECTION CHAINAGE LENGTHS ARE MEASURED FROM NODE CENTRE POINTS ALONG THE PROPOSED ALIGNMENT INCLUDING PIPE OFFSETS SUCH AS TO CENTRE OF PIT SIDE WALL AND CUSTOM PIPE SPACING INTO STRUCTURES. REFER STORMWATER DRAINAGE STRUCTURE DETAILS DRAWINGS.





FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB








BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 0.4 0.8 1.2m
SCALE 1:20 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
STORMWATER DRAINAGE STRUCTURE DETAILS - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C430
REV
B



FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB




 **BRISBANE OFFICE**
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 0.4 0.8 1.2m
SCALE 1:20 (A1)
ORIGINAL SHEET SIZE A1



CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
STORMWATER DRAINAGE STRUCTURE DETAILS - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C431
REV
B

FOR CONSTRUCTION										 BRISBANE OFFICE LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au		<div>DESIGNED KLYNT KIWANG</div> <div>CHECKED ANDREW LANGDON</div> <div>PROJECT MANAGER NICK SOMERVILLE</div> <div>PROJECT DIRECTOR  PATRICK BRADY</div>		SCALE		CLIENT MIRVAC QLD PTY LTD		JOB CODE MIR-0802	
<div>19/07/2024</div> <div>B</div> <div>ISSUED FOR CONSTRUCTION</div> <div>KK</div> <div>PB</div> <div>28/05/2024</div> <div>A</div> <div>ISSUED FOR APPROVAL</div> <div>KK</div> <div>PB</div> <div>DATE</div> <div>REV</div> <div>DESCRIPTION</div> <div>REC</div> <div>APP</div> <div>REVISIONS</div>												<div>PROJECT MANAGER NICK SOMERVILLE</div> <div>PROJECT DIRECTOR  PATRICK BRADY</div>		<div>PROJECT EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT</div> <div>LOCATION TEVIOT ROAD, GREENBANK</div> <div>SHEET TITLE STORMWATER CALCULATIONS 39% AEP STORM - SHEET 1</div>		<div>SHEET NUMBER C440</div> <div>REV B</div>			

LOCATION			TIME			SUB-CATCHMENT RUNOFF				INLET DESIGN				DRAIN DESIGN								HEADLOSSES										PART FULL		DESIGN LEVELS						RUNOFF								
STRUCTURE NUMBER	DOWNSTREAM STRUCTURE	SUB-CATCHMENTS CONTRIBUTING	tc	I	C	A	CA	Q			Qg	Qb		tc	I	CA		Qp	L	S			Vf=Q/A		CHARTS USED	Qg/Qo	Du/Do	S/Do	VELOCITY HEAD	UPSTREAM HEADLOSS CO-EFFICIENT	UPSTREAM HEADLOSS	W.S.E. CO-EFFICIENT	CHANGE IN W.S.E.	PIPE FRICTION SLOPE	PIPE FRICTION HEADLOSS (L x Sf)	NORMAL DEPTH	NORMAL DEPTH VELOCITY	UPSTREAM OBVERT LEVEL	DOWNSTREAM OBVERT LEVEL	UPSTREAM H.G.L.	DOWNSTREAM H.G.L.	W.S.E.	SURFACE OR GRATE LEVEL	MAJOR SURFACE FLOW CAPACITY	MAJOR SURFACE FLOW	DEPTH x VELOCITY PRODUCT	STRUCTURE NUMBER	
			min	mm/h	ha	ha	L/s	L/s	%	L/s	L/s		min	mm/h	ha	L/s	L/s	m	%	mm		m/s	min																									
TE1/5	6/5	1/80 1/81 1/5 2/5 3/5 4/5	0.00	0		0.000	0.000	0	0	5.02	0	0		8.65	245	1.324	0	579	56.104	4.272	525	2	2.67	0.47					0.365	0.00	0.000		0.000	2.71	1.542	0.309	4.37	57.337	54.941	57.300	55.783	57.300	58.580		0			TE1/5
6/5	7/5	1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5	0.00	0		0.000	0.000	0	747		0	747	1/75	8.91	243	1.683	0	598	6.574	1.000	600	2	2.11	0.05	34 37	0.00	1.00	2.40	0.228	0.33	0.075		0.075	0.95	0.062	0.478	2.47	54.941	54.875	55.708	55.645	55.783	56.221	1929	747			6/5
7/5	8/5	1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5												8.97	242	2.773	0	851	27.373	1.300	675	2	2.38	0.23	37 42 43	0.00	1.00	2.16	0.289	1.11	0.320	1.15	0.331	1.02	0.280	0.495	3.03	54.875	54.519	55.325	55.045	55.656	56.228					7/5
8/5	9/5	1/76 2/76 3/76 4/76 1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5	0.00	0		0.000	0.000	0	424		0	424	1/72	9.19	240	2.969	0	957	49.552	1.613	675	2	2.67	0.41	33 34	0.00	1.00	2.07	0.365	0.24	0.086		0.086	1.30	0.642	0.499	3.37	54.319	53.520	54.958	54.316	55.045	55.659	1787	424			8/5
9/5	10/5	1/72 1/73 2/73 1/74 1/75 1/76 2/76 3/76 4/76 1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5	0.00	0		0.000	0.000	0	861		0	861	1/70	9.37	239	3.672	0	1334	64.059	1.000	750	2	3.02	0.53	33 34	0.00	1.00	1.99	0.465	0.25	0.118		0.118	1.43	0.919	0.750	3.02	53.575	52.934	54.199	53.280	54.316	54.777	1787	861			9/5
10/5	11/5	1/70 1/71 1/72 1/73 2/73 1/74 1/75 1/76 2/76 3/76 4/76 1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5												9.90	234	4.222	0	1688	56.761	2.433	750	2	3.82	0.47	33 34	0.00	1.00	1.49	0.745	0.26	0.193		0.193	2.30	1.305	0.597	4.48	52.914	51.533	53.087	51.782	53.280	54.032					10/5
11/5	12/5	1/69 1/69A 1/70 1/71 1/72 1/73 2/73 1/74 1/75 1/76 2/76 3/76 4/76 1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5												10.37	230	4.615	0	2046	32.237	3.003	750	2	4.63	0.27	33 34	0.00	1.00	1.38	1.095	0.26	0.283		0.283	3.18	0.922	0.669	4.92	51.513	50.545	51.500	50.474	51.782	52.487					11/5
12/5	13/5	1/65 1/67 1/68 1/66 2/66 3/66 1/69 1/69A 1/70 1/71 1/72 1/73 2/73 1/74 1/75 1/76 2/76 3/76 4/76 1/77 2/77 3/77 4/77 1/78 1/79 1/80 1/81 1/5 2/5 3/5 4/5												10.56	229	5.980	0	2772	17.946	2.779	1050	2	3.20	0.15	34	0.00	0.91	1.05	0.523	0.10	0.052		0.052	2.85	0.498	0.592	5.51	50.545	50.046	50.422	49.909	50.474	52.039					12/5
13/5																																														13/5		
1/64	2/64	1/64	8.00	252	1.00	0.076	0.076	53	1151	0.95	8	1144	3/64	8.00	252	0.076	0	8	5.068	1.004	450	2	0.05	0.04	32	1.00		2.96	0.000	3.88	0.000		0.000	0.00	0.000	0.051	0.77	51.009	50.958	51.892	51.892	51.892	51.892	1548	1151			1/64
2/64	3/64	1/64 2/64	8.00	252	1.00	0.213	0.213	149	928	1.68	216	712	1/64	8.00	252	0.289	0	223	12.002	1.200	525	2	1.03	0.10	32 42 46 43 47	0.97	0.86	2.70	0.045	4.28	0.192	4.29	0.193	0.22	0.027	0.254	2.15	51.001	50.857	51.699	51.673	51.892	51.969	1929	928	0.23		2/64
3/64	13/5	1/64 2/64 3/64	8.00	252	1.00	0.275	0.275	193	2179	0.32	450	1729	13/5	8.10	251	0.564	0	672	15.591	2.032	600	2	2.38	0.13	32 34 37	0.67	0.88	2.39	0.288	2.90	0.835		0.835	2.82	0.194	0.396	3.39	50.912	50.595	50.838	50.391	51.673	51.969	2752	2179			3/64
13/5																																														13/5		
1/65	12/5	1/65	8.00	252	1.00	0.136	0.136	95	899	1.05	250	649	3/64	8.00	252	0.136	0	250	11.358	1.014	375	2	2.26	0.10	32	1.00		3.53	0.261	3.23	0.842		0.842	2.16	0.232	0.375	2.26	50.949	50.834	51.056	50.807	51.898	51.898	1787	899			1/65
4/66	5/66	1/66 2/66 3/66												8.49	247	0.777	0	280	30.906	4.217	375	2	2.54	0.26	37	0.00	1.00	1.75	0.329	0.74	0.243		0.243	2.56	0.790	0.249	3.60	52.946	51.643	52.983	52.193	53.226	53.959					4/66
5/66	12/5	1/67 1/68 1/66 2/66 3/66												8.75	245	1.238	0	564	25.486	2.585	450	2	3.55	0.21	34 37	0.00	1.00	2.22	0.642	0.33	0.215		0.215	3.93	0.997	0.450	3.55	51.643	50.984	51.978	50.976	52.193	52.721					5/66
1/67	5/66	1/67	8.00	252	1.00	0.201	0.201	141	207	4.05	124	84	1/65	8.00	252	0.201	0	124	10.286	3.130	375	2	1.12	0.09	32	1.00		2.42	0.064	5.25	0.336		0.336	0.50	0.052	0.165	2.64	52.0.										

LOCATION			TIME			SUB-CATCHMENT RUNOFF				INLET DESIGN				DRAIN DESIGN								HEADLOSSES										PART FULL		DESIGN LEVELS						RUNOFF								
STRUCTURE NUMBER	DOWNSTREAM STRUCTURE	SUB-CATCHMENTS CONTRIBUTING	SUB-CATCHMENT TIME OF CONCENTRATION	RAINFALL INTENSITY	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA	EQUIVALENT AREA	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS)	ROAD GRADE AT INLET	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE NUMBER	CRITICAL TIME OF CONCENTRATION	RAINFALL INTENSITY	TOTAL (C x A)	SUM ADDITIONAL PIPE FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE/BOX DIMENSIONS	CLASS	FULL PIPE VELOCITY	TIME OF FLOW IN REACH	CHARTS USED	Qg/Qo	Du/Do	S/Do	VELOCITY HEAD	UPSTREAM HEADLOSS CO-EFFICIENT	UPSTREAM HEADLOSS	W.S.E. CO-EFFICIENT	CHANGE IN W.S.E.	PIPE FRICTION SLOPE	PIPE FRICTION HEADLOSS (L x Sf)	NORMAL DEPTH	NORMAL DEPTH VELOCITY	UPSTREAM OBVERT LEVEL	DOWNSTREAM OBVERT LEVEL	UPSTREAM H.G.L.	DOWNSTREAM H.G.L.	W.S.E.	SURFACE OR GRATE LEVEL	MAJOR SURFACE FLOW CAPACITY	MAJOR SURFACE FLOW	DEPTH x VELOCITY PRODUCT	STRUCTURE NUMBER	
			min	mm/h		ha	ha	l/s	l/s	%	l/s	l/s		min	mm/h	ha	l/s	l/s	m	%	mm		m/s	min											m	m	m/s	m	m	m	m	m	m	l/s	l/s	m ² /s		
9/82	10/82	1/115 2/115 3/115 1/131A 1/131B 2/131B 1/132 1/133 1/134 2/134 1/135 1/136 1/137 1/82 2/82 3/82 4/82 8/82	0.00	0		0.000	0.000	0	0		0	0	1/113	9.95	233	3.852	0	1100	17.447	1.008	750	2	2.49	0.15	37 42 43	0.00	1.00	1.43	0.316	1.00	0.315	1.02	0.324	1.22	0.170	0.604	2.88	63.963	63.788	63.855	63.642	64.179	65.575		0			9/82
10/82	11/82	1/113 1/114 1/115 2/115 3/115 1/131A 1/131B 2/131B 1/132 1/133 1/134 2/134 1/135 1/136 1/137 1/82 2/82 3/82 4/82 8/82											10.10	232		4.149	0	1223	48.442	2.025	750	2	2.77	0.40	33 34	0.00	1.00	1.12	0.391	0.24	0.092		0.092	1.24	0.653	0.494	3.96	63.288	62.307	63.205	62.603	63.297	64.768					10/82
11/82																																														11/82		
1/113	10/82	1/113	8.00	252	1.00	0.092	0.092	64	64	4.68	54	10	1/111	8.00	252	0.092	0	54	5.177	1.007	375	2	0.49	0.04	32	1.00		1.32	0.012	9.70	0.120		0.120	1.50	0.042	0.143	1.40	63.838	63.785	63.632	63.554	63.752	64.779	1680	64	0.09	1/113	
1/114	10/82	1/114	8.00	252	1.00	0.206	0.206	144	144	7.20	97	47	1/77	8.00	252	0.206	0	97	5.466	0.404	375	2	0.88	0.05	32	1.00		1.84	0.040	7.89	0.313		0.313	0.93	0.028	0.272	1.13	63.758	63.736	63.641	63.590	63.955	64.699	1567	144	0.11	1/114	
TE/115	9/82	1/115 2/115 3/115	0.00	0		0.000	0.000	0	0		0	0		8.41	248	0.329	0	182	34.138	6.000	375	2	1.65	0.28					0.139	0.00	0.000		0.000	4.90	1.708	0.171	3.73	65.904	63.856	65.841	64.170	65.841	67.173		0			TE/115


FOR CONSTRUCTION										 BRISBANE OFFICE LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au		DESIGNED KLYNT KIWANG		SCALE		CLIENT MIRVAC QLD PTY LTD				JOB CODE MIR-0802	
												CHECKED ANDREW LANGDON				PROJECT EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT				SHEET NUMBER C443	
												PROJECT MANAGER NICK SOMERVILLE				LOCATION TEVIOT ROAD, GREENBANK				REV B	
												PROJECT DIRECTOR  PATRICK BRADY RPEQ 7112				SHEET TITLE STORMWATER CALCULATIONS 1% AEP STORM - SHEET 2					
19/07/2024 B ISSUED FOR CONSTRUCTION KK PB 28/05/2024 A ISSUED FOR APPROVAL KK PB DATE REV DESCRIPTION REC APP																					
REVISIONS												ORIGINAL SHEET SIZE A1									

EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK

FOR MIRVAC QLD PTY LTD

SEWERAGE



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844
LOT 9 on S312355

NAME OF ESTATE		EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
SUBDIVIDER		Mirvac QLD Pty Ltd
APPLICATION No.		DEV2022/1277
SP DELEGATE APPROVAL DATE		11/11/2022
COUNCIL DA APPROVAL No.		-
DRAWING/PLAN No.		C510-C511
No. OF ALLOTMENTS		66
AREA ha		3.99ha
LENGTH OF SEWERS	DN150 uPVC SN8	1,139m

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND SEWERAGE CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- THE CONSTRUCTION OF THE SEWERAGE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. SEWERAGE WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER SEWERAGE SYSTEM.
- ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE CONTRACTOR UNDER LOGAN WATER SUPERVISION AT THE DEVELOPER'S COST.
- ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE "ACCEPTED PRODUCTS AND MATERIALS" LIST.
- EACH ALLOTMENT SHALL BE SERVED BY A DN100 PROPERTY CONNECTION. FOR ALLOTMENTS OTHER THAN SINGLE RESIDENTIAL, A DN150 PROPERTY CONNECTION SHALL BE PROVIDED.
- PROPERTY CONNECTIONS SHALL BE LOCATED WITHIN THE PROPERTY AS SHOWN IN THE DRAWINGS.
- PROPERTY CONNECTION BRANCHES SHALL EXTEND INTO THE PROPERTY A MINIMUM OF 300mm AND A MAXIMUM OF 750mm.
- WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE CARRIED OUT IN LAYERS NOT EXCEEDING 300mm (LOOSE) IN DEPTH AND SHALL BE COMPACTED UNTIL THE COMPACTION IS NOT LESS THAN 95% OF THE MATERIALS MAXIMUM COMPACTION WHEN TESTED IN ACCORDANCE WITH A.S. 1289 (MODIFIED COMPACTION). TESTING SHALL BE CARRIED OUT AFTER EACH ALTERNATE LAYER. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED SEWERS WILL NOT BE ISSUED BY THE SEQ SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED.
- WHERE SEWERS HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SEQ SEWER CODE.
- THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
- SEWERS SHALL BE DISUSED /ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ SEWER CODE.
- BENCH MARK AND LEVELS TO AHD.
- REFER TO BULK EARTHWORKS DRAWINGS FOR FINISHED SURFACE LEVELS.
- ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT. FOR INFORMATION PHONE: 1300 369 915.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS TO ALLOW CONSTRUCTION OF THE SEWER SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE FOR EXCAVATION AND SAFE SHORING TO ALLOW SEWER MAINTENANCE SECTION TO CARRY OUT LIVE SEWER WORK.
- CONSTRUCT TRENCHES TO SEQ-SEW-1200-2, WITH EMBEDMENT TYPE 3 SUPPORT MINIMUM TO SEQ-SEW-1201-1, AND ROAD CROSSINGS TO SEQ-SEW-1205-1 AND LCC STANDARDS.
- CONSTRUCT PROPERTY CONNECTIONS TO SEQ-SEW-1100 SERIES.
- CONSTRUCT MAINTENANCE STRUCTURES TO SEQ-SEW-1300 SERIES.
- CONSTRUCT BULKHEADS TO SEQ-SEW-1206-1.
- INSTALL DETECTABLE MARKER TAPE ON ALL MAINS AND PROPERTY CONNECTIONS.
- CALCAREOUS CONCRETE IN MAINTENANCE HOLES REQUIRED IN ACCORDANCE WITH SEQ WS&S D&C CODE REQUIREMENTS.
- CCTV OF SEWER TO BE UNDERTAKEN AND SUPPLIED TO SUPERINTENDENT PRIOR TO, BUT NO GREATER THAN 2 WEEKS BEFORE, THE ON-SITE INSPECTION FOR OFF MAINTENANCE.

VEGETATION PROTECTION

- A. TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- B. WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- C. TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- D. ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST

SOIL

- A. TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- B. CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.
- C. IF ACID SULPHATE SOILS EXIST IN THE WORKS AREA, ACID SULPHATE SOILS ARE TO MANAGED IN ACCORDANCE WITH AN APPROVED ACID SULPHATE SOIL MANAGEMENT PLAN.

CREEK CROSSINGS

- A. SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- B. APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- C. NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

REHABILITATION

- A. PREDISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- B. PREDISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED.

SAFETY

- A. THE DESIGN AND CONSTRUCTION OF THE WORKS SHALL COMPLY WITH ALL QUEENSLAND LEGISLATION.

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL SEWER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORKPLACE HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 369 915

CONTACT "DIAL BEFORE YOU DIG" ON 1100 FOR LOCATION OF EXISTING PUBLIC SERVICES PRIOR TO EXCAVATION.

TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED IN FUTURE FILL AREA AS NOMINATED BY THE SUPERINTENDENT INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

SHEET LIST TABLE

SHEET NO.	SHEET TITLE
C500	SEWERAGE LOCALITY PLAN & NOTES
C510	SEWERAGE LAYOUT PLAN - SHEET 1
C511	SEWERAGE LAYOUT PLAN - SHEET 2
C520	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 1
C521	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 2
C522	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 3
C523	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 4
C524	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 5
C530	SEWERAGE NOTES AND DETAILS

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 100 200 300m
SCALE 1:5000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
SEWERAGE LOCALITY PLAN & NOTES

JOB CODE
MIR-0802
SHEET NUMBER
C500
REV
B



LEGEND - PROPOSED

- GRAVITY SEWER
- Ø100mm PROPERTY CONNECTION. 7.5m OFFSET FROM SIDE BDY WITH DWAY. 1.2m OFFSET FROM SIDE BDY WITHOUT DWAY. TYPICAL U.N.O.
- MAINTENANCE STRUCTURE
- PROPOSED MAINTENANCE HOLE OR MAINTENANCE SHAFT NUMBER. REFER LONG SECTION DRAWINGS FOR STRUCTURE DETAILS.
- HORIZONTAL BEND (3m RADIUS).
- LOT NUMBER
- STORMWATER DRAINAGE
- DRINKING WATER MAIN
- ELECTRICAL (PROPOSED)
- ZERO LOT LINE
- FUTURE DRIVEWAY LOCATION
- PROPOSED CONCRETE SLEEPER RETAINING WALL
- PROPOSED CONCRETE PANEL RETAINING WALL
- PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
- PROPOSED CONCRETE FOOTPATH & KERB RAMP
- STAGE BOUNDARY
- FALL ARROW
- PAD EXCLUSION ZONE

LEGEND - CONSTRUCTED

- Ø100mm CONSTRUCTED PROPERTY CONNECTION
- GRAVITY SEWER
- SEWER RISING MAIN
- MAINTENANCE STRUCTURE
- STORMWATER DRAINAGE
- DRINKING WATER MAIN
- MAINTENANCE HOLE OR MAINTENANCE SHAFT NUMBER. REFER LONG SECTION DRAWINGS FOR STRUCTURE DETAILS.
- HORIZONTAL BEND (3m RADIUS).

CONTRACTOR TO CONSTRUCT PROPOSED SEWER MANHOLES WITH SUFFICIENT NECK HEIGHT SHOULD FUTURE LAND OWNER REQUIRE ADJUSTMENT TO LID LEVEL TO SUIT POTENTIAL DRIVEWAY.

CONTRACTOR TO ENSURE THAT ALL SLOPED PROPERTY CONNECTIONS LOCATED AT REAR OF LOTS SHALL TERMINATE AT SHORTEST LENGTH POSSIBLE FROM THE JUNCTION WITH THE SEWER MAIN.

PROPERTY CONNECTIONS HAVE BEEN DESIGNED TO CONTROL THE REQUIRED SERVICE AREA OF EACH LOT AT A GRADE OF 1:60 AND A MAXIMUM DEPTH TO INVERT OF PROPERTY CONNECTION AT 1.5m, UNLESS OTHERWISE STATED.

FOR SEWERAGE RETICULATION NOTES REFER DWG No. C500.

ALL PROPERTY CONNECTIONS DIA 100 PVC UNLESS OTHERWISE DENOTED.


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112



CLIENT
PROJECT
LOCATION
SHEET TITLE

MIRVAC QLD PTY LTD
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
TEVIOT ROAD, GREENBANK
SEWERAGE LAYOUT PLAN - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C511
REV
B

LEGEND

RR DENOTES ROAD RESERVE
PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.05Ø
B	CONCRETE MANHOLE 1.20Ø
C	CONCRETE MANHOLE 1.50Ø
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
LRB	HORIZONTAL BEND (3m HORIZ. RADIUS)

LID TYPES	
B	CLASS B NON TRAFFICABLE CAST IRON
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CAST IRON

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL
D(E)	TYPE D - EXTENDED

NOTES:


1. EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
2. DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

DATUM RL

PROPERTY DESCRIPTION	RR					
PIPE SIZE (mm), CLASS	DN150 uPVC SN8					
GRADE (1 IN X)	180	21	21	21	21	21
LENGTH	12.535	3.410	0.393	0.392	21.335	1.000
EMBEDMENT TYPE	TYPE 3					
DEPTH OF INVERT BELOW FSL	2.721	2.753	2.581	2.573	2.565	2.287
INVERT LEVEL (IL)	49.375	49.444	49.574	49.758	49.777	50.812
FINISHED SURFACE LEVEL (FSL)	52.095	52.197	52.320	52.331	52.342	53.137
EXISTING SURFACE LEVEL (ESL)	50.120	50.461	50.610	50.627	50.644	51.641
CHAINAGE (CH)	325.797	338.331	341.742	342.134	342.527	364.862

LINE

4



HORIZONTAL BEND NOTE:
DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).
PROPERTY CONNECTION NOTE:
CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.
MANHOLE COVER NOTE:
ALL MANHOLE COVERS IN VERGE WITHOUT FOOTPATH TO HAVE CONCRETE SURROUND.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
HORIZONTAL 1:500 (A1)
VERTICAL 1:50 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C520
REV
B

LEGEND

RR

PP

RENOTES ROAD RESERVE

RENOTES PRIVATE PROPERTY

MANHOLE TYPES		
A	CONCRETE MANHOLE	1.05Ø
B	CONCRETE MANHOLE	1.20Ø
C	CONCRETE MANHOLE	1.50Ø
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)	
TE	TEMPORARY END	
LRB	HORIZONTAL BEND (3m HORIZ. RADIUS)	

LID TYPES		
B	CLASS B NON TRAFFICABLE CAST IRON	
BD	CLASS B NON TRAFFICABLE BOLT DOWN	
D	CLASS D TRAFFICABLE CAST IRON	


MAINTENANCE STRUCTURE DROP TYPES		
V	FALL THROUGH MH	
W	OBLIQUE 45° BACKDROP	
X	INTERNAL DROP	
Y	EXTERNAL DROP	
VORT	INTERNAL VORTEX DROP	
Z	MAINTENANCE SHAFT DROP	

PROPERTY CONNECTION TYPES		
A	TYPE A - STD	
B	TYPE B - SLOPE UP	
D	TYPE D - VERTICAL	
D(E)	TYPE D - EXTENDED	




NOTES:

1. EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).

2. DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.



LINE 20

<div>FOR CONSTRUCTION</div> <table border="1"> <tr> <td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr> <td>19/07/2024</td><td>B</td><td>ISSUED FOR CONSTRUCTION</td><td></td><td>KK</td><td>PB</td></tr> <tr> <td>28/05/2024</td><td>A</td><td>ISSUED FOR APPROVAL</td><td></td><td>KK</td><td>PB</td></tr> <tr> <td>DATE</td><td>REV</td><td>DESCRIPTION</td><td></td><td>REC</td><td>APP</td></tr> <tr> <td colspan="6">REVISIONS</td></tr> </table>												19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB	28/05/2024	A	ISSUED FOR APPROVAL		KK	PB	DATE	REV	DESCRIPTION		REC	APP	REVISIONS						 <div> BRISBANE OFFICE LEVEL 11, 300 ADELAIDE STREET BRISBANE, QLD 4000 PH: (07) 3253 2222 WEB: www.premise.com.au </div>		<div> DESIGNED KLYNT KIWANG </div> <div> CHECKED ANDREW LANGDON </div> <div> PROJECT MANAGER NICK SOMERVILLE </div> <div> PROJECT DIRECTOR  PATRICK BRADY </div>		<div> SCALE  HORIZONTAL 1:500 (A1) VERTICAL 1:50 (A1) </div>		<div> CLIENT MIRVAC QLD PTY LTD </div>		<div> JOB CODE MIR-0802 </div>	
19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB																																								
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB																																								
DATE	REV	DESCRIPTION		REC	APP																																								
REVISIONS																																													
<div> PROJECT EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT </div>		<div> LOCATION TEVIOT ROAD, GREENBANK </div>		<div> SHEET TITLE SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 2 </div>		<div> SHEET NUMBER C521 </div>		<div> REV B </div>																																					

5/4	HB1/23	1/23	HB2/23	2/23	3/23	HB3/23	HB4/23	4/23	5/23	TE1/23			
B		B		B	B			B	B	TE			
A	LRB	A	LRB	J	J	LRB	LRB	J	J				
V		V W		V	V			V	V				
23	4	20 23		23	23			23	23 23				
		1.250	1.250	1.250	1.250	1.250	1.250	1.250					
		51.701	52.476	52.874	53.076	53.249	53.381	53.529	53.729	54.469	55.265		
		B	B	B	B	B	B	B	B	B			
		4256	4257	4258	4259	4260	4261	4262	4277	4278	4279		

JOB CODE	
MIR-0802	
SHEET NUMBER	REV
C522	B

[illegible]

	4/20	1/27	HB1/27	2/27	TE1/27
	B	B		B	
	A	A	LRB	J	TE
V	W	V	V	V	
27	20	32	27		27 27
		1.250		1.250	
		55.223		55.970	1.250
		B		B	56.774
		4226		4225	4224

	TE1/29	2/29	3/29	4/29
	B	B		B
TE	J	J		J
	V	V		
	29	29		
	1.250		1.250	
60.608	1.250		1.250	
60.608	60.962		61.145	
B	B		61.329	
4194	4195		4197	
		4196		4198

E1/31	1/31	TE2/31
	B	TE
TE	J	
	V	
	31 31	

RR DENOTES ROAD RESERVE
PP DENOTES PRIVATE PROPERTY

LID TYPES	
B	CLASS B NON TRAFFICABLE CAST IRON
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CAST IRON

PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL
D(E)	TYPE D - EXTENDED

1. EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
2. DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

44.000		
	RR	
	DN150 uPVC SN8	
	29	
	41.250	
	TYPE 3	
3.300		2.203
48.761		50.205
52.060		52.407
50.054		51.079
1.000		42.250

[illegible]

						56.000
					RR	
					DN150 uPVC SN8	
				29	45	59
				1.000	17.538	30.919
					TYPE 3	
89.948	63.891	61.876	59.784	2.042		
90.949	63.921	61.858	59.818	2.040		
108.487	64.466	62.368	60.234	2.134		
139.405	64.696	62.889	60.789	2.099		

58.000			
	RR		
	DN150 uPVC SN8		
	29		180
	35.055		1.000
	TYPE 3		
2.794		2.693	
62.507		2.663	
		2.664	
65.301		63.734	
		63.764	
		63.770	
65.748		66.427	
		64.644	
1.000	36.055	64.635	
	37.055		

HORIZONTAL BEND NOTE:
DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).
PROPERTY CONNECTION NOTE:
CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.
MANHOLE COVER NOTE:
ALL MANHOLE COVERS IN VERGE WITHOUT FOOTPATH TO HAVE CONCRETE SURROUND.

25

26


27

29


31



Premise

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR  PATRICK BRADY

RPEU 7112



PROIEC

LOCATI

SHEET 1

SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 4

JOB CODE

SHEET NUMBER

E

MAINTENANCE HOLE / SHAFT NO.		1/27	HB1/32	1/32	HB2/32	HB3/32	2/32
MH / MS COVER TYPE	B			B			B
MH / MS TYPE	A		LRB	J	LRB	LRB	J
MH DROP TYPE	V V			V			
LINE NO.	32 27			32			
PROPERTY CONNECTION DEPTH		1.250	1.250	1.250	1.250	1.250	
PROPERTY CONNECTION INVERT LEVEL		55.778	56.595	57.404	57.995	58.626	59.480
PROPERTY CONNECTION TYPE		B	B	B	B	B	B
LOT NO.		4175	4176	4177	4178	4179	4180

END RR DENOTES ROAD RESERVE
PP DENOTES PRIVATE PROPERTY

MANHOLE TYPES	
A	CONCRETE MANHOLE 1.050
B	CONCRETE MANHOLE 1.200
C	CONCRETE MANHOLE 1.500
J	TYPE 'J' 1 MAINTENANCE SHAFT (DN300 SHAFT)
TE	TEMPORARY END
LRB	HORIZONTAL BEND (3m HORIZ. RADIUS)

LID TYPES	
B	CLASS B NON TRAFFICABLE CAST IRON
BD	CLASS B NON TRAFFICABLE BOLT DOWN
D	CLASS D TRAFFICABLE CAST IRON

MAINTENANCE STRUCTURE DROP TYPES	
V	FALL THROUGH MH
W	OBLIQUE 45° BACKDROP
X	INTERNAL DROP
Y	EXTERNAL DROP
VORT	INTERNAL VORTEX DROP
Z	MAINTENANCE SHAFT DROP



PROPERTY CONNECTION TYPES	
A	TYPE A - STD
B	TYPE B - SLOPE UP
D	TYPE D - VERTICAL
D(E)	TYPE D - EXTENDED

NOTES:



1. EMBEDMENT TYPE 3 SHALL USE CRUSHED ROCK NOMINAL 5-7mm (SINGLE SIZED).
2. DUCTILE IRON PIPES SHALL HAVE MIN. 1300 MICRON POLYURETHANE INTERNAL LINING.

DATUM RL	51.000				1				4				9			
PROPERTY DESCRIPTION						RR										
PIPE SIZE (mm), CLASS						DN150 uPVC SN8										
GRADE (1 IN X)		29	29	29	29	17	17	17	17	17	17	17	17	17		
LENGTH		20.061	0.264	0.264	2.466	38.937	0.119	0.119	11.679	0.238	0.238	12.701				
EMBEDMENT TYPE						TYPE 3										
DEPTH OF INVERT BELOW FSL		2.440	2.360	2.338	2.343	2.332		2.270	2.270	2.270	2.321	2.322	2.323	2.315		
INVERT LEVEL (IL)		53.784	53.864	54.566	54.575	54.584	54.671	54.701	56.960	56.967	56.973	57.651	57.665	58.415		
FINISHED SURFACE LEVEL (FSL)		56.273		56.904	56.918	56.917	57.028		59.229	59.236	59.244	59.972	59.986	60.730		
EXISTING SURFACE LEVEL (ESL)		55.872		56.578	56.587	56.597	56.693		58.547	58.554	58.561	59.231	59.245	60.134		
CHAINAGE (CH)		0.000		20.061	20.325	20.589	23.054		61.991	62.110	62.230	73.909	74.147	87.087		

LINE 32



33



35

HORIZONTAL BEND NOTE:
DEFLECTION ANGLES FOR IN LINE BENDS EXCEEDING 45° SHALL BE ACHIEVED BY THE R.R.J. CONNECTION OF TWO BENDS (MAXIMUM 45° INDIVIDUAL BEND DEFLECTION ANGLE).

PROPERTY CONNECTION NOTE:
CONTRACTOR TO ENSURE MINIMUM CLEARANCE BETWEEN PROPOSED PROPERTY CONNECTION AND PROPOSED WATER MAIN IS ACHIEVED.

MANHOLE COVER NOTE:
ALL MANHOLE COVERS IN VERGE WITHOUT FOOTPATH TO HAVE CONCRETE SURROUND.

FOR CONSTRUCTION				
19/07/2024	B	ISSUED FOR CONSTRUCTION		
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				

 <p>Premise</p>	<p>BRISBANE OFFICE</p> <p>LEVEL 11, 300 ADELAIDE STREET</p> <p>BRISBANE, QLD 4000</p> <p>PH: (07) 3253 2222</p> <p>WEB: www.premise.com.au</p>	<p>DESIGNED KLYNT KIWANG</p>
		<p>CHECKED ANDREW LANGDON</p>
		<p>PROJECT MANAGER NICK SOMERVILLE</p>
		<p>PROJECT DIRECTOR</p> <p><i>[Signature]</i></p>
		<p>PATRICK BRADY</p> <p>RPEQ 7112</p>

SCALE

HORIZONTAL 1:500 (A1)

0 10 20 30m

0 1 2 3m

VERTICAL 1:50 (A1)

ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	SEWERAGE GRAVITY MAIN LONG SECTIONS - SHEET 5


JOB CODE	
MIR-0802	
SHEET NUMBER	REV
C524	B

LIVE SEWER WORKS

No.	DESCRIPTION	DIA. SEWER	MH NO.	MH TYPE	COVER TYPE	LOT NO.	F.S.L.	E.S.L.	I.L.	DEPTH
1(A)	0.5m FROM STUB END CAP TE1/31, CONSTRUCTOR TO LAY NEW LINE 31. AFTER CLEANSING, TESTING AND INSPECTING.	150	TE1/31	END	-	4158	65.301	65.748	62.507	2.794
1(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 31 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
2(A)	0.5m FROM STUB END CAP TE1/20, CONSTRUCTOR TO LAY NEW LINE 20. AFTER CLEANSING, TESTING AND INSPECTING.	150	TE1/20	END	-	4158	65.298	65.753	62.387	2.911
2(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 20 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
3(A)	0.5m FROM STUB END CAP TE2/4, CONSTRUCTOR TO LAY NEW LINE 4. AFTER CLEANSING, TESTING AND INSPECTING.	150	TE2/4	END	-	4486	52.095	50.120	49.375	2.721
3(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 4 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
4(A)	0.5m FROM STUB END CAP TE1/21, CONSTRUCTOR TO LAY NEW LINE 21. AFTER CLEANSING, TESTING AND INSPECTING.	150	TE1/21	END	-	4486	52.130	50.131	50.091	2.039
4(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 21 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									
5(A)	0.5m FROM STUB END CAP TE1/26, CONSTRUCTOR TO LAY NEW LINE 26. AFTER CLEANSING, TESTING AND INSPECTING.	150	TE1/26	END	-	4486	52.060	50.054	48.761	3.300
5(B)	AGENCY TO REMOVE TEMPORARY END CAP ON STUB AND LINE 26 AND MAKE LIVE CONNECTIONS AFTER SUCCESSFUL "ON MAINTENANCE" INSPECTION.									


LEVELS IN THE LIVE SEWER TABLE ARE DESIGN LEVELS.
AS CONSTRUCTED INFORMATION TO BE ADDED WHEN AVAILABLE.

CONSULTING ENGINEERS ARE TO CONTACT PRIOR TO COMMENCEMENT OF CONSTRUCTION TO ARRANGE FOR THIS WORK TO BE CARRIED OUT. (EXCAVATION, SAFE-SHORTING AND ASSOCIATED WORK BY CONTRACTOR).
EXCAVATION WORKS CARRIED OUT BY CONTRACTORS AT DEPTH OF 1.5m OR GREATER MUST PROVIDE A "SAFE WORK PLAN" AS PER WORKPLACE HEALTH AND SAFETY LEGISLATION TO SEQ-SPS PRIOR TO COMMENCING ANY WORK.
IT IS THE DEVELOPER'S RESPONSIBILITY TO ENSURE ALL LIVE SEWER WORKS ARE COMPLETE BEFORE ALLOWING PRIVATE DRAINAGE TO BE CONNECTED.




SERVICE LINE CROSSING BOULDER OR BLOCK RETAINING WALL
BRIDGING SLAB DETAIL

NTS




EXTENDED PROPERTY CONNECTION UNDER RETAINING WALL - TYPE D (E)

NTS




SEWER LINE CROSSING CONCRETE SLEEPER RETAINING WALL
BRIDGING SLAB DETAIL

NTS




TYPICAL MAINTENANCE STRUCTURE
IN CONCRETE FOOTPATH DETAIL

NTS




CONCRETE STORMWATER SUPPORT TYPICAL DETAIL

SCALE 1:20



CONCRETE STORMWATER SUPPORT IN ROCK SUBGRADE DETAIL

SCALE 1:40



ELEVATION

STRUCTURAL DETAILS APPROVED	DATE
	22/07/2024
ARTHUR ROWSON	RPEQ 12412

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED KLYNT KIWANG
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY RPEQ 7112

SCALE
NTS
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	SEWERAGE NOTES AND DETAILS


JOB CODE	MIR-0802
SHEET NUMBER	C530
REV	B

EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

TEVIOT ROAD, GREENBANK

FOR MIRVAC QLD PTY LTD

WATER RETICULATION



LOCALITY PLAN

REAL PROPERTY DESCRIPTION

LOT 205 & 434 on RP845844
LOT 9 on S312355

SHEET LIST TABLE

SHEET NO.	SHEET TITLE
C600	WATER RETICULATION LOCALITY PLAN & NOTES
C610	WATER RETICULATION LAYOUT PLAN - SHEET 1
C611	WATER RETICULATION LAYOUT PLAN- SHEET 2
C620	WATER LIVE CONNECTION AND TYPICAL DETAILS

GENERAL NOTES

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- ADOPT LIP OF KERB OR SHOULDER OF ROAD AS PERMANENT LEVEL.
- COVER OF MAIN FROM PERMANENT LEVEL TO BE AS SHOWN IN SEQ-WAT-1200-2.
- CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD DRAWINGS.
- ALL MATERIALS USED IN THE WORKS SHALL COMPLY WITH SEQ-SP'S ACCEPTED PRODUCTS AND MATERIALS LIST OR BE APPROPRIATELY SHOWN, LISTED AND DEFINED IN THE ENGINEERING SUBMISSION SO THAT THE ALTERNATIVE PRODUCT OR MATERIAL CAN BE ASSESSED AND IF APPROPRIATE, APPROVED BY SEQ-SP'S
- ALL CONCRETE FOOTPATHS TO BE CLEAR OF WATER MAINS. WHERE POSSIBLE
- CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT TO THE RETICULATION SYSTEM.
- ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128.
- CONSTRUCT THRUST BLOCKS ON ALL BENDS, TEES, TAPERS AND DEAD ENDS IN ACCORDANCE WITH SEQ-WAT-1205-1, AND SEQ-WAT-1206-1.
- CONSTRUCT TRENCHES IN ACCORDANCE WITH SEQ-WAT-1200-2, PIPE EMBEDMENT TO SEQ-WAT-1201-1 (TYPE C SUPPORT) AND ROAD CROSSINGS TO SEQ-WAT-1204-1 AND LCC STANDARDS.
- INSTALL SCOURS IN ACCORDANCE WITH SEQ-WAT-1307-3.
- INSTALL DETECTABLE MARKER TAPE ON ALL WATER MAINS AND PROPERTY SERVICES.
- INSTALL HYDRANTS IN ACCORDANCE WITH SEQ-WAT-1302-1, SEQ-WAT-1303-1
- INSTALL PAVEMENT MARKERS IN ACCORDANCE WITH SEQ-WAT-1300-1 & 2.
- WATER SERVICE CONNECTIONS INCLUSIVE OF WATER METER BOXES ARE TO BE INSTALLED IN ACCORDANCE WITH STANDARD DRAWINGS SEQ-WAT-1110-1 & SEQ-WAT-1110-2 AND OTHER RELEVANT STANDARD DRAWINGS FROM SEQ DESIGN AND CONSTRUCTION CODE.
- TERMINATE ALL WATER SERVICES AFTER INSTALLATION OF THE BALL VALVE (PRIOR TO THE WATER METER). THE APPLICANT IS NOT REQUIRED TO MAKE AN APPLICATION TO COUNCIL FOR THE PROVISION OF A WATER METER AT THIS TIME.
- THE POLYETHYLENE SERVICE LINE MUST COMPLY WITH AS/NZ4130 SERIES 1 DN20 PN16.
- TAPPING BANDS MUST BE USED WHEN PROVIDING CONNECTION, UNLESS OTHERWISE APPROVED BY COUNCIL.
- PROPERTY SERVICES WITHIN ANY FOOTWAY SHALL BE POSITIONED AT 90+/-5 DEGREES TO THE WATER MAIN OR KERB. WHERE REQUIRED TO CROSS THE ROAD CARRIAGEWAY, PROPERTY SERVICES SHALL BE LOCATED WITHIN THE SERVICE DUCTS (CONDUITS) POSITIONED AT 90+/-5 DEGREES TO THE ROAD CARRIAGEWAY OR FROM SIDE BOUNDARY TO SIDE BOUNDARY AND EXTENDING BEHIND EACH KERB IN ACCORDANCE WITH CLAUSE 5.11.3 OF THE SOUTH EAST

QUEENSLAND WATER SUPPLY AND SEWERAGE DESIGN AND CONSTRUCTION CODE. THE CONDUIT SHALL HAVE A MAXIMUM LENGTH OF 25m AND EXTEND 300mm BEYOND THE BACK OF THE KERB OR CONCRETE/PAVED AREA.

21. WHERE PRACTICABLE, PROPERTY SERVICE CONNECTION POINTS MUST BE LOCATED 300mm FROM THE RESIDENTIAL PROPERTY SIDE BOUNDARY ON THE OPPOSITE SIDE OF THE ALLOTMENT TO THE ELECTRICAL SERVICE PILLAR-BOX. SERVICES MUST BE LOCATED AT LEAST 1.0m FROM ALL ELECTRICAL SOURCES AND CLEAR OF EXISTING OR FUTURE DRIVEWAYS. PROPERTY SERVICES LAID PARALLEL TO THE FOOTPATH AND/OR PROPERTY BOUNDARY ARE NOT PERMITTED (SEQ CODE CLAUSE 5.11.5).TERMINATE ALL WATER SERVICES AFTER INSTALLATION OF THE BALL VALVE (PRIOR TO THE WATER METER)

VEGETATION PROTECTION

- TREES LOCATED ALONG THE FOOTPATH SHALL BE, TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
- WHEN WORKING WITHIN 4m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
- TREE ROOTS SHALL BE TUNNELLED UNDER, RATHER THAN SEVERED, IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
- ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST.

SOIL

- TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
- CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.

CREEK CROSSINGS

- SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
- APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
- NO SOIL SHALL BE STOCKPILED WITHIN 5m OF THE CREEK.

REHABILITATION

- PRE-DISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
- PRE-DISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED, ALL DISTURBED AREAS ASSOCIATED WITH CONSTRUCTION SHALL BE REHABILITATED, HEAVILY COMPACTED AREAS SHOULD BE RIPPED PRIOR TO TREATMENT.
- ALL DISTURBED AREAS ARE TO BE LEFT IN STABLE CONDITION.
- ALL PLANTING/RE-VEGETATION WILL NEED TO BE MAINTAINED THROUGHOUT THE MAINTENANCE PERIOD.

CONSTRUCTION REQUIREMENTS

- LIVE WATER CONNECTIONS TO BE CARRIED OUT BY LOGAN WATER AS PER THE LIVE CONNECTION REQUEST UNLESS AGREED OTHERWISE WITH LOGAN WATER.
- PRIOR TO ANY EXCAVATION, CONTRACTOR IS TO LOCATE ACTUAL POSITIONS OF PUBLIC SERVICE UTILITIES BY POT HOLES.
- UPON COMPLETION OF ALL WORKS, CONTRACTORS SHALL SUPPLY THE SUPERVISING RPEQ DETAILED "AS CONSTRUCTED" INFORMATION OF THE WORK. "AS CONSTRUCTED" INFORMATION SHALL COMPLY WITH CURRENT SEQ CODE OR LOCAL AUTHORITY STANDARDS FOR PLAN AND DIGITAL INFORMATION.
- CONTRACTOR IS TO BE RESPONSIBLE FOR ARRANGING ALL LOGAN WATER CONNECTIONS AND PAYMENTS OF CONNECTION FEES.

TRENCH SPOIL NOTE:

SPOILAGE OF EXCESS MATERIAL TO BE PLACED IN FUTURE FILL AREA AS NOMINATED BY THE SUPERINTENDENT INCLUDING ALL LEVEL ONE COMPACTION REQUIREMENTS AND TESTING IN ACCORDANCE WITH MORRISON GEOTECHNICAL SPECIFICATION AND ALL LOCAL AUTHORITY STANDARDS, AND SHALL BE FREE DRAINING.

EXCAVATION IN ROCK NOTE:

CONTRACT SHALL INCLUDE TREATING, SIZING CONDITIONING AND PROCESSING ALL TYPES OF ROCK IN ALL EXCAVATIONS. PROCESSING TO BE COMPLETED AS PER MORRISON GEOTECHNICAL REPORTS TO ENSURE LEVEL 1 IS ACHIEVED.

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

RPEQ CERTIFICATION

THE CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO LOGAN WATER RETICULATION SYSTEM. ALL RPEQ CERTIFIED DRAWINGS COMPLY WITH SEQ CODE AND LOGAN WATER REQUIREMENTS.

INSPECTION REQUIREMENTS

PRIOR TO COMMENCEMENT OF WORKS, CONTACT PREMISE (07) 3253 2222 AND LOGAN WATER TO CONFIRM INSPECTION REQUIREMENTS INCLUDING LIVE CONNECTIONS.

A MINIMUM 48 HOURS NOTICE IS REQUIRED.

INSPECTIONS ARE REQUIRED TO BE ORGANIZED WITH PREMISE AND LOGAN WATER. ANY COSTS ASSOCIATED WITH ENGAGING LOGAN WATER TO UNDERTAKE INSPECTIONS OUTSIDE OF THE FEE PAID SHALL BE BORNE BY THE CONTRACTOR.

ALL ENVIRONMENT PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCING ANY CONSTRUCTION WORK, INCLUDING CLEARING.

ALL WATER CONSTRUCTION WORK UNDERTAKEN BY THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011. CONTACT THE DIVISION OF WORKPLACE HEALTH & SAFETY FOR INFORMATION. PHONE: 1300 362 128

SEQ CODE STD DRAWING SCHEDULE

SOIL CLASSIFICATION	SEQ-WAT-1200-1
EMBEDMENT AND TRENCH FILL	SEQ-WAT-1200-2
THRUST BLOCK DETAILS	SEQ-WAT-1205-1
VALVE THRUST BLOCKS	SEQ-WAT-1206-1
IDENTIFICATION MARKERS	SEQ-WAT-1300-1,2

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
NPEQ 7112

SCALE
0 150 300 450m
SCALE 1:7500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
WATER RETICULATION LOCALITY PLAN & NOTES

JOB CODE
MIR-0802
SHEET NUMBER
C600
REV
B



- LEGEND - PROPOSED**
- W POTABLE WATERMAIN
 - DN25 PE POTABLE WATER RETICULATION SERVICE WITHIN DN100 uPVC (PN9) CONDUIT
 - DN100 uPVC (PN9) WATER SERVICES & WATER METER BOX POINT, METER BY OTHERS
 - SLUICE VALVE
 - FH FIRE HYDRANT
 - TEST POINT
 - DEAD END
 - DEFLECTION
 - TRUNCATIONS 5 DEGREES OR LESS
 - 3260 LOT NUMBER
 - SW STORMWATER
 - RM SEWER RISING MAIN
 - S GRAVITY SEWER
 - ZERO LOT BOUNDARY
 - PREFERRED DRIVEWAY LOCATION (BY OTHERS)
 - SITE BOUNDARY
 - PROPOSED CONCRETE SLEEPER RETAINING WALL
 - PROPOSED CONCRETE PANEL RETAINING WALL
 - PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
 - PROPOSED CONCRETE FOOTPATH & KERB RAMP

- LEGEND - CONSTRUCTED**
- W WATER
 - SLUICE VALVE
 - FH FIRE HYDRANT
 - TEST POINT
 - DEAD END
 - WATER METER
 - STORMWATER
 - GRAVITY SEWER
 - GRAVITY SEWER
 - PMT PMT EXCLUSION ZONE

LAYOUT PLAN
SCALE 1:500

INDEMNITY - EXISTING SERVICES
NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

AS CONSTRUCTED DETAILS FOR AMEND.
I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS
SIGNED
NAME of SIGNATORY
RPEQ No. or LICENCE

FOR WATER RETICULATION NOTES, REFER DWG No. C600

FOR CONSTRUCTION				
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
DATE	REV	DESCRIPTION	REC	APP
REVISIONS				



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG

CHECKED
ANDREW LANGDON

PROJECT MANAGER
NICK SOMERVILLE

PROJECT DIRECTOR
PATRICK BRADY

SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD


PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT

LOCATION
TEVIOT ROAD, GREENBANK

SHEET TITLE
WATER RETICULATION LAYOUT PLAN - SHEET 1

JOB CODE
MIR-0802

SHEET NUMBER C610	REV B
-----------------------------	-----------------



LEGEND - PROPOSED

- W POTABLE WATERMAIN
- DN25 PE POTABLE WATER RETICULATION SERVICE WITHIN DN100 uPVC (PN9) CONDUIT
- DN100 uPVC (PN9) WATER SERVICES & WATER METER BOX POINT, METER BY OTHERS
- W SLUICE VALVE
- FH FIRE HYDRANT
- W TEST POINT
- W DEAD END
- DEFLECTION TRUNCATIONS 5 DEGREES OR LESS
- 3260 LOT NUMBER
- SW STORMWATER
- RM SEWER RISING MAIN
- S GRAVITY SEWER
- ZERO LOT BOUNDARY
- PREFERRED DRIVEWAY LOCATION (BY OTHERS)
- SITE BOUNDARY
- PROPOSED CONCRETE SLEEPER RETAINING WALL
- PROPOSED CONCRETE PANEL RETAINING WALL
- PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
- PROPOSED CONCRETE FOOTPATH & KERB RAMP

LEGEND - CONSTRUCTED

- W WATER
- W SLUICE VALVE
- FH FIRE HYDRANT
- W TEST POINT
- W DEAD END
- W WATER METER
- SW STORMWATER
- S GRAVITY SEWER
- RM GRAVITY SEWER
- PMT PMT EXCLUSION ZONE

LAYOUT PLAN
SCALE 1:500

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

AS CONSTRUCTED DETAILS FOR AMEND.

I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS

SIGNED
NAME of SIGNATORY
RPEQ No. or LICENCE

FOR WATER RETICULATION
NOTES, REFER DWG No. C600

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112


SCALE
0 10 20 30m
SCALE 1:500 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
WATER RETICULATION LAYOUT PLAN- SHEET 2


JOB CODE
MIR-0802
SHEET NUMBER
C611
REV
B




LIVE CONNECTION 1 DETAIL
SCALE 1:25



LIVE CONNECTION 2 DETAIL
SCALE 1:25



LIVE CONNECTION 3 DETAIL
SCALE 1:25



- LIVE CONNECTION NOTES:**
1. LIVE CONNECTIONS BY LOGAN WATER
 2. LIVE CONNECTION IN ACCORDANCE WITH SEQ-WAT-1303-1
 3. THRUST BLOCKS NOT SHOWN FOR CLARITY.
 4. PRE-CHLORINATION FITTINGS AS REQUIRED.

AS CONSTRUCTED DETAILS FOR AMEND.

I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE TRUE AND ACCURATE RECORD OF THE WORKS


SIGNED: _____ DATE: _____

NAME of SIGNATORY: _____

RPEQ No. or LICENCE: _____

COMPANY NAME: _____

START DATE: _____



LEGEND - PROPOSED

- 12.0 FINISHED CONTOURS AND LABELS
- SW STORMWATER
- CATCHMENT BOUNDARY (POST-DEVELOPED)
- PRECINCT BOUNDARY
- PRECINCT BOUNDARY (FUTURE/EXISTING)
- CATCHMENT A 4.13ha CATCHMENT NAME AND AREA

LEGEND - CONSTRUCTED

- SW STORMWATER

NOTE:
FOR CLEARING AND GRUBBING ESC DETAILS
REFER TO DRAWING SET MIR-1010.

EROSION RISK RATING												
BASED ON AVERAGE MONTHLY RAINFALL (SOURCE TABLE 4.4.2 IECA 2008)												
MONTHLY DATA	JAN.	FEB.	MAR.	APR.	MAY	JUN.	JUL.	AUG.	SEPT.	OCT.	NOV.	DEC.
MEAN RAINFALL	134.9	152.2	128.3	77.5	71.7	65.8	46.7	35.9	34.3	78.9	97.8	125.7
EROSION RISK	HIGH	HIGH	HIGH	MODERATE	MODERATE	MODERATE	MODERATE	LOW	LOW	MODERATE	MODERATE	HIGH
	VERY LOW RISK: 0 TO 30mm											
	LOW RISK: 30+ TO 45mm											
	MODERATE RISK: 45+ TO 100mm											
	HIGH RISK: 100+ TO 225mm											
	EXTREME RISK: >225mm											

CATCHMENT RISK ASSESSMENT - ANNUAL SOIL LOSS

CATCHMENT ID	AREA (HA)	R	K	SLOPE LENGTH (m)	SLOPE (%)	LS	P	C	A (t/ha/yr)	A (t/yr)	CONTROL
CATCHMENT A	12.58	2627	0.050	80	4.0	0.91	1.3	0.70	109	1,368	TYPE 1
CATCHMENT B	1.03	2627	0.050	40	1.0	0.16	1.3	0.70	19	20	TYPE 3

EROSION RISK RATING

APPLICABLE MONTH	EROSION RISK RATING	ADVANCE LAND CLEARING ALLOWED (WEEKS WORK)	MAX DAYS TO STABILISATION	STAGED CONSTRUCTION AND STABILISATION OF EARTH BATTERS > 6H : 1V	STOCKPILES STABILISED
	VERY LOW	8	30 (60%)		
AUG. SEPT.	LOW	8	30 (70%)		
APR. MAY. JUN. JUL. OCT. NOV.	MODERATE	6	20 (70%)	X	
JAN. FEB. MAR. DEC	HIGH	4	10 (75%)	X	X
	EXTREME	2	10 (80%)	X	X

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

T. CLARK (CPESC #6089)

T. Clark

NOTE:
FOR DISPERSIVE SOILS MANAGEMENT
NOTES, REFER TO DRAWING C210.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REC	APP
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
MARK DAVIS
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 40 80 120m
SCALE 1:2000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
OVERALL EROSION & SEDIMENT CONTROL KEY PLAN

JOB CODE
MIR-0802
SHEET NUMBER
C700
REV
B



LEGEND - PROPOSED

- NO CHANGES TO BULK EARTHWORKS WITHIN PRECINCT BOUNDARY
- EXTENT OF CUT
- EXTENT OF FILL
- FLOW DIRECTION OR RUNOFF
- CONCRETE SLEEPER RETAINING WALL
- CONCRETE PANEL RETAINING WALL
- PROPOSED TERRACE LOT FRONTING PARK RETAINING WALL BY OTHERS
- FINISHED CONTOURS AND LABELS
- STORMWATER
- PRECINCT BOUNDARY
- PRECINCT BOUNDARY (FUTURE/EXISTING)

LEGEND - CONSTRUCTED

- DIVERSION DRAIN
- STORMWATER

NOTE:

FOR CLEARING AND GRUBBING ESC DETAILS REFER TO DRAWING SET MIR-1010.

INSTALLATION SEQUENCE EARTHWORKS

- STEP 1
PERFORM EARTHWORKS ON LEADS CUT TO FILL ON SITE IN ACCORDANCE WITH THE CIVIL EARTHWORKS DRAWINGS.
- STEP 2
ONCE FINAL CUT AND FILL BATTER LEVELS HAVE BEEN ACHIEVED, REMOVE REQUIRED TOPSOIL FROM STOCKPILED AREAS AND PLACE ON BATTERS AND OTHER DISTURBED AREAS AS DIRECTED BY THE SITE SUPERINTENDENT.
- STEP 3
AS SOON AS POSSIBLE AFTER TOPSOIL HAS BEEN PLACED ON BATTERS AND OTHER DISTURBED AREAS, THESE AREAS SHOULD BE STABILISED PER FINAL DESIGN TREATMENT (REFER DRAWING C702) WITHIN TIMEFRAMES PER 'MAX DAYS TO STABILISATION' BASED ON EROSION RISK (REFER DRAWING C700). IF A RAINFALL EVENT IS FORECAST WHICH IS LIKELY TO CAUSE RUNOFF PRIOR TO DISTURBED OR EXPOSED AREAS BEING STABILISED, A COMBINATION OF MULCH, BINDER OR BIDUM IS TO BE USED TO COVER EXPOSED AREAS. INSTALLATION OF TEMPORARY EROSION CONTROL TO ACTIVE OR INACTIVE WORK AREAS, PRIOR TO RAINFALL EVENTS UNTIL FINAL DESIGN TREATMENT (STABILISATION PER DRAWING C701) IS CRITICAL FOR CATCHMENTS WHICH DO NOT DRAIN TO TYPE 1 CONTROLS.
- STEP 4
ALL SEDIMENT AND EROSION CONTROL MEASURES ARE TO REMAIN IN PLACE AND BE MONITORED UNTIL CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED. ADDITIONAL EROSION CONTROLS ARE TO BE ERECTED AS REQUIRED BY THE SUPERINTENDENT.

NOTES

- REFER EROSION AND SEDIMENT CONTROL NOTES AND DETAILS DRAWINGS.
- ALL FOOTPATHS RELEVANT TO PROPOSED SUB-PRECINCT ARE TO BE FULLY TURFED AS SOON AS PRACTICAL.
- ALL CLEAN AND DIRTY WATER CATCH DRAINS ARE TO HAVE ROCK CHECK DAMS PLACED IN ACCORDANCE WITH IECA STD DWG RCD-01.
- CONTRACTOR TO ENSURE STORMWATER DRAINAGE IS COVERED AT ALL TIMES DURING EARTHWORKS PHASE.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

T. CLARK (CPESC #6089)

NOTE:

FOR DISPERSIVE SOILS MANAGEMENT NOTES, REFER TO DRAWING C210.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
MARK DAVIS
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 20 40 60m
SCALE 1:1000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
EROSION AND SEDIMENT CONTROL - BULK EARTHWORKS PHASE

JOB CODE
MIR-0802
SHEET NUMBER
C701
REV
B



LEGEND - PROPOSED

- NO CHANGES TO STABILISATION WITHIN PRECINCT BOUNDARY
- 100mm THICK TOPSOIL RESPREAD AND DRILL SEEDING. APPLY BINDER IMMEDIATELY AFTER DRILL SEEDING
- 100mm THICK TOPSOIL AND TURF
- NO TOPSOIL AND POLYMER SPRAY (LOTS AS PART OF FUTURE PRECINCT)
- FIELD INLET PROTECTION. REFER DETAIL IECA DRAWING ESC-02 FOR DETAILS.
- GULLY INLET PROTECTION. REFER DETAIL IECA DRAWING ESC-03 FOR DETAILS.
- 12.0 FINISHED CONTOURS AND LABELS
- SW STORMWATER
- KERB LINE
- PRECINCT BOUNDARY
- PRECINCT BOUNDARY (FUTURE/EXISTING)

LEGEND - CONSTRUCTED

- SW --- SW --- STORMWATER
- KERB LINE

SERVICE TRENCH AND ROAD CONSTRUCTION SEQUENCE

- STEP 6
- A. PRIORITY SHOULD BE GIVEN TO PLACEMENT OF GRAVELS WITHIN ROAD AS A MEANS TO REDUCE EROSION RISK
 - B. PAVEMENT CONSTRUCTION
 - C. MAINTAIN ALL EXISTING ESC MEASURES DURING PAVEMENT CONSTRUCTION
 - D. GULLY INLET CONTROLS TO BE REINSTATED DURING PAVEMENT AND STORMWATER CONSTRUCTION AND MAINTAINED UNTIL ENTIRE UPSLOPE CATCHMENT HAS BEEN STABILISED.
- STEP 7
- A. MAINTENANCE PERIOD
 - B. MAINTAIN CONTROL AND ESC AND VEGETATIVE TREATMENTS WHICH CONTROL SEDIMENTATION AND EROSION PRIOR TO THE ESTABLISHMENT OF STABILIZED GRASS COVER.
- STEP 8
- A. REMOVE CONSTRUCTION ENTRANCES.
 - B. ADDITIONAL EROSION CONTROLS ARE TO BE ERCTED AND MONITORED AS REQUIRED BY THE SUPERINTENDENT

NOTES

- REFER EROSION AND SEDIMENT CONTROL NOTES AND DETAILS DRAWINGS.
- ALL FOOTPATHS ARE TO BE FULLY TURFED AS SOON AS PRACTICAL.
- CONTRACTOR TO ENSURE THAT GRASS SEEDER AREAS SHOWN ON THIS PLAN ACHIEVE SUFFICIENT STRIKE AND COVERAGE IN ACCORDANCE WITH LOGAN CITY COUNCIL STANDARDS.
- POLYMER AREAS TO BE ROUTINELY INSPECTED FOR STABILISATION PERFORMANCE AND REAPPLIED AS REQUIRED TO PREVENT SCOURING UNTIL FURTHER WORKS COMMENCE.

TURFING AND TOPSOIL NOTE

CONTRACTOR SHALL RESPREAD AMELIORATED TOPSOIL (AMELIORATION REQUIREMENTS AS DIRECTED BY SUPERINTENDENT) TO VERGES AT A THICKNESS OF 100mm.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

T. CLARK (CPESC #6089)

NOTE:

FOR DISPERSIVE SOILS MANAGEMENT NOTES, REFER TO DRAWING C210.

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	REVISIONS
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK PB
28/05/2024	A	ISSUED FOR APPROVAL	KK PB
			REC APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
MARK DAVIS
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
RPEQ 7112

SCALE
0 20 40 60m
SCALE 1:1000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
EROSION AND SEDIMENT CONTROL - STABILISATION PHASE

JOB CODE
MIR-0802
SHEET NUMBER
C702
REV
B

ROLES AND RESPONSIBILITIES

EROSION & SEDIMENT CONTROL NOTES

1.

LOCATION & LEVELS OF ALL EXISTING SERVICES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
2.

REFER EARTHWORKS DRAWINGS FOR ADDITIONAL NOTES.
3.

ALL TRENCHES, FOOTPATH EXCAVATIONS & STOCKPILES TO BE PROTECTED BY TEMPORARY SEDIMENT FENCES UNTIL 80% GRASS COVERAGE IS ACHIEVED TO DISTURBED AREAS.
4.

EVERY PRECAUTION IS TO BE TAKEN TO PREVENT THE TRANSPORT OF SILT INTO THE NEWLY LAID STORMWATER PIPES THAT ARE CONNECTED TO THE DOWNSTREAM PIPE SYSTEMS, AND ANY EXISTING OPEN CHANNELS.
5.

THESE NOTES SHALL BE READ IN CONJUNCTION WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
6.

THE EROSION AND SEDIMENT CONTROL WORKS SHALL COMPLY WITH THE REQUIREMENTS OF THE LOCAL AUTHORITIES EROSION AND SEDIMENT CONTROL STANDARDS.
7.

THE CONTRACTOR SHALL TAKE ALL REASONABLE AND PRACTICABLE MEASURES TO:
- ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON EROSIVE FLOW VELOCITIES;
- MINIMISE SOIL EROSION FROM WATER AND WIND;
- MINIMISE ADVERSE EFFECTS OF SEDIMENT RUN-OFF;
- MINIMISE OR PREVENT ENVIRONMENTAL HARM ASSOCIATED WITH DISCHARGES FROM THE SITE (E.G. THE EFFECTS OF SEDIMENTATION ON THE ENVIRONMENTAL VALUES OF RECEIVING WATERS); AND
- ENSURE THAT THE VALUE AND USE OF RESIDENTIAL PROPERTIES ADJACENT TO THE DEVELOPMENT (SUCH AS DRAINAGE AND ROADS) ARE NOT DIMINISHED AS A RESULT OF THE MIGRATION OF SEDIMENT FROM THE DEVELOPMENT.
4.

THE CONTRACTOR SHALL APPOINT AN APPROPRIATELY EXPERIENCED PERSON TO BE MADE RESPONSIBLE FOR IMPLEMENTATION OF THE ESC.
5.

ALL ESC MEASURES SHALL BE INSPECTED:
- AT LEAST DAILY (WHEN WORK IS OCCURRING ON SITE).
- AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON SITE).
- WITHIN 24 HOURS OF EXPECTED RAINFALL.
- WITHIN 18 HOURS OF RAINFALL OCCURRING.
6.

MAINTENANCE OF ESC MEASURES SHALL OCCUR TO ENSURE THEY ARE OPERATING EFFICIENTLY AND IN ACCORDANCE WITH THE FOLLOWING SCHEDULE:

ESC MEASURES	MAINTENANCE TRIGGER	TIME FRAME FOR UNDERTAKING MAINTENANCE
ESC MEASURES	WHEN SETTLED SEDIMENT VOLUME EXCEEDS 25% OF THE CAPACITY OF THE ESC MEASURE	BY THE END OF THE DAY

7.

INSTALL DIVERSION CATCH DRAINS UPSTREAM OF, AND SILT FENCE DOWNSTREAM OF, STOCKPILES.
8.

STOCKPILES ARE TO BE LOCATED AWAY FROM EROSION HAZARD AREAS SUCH AS DRAINAGE LINES AND STEEP SLOPES.
9.

STOCKPILES ARE TO BE PROTECTED FROM EROSION BY THE WIND.
10.

ADEQUATE SUPPLIES OF EMERGENCY MAINTENANCE MATERIALS, INCLUDING (BUT NOT LIMITED TO) TIE WIRE, STAKES, FILTER CLOTH, WIRE MESH AND CLEAN GRAVEL SHOULD BE AVAILABLE ON-SITE.
11.

ESC MAINTENANCE ACTIVITIES ARE TO BE RECORDED IN AN ON-SITE REGISTER. THE REGISTER IS TO BE MAINTAINED FOR THE DURATION OF THE WORKS AND IS TO BE MADE AVAILABLE TO THE SUPERINTENDENT.
12.

DISTURBED AREA ARE TO BE STABILISED AS SOON AS POSSIBLE ON COMPLETION OF BULK EARTHWORKS. LOTS TO BE STABILISED FOLLOWING RESPREADING OF TOPSOIL.
13.

SUPPLEMENTARY ESC MEASURES SHALL BE DIRECTED BY THE SUPERINTENDENT.

MAINTENANCE

1.

INSPECT ALL CATCH DRAINS AT LEAST WEEKLY AND AFTER RUNOFF-PRODUCING STORM EVENTS AND REPAIR ANY SLUMPS, BANK DAMAGE, OR LOSS OF FREEBOARD.
2.

CLOSELY INSPECT THE OUTER EDGES OF THE ROCK PROTECTION. ENSURE WATER ENTRY INTO THE ROCK -LINED AREA IS NOT CAUSING EROSION ALONG THE EDGE OF THE ROCK PROTECTION.
3.

CAREFULLY CHECK THE STABILITY OF THE ROCK LOOKING FOR INDICATIONS OF PIPING, SCOUR HOLES, OR BANK FAILURES.
4.

REPLACE OR REPOSITION THE SURFACE ROCK SUCH THAT THE DRAIN FUNCTIONS AS REQUIRED AND THE DRAIN'S REQUIRED HYDRAULIC CAPACITY IS NOT REDUCED.
5.

REPLACE ANY DISPLACED ROCK WITH ROCK OF SIGNIFICANTLY (MINIMUM 110%) LARGER SIZE THAN THE DISPLACED ROCK.
6.

ENSURE SEDIMENT IS NOT PARTIALLY BLOCKING THE DRAIN. WHERE NECESSARY, REMOVE ANY DEPOSITED MATERIAL TO ALLOW FREE DRAINAGE.
7.

DISPOSE OD ANY SEDIMENT OF FILL IN A MANNER THAT WILL NOT CREATE AN EROSION OR POLLUTION HAZARD.

ROLE	RESPONSIBILITY
PROJECT MANAGER	<div>• OVERALL RESPONSIBILITY OF ESC IMPLEMENTATION</div> <div>• NOTIFY THE ENVIRONMENTAL MANAGER IMMEDIATELY OF ANY NON-COMPLIANCE WITH ESCP</div> <div>• ENSURE THE PROMPT IMPLEMENTATION OF MEASURES TO MITIGATE EROSION AND SEDIMENT GENERATION</div>
SITE SUPERVISOR / FOREMEN	<div>• MONITOR DAILY RAINFALL</div> <div>• NOTIFY ENVIRONMENTAL ADVISOR/CONSULTANT WHEN RUNOFF GENERATING RAINFALL OCCURS IN THE PREVIOUS 24 HOURS</div> <div>• MAINTAIN CURRENT RECORDS OF RAINFALL, STORAGE VOLUMES, WATER QUALITY, TREATMENT PRACTICES, DISCHARGE VOLUMES (AS APPROPRIATE)</div> <div>• INSTALLATION AND MAINTENANCE OF ESC</div>
ENVIRONMENTAL MANAGER	<div>• PROVIDE DESIGN INFORMATION AS REQUIRED</div> <div>• CONDUCT IN-SITU MONITORING (AS REQUIRED)</div> <div>• COLLECT AND SUBMIT SAMPLES TO LABORATORY (AS REQUIRED)</div> <div>• COLLATE RESULTS AND PREPARE REPORTS (AS REQUIRED)</div> <div>• CONDUCT SITE INSPECTIONS AN AUDITS (AS REQUIRED)</div> <div>• INSPECT ESC INSTALLATION AND MAINTENANCE</div> <div>• INSPECT OFFSITE IMPACTS AND MANAGEMENT</div> <div>• PROVIDE ADVICE REGARDING ESC SITE IMPROVEMENT (AS REQUIRED)</div>
ALL PERSONNEL	<div>• REPORT ANY DAMAGE TO ESC DEVICES AND ANY POTENTIAL OR ACTUAL ENVIRONMENTAL HARM IN LINE WITH DUTY TO NOTIFY UNDER THE REQUIREMENTS OF THE ENVIRONMENTAL PROTECTION ACT 1994</div>

CORRECTIVE AND PREVENTATIVE ACTION

AN ENVIRONMENTAL INCIDENT WITH RESPECT TO THE ESCP IS DEFINED AS ANY OCCURRENCE WHERE SEDIMENT IS RELEASED FROM THE SITE, WHETHER CONTROLLED OR UNCONTROLLED, OR WHERE STORM WATER IS RELEASED (CONTROLLED) FROM SITE WHICH DOES NOT MEET THE WATER QUALITY REQUIREMENTS.

ALL INCIDENTS AND NON-CONFORMANCES ARE TO BE REPORTED, INVESTIGATED AND CORRECTED IN ACCORDANCE WITH THE ESCP TO ENSURE EFFECTIVE SOIL AND WATER QUALITY MANAGEMENT PRACTICES AT ALL TIMES.

BEST PRACTICE SITE MANAGEMENT REQUIRES ALL ESC MEASURES TO BE INSPECTED BY THE CONTRACTORS NOMINATED REPRESENTATIVE AT LEAST DAILY WHEN RAIN IS OCCURRING, WITHIN 24 HOURS PRIOR TO EXPECTED RAINFALL, AND WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE ONSITE RUNOFF (IECA, 2008). SUCH INSPECTIONS MUST CHECK:

- DAILY SITE INSPECTIONS (DURING PERIODS OF RUNOFF PRODUCING RAINFALL)

■ ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES

■ OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)

■ ALL SITE DISCHARGE POINTS (INCLUDING DEWATERING ACTIVITIES AS APPROPRIATE)
- WEEKLY SITE INSPECTIONS (EVEN IF WORK IS NOT OCCURRING ON-SITE)

■ ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES

■ OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)

■ OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FROM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.

■ LITTER AND WASTE RECEPTORS

■ OIL, FUEL AND CHEMICALS STORAGE FACILITIES
- PRIOR TO ANTICIPATED RUNOFF PRODUCING RAINFALL

■ ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES

■ ALL TEMPORARY FLOW DIVERSION AND DRAINAGE WORKS
- FOLLOWING RUNOFF PRODUCING RAINFALL

■ ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES

■ OCCURRENCES OF EXCESSIVE SEDIMENT DEPOSITION (WHETHER ON-SITE OR OFF-SITE)

■ OCCURRENCES OF CONSTRUCTION MATERIALS, LITTER OR SEDIMENT PLACED, DEPOSITED, WASHED OR BLOWN FORM THE SITE, INCLUDING DEPOSITION BY VEHICULAR MOVEMENTS.

I CERTIFY THAT THIS EROSION AND SEDIMENT CONTROL DRAWING HAS BEEN DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL EROSION CONTROL ASSOCIATION GUIDELINES.

T. CLARK (CPESC #6089)

T. Clark

FOR CONSTRUCTION

19/07/2024	B	ISSUED FOR CONSTRUCTION		KK	PB
28/05/2024	A	ISSUED FOR APPROVAL		KK	PB
DATE	REV	DESCRIPTION		REC	APP
REVISIONS					



BRISBANE OFFICE

LEVEL 11, 300 ADELAIDE STREET

BRISBANE, QLD 4000

PH: (07) 3253 2222


WEB: www.premise.com.au

DESIGNED MARK DAVIS
CHECKED ANDREW LANGDON
PROJECT MANAGER NICK SOMERVILLE
PROJECT DIRECTOR <i>Patrick Brady</i> PATRICK BRADY KPEQ 7112

SCALE
ORIGINAL SHEET SIZE A1

CLIENT	MIRVAC QLD PTY LTD
PROJECT	EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION	TEVIOT ROAD, GREENBANK
SHEET TITLE	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS

JOB CODE	MIR-0802
SHEET NUMBER	C710
REV	B




LEGEND

- LOT BOUNDARIES
- - - STAGE BOUNDARIES

NOTE

CONTRACTOR TO ENSURE THAT THE SURFACE WATER IN TURNAROUND IS DIRECTED TO KERB AND CHANNEL AND OVERLAND FLOW PATHS ARE CONSIDERED. CONTRACTOR TO NOTIFY SUPERINTENDENT SHOULD THIS CRITERIA NOT BE MET.



D4-5 1800mm x 450mm

R 9.0

R 9.0

200mm THICK COMPACTED GRAVEL (CBR45) SEALED WITH 2 COATS OF BITUMEN.

TYPICAL TEMPORARY TURN AROUND DETAIL

SCALE 1:250

LAYOUT PLAN

SCALE 1:500

FOR CONSTRUCTION

DATE	REV	DESCRIPTION	KK	PB
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
			REC	APP




BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112

SCALE
0 20 40 60m
SCALE 1:1000 (A1)
ORIGINAL SHEET SIZE A1

CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
TEMPORARY WORKS - ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 1

JOB CODE
MIR-0802
SHEET NUMBER
C900
REV
B




LAYOUT PLAN
SCALE 1:500

LEGEND

- LOT BOUNDARIES
- STAGE BOUNDARIES

NOTE

CONTRACTOR TO ENSURE THAT THE SURFACE WATER IN TURNAROUND IS DIRECTED TO KERB AND CHANNEL AND OVERLAND FLOW PATHS ARE CONSIDERED. CONTRACTOR TO NOTIFY SUPERINTENDENT SHOULD THIS CRITERIA NOT BE MET.



TYPICAL TEMPORARY
TURN AROUND DETAIL
SCALE 1:250


FOR CONSTRUCTION

DATE	REV	DESCRIPTION	KK	PB
19/07/2024	B	ISSUED FOR CONSTRUCTION	KK	PB
28/05/2024	A	ISSUED FOR APPROVAL	KK	PB
			REC	APP



BRISBANE OFFICE
LEVEL 11, 300 ADELAIDE STREET
BRISBANE, QLD 4000
PH: (07) 3253 2222
WEB: www.premise.com.au

DESIGNED
KLYNT KIWANG
CHECKED
ANDREW LANGDON
PROJECT MANAGER
NICK SOMERVILLE
PROJECT DIRECTOR
PATRICK BRADY
KPEQ 7112



CLIENT
MIRVAC QLD PTY LTD
PROJECT
EVERLEIGH PRECINCT 8.2 SUBDIVISION DEVELOPMENT
LOCATION
TEVIOT ROAD, GREENBANK
SHEET TITLE
TEMPORARY WORKS - ROADWORKS AND DRAINAGE LAYOUT PLAN - SHEET 2

JOB CODE
MIR-0802
SHEET NUMBER
C901
REV
B